

PROJECT MANUAL

for

TERMINAL APRON REHABILITATION

AIP Project No. 3-20-0082-027 BIL-AIG Project No. 3-20-0082-028

AT

PHILIP BILLARD MUNICIPAL AIRPORT

February 14, 2025

Prepared By:



WSP USA Inc. 300 Wyandotte Street Suite 200 Kansas City, Missouri 64105

CERTIFICATION PAGE

I am responsible for the following drawings and specifications:

_	-	-
Drawings:	G0.00	Cover Sheet
_	G0.01	Index, Legend of Symbols, Abbreviations & Quantities
	GI1.01	Location Map and Alignment Control
	GC0.01 - GC0.02	Construction Safety & Phasing Plan - Overall
	GC0.03 - GC0.04	Construction Safety & Phasing Plan Notes
	GC5.01	Construction Safety & Phasing Details
	VF1.01 - VF1.02	Existing Conditions Plan
	CD1.01 - CD1.03	Airfield Demolition Plan
	CA1.01 - CA1.02	Paving Plan
	CA5.01	Typical Pavement Sections
	CG1.01 - CG1.02	Grading Plan
	CE5.01	Erosion Control Details
	CM1.01 - CM1.02	Pavement Marking Plan
	CM5.01	Pavement Marking Details

Specifications: C-100 Contractor Quality Control Program (CQCP)

C-102 Temporary Air and Water Pollution, Soil Erosion, and Siltation Control

C-105 Mobilization C-106 Traffic Control

P-101 Preparation/Removal of Existing Pavements P-152 Excavation, Subgrade, and Embankment

P-401 Asphalt Mix Pavement

P-603 Emulsified Asphalt Tack Coat

P-610 Concrete for Miscellaneous Structures

P-615 Aircraft Tie Downs

P-620 Runway and Taxiway Marking

P-629 Thermoplastic Coal Tar Emulsion Surface Treatment

T-901 Seeding T-905 Topsoiling T-908 Mulching



Samuel Fridolin Stallbaumer (SEAL)

Each professional whose signature and personal seal appears above assumes responsibility in these bidding documents only for what is listed above and disclaims any responsibility for all other plans, specifications, estimates, reports, or other documents or instruments not sealed by the signed professional relating to or intended to be used for any part or parts of the project.

Certification Page CP-1 of 2

THIS PAGE INTENTIONALLY LEFT BLANK

Certification Page CP-2 of 2

THIS PAGE INTENTIONALLY LEFT BLANK

Certification Page CP-2 of 2

TABLE OF CONTENTS

SECTION	DESCRIPTION	PAGE NO.
	Cover Sheet	
CP	Certification Page	CP-1 to CP-2
TOC	Table of Contents	TOC-1 to TOC-2
FRONT E	ND DOCUMENTS	
RFB	Request for Bidders	RFB-1 to RFB-2
NTB	Notice to Bidders	NTB-1 to NTB-6
ITB	Instructions to Bidders	ITB-1 to ITB-10
PF	Proposal Form	PF-1 to PF-12
BA	Buy American Certification	BA-1 to BA-2
DBE	Utilization Statement	DBE-1 to DBE-2 of 4
DBE	Letter of Intent	DBE-3 to DBE 4 of 4
CA	Construction Contract Agreement	CA-1 to CA-6
PB	Performance Bond	PB-1 to PB-6
PAY	Payment Bond	PAY-1 to PAY-6
SP	Supplementary Provisions	SP-1 to SP-4
WR	Wage Rates - Highways	WR-1 to WR-6
	Part A - Federal Contract Provisions for Construction and	
	Equipment Contracts	Part A-1 to Part A-82
GENERA	L PROVISIONS	
GP-10	Definition of Terms	GP-10-1 to GP-10-6
GP-20	Proposal Requirements and Conditions	GP-20-1 to GP-20-4
GP-30	Award and Execution of Contract	GP-30-1 to GP-30-2
GP-40	Scope of Work	GP-40-1 to GP-40-4
GP-50	Control of Work	GP-50-1 to GP-50-6
GP-60	Control of Materials	GP-60-1 to GP-60-4
GP-70	Legal Regulations and Responsibilities to Public	GP-70-1 to GP-70-6
GP-80	Execution and Progress	GP-80-1 to GP-80-6
GP-90	Measurement and Payment	GP-90-1 to GP-90-6
FAA TEC	HNICAL SPECIFICATIONS	
C-100	Contractor Quality Control Program (CQCP)	C-100-1 to C-100-8
C-102	Temporary Air and Water Pollution, Soil Erosion, and Siltation Control	
C-105	Mobilization	C-105-1 to C-105-2
C-106	Traffic Control	C-106-1 to C-106-2
P-101	Preparation/Removal of Existing Pavements	P-101-1 to P-101-6
P-152	Excavation, Subgrade, and Embankment	P-152-1 to P-152-8
P-401	Asphalt Mix Pavement	P-401-1 to P-401-20
P-603	Emulsified Asphalt Tack Coat	P-603-1 to P-603-4
P-610	Concrete for Miscellaneous Structures	P-610-1 to P-610-8
P-615	Aircraft Tie Downs	P-615-1 to P-615-2
P-620	Runway and Taxiway Marking	P-620-1 to P-620-6
P-629	Thermoplastic Coal Tar Emulsion Surface Treatment	P-629-1 to P-620-16
T-901	Seeding	T-901-1 to T-901-6
T-905	Topsoil	T-905-1 to T-905-4
T-908	Mulching	T-908-1 to T-908-2
		· · · · -

Table of Contents TOC-1 of 2

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

ADVISORY CIRCULARS

150/5210-5D Painting, Marking, and Lighting of Vehicles Used on an Airport	14 Pages
150/5370-2G Operational Safety on Airports During Construction	95 Pages

APPENDICES

Appendix A – Geotechnical Engineering Report	60 Pages
Appendix B – Construction Safety and Phasing Plan	39 Pages

Table of Contents TOC-2 of 2

REQUESTS FOR BIDS / INVITATION FOR BIDS

(Advertisement)

METROPOLITAN TOPEKA AIRPORT AUTHORITY
TERMINAL APRON REHABILITATION
PHILIP BILLARD MUNICIPAL AIRPORT
TOPEKA, KANSAS
AIP PROJECT NO. 3-20-0082-027
BIL-AIG PROJECT NO. 3-20-0082-028

Sealed bids will be received until 2:00 PM (CST) March 20, 2025, and then publicly opened and read at Metropolitan Topeka Airport Authority Administrative Offices, 6510 SE Forbes Avenue, Suite # 1, Topeka, Kansas 66619 for furnishing all labor, materials and equipment and performing all work necessary for Terminal Apron Rehabilitation, Philip Billard Municipal Airport, Topeka, Kansas, AIP Project No. 3-20-0082-027, BIL-AIG Project No. 3-20-0082-028.

Copies of the bid documents including project drawings and technical specifications are on file and may be inspected at:

Metropolitan Topeka Airport Authority 6510 SE Forbes Avenue, Suite # 1 Topeka, KS 66619

A "pdf" copy of the project construction drawings and project manual will be provided via e-mail to prospective bidders upon request and at no cost by contacting the project manager at the address provided below or via e-mail. Printing of the project documents from the pdf file are to be borne by the prospective bidder.

Sam Stallbaumer, PE, Project Manager WSP USA 300 Wyandotte, Suite 200 Kansas City, Missouri 64105 TEL: 816-702-4244

MOB: 210-867-6532

E-Mail: sam.stallbaumer@wsp.com

A pre-bid conference for this project will be held at **Philip Billard Municipal Airport Terminal (Building 4A) Conference Room, 3600 NE Sardou Ave., Topeka, Kansas on Wednesday March 5, 2025, at 2:00PM.** Representatives of the Owner and the Engineer will be present to answer questions. Attendance at the pre-bid conference is **mandatory**.

Each proposal must be accompanied by a bid guarantee in the amount of five (5) percent of the total amount of the bid. The bid guarantee may be by certified check, cashier's check or bid bond made payable to the **Metropolitan Topeka Airport Authority**.

Bids may be held by the Metropolitan Topeka Airport Authority for a period not to exceed ninety (90) days from the date of the bid opening for the purpose of evaluating bids prior to award of contract.

The right is reserved, as the Metropolitan Topeka Airport Authority may require, to reject any and all bids and to waive any informality in the bids received.

This project is subject to the requirements of the Davis-Bacon Act, as amended. The Contractor is required to comply with wage and labor provisions and to pay minimum wages in accordance with the schedule of wage rates established by the United States Department of Labor.

Requests for Bids RFB-1 of 2

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

This project is subject to the requirements of 49 CFR Part 26 Disadvantaged Business Enterprise Participation. The owner has established a contract goal of nine percent (9.0%) participation for small business concerns owned and controlled by qualified disadvantaged business enterprises (DBE). The bidder shall make and document good faith efforts, as defined in Appendix A of 49 CFR Part 26, to meet the established goal.

The CONTRACTOR agrees to commence on or about June 2, 2025, contingent on FAA funding, and to have the project substantially completed within 90 Calendar Days from the Notice-to-Proceed.

The bidder acknowledges and accepts that for each and every Calendar Day the project remains incomplete beyond the contract time of performance, the substantial completion date, or not open to traffic as stipulated in the preceding paragraphs of this section, the CONTRACTOR shall pay the non-penal amount of \$1,500.00 per day as a liquidated damage to the OWNER.

All persons seeking to enter into a contract with the Metropolitan Topeka Airport Authority shall submit and acceptable affirmative action program in accordance with Federal Regulations.

Bidders shall take note of requirements for notification of Disadvantaged Business Enterprise (DBE).

Award of contract is also subject to the Federal provisions provided for in the section of the project manual entitled "Federal Contract Provisions for Construction and Equipment Contracts".

END OF REQUEST FOR BIDDERS

Requests for Bids RFB-2 of 2

NOTICE TO BIDDERS

METROPOLITAN TOPEKA AIRPORT AUTHORITY
TERMINAL APRON REHABILITATION
PHILIP BILLARD MUNICIPAL AIRPORT
TOPEKA, KANSAS
AIP PROJECT NO. 3-20-0082-027
BIL-AIG PROJECT NO. 3-20-0082-028

Sealed bids will be received until 2:00 PM (CST) March 20, 2025, and then publicly opened and read at Metropolitan Topeka Airport Authority Administrative Offices, 6510 SE Forbes Avenue, Suite # 1, Topeka, Kansas 66619 for furnishing all labor, materials and equipment and performing all work necessary for Terminal Apron Rehabilitation, Philip Billard Municipal Airport, Topeka, Kansas, AIP Project No. 3-20-0082-027, BIL-AIG Project No. 3-20-0082-028.

Copies of the bid documents including project drawings and technical specifications are on file and may be inspected at:

Metropolitan Topeka Airport Authority 6510 SE Forbes Avenue, Suite # 1 Topeka, KS 66619

A "pdf" copy of the project construction drawings and project manual will be provided via e-mail to prospective bidders upon request and at no cost by contacting the project manager at the address provided below or via e-mail. Printing of the project documents from the pdf file are to be borne by the prospective bidder.

Sam Stallbaumer, PE, Project Manager WSP USA 300 Wyandotte, Suite 200 Kansas City, Missouri 64105 TEL: 816-702-4244

MOB: 210-867-6532

E-Mail: sam.stallbaumer@wsp.com

A pre-bid conference for this project will be held at Philip Billard Municipal Airport Terminal (Building 4A) Conference Room, 3600 NE Sardou Ave., Topeka, Kansas on Wednesday, March 5, 2025, at 2:00 PM. Representatives of the Owner and the Engineer will be present to answer questions. Attendance at the pre-bid conference is mandatory.

CONTRACT WORK ITEMS. This project will involve the following work items and estimated quantities. Prospective bidders are hereby advised that the quantities indicated herein are approximate and are subject to change per the Section 40 of the General Provisions.

Notice to Bidders NTB-1 of 6

Item No.	Description	Unit	Quantity
C-102-5.1	Temporary Erosion Control	LS	1
C-105-6.1	Mobilization	LS	1
C-106-4.1	Traffic Control	LS	1
P-101-5.1	Joint and Crack Repair	LF	23,240
P-101-5.2	Cold Milling (0"-3")	SY	11,885
P-101-5.3	Tie-Down Abandonment Type 1	EA	5
P-101-5.4	Tie-Down Abandonment Type 2	EA	32
P-101-5.5	Pavement Patching	SY	580
P-152-4.1	Unclassified Excavation	CY	200
P-401-8.1	Asphalt Mix Pavement - Overlay	TON	1,300
P-603-5.1	Emulsified Asphalt Tack Coat	GAL	840
P-615-5.1	Aircraft Tie Down	EA	6
P-620-5.1	Pavement Marking Removal	SF	170
P-620-5.2	Temporary Pavement Marking (Yellow)	SF	850
P-620-5.3	Reflectorized Pavement Marking (Yellow)	SF	1,100
P-620-5.4	Non-Reflectorized Pavement Marking (Black)	SF	1,685
P-629-8.1	Thermoplastic Coal Tar Emulsion Sand Slurry Seal	SY	11,405
T-901-5.1	Permanent Seeding & Mulching	SY	400

CONTRACT TIME. The anticipated date that project work may commence on or about **June 2, 2025**, contingent upon FAA funding. The owner has established a contract time of **90** Calendar Days. All project work shall be substantially completed within the stated timeframe. This project is subject to liquidated damages as prescribed within the project manual.

BID GUARANTEE. Each proposal must be accompanied by a bid guarantee in the amount of five (5) percent of the total amount of the bid. The bid guarantee may be by certified check or bid bond made payable to Metropolitan Topeka Airport Authority.

BONDING REQUIREMENTS. The successful bidder will be required to furnish separate performance and payment bonds each in the amount equal to 100% of the contract price at the time of contract execution.

AWARD OF CONTRACT. All proposals submitted in accordance with the instructions presented herein will be subject to evaluation. Bids may be held by the <u>Metropolitan Topeka Airport Authority</u> for a period not to exceed <u>ninety (90) days</u> from the date of the bid opening for the purpose of evaluating bids prior to award of contract.

Award of contract will be based on the lowest aggregate sum proposal submitted from those bidders that are confirmed as being responsive and responsible. The right is reserved, as the <u>Metropolitan Topeka Airport Authority</u> may require, to reject any and all bids and to waive any informality in the bids received.

Notice to Bidders NTB-2 of 6

Prospective Bidders are hereby advised that award of contract is contingent upon the owner receiving Federal funding assistance under the Airport Improvement Program.

PROJECT SCHEDULE AND LIQUIDATED DAMAGES. The CONTRACTOR agrees to commence and to have the project substantially completed within 90 Calendar Days after the Notice-to-Proceed.

The bidder acknowledges and accepts that for each and every Calendar Day the project remains incomplete beyond the contract time of performance, the substantial completion date, or not open to traffic as stipulated in the preceding paragraphs of this section, the CONTRACTOR shall pay the non-penal amount of \$1,500.00 per calendar day as a liquidated damage to the OWNER.

FEDERAL PROVISIONS. This project is subject to the following partial listing of Federal provisions, statutes and regulations:

Equal Employment Opportunity - Executive Order 11246 and 41 CFR Part 60: The Bidder's attention is called to the "Equal Opportunity Clause" and the "Standard Federal Equal Employment Opportunity Construction Contract Specifications" set forth within the supplementary provisions. The successful Bidder shall not discriminate against any employee or applicant for employment because of race, color, religion, sex, or national origin. The Contractor will take affirmative action to ensure that applicants are employed, and that employees are treated during employment without regard to their race, color, religion, sex, or national origin.

Goals for Minority and Female Participation – Executive Order 11246 and 41 CFR Part 60:

- 1. The Bidder's attention is called to the "Equal Opportunity Clause" and the "Standard Federal Equal Employment Opportunity Construction Contract Specifications" set forth within the supplementary provisions.
- 2. The goals and timetables for minority and female participation, expressed in percentage terms for the contractor's aggregate workforce in each trade on all construction work in the covered area, are as follows:

Timetables:

Goals for minority participation for each trade: 9.0% Goals for female participation in each trade: 6.9%

These goals are applicable to all of the contractor's construction work (whether or not it is Federal or federally assisted) performed in the covered area. If the contractor performs construction work in a geographical area located outside of the geographical area where the work is actually performed. With regard to this second area, the contractor also is subject to the goals for both its Federally involved and non-federally involved construction.

<u>Certification of Non-Segregated Facilities – 41 CFR Part 60</u>: A certification of Non-Segregated Facilities must be submitted prior to the award of a federally-assisted construction contract exceeding \$10,000 which is not exempt from the provisions of the Equal Opportunity Clause.

Contractors receiving federally assisted construction contract awards exceeding \$10,000, which are not exempt from the provisions of the Equal Opportunity Clause will be required to provide for the forwarding of the notice to prospective subcontractors for supplies and construction contracts where the subcontracts exceed \$10,000 and are not exempt from the provisions of the Equal Opportunity Clause. The penalty for making false statements in offers in prescribed in 18 U.S.C. 1001.

<u>Disadvantaged Business Enterprise – 49 CFR Part 26:</u> The contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of this DOT-assisted contracts. In accordance with 49 CFR Part 26.45, the sponsor has established a contract goal of <u>nine percent</u> (9.0%) participation for small business concerns owned and controlled by certified socially and

Notice to Bidders NTB-3 of 6

economically disadvantaged enterprise (DBE). The bidder shall make and document good faith efforts, as defined in Appendix A of 49 CFR Part 26, to meet this established goal.

<u>Davis-Bacon Act</u>, as amended – 29 CFR Part 5: The Contractor is required to comply with wage and labor provisions and to pay minimum wages in accordance with the current schedule of wage rates established by the United States Department of Labor.

<u>Debarment, Suspension, Ineligibility and Voluntary Exclusion – 49 CFR Part 29</u>: The bidder certifies, by submission of a proposal or acceptance of a contract, that neither it nor its principals are presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency. Individuals or companies listed in the General Services Administration's "Excluded Parties Listing System" will not be considered for award of contract.

Foreign Trade Restriction – 49 CFR Part 30

The Bidder and Bidder's subcontractors, by submission of an offer and/or execution of a contract, is required to certify that it:

- a. Is not owned or controlled by one or more citizens of a foreign country included in the list of countries that discriminate against U.S. firms published by the Office of the United States Trade Representative (USTR);
- b. Has not knowingly entered into any contract or subcontract for this project with a person that is a citizen or national of a foreign country on said list, or is owned or controlled directly or indirectly by one or more citizens or nationals of a foreign country on said list;
- c. Has not procured any product nor subcontracted for the supply of any product for use on the project that is produced in a foreign country on said list.

Buy American Certificate - Aviation Safety and Capacity Act of 1990:

This contract is subject to the "Buy American Preferences" of the Aviation Safety and Capacity Act of 1990. Per Title 49 U.S.C. Section 50101, all steel and manufactured products installed under an AIP assisted project must be produce in the United States unless the Federal Aviation Administration has granted a formal waiver. As a condition of bid responsiveness, Bidders must submit the appropriate Buy American certification with their proposal.

ADDITIONAL PROVISIONS. A complete listing of the provisions applicable to this project can be found in the Supplemental Provisions.

MODIFICATION OF DOCUMENTS. Modification to the project documents may only be made by written addendum by the Owner or Owner's authorized Representative.

The proposal must be made on the forms provided within the bound project manual. Bidders must supply all required information prior to the time of bid opening.

SUBMITTAL OF PROPOSALS. Additional information and instruction for submittal of a proposal are provided within the Instructions-to-Bidders. Envelopes containing bids must be sealed and addressed to:

Hand Delivery of Proposals: Metropolitan Topeka Airport Authority

6510 SE Forbes Avenue, Suite # 1

Topeka, KS 66619 TEL: 785-862-2362

Mail Delivery of Proposals: Metropolitan Topeka Airport Authority

P.O. Box 19053 Topeka, KS 66619

Notice to Bidders NTB-4 of 6

The upper left-hand corner of the sealed envelope must identify the following information:

CONTRACT PROPOSAL

Bid of {Insert Name of Bidder} Philip Billard Municipal Airport Terminal Apron Rehabilitation AIP Project No.: 3-20-0082-027

BIL-AIG Project No.: 3-20-0082-028 To be opened at: 2:00 PM, March 20, 2025

END OF NOTICE TO BIDDERS

Notice to Bidders NTB-5 of 6

THIS PAGE INTENTIONALLY LEFT BLANK

Notice to Bidders NTB-6 of 6

INSTRUCTIONS TO BIDDERS

OWNER AND OWNER'S REPRESENTATIVE. The Owner as stated herein refers to the following agency **Metropolitan Topeka Airport Authority.** The Owner's authorized representative as stated herein refers to the Owner's Consultant **WSP USA Inc.** herein referred to as Engineer.

SUCCESSFUL BIDDER. The term "Successful Bidder" means the lowest, qualified, responsible Bidder to whom the Owner (on the basis of Owner's evaluation as hereinafter provided) makes an award.

BIDDER REPRESENTATIONS. By submittal of a proposal (bid), the BIDDER represents the following:

- The Bidder has read and thoroughly examined the project documents
- The Bidder has a complete understanding of the terms and conditions required for the satisfactory performance of project work.
- The Bidder has familiarized themselves of the requirements of working on an operating airport, has fully informed themselves of the project site conditions and the surrounding area, and has visited the site to familiarize himself with local conditions that may in any manner affect cost, progress or performance of the work.
- The Bidder has studied and carefully correlated Bidder's observations with that of the project documents.
- The Bidder has found no errors, conflicts, ambiguities or omissions in the project documents, except as previously submitted in writing to the owner that would affect cost, progress or performance of the work.
- The Bidder is familiar with all applicable Federal, State and local laws, rules and regulations pertaining to execution of the contract and the project work that may in any manner affect cost, progress or performance of the Work.
- The Bidder has complied with all requirements of these instructions and the associated bid documents.

BID DOCUMENTS/PROJECT MANUAL. The bid documents are comprised of the following; Notice-to-Bidders, Instructions-to-Bidders, Supplementary Provisions, General Provisions, Technical Specifications, Project Drawings, Proposal Form with attachments, Form of Contract Agreement, any authorized addenda issued by the Owner and any document incorporated in whole or in part by reference therein.

All documents comprising the Bid Documents are complementary to one another and together establish the complete terms, conditions and obligations of the successful bidder.

Those individual elements of the Contract Documents that are bound together shall also be referred to as the Project Manual. No part of the project manual that is bound may be removed or detached.

Complete set of Bid Documents shall be used in preparing Bids; neither the Owner nor the Engineer assumes responsibility for errors or misinterpretations resulting from the use of incomplete sets of Bid Documents/Project Manual.

Prospective bidders may obtain a copy of the project manual and project drawings from the designated office identified within the Notice-to-Bidders.

Owner and Engineer in making copies of Bidding Documents available on the above terms do so only for the purpose of obtaining Bids on the Work and do not confer a license or grant for any other use.

Instructions to Bidders ITB-1 of 10

MODIFICATIONS TO BID DOCUMENTS. Modifications to the bid documents may only be made by written addendum issued by the Owner or the Engineer. Verbal explanations, interpretations or comments made by the Owner or Owner's representative shall not be binding. Addenda will be transmitted to all known official plan holders. Each bidder shall certify at the time of bid submittal that they acknowledge receipt of all issued addenda.

ERRORS AND DISCREPANCIES IN BID DOCUMENTS. Should Bidder find an error, discrepancy, ambiguity or omission in the bid documents prior to submittal of a proposal, the Bidder is obligated to contact the Owner or the Engineer with written notice of the error, discrepancy, ambiguity or omission. The written notice shall identify the nature and location of the error, discrepancy, ambiguity or omission. Corrections or modifications to the project documents will only be made by written addendum as prescribed herein. By submittal of a Bid Proposal, Bidder represents that they have thoroughly reviewed the bid documents and that they have not identified any error, discrepancy, ambiguity or omission that would affect cost, progress or performance of the project work.

CLARIFICATIONS AND INTERPRETATIONS. A bidder requiring a clarification or interpretation of the bid documents shall make a written request to the Owner or Engineer. The Owner or Engineer must receive the written request a minimum of ten (10) calendar days prior to the date of the bid opening. All questions and answers will be posted to the Bid Event. Questions and answers that result in a material changed to the scope of work or quantities will require issuance of an addendum. Only questions answered by formal written Addenda will be binding. Oral and other interpretations or clarifications will be without legal effect.

INTERPRETATIONS OF ESTIMATED PROPOSAL QUANTITIES. An estimate of quantities of work to be accomplished and materials to be furnished under these specifications is stated within the project manual. This estimate is a result of careful calculations and is believed to be correct. The estimated quantities are given only as a basis for comparison of proposals and the award of contract. The Owner does not expressly or impliedly agree that the actual quantities involved will correspond exactly with the estimated quantities.

The Bidder shall not plead misunderstandings or deception because of such estimates of quantities, or of the character, location, or other conditions pertaining to the work. Payment to the Contractor will be made only for the actual quantities of work performed or materials furnished in accordance with the plans and specifications. It is understood that the quantities may be increased or decreased as hereinafter provided in the subsection titled "Alteration of Work and Quantities" of the general provisions without in any way invalidating the unit bid prices.

SUBSTITUTE MATERIAL AND EQUIPMENT. The Contract, if awarded, will be on the basis of material and equipment described in the Drawings or specified in the Specifications without consideration of possible substitute or "or equal" items. Whenever it is indicated in the Drawings or specified in the Specifications that a substitute or "or-equal" item of material or equipment may be furnished or used by Contractor if acceptable to the Engineer, application for such acceptance will not be considered by the Engineer until after the "Effective date of the Agreement". The procedure for submittal of any such application by Contractor and consideration by Engineer is set forth in the General Provisions.

EXAMINATION OF CONTRACT DOCUMENTS, PLANS, SPECIFICATIONS AND SITE CONDITIONS. As stated within the "Bidder Representations" and reaffirmed herein, the Bidder is expected to carefully examine the Contract Documents, visit the site of the proposed work, examine the proposal, drawings, specifications, terms and conditions of the proposed agreement and the form of agreement and familiarize himself with federal, state and local laws, ordinances, rules and regulations that may in any manner affect cost, progress or performance of Work.

The Bidder shall satisfy themselves as to the character, quality, and quantities of work to be performed, materials to be furnished and as to the requirements of the proposed contract. The submission of a

Instructions to Bidders ITB-2 of 10

proposal shall be prima facie evidence that the Bidder has made such examination and is satisfied as to the conditions to be encountered in performing the work and as to the requirements of the proposed contract, plans and specifications.

Boring logs and other records of subsurface investigations and tests, as appropriate may be available for inspection by the Bidder. It is understood and agreed that such subsurface information, whether included in the project drawings, specifications or otherwise made available to the Bidder, was obtained and is intended for the owner's design and estimating purposes only. Such information has been made available for the convenience of all bidders. It is further understood and agreed that the Bidder is solely responsible for all assumptions, deductions, or conclusions which he or she may make from his or her examination of the boring logs and other records of subsurface investigations and tests that are furnished by the Owner.

These reports are not guaranteed as to accuracy or completeness, nor are they part of the Bid Documents. Before submitting the Bid each Bidder will, at his own expense, make such additional investigations and tests as the Bidder may deem necessary to determine his Bid for performance of the Work in accordance with the time, price and other terms and conditions of the Bid Documents.

On request Owner will provide each Bidder access to the site to conduct such investigations and tests as each Bidder deems necessary for submission of his Bid.

The lands upon which the Work is to be performed, rights-of-way for access thereto and other lands designated for use by Contractor in performing the Work are identified in the Specifications or Drawings.

The submission of a Bid will constitute an incontrovertible representation by the Bidder that he has complied with every requirement described and that the Bid Documents are sufficient in scope and detail to indicate and convey understanding of all terms, and conditions for performance of the Work.

ISSUANCE OF PROPOSAL FORMS. The Owner reserves the right to refuse to issue a proposal form to a prospective bidder should the bidder be in default for any of the following reasons:

- Failure to comply with any pre-qualification regulations of the owner, if such regulations are cited or otherwise included, in the proposal as a requirement for bidding.
- Failure to pay, or satisfactory settle, all bills due for labor and materials on former contracts in force (with the owner) at the time the owner issues the proposal to a prospective bidder.
- Contractor default under previous contracts with the owner
- Unsatisfactory work on previous contracts with the owner

BID PROPOSAL FORM. All bid proposals shall be made on the forms provided by the Owner within the bound Project Manual. No bidder may submit more than one proposal. All proposals are to be written in ink and shall be clearly legible. All blank spaces in the proposal forms shall be legibly completed for each and every bid item. The Bidder shall not qualify any bid item. The Bidder shall initial any erasures and alterations made on the proposal form by the bidder.

The Bidder shall state the price of their bid in U.S. dollars and cents in both written and numeral format. In the event of a discrepancy, the written value will take precedence.

SIGNATURE OF PROPOSAL. The proposal shall be signed and dated by an authorized representative of the Bidder. All signatures shall be made with an ink pen. The Bidder's representative shall have the legal authority to obligate and bind the Bidder to the terms and conditions of the contract. The Bidder shall legibly state the name of the Bidder's representative, the legal name of the Bidder, the address of the Bidder including City, State and Zip Code, and the telephone number of the Bidder.

Bids submitted by an agent, evidence of the power of attorney shall be attached to the bid.

MODIFICATION OR WITHDRAWAL OF BID PROPOSAL. Bidder may modify or withdraw their proposal at any point up to the specified time and date identified for receipt of proposals. Any request for

Instructions to Bidders ITB-3 of 10

bid withdrawal or modification by the Bidder that is received after the specified time and date for receipt of proposals will be returned unopened to the sender.

Any modification to a Bidder's proposal, subject to the time constraint noted herein, must be made on the proposal forms contained in the project manual. The Bidder's authorized representative must sign the modification. The modification shall be placed in a sealed envelope and the statement "Modification to Proposal" shall be legibly marked in the upper left-hand corner. Withdrawal of a proposal may be made, subject to the time constraint noted herein, only with written confirmation under signature of the Bidder.

BID GUARANTEE. Each bid proposal must be accompanied by a Bid Guarantee, to be made payable to the Owner, in the amount of five percent (5%) of the Bidder's maximum Bid price (including alternates) and in the form of a certified check, cashier's check or bid bond issued by the Surety meeting the requirements of the General Provisions. The bid bond shall be from a responsible surety qualified to conduct business within the State of Kansas. A certified check shall be issued from a responsible and solvent bank or trust company. All forms of Bid guarantee must be delivered in original form. Facsimile transmissions of Bid guarantee documents will not be accepted.

SUBCONTRACTORS, ETC. Bidder must submit to Owner, as part of their Bid Form, a complete list of all Subcontractors and other persons and organizations (including those who will be furnishing the principal items of material and equipment) proposed to be used by the bidder to complete this project. Failure by the Bidder to provide this list with his bid shall render the bid nonresponsive. If requested by the Owner, the Successful Bidder shall submit to the Owner, in writing, an experience statement with pertinent information as to similar projects and other evidence of qualifications for each such Subcontractor, person and organization listed on the Bid Form. If Owner or Engineer, after due investigation, has reasonable objection to any proposed Subcontractor, other person or organization, either Owner or Engineer may before giving the award of contract, request the apparent Successful Bidder to submit an acceptable substitute without an increase in Bid Price. If the apparent Successful Bidder declines to make any such substitution, the contract shall not be awarded to such Bidder, but his declining to make any such substitution will not constitute grounds for sacrificing his Bid Guarantee. Any Subcontractor, other person or organization so listed and to whom Owner or Engineer does not make written objection prior to the giving the award of contract, will be deemed acceptable to Owner and Engineer. Substitutions to this list of acceptable Subcontractors and other persons and organizations after the apparent Successful Bidder has been awarded a contract by the Owner will not be allowed without the written approval of the Owner or Engineer.

No Contractor shall be required to employ any Subcontractor, other person or organization against whom he has reasonable objection.

The amount of the Work performed by Subcontractors in aggregate shall not exceed seventy (70) percent of the Total Bid. A contract will not be awarded to a bidder not in compliance with this requirement.

DISADVANTAGE BUSINESS ENTERPRISE (DBE). The requirements of 49 CFR Part 26, Regulations of the U.S. Department of Transportation, apply to this contract. It is the policy of the Metropolitan Topeka Airport Authority to practice nondiscrimination based on race, color, sex or national origin in the award or performance of this contract. All firms qualifying under this solicitation are encouraged to submit bids/proposals. Award of this contract will be conditioned upon satisfying the requirements of this bid specification. These requirements apply to all bidders, including those who qualify as a Disadvantaged Business Enterprise.

The Owner has established a DBE contract goal of **nine** (9) **percent** for this contract. The Bidder/Offeror shall make good faith efforts, as defined in Appendix A, 49 CFR Part 26, to subcontract **nine** (9) **percent** of the dollar value of the prime contract to certified DBE firms as defined in 49 CFR Part 26.

Instructions to Bidders ITB-4 of 10

All bidders shall submit the following information with their proposal on the forms provided:

The names and addresses of DBE firms that will participate in the contract,

A description of the work that each DBE firm will perform,

The dollar amount of the participation of each DBE firm participating,

Written documentation of the Bidder/Offeror's commitment to use a DBE subcontractor whose participation it submits to meet the contract goal.

Evidence of good faith efforts undertaken by the bidder, as described in appendix A to 49 CFR Part 26.

The successful Bidder will be required to provide written confirmation from the participating DBE firms verifying their intent to participate as in the project. This written confirmation shall be submitted along with the proposal documents as a condition of bid responsiveness.

GOOD FAITH EFFORTS (DBE). Bidder must demonstrate that they made good faith efforts to achieve participation with DBE firms. This requires that the bidder show that it took all necessary and reasonable steps to secure participation by certified DBE firms. Mere pro forma efforts will not be considered as a good faith effort.

Actions constituting evidence of good faith efforts are described in appendix A to 49 CFR Part 26. Such actions include but are not limited to:

- Soliciting DBE participation through all reasonable and available means. This may include public advertisements and phone calls/faxes to known certified DBE firms.
- Consult State Department of Transportation office to obtain a list of certified DBE firms.
- Selecting portions of work that increases the likelihood that DBE firms will be available to participate
- Providing DBE firms with sufficient information and time to review the project plans and specifications.
- Documenting all contacts with DBE firms. This includes name, address, phone number, date of contact and record of conversation/negotiation.

BIDDER QUALIFICATIONS. Each Bidder shall furnish the owner satisfactory evidence of their competency and financial capability to perform the proposed work. The Bidder shall demonstrate that they are a responsible firm that possesses the skills, abilities, and integrity to faithfully perform the project work. To be determined responsible, a prospective contractor must:

- Have adequate resources (financial, technical, etc.) to perform the contract, or the ability to obtain them.
- Have previous experience and evidence of authority to conduct business in the jurisdiction
 where the Project is located and evidence of Bidder's qualification to do business in the State of
 Kansas or covenant to obtain such qualification prior to award of the contract.
- Be able to comply with the required or proposed delivery or performance schedule, considering all existing business commitments.
- Have a satisfactory performance record.
- Have a satisfactory record of integrity and business ethics.
- Be otherwise qualified and eligible to receive an award under applicable laws and regulations.

Instructions to Bidders ITB-5 of 10

Evidence of competency shall consist of statements covering the Bidder's past experience on similar work, a listing of plant and equipment immediately available for use on the project, and a listing of key personnel that are available for the project. The listing for plant and equipment shall identify the type, the capacity and the present condition of the item.

Evidence of financial responsibility shall consist of a confidential statement or report of the Bidder's financial resources and liabilities as of the last calendar year. A public accountant must certify such statements and reports. If the Bidder is presently pre-qualified with the State Highway agency, evidence of this pre-qualification may serve as evidence of financial responsibility in lieu of the certified financial statements and reports.

STATE REGISTRATION OF OUT-OF-STATE CONTRACTORS. Bidders are advised that K.S.A. 79-1008, 79-1009 requires the registration of out-of-state contractors with the Director of Revenue for collection of tax.

NON-RESIDENT BIDDERS. Attention is directed to Section 16-113 and 16-114 of the Kansas Statutes Annotated which requires that any Non-Resident Contractor who undertakes the construction of any public improvement to be paid for out of public funds, must appoint in writing and file with the Kansas Secretary of State, some person (resident in Shawnee County, Kansas) on whom service may be had in any civil action which may arise out of such contractual relation.

ALTERNATE BIDS. Bidder shall complete all blanks provided on the proposal forms. When so permitted by the Owner, the Bidder shall legibly write the statement "No Bid" for those alternate bid options that the Bidder elects not to submit a proposal.

SUBMISSION OF BID PROPOSAL. Proposals shall be sent to arrive at the specified time and date for receipt of bids. Proposals received after the specified time will not receive consideration and will be returned unopened. Proposals shall be enclosed in a sealed opaque envelope. Each proposal shall be addressed to the office location identified in the Notice-to-bidders. The upper left-hand corner of the envelope shall be marked as follows:

CONTRACT PROPOSAL

Bid of {Insert Name of Bidder} Philip Billard Municipal Airport Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

To be opened at: 2:00 PM, March 20, 2025

BID OPENING. All proposals submitted prior to the stated time and date for receipt of bids will be publicly opened and read aloud by the Owner or the Owner's representative. Bidders, their authorized agents, and other interested parties are invited to attend. Proposals submitted after the stated time and date for receipt of bids will be automatically rejected without consideration and will be returned unopened.

EVALUATION OF PROPOSALS. Proposals may be held by the Owner, in his sole discretion, for purposes of review and evaluation by the Owner for a period not to exceed ninety (90) calendar days from the stated date for receipt of bids. The Owner will tabulate all bids and verify proper extension of unit costs. The Bidder shall honor their proposal for the duration of this period of review and evaluation. The bid guaranty will be held by the Owner until this period of review has expired or a contract has been formally executed.

BID INFORMALITIES AND IRREGULARITIES. The Owner reserves the right to waive any informality or irregularity discovered in any proposal, which in the owner's judgment best serves the Owner's interest. In the situation where an extension of a unit price is found to be incorrect, the stated

Instructions to Bidders ITB-6 of 10

unit price and correct extension will govern. In the event of a discrepancy between the written and numeral values, the written value shall take precedence.

IRREGULAR PROPOSALS. Proposals meeting the following criteria are subject to consideration as being irregular:

- If the proposal is on a form other than that furnished by the Owner or Owner's representative.
- If the form furnished by the Owner or Owner's representative is altered or detached from the original document.
- If there are unauthorized additions, conditional or alternate pay items or irregularities of any kind that make the proposal incomplete, indefinite, or otherwise ambiguous.
- If the proposal does not contain a unit price for each pay item listed in the proposal, except in the case of authorized pay items, for which the Bidder is not required to furnish a unit price.
- If the proposal contains unit prices that are obviously unbalanced.
- If the proposal is not accompanied by the bid guarantee specified herein.

DISQUALIFICATION OF BID PROPOSALS. The Owner reserves the right to reject any or all bids, as determined to be in the best interest of the Owner.

Causes for rejection of proposals include but are not limited to:

- Submittal of an irregular proposal.
- Submittal of more than one proposal from the same partnership, firm or corporation.
- Failure by Bidder to submit the bid prior to the stated time and date for receipt of bids.
- Failure by Bidder to furnish satisfactory bid guarantee.
- Failure by Bidder to provide all information required of the bid forms.
- Failure by Bidder to comply with the requirements of bid instructions.
- Failure by the Bidder to demonstrate good faith efforts in obtaining participation by certified DBE firms.
- Failure by the Bidder to conform to the Affirmative Action and Notification of DBE requirements shall be deemed non-responsive and will not be accepted.
- Determination by the Owner that Bidder is not qualified to accomplish the project work.
- Determination by the Owner that the Bidder has placed conditions on or qualified their proposal.
- Discovery of any alteration, interlineations or erasure of any project requirement by the Bidder.
- Inclusion of the Bidder on the "Excluded Parties Listing System" as maintained and published by the General Services Administration.
- Evidence of collusion among bidders.

MODIFICATION AND WITHDRAWAL OF BIDS. Bids may be modified or withdrawn by an appropriate document duly executed (in the manner that a Bid must be executed) and delivered to the place where Bids are to be submitted at any time prior to the opening of Bids.

If, within twenty-four hours after Bids are opened, any Bidder files a duly signed written notice with Owner and promptly thereafter demonstrates to the reasonable satisfaction of Owner that there was a

Instructions to Bidders ITB-7 of 10

material and substantial mistake in the preparation of his Bid, Owner may, at its sole discretion, allow that bidder to withdraw his Bid and the Bid Security will be returned.

CANCELLATION OF AWARD. At any time prior to execution of a contract agreement, the Owner reserves the right to cancel the award for any reason without liability to the Bidder, with the exception of the return of the bid guaranty, at any time prior to execution of the contract.

NOTICE OF AWARD OF CONTRACT. It is the intent of the Owner, after a period of review and evaluation, to award a contract to the responsible bidder that submits the lowest responsive proposal. The successful bidder will be informed their bid has been accepted through the Owner's issuance of a Notice-of-Award. The Notice-of-Award shall not be construed as a binding agreement. The proper execution of a contract agreement shall serve as the binding agreement.

FEDERAL FUNDING ASSISTANCE. It is the intent of the Owner to seek Federal participation assistance for this project under the Airport Improvement Program (AIP). Award of contract is conditioned upon the FAA concurring in award of contract and the owner securing Federal assistance. The issuance of the Notice-of-award will not be made until the FAA has concurred in award and Federal funding is confirmed.

AWARD OF ALTERNATES. Unless specifically stated, the Owner reserves the right to accept alternates in any order or combination, which in the judgment of the Owner, best serves the Owner's interest.

RETURN OF BID GUARANTY. The bid guaranty of the successful Bidder will be returned upon successful execution of the contract documents as specified herein. Failure by the successful Bidder to execute the contract documents within the specified time shall result in forfeiture of the bid guaranty. The bid guaranty of the second and third lowest responsible bidders will be retained for a period of ninety (90) days pending the execution of the contract documents by the successful bidder. Except as noted above, the bid guaranty of unsuccessful bidders will be returned at the point their proposal is rejected.

CONTRACT AGREEMENT. The successful Bidder shall execute the contract agreement in accordance with the accepted bid proposal within **thirty (30) days** of the date of the Notice-of-Award. Failure to execute the contract agreement within the specified time frame may result in the bid being awarded to the next low bidder and shall result in the forfeiture of the Bidder's bid guarantee as a liquidated damage.

CONTRACT TIME. The number of days within which or the date by which the Work is to be completed (the Contract Time) is set forth in the Agreement.

LIQUIDATED DAMAGES. Provisions for liquidated damages are set forth in the Agreement.

PERFORMANCE AND PAYMENT BONDS. The successful Bidder shall furnish separate performance and payment bonds each in the amount of 100% of the contract price. The bonds shall be made payable to the Owner as security for faithful performance of the contract and for the payment of all persons, firms or corporations to whom the Bidder may become legally indebted for labor, materials, tools, equipment or services in the performance of the project work. The form of the bond shall be that provided within the project manual. The current power of attorney for the person signing the bond as a representative of the surety shall be attached to the bonds.

The executed bonds shall be delivered to the Owner within fifteen (15) calendar days from the date of contract execution. Bonds should not be executed prior to execution of the contract agreement. The bonds shall be issued by a solvent Surety, which is certified to operate within the State the project work is located, and which is listed in the current issue of the U.S. Treasury Circular 570. If specifically requested by the Owner, the successful Bidder shall obtain and submit information on the surety's financial strength rating.

Instructions to Bidders ITB-8 of 10

SALES TAXES. For all projects, payment of Kansas State Sales Tax or Compensating (Use) tax is not necessary and should not be included in unit prices bid for materials to be incorporated in the work. The Metropolitan Topeka Airport Authority will furnish an exemption certificate (including exemption certificate number) obtained from the Sales and Compensating Tax Division of the Department of Revenue of the State of Kansas to the Contractor, Subcontractor or repairmen making purchases of any tangible personal property to be incorporated in this project. The Contractor, Subcontractor or repairmen must furnish all suppliers with a copy of the properly executed exemption certificate secured for this project. He may reproduce as many copies of the certificate as he may need.

CERTIFICATES OF INSURANCE. The successful Bidder shall furnish to the Owner all required certificates of insurance as specified with the project manual.

DBE AFFIRMATION. If not submitted with the proposal, the successful Bidder shall furnish, prior to execution of the contract agreement, written affirmation from each identified Disadvantaged Business Enterprise (DBE) firm of their intent to participate in the project.

APPROVAL OF THE CONTRACT. Upon receipt of the Contract Agreement, Contract Bonds and Certificate of Insurance as executed by the successful Bidder, the Owner will complete execution of the contract conditioned upon the Owner's judgment that it remains in their best interest to enter into the Agreement.

Delivery of the fully executed Contract Agreement to the successful Bidder shall constitute the Owner's approval to be bound by the successful Bidder's proposal and all terms and conditions of the Contract Agreement.

Upon satisfactory execution of the contract by the successful Bidder and the Owner, all references to "Bidder" in the bid documents become equivalent to the term "Contractor".

STANDARD TECHNICAL SPECIFICATIONS. This project shall be subject to the applicable Advisory Circulars (latest edition) of the Federal Aviation Administration with any addenda thereto, except as modified or supplemented by specifications contained in this Project Manual.

END OF INSTRUCTIONS TO BIDDERS

Instructions to Bidders ITB-9 of 10

THIS PAGE INTENTIONALLY LEFT BLANK

Instructions to Bidders ITB-10 of 10

PROPOSAL FORM

METROPOLITAN TOPEKA AIRPORT AUTHORITY TERMINAL APRON REHABILITATION PHILIP BILLARD MUNICIPAL AIRPORT TOPEKA, KANSAS AIP PROJECT NO. 3-20-0082-027 **BIL-AIG PROJECT NO. 3-20-0082-028**

TO: Metropolitan Topeka Airport Authority

6510 SE Forbes Avenue, Suite # 1

Topeka, Kansas 66619

AIP Project No.: 3-20-0082-027

BIL-AIG Project No. 3-20-0028-028

Description: Terminal Apron Rehabilitation, Philip Billard Municipal Airport, Topeka, Kansas.

The undersigned Bidder, in compliance with the request for bids for construction of the above mentioned Project, hereby proposes and agrees, if this Bid is accepted, to enter into an agreement with the Owner in the form included in the contract Documents to furnish all labor, permits, material, machinery, tools, supplies and equipment to faithfully perform all work as specified or indicated in the Bid Documents in accordance with the project manual, project drawings and issued Addenda within the specified time of performance for the following prices:

Item No.	Description	Unit	Quantity	Unit Price	Extension
C-102-5.1	Temporary Erosion Control	LS	1		
C-105-6.1	Mobilization	LS	1		
C-106-4.1	Traffic Control	LS	1		
P-101-5.1	Joint and Crack Repair	LF	23,240		
P-101-5.2	Cold Milling (0"-3")	SY	11,885		
P-101-5.3	Tie-Down Abandonment Type 1	EA	5		
P-101-5.4	Tie-Down Abandonment Type 2	EA	32		
P-152-5.5	Pavement Patching	SY	580		
P-152-4.1	Unclassified Excavation	CY	200		

Proposal Form PF-1 of 10

Item No.	Description	Unit	Quantity	Unit Price	Extension
P-401-8.1	Asphalt Mix Pavement - Overlay	TON	1,300		
P-603-5.1	Emulsified Asphalt Tack Coat	GAL	840		
P-615-5.1	Aircraft Tie Down	EA	6		
P-620-5.1	Pavement Marking Removal	SF	170		
P-620-5.2	Temporary Pavement Marking (Yellow)	SF	850		
P-620-5.3	Reflectorized Pavement Marking (Yellow)	SF	1,100		
P-620-5.4	Non-Reflectorized Pavement Marking (Black)	SF	1,685		
P-629-8.1	Thermoplastic Coal Tar Emulsion Sand Slurry Seal	SY	11,405		
T-901-5.1	Permanent Seeding & Mulching	SY	400		

TOTAL BASE BID (Numeral Format) \$
TOTAL BASE BID (Word Format)

Proposal Form PF-2 of 10

ACKNOWLEDGEMENTS BY BIDDER

- a. By submittal of a proposal, the BIDDER acknowledges and accepts that the quantities established by the OWNER are an approximate estimate of the quantities required to fully complete the Project and that the estimated quantities are principally intended to serve as a basis for evaluation of bids. The BIDDER further acknowledges and accepts that payment under this contract will be made only for actual quantities and that quantities will vary in accordance with the General Provisions subsection entitled "Alteration of Work and Quantities".
- b. The BIDDER acknowledges and accepts that the Bid Documents are comprised of the documents identified within the Instructions to Bidders, including without limitation those dealing with the disposition of Bid guarantee. The BIDDER further acknowledges that each of the individual documents that comprise the Bid Documents are complementary to one another and together establishes the complete terms, conditions and obligations of the successful BIDDER.
- c. As evidence of good faith in submitting this proposal, the undersigned encloses a bid guaranty in the form of a certified check, cashier's check or bid bond in the amount of 5% of the bid price. The BIDDER acknowledges and accepts that refusal or failure to accept award and execute a contract within the terms and conditions established herein will result in forfeiture of the bid guaranty to the owner as a liquidated damage.
- d. The BIDDER acknowledges and accepts the OWNER'S right to reject any or all bids and to waive any minor informality in any Bid or solicitation procedure.
- e. The BIDDER acknowledges and accepts the OWNER'S right to hold all Proposals for purposes of review and evaluation and not issue a notice-of-award for a period not to exceed **ninety** (90) days from the stated date for receipt of bids.
- f. The undersigned agrees that upon written notice of award of contract, he or she will execute the contract within **thirty** (30) **days** of the notice-of-award and furthermore, provide executed payment and performance bonds within **fifteen** (15) **days** from the date of contract execution. The undersigned accepts that failure to execute the contract and provide the required bonds within the stated timeframe shall result in forfeiture of the bid guaranty to the owner as a liquidated damage.
- g. By submittal of this proposal, the undersigned acknowledges and agrees to commence work within ten (10) calendar days of the date specified in the written "Notice-to-Proceed" as issued by the OWNER. The anticipated date that project work may commence is on or about **June 2, 2025.** The undersigned further agrees to complete the Project within **90** Calendar Days from the Notice-to-Proceed.
- h. The bidder acknowledges and accepts that for each and every Calendar Day the project remains incomplete beyond the contract time of performance, the substantial completion date, or not open to traffic as stipulated in the preceding paragraphs of this section, the CONTRACTOR shall pay the non-penal amount of \$1,500.00 per calendar day as a liquidated damage to the OWNER.
- i. The BIDDER acknowledges that the OWNER has established a contract Disadvantaged Business Enterprise goal of **nine (9) percent** for this project. The BIDDER acknowledges and accepts the requirement to apply and document good faith efforts, as defined in Appendix A, 49 CFR Part 26, for subcontracting a portion of the prime contract to certified Disadvantaged Business Enterprises (DBE), as defined in 49 CFR Part 26 for purposes of meeting the OWNER'S established goal. The BIDDER, in complying with this requirement, proposes participation by Disadvantaged Business Enterprises as stated on the attached forms, "Utilization Statement" and "Letter of Intent".

Proposal Form PF-3 of 10

j. The BIDDER, by submission of a proposal, acknowledges that award of this contract is subject to the provisions of the Davis-Bacon Act. The BIDDER accepts the requirement to pay prevailing wages for each classification and type of worker as established in the attached wage rate determination as issued by the United States Department of Labor. The BIDDER further acknowledges and accepts their requirement to incorporate the provision to pay the established prevailing wages in every subcontract agreement entered into by the Bidder under this project.

Compliance Reports (41 CFR Part 60-1.7): Within 30 days after award of this contract, the Contractor/Subcontractor shall file a compliance report (Standard Form 100) if s/he has not submitted a complete compliance report within 12 months preceding the date of award. This report is required if the Contractor/Subcontractor meets all of the following conditions:

- 1. Contractors/Subcontractors are not exempt based on 41 CFR 60-1,5.
- 2. Has 50 or more employees.
- 3. Is a prime contractor or first tier subcontractor.
- 4. There is a contract, subcontract, or purchase order amounting to \$50,000 or more
- k. The undersigned acknowledges receipt of the following addenda:

Addendum Number dated	Received
Addendum Number dated	Received
Addendum Number dated	Received

REPRESENTATIONS BY BIDDER

By submittal of a proposal (bid), the BIDDER represents the following:

- a. The BIDDER has read and thoroughly examined the bid documents including all authorized addenda.
- b. The BIDDER has obtained and carefully studied (or assumes responsibility for obtaining and carefully studying) all such examinations, investigations, explorations, tests and studies (in addition to or to supplement these referred to in (c) above) which pertain to the subsurface or physical conditions at the site or otherwise may affect the cost, progress, performance or furnishing of the Work as Bidder considers necessary for the performance or furnishing of the Work at the Contract Price, within the Contract Time and in accordance with the other terms and conditions of the Contract Documents; and no additional examinations, investigations, explorations, tests, reports or similar information or data are or will be required by Bidder for such purposes.
- c. The BIDDER has reviewed and checked all information and data shown or indicated on the Contract Documents with respect to existing Underground Facilities at or contiguous to the site and assumes responsibility for the accurate location of said Underground Facilities. No additional examinations, investigations, explorations, tests, reports or similar information or data in respect of said Underground Facilities are or will be required by Bidder in order to perform and furnish the Work at the Contract Price, within the Contract Time and in accordance with the other terms and conditions of the Contract Documents.
- d. The BIDDER has correlated the results of all such observations, examinations, investigations, explorations, tests, reports and studies with the terms and conditions of the Contract Documents.
- e. The BIDDER has given the Engineer written notice of all conflicts, errors, or discrepancies that it has discovered in the Contract Documents and the written resolution thereof by Engineer is acceptable to Bidder.
- f. The BIDDER has a complete understanding of the terms and conditions required for the satisfactory performance of project work.

Proposal Form PF-4 of 10

- g. The BIDDER has fully informed themselves of the project site, the project site conditions and the surrounding area.
- h. The BIDDER has familiarized themselves of the requirements of working on an operating airport and understands the conditions that may in any manner affect cost, progress, or performance of the work
- i. The BIDDER has correlated their observations with that of the project documents.
- j. The BIDDER has found no errors, conflicts, ambiguities, or omissions in the project documents, except as previously submitted in writing to the owner that would affect cost, progress or performance of the work.
- k. The BIDDER is familiar with all applicable Federal, State, and local laws, rules and regulations pertaining to execution of the contract and the project work that may in any manner affect cost, progress or performance of the work.
- 1. The BIDDER has complied with all requirements of these instructions and the associated project documents.
- m. This BID is genuine and not made in the interest of or on behalf of any undisclosed person, firm or corporation and is not submitted in conformity with any agreement or rules of any group, association, organization or corporation; Bidder has not directly or indirectly induced or solicited any other Bidder to submit a false or sham Bid; Bidder has not solicited or induced any person, firm or corporation to refrain from bidding; and Bidder has not sought by collusion to obtain for itself any advantage over any other bidder or over Owner.

CERTIFICATIONS BY BIDDER

- a. The undersigned hereby declares and certifies that the only parties interested in this proposal are named herein and that this proposal is made without collusion with any other person, firm or corporation. The undersigned further certifies that no member, officer, or agent of OWNER'S has direct or indirect financial interest in this proposal.
- b. Certification of Non-Segregated Facilities: (41 CFR Part 60-1.8) The BIDDER, as a potential federally assisted construction contractor, certifies that it does not maintain or provide, for its employees, any segregated facilities at any of its establishments and that it does not permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. The BIDDER certifies that it will not maintain or provide, for its employees, segregated facilities at any of its establishments and that it will not permit its employees to perform their services at any location under its control where segregated facilities are maintained. The Bidder agrees that a breach of this certification is a violation of the Equal Opportunity Clause, which is to be incorporated in the contract.

As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms, and washrooms, restaurants and other eating areas, timeclocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated on the basis of race, color, religion, or national origin because of habit, local custom, or any other reason. The Bidder agrees that (except where it has obtained identical certifications from proposed subcontractors for specific time periods) it will obtain identical certifications from proposed subcontractors prior to the award of subcontracts exceeding \$10,000 which are not exempt from the provisions of the Equal Opportunity Clause and that it will retain such certifications in its files.

Proposal Form PF-5 of 10

c. **Trade Restriction Certification:** (49 CFR Part 30)

The Bidder, by submission of an offer certifies that it:

- 1. is not owned or controlled by one or more citizens of a foreign country included in the list of countries that discriminate against U.S. firms published by the Office of the United States Trade Representative (USTR).
- 2. has not knowingly entered into any contract or subcontract for this project with a person that is a citizen or national of a foreign country on said list, or is owned or controlled directly or indirectly by one or more citizens or nationals of a foreign country on said list.
- 3. has not procured any product nor subcontracted for the supply of any product for use on the project that is produced in a foreign country on said list.
- d. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion: (49 CFR Part 29) The Bidder certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency. It further agrees by submitting this proposal that it will include this clause without modification in all lower tier transactions, solicitations, proposals, contracts, and subcontracts. Where the Bidder or any lower tier participant is unable to certify to this statement, it shall attach an explanation to this solicitation/proposal.
- e. **Buy American Certification:** (Title 49 U.S.C. Chapter 501) As a condition of bid responsiveness, the bidder must certify its compliance with the Buy American preferences established under Title 49 U.S.C. Section 50101. Bidders must complete the Buy American certification that is attached to this proposal form.

ATTACHMENTS TO THIS BID

The following documents are attached to and made a part of this Bid:

- 1. Bid Guaranty in the form of _____;
- 2. Completed DBE forms "Utilization Statement" and "Letter of Intent".
- 3. Evidence of good faith efforts required by 49 CFR Part 26, Appendix A. If proposed DBE goal is met, submittal of evidence of good faith efforts is not required.
- 4. Evidence of BIDDER'S qualifications per the requirements of the Instructions-to-Bidders.
- 5. Buy American Certification.

Proposal Form PF-6 of 10

SIGNATURE OF BIDDER

IF AN INDIVIDUAL:		
Name:		_
By:		_
	(Signature of Individual)	
Doing Business as:		_
Business Address:		_
		_
Telephone Number:		_
IF A PARTNERSHIP:		
Partnership Name:		_
By:		
	(Authorized Signature) (Attach Evidence of Authority to sign as a Partn	ership)
Name and Title:		- '
		_
T 1 1 N 1		_
Telephone Number:		
IF A CORPORATION:		
Corporation Name:		_
By:	(And print I Simulation)	
	(Authorized Signature) (Attach Evidence of Authority to sign)	
Name and Title:		_
Business Address:		_
Telephone Number:		- CORPORATE SEAL)
ATTEST:		
By:		_
	(Authorized Signature)	
Name and Title:		_

Proposal Form PF-7 of 10

Joint Venture Name: _	
Ву: _	
	(Authorized Signature) (Attach Evidence of Authority to sign)
Name and Title: _	
Business Address: _	
Telephone Number: _	
oint Venture Name: _	
Ву: _	
	(Authorized Signature) (Attach Evidence of Authority to sign)
Name and Title: _	
Business Address: _	
_	

Proposal Form PF-8 of 10

Project Number	: AIP 3-20-0082-027, BIL-AIG 3-20)-0082-028	
Contractor's Na	me:		
	List of Subcon	tractors	
Subcontractors, subcontractors for of Work as is contractors.	Etc., in the Instructions to Bidders or the same work. The Contractor shall defined by the Contractor in his bid.	on in accordance with the provisions of particle for ALL Subcontractors. Do not list a list only one subcontractor for each such Contractor shall not substitute any per except as provided in paragraph Subcont	lternate portion rson as
performed under he shall be deeme	the contract or specifies more than one ed to have agreed that he is fully qualified to sublet or subcontract that portion	abcontractor for any portion of the Work e subcontractor for the same portion of the ed to perform that portion himself and that had of the Work, except as provided in part	e Work, he shall
Subcontractor:			
Amount:	(mondo)	(\$)
	(words)		
Subcontractor:		(4)	
Amount:	(words)	(\$)
0.1			
Subcontractor: Amount:		(\$)
	(words)		
Subcontractor:			
Amount:		(\$)
	(words)		
Subcontractor:			
Amount:		(\$)
	(words)		
Subcontractor:			
Amount:		(\$)
	(words)		
Subcontractor:			
Amount:	(words)	(\$)
	(words)		

Proposal Form PF-9 of 10

THIS PAGE INTENTIONALLY LEFT BLANK

Proposal Form PF-10 of 10

CERTIFICATE OF BUY AMERICAN COMPLIANCE FOR TOTAL FACILITY

PROJECT NAME:	Terminal Apron Rehabilitation
AIRPORT NAME:	Philip Billard Municipal Airport
AIP NUMBER:	3-20-0082-027-2025
BIL-AIG NUMBER	3-20-0082-028-2025

As a matter of bid responsiveness, the bidder or offeror must complete, sign, date, and submit this certification statement with its proposal. The bidder or offeror must indicate how it intends to comply with 49 USC § 50101 by selecting one of the following certification statements. These statements are mutually exclusive. Bidder must select one or the other (i.e. not both) by inserting a checkmark (\checkmark) or the letter "X".

- ☐ Bidder or offeror hereby certifies that it will comply with 49 USC § 50101 by:
 - a) Only installing steel and manufactured products produced in the United States; or
 - b) Installing manufactured products for which the Federal Aviation Administration (FAA) has issued a waiver as indicated by inclusion on the current FAA Nationwide Buy American Waivers Issued listing; or
 - c) Installing products listed as an Excepted Article, Material or Supply in Federal Acquisition Regulation Subpart 25.108.

By selecting this certification statement, the bidder or offeror agrees:

- To provide to the Owner evidence that documents the source and origin of the steel and manufactured product.
- To faithfully comply with providing U.S. domestic products.
- To refrain from seeking a waiver request after establishment of the contract, unless extenuating circumstances emerge that the FAA determines justified.
- The bidder or offeror hereby certifies it cannot comply with the 100 percent Buy American Preferences of 49 USC § 50101(a) but may qualify for either a Type 3 or Type 4 waiver under 49 USC § 50101(b). By selecting this certification statement, the apparent bidder or offeror with the apparent low bid agrees:
 - a) To the submit to the Owner within 15 calendar days of the bid opening, a formal waiver request and required documentation that supports the type of waiver being requested.
 - b) That failure to submit the required documentation within the specified timeframe is cause for a non-responsive determination that may result in rejection of the proposal.
 - c) To faithfully comply with providing U.S. domestic products at or above the approved U.S. domestic content percentage as approved by the FAA.
 - d) To furnish U.S. domestic product for any waiver request that the FAA rejects.
 - e) To refrain from seeking a waiver request after establishment of the contract, unless extenuating circumstances emerge that the FAA determines justified.

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

Required Documentation

Type 3 Waiver – The cost of components and subcomponents produced in the United States is more than 60 percent of the cost of all components and subcomponents of the "facility". The required documentation for a Type 3 waiver is:

- a) Listing of all manufactured products that are not comprised of 100 percent U.S. domestic content (excludes products listed on the FAA Nationwide Buy American Waivers Issued listing and products excluded by Federal Acquisition Regulation Subpart 25.108; products of unknown origin must be considered as non-domestic products in their entirety).
- b) Cost of non-domestic components and subcomponents, excluding labor costs associated with final assembly and installation at project location.
- c) Percentage of non-domestic component and subcomponent cost as compared to total "facility" component and subcomponent costs, excluding labor costs associated with final assembly and installation at project location.

Type 4 Waiver – Total cost of project using U.S. domestic source product exceeds the total project cost using non-domestic product by 25 percent. The required documentation for a Type 4 of waiver is:

- a) Detailed cost information for total project using U.S. domestic product
- b) Detailed cost information for total project using non-domestic product

False Statements: Per 49 USC § 47126, this certification concerns a matter within the jurisdiction of the Federal Aviation Administration and the making of a false, fictitious or fraudulent certification may render the maker subject to prosecution under Title 18, United States Code.

Date	Signature	
Company Name	Title	

UTILIZATION STATEMENT

Disadvantage Business Enterprise

	ng manner. (Please mark the appropriate box)
	The bidder/offeror is committed to a minimum of% DBE utilization on this contract.
	The bidder/offeror, while unable to meet the DBE contract goal of%, hereby commits to a minimum of% DBE utilization on this contract and submits the attached documentation as evidence demonstrating good faith efforts (GFE) in seeking participation by certified DBE firms.
and that to perfo further	dersigned hereby further assures that the information included herein is true and correct, the DBE firm or firms identified within the submitted Letter-of-Intent forms have agreed orm a commercially useful function for the indicated work elements. The undersigned understands that no changes to this statement may be made without prior approval from ner and the Federal Aviation Administration
Bidder's/C	Offeror's Firm Name
Signature	Date

DBE UTILIZATION SUMMARY

	Contract Amount		DBE Amount	Contract
<u>Percentage</u>				
DBE Prime Contractor	\$	x 1.00 =	\$	%
DBE Subcontractor	\$	x 1.00 =	\$	%
DBE Supplier	\$	x 0.60 =	\$	%
DBE Manufacturer	\$	x 1.00 =	\$	%
Total Amount DBE DBE Goal			\$ \$	% %

Note: If the total proposed DBE participation is less than the established DBE goal, Bidder must provide written documentation of the good faith efforts as required by 49 CFR Part 26.

THIS PAGE INTENTIONALLY LEFT BLANK

LETTER OF INTENT

Disadvantage Business Enterprise

(This page shall be submitted for each DBE firm)

Bidder/Offer	Name:		
	Address:		
	City:	State:	Zip:
DBE Firm:	DBE Firm <u>:</u>		
	Address:		
	City:		
DBE Contact Person:	Name:	Phone:	()
DBE Certifying Agency		•	te:
	Each DBE Firm shall submit certification status.	evidence (such as a pho	otocopy) of their
_		Subcontractor Supplier	□Joint Venture
Work item(s) to be performed by DBE	Description of Work Item	Quantity	Total
The bidder/offeror is committed participation is as for	ed to utilizing the above-named DE ollows:	E firm for the work desc	cribed above. The
OBE contract amount: \$		Percent of total contrac	t:%
AFFIRMATION: The above-named DBE firm tated above.	affirms that it will perform the port	ion of the contract for the	ne estimated dollar value a
By:			
	bidder/offeror does not receive		ie contract any and a
	his Letter of Intent and Affirmati		

THIS PAGE INTENTIONALLY LEFT BLANK

Form of CONTRACT AGREEMENT

METROPOLITAN TOPEKA AIRPORT AUTHORITY TERMINAL APRON REHABILITATION PHILIP BILLARD MUNICIPAL AIRPORT TOPEKA, KANSAS AIP PROJECT NO. 3-20-0082-027 BIL-AIG PROJECY NO. 3-20-0082-028

THIS AGREEMENT, made as of		, 2025 is
BY AND BETWEEN		
The OWNER:	Metropolitan Topeka Airport Authority 6510 SE Forbes Avenue, Suite # 1 Topeka, KS 66619	
And the CONTRACT	OR:	

WITNESSETH:

WHEREAS it is the intent of the Owner to make improvements at Topeka Regional Airport generally described as follows: **Terminal Apron Rehabilitation**, **Pilip Billard Municipal Airport**, **Topeka**, **Kansas**, **AIP 3-20-0082-027**, **BIL-AIG 3-20-0082-028**, hereinafter referred to as the "Project".

NOW THEREFORE in consideration of the mutual covenants hereinafter set forth, OWNER and CONTRACTOR agree as follows:

Article 1 - Work

It is hereby mutually agreed that for and in consideration of the payments as provided for herein to the CONTRACTOR by the OWNER, CONTRACTOR shall faithfully furnish all necessary labor, equipment, and material and shall fully perform all necessary work to complete the Project in strict accordance with this Contract Agreement and the Contract Documents.

Article 2 – Contract Documents

CONTRACTOR agrees that the Contract Documents consist of the following: this Agreement, General Provisions, Supplementary Provisions, Specifications, Drawings, all issued addenda, Notice-to-Bidders, Instructions-to-Bidders, Proposal and associated attachments, Performance Bond, Payment Bond, Wage Rate Determination, Insurance certificates, Equal Opportunity and Affirmative Action Plan, documents incorporated by reference, documents incorporated by attachment, and all OWNER authorized change orders issued subsequent to the date of this agreement. All documents comprising the Contract Documents are complementary to one another and together establish the complete terms, conditions and obligations of the CONTRACTOR. All said Contract Documents are incorporated by reference into the Contract Agreement as if fully rewritten herein or attached thereto.

Contract Agreement CA-1 of 6

Article 3 – Contract Price

In consideration of the faithful performance and completion of the Work by the CONTRACTOR in accordance with the Contract Documents, OWNER shall pay the CONTRACTOR an amount equal to:

\$	 	
(Amount in Written Words)		
(Amount in Written Words) (\$)		

subject to the following:

- a. Said amount is based on the schedule of prices and estimated quantities stated in CONTRACTOR'S Bid Proposal, which is attached to and made a part of this Agreement;
- b. Said amount is the aggregate sum of the result of the CONTRACTOR'S stated unit prices multiplied by the associated estimated quantities;
- c. CONTRACTOR and OWNER agree that said estimated quantities are not guaranteed and that the determination of actual quantities is to be made by the OWNER'S ENGINEER;
- d. Said amount is subject to modification for additions and deductions as provided for within the Contract General Provisions.

Article 4 - Payment

Upon the completion of the work and its acceptance by the OWNER, all sums due the CONTRACTOR by reason of faithful performance of the work, taking into consideration additions to or deductions from the Contract price by reason of alterations or modifications of the original Contract or by reason of "Extra Work" authorized under this Contract, will be paid to the CONTRACTOR by the OWNER after said completion and acceptance.

The acceptance of final payment by the CONTRACTOR shall be considered as a release in full of all claims against the OWNER, arising out of, or by reason of, the work completed and materials furnished under this Contract.

OWNER shall make progress payments to the CONTRACTOR in accordance with the terms set forth in the General Provisions. Progress payments shall be based on estimates prepared by the ENGINEER for the value of work performed and materials completed in place in accordance with the Contract Drawings and Specifications.

Progress payments are subject to retainage requirements as set forth in the General Provisions.

Contract Agreement CA-2 of 6

Article 5 – Contract Time

The CONTRACTOR agrees to commence and to have the project substantially completed within 120 Calendar Days of the Notice-to-Proceed.

It is expressly understood and agreed that the stated Contract Time is reasonable for the completion of the Work, taking all factors into consideration. Furthermore, extensions of the Contract Time may only be permitted by execution of a formal modification to this Contract Agreement in accordance with the General Provisions and as approved by the OWNER.

Article 6 – Liquidated Damages

The undersigned acknowledges and accepts that for each and every Calendar Day the project remains incomplete beyond the contract time of performance, the substantial completion date, or not open to traffic as stipulated in the preceding paragraphs of this section, the CONTRACTOR shall pay the non-penal amount of \$1,500.00 per calendar day as a liquidated damage to the OWNER.

Furthermore, the CONTRACTOR understands and agrees that.

- a. the OWNER has the right to deduct from any moneys due the CONTRACTOR, the amount of said liquidated damages,
- b. the OWNER has the right to recover the amount of said liquidated damages from the CONTRACTOR, SURETY or both.

Article 7 – CONTRACTOR'S Representations

The CONTRACTOR understands and agrees that all representations made by the CONTRACTOR within the Proposal shall apply under this Agreement as if fully rewritten herein.

Article 8 – CONTRACTOR'S Certifications

The CONTRACTOR understands and agrees that all certifications made by the CONTRACTOR within the Proposal shall apply under this Agreement as if fully rewritten herein. The CONTRACTOR further certifies the following;

- a. <u>Certification of Eligibility</u> (29 CFR Part 5.5)
 - i. By Entering into this contract, the CONTRACTOR certifies that neither he or she nor any person or firm who has an interest in the CONTRACTOR'S firm is a person or firm ineligible to be awarded Government contracts by virtue of Section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1);
 - ii. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of Section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1);
 - iii. The penalty for making false statements is prescribed in the U.S. Criminal Code 18 U.S.C.
- b. <u>Certification of Non-Segregated Facilities</u> (41 CFR Part 60-1.8)

The federally assisted construction CONTRACTOR, certifies that it <u>does not</u> maintain or provide, for its employees, any segregated facilities at any of its establishments and that it does not permit its employees to perform their services at any location, under its control,

Contract Agreement CA-3 of 6

where segregated facilities are maintained. The BIDDER certifies that it <u>will not</u> maintain or provide, for its employees, segregated facilities at any of its establishments and that it will not permit its employees to perform their services at any location under its control where segregated facilities are maintained. The Bidder agrees that a breach of this certification is a violation of the Equal Opportunity Clause, which is to be incorporated in the contract.

As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms, and washrooms, restaurants and other eating areas, timeclocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are

segregated on the basis of race, color, religion, or national origin because of habit, local custom, or any other reason. The Bidder agrees that (except where it has obtained identical certifications from proposed subcontractors for specific time periods) it will obtain identical certifications from proposed subcontractors prior to the award of subcontracts exceeding \$10,000 which are not exempt from the provisions of the Equal Opportunity Clause and that it will retain such certifications in its files.

Article 9 – Miscellaneous

- a. CONTRACTOR understands that it shall be solely responsible for the means, methods, techniques, sequences and procedures of construction in connection with completion of the Work,
- b. CONTRACTOR understands and agrees that it shall not accomplish any work or furnish any materials that are not covered or authorized by the Contract Documents unless authorized in writing by the OWNER or ENGINEER,
- c. The rights of each party under this Agreement shall not be assigned or transferred to any other person, entity, firm or corporation without prior written consent of both parties,
- d. OWNER and CONTRACTOR each bind itself, their partners, successors, assigns and legal representatives to the other party in respect to all covenants, agreements, and obligations contained in the Contract Documents.
- e. All equipment and materials furnished and installed under this section shall be guaranteed against defects in materials and workmanship for a period of at least twelve (12) months from final acceptance by the Owner. The defective materials and/or equipment shall be repaired or replaced, at the Owner's discretion, with no additional cost to the Owner.

Article 10 – OWNER'S Representative

The OWNER'S Representative, herein referred to as ENGINEER, and is defined as follows:

Sam Stallbaumer, PE, Project Manager WSP USA 300 Wyandotte, Suite 200 Kansas City, Missouri 64105

TEL: 816-72-4244 MOB: 210-867-6532

E-Mail: sam.stallbaumer@wsp.com

Contract Agreement CA-4 of 6

Said ENGINEER will act as the OWNER'S representative and shall assume all rights and authority assigned to the ENGINEER as stated within the Contract Documents in connection with the completion of the Project Work.

IN WITNESS WHEREOF, OWNER and CONTRACTOR have executed five (5) copies of this Agreement on the day and year first noted herein.

JWNEK	CONTRACTOR
Name: Metropolitan Topeka Airport Authority	Name:
Address: 6510 SE Forbes Avenue, Suite 1 Topeka, Kansas 66619	Address:
By:	By:
President & Director of Airports Title of Representative	Title of Representative
ATTEST	ATTEST
By:	By: Signature:
Title: Director of Administration & Finance	Title:

Contract Agreement CA-5 of 6

Project Number:	AIP 3-20-0082-027-2025 BIL-AIG 3-20-0082-027-2025
Contractor's Name:	

List of Subcontractors

The Bidder is required to furnish the following information in accordance with the provisions of the Instructions to Bidders for <u>ALL</u> Subcontractors. Do not list alternate subcontractors for the same work. The Contractor shall list only one subcontractor for each such portion of Work as is defined by the Contractor in his bid. Contractor shall not substitute any person as subcontractor in the place of a subcontractor listed below, except as provided in the Instruction to Bidders.

The Bidder understands that if he fails to specify a subcontractor for any portion of the Work to be performed under the contract or specifies more than one subcontractor for the same portion of the Work, he shall be deemed to have agreed that he is fully qualified to perform that portion himself and that he shall not be permitted to sublet or subcontract that portion of the Work, except as provided in the Instruction to Bidders.

Subcontractor:			
Amount:		(\$)
	(words)		
Subcontractor:			
Amount:		(\$)
	(words)		
Subcontractor:			
Amount:		(\$)
	(words)		
Subcontractor:			
Amount:		(\$)
	(words)		
Subcontractor:			
Amount:		(\$)
	(words)		
Subcontractor:			
Amount:		(\$)
	(words)		

Contract Agreement CA-6 of 6

Performance Bond

Any singular reference to Contractor, Surety, Owner of other party shall be considered plural where applicable. SURETY (Name and Address of Principal Place of CONTRACTOR (Name and Address): Business): OWNER (Name and Address): Metropolitan Topeka Airport Authority 6510 SE Forbes Avenue, Suite 1 Topeka, KS 66619 **CONTRACT** Date: Amount: AIP 3-20-0082-027 Description (Name and Location): BIL-AIG 3-20-0082-028 Terminal Apron Rehabilitation Philip Billard Municipal Airport **BOND** Date (Not earlier than Contract Date): Amount: Modifications to this Bond Form: Surety and Contractor, intending to be legally bound hereby, subject to the terms printed on the reverse side hereof, do each cause this Performance Bond to be duly executed on its behalf by its authorized officer, agent or representative. CONTRACTOR AS PRINCIPAL **SURETY** Company: (Corp. Seal) Company: (Corp. Seal) Signature: _ Signature: _ Name and Title: Name and Title: (Attach Power of Attorney) (Space is provided below for signatures of additional parties, if required.) CONTRACTOR AS PRINCIPAL **SURETY** Company: (Corp. Seal) Company: (Corp. Seal) Signature: -Signature: -Name and Title: Name and Title: EJCDC No. 1910-28-A (1996 Edition) Originally prepared through the joint efforts of the Surety Association of America, Engineers Joint Contract Documents Committee, the Associated General Contractors of America, and the American Institute of Architects.

Performance Bond PB-1 of 6

THIS PAGE INTENTIONALLY LEFT BLANK

Performance Bond PB-2 of 6

Metropolitan Topeka Airport Authority Philip Billard Municipal Airport

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

- 1. The CONTRACTOR and the Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Owner for the performance of the Contract, which is incorporated herein by reference.
- 2. If the CONTRACTOR performs the Contract, the Surety and the CONTRACTOR have no obligation under this Bond, except to participate in conferences as provided in paragraph 3.1.
- 3. If there is no OWNER Default, the Surety's obligation under this Bond shall arise after:
- 3.1. The OWNER has notified the CONTRACTOR and the Surety at the addresses described in paragraph 10 below, that the OWNER is considering declaring a CONTRACTOR Default and has requested and attempted to arrange a conference with the CONTRACTOR and the Surety to be held not later than fifteen days after receipt of such notice to discuss methods of performing the Contract. If the OWNER, the CONTRACTOR and the Surety agree, the CONTRACTOR shall be allowed a reasonable time to perform the Contract, but such an agreement shall not waive the OWNER's right, if any, subsequently to declare a CONTRACTOR Default; and
- 3.2. The OWNER has declared a CONTRACTOR Default and formally terminated the CONTRACTOR's right to complete the Contract. Such CONTRACTOR Default shall not be declared earlier than twenty days after the CONTRACTOR and Surety have received notice as provided in paragraph 3.1; and
 - 3.3. The OWNER has agreed to pay the Balance of the Contract Price to:
 - 3.3.1. The Surety in accordance with the terms of the Contract;
- 3.3.2. Another contractor selected pursuant to paragraph 4.3 to perform the Contract.
- 4. When the OWNER has satisfied the conditions of paragraph 3, the Surety shall promptly and at the Surety's expense take one of the following actions:
- 4.1. Arrange for the CONTRACTOR, with consent of the OWNER, to perform and complete the Contract; or
- 4.2. Undertake to perform and complete the Contract itself, through its agents or through independent contractors; or
- 4.3. Obtain bids or negotiated proposals from qualified contractors acceptable to the OWNER for a contract for performance and completion of the Contract, arrange for a contract to be prepared for execution by the OWNER and the contractor selected with the OWNER's concurrence, to be secured with performance and payment bonds executed by a qualified surety equivalent to the Bonds issued on the Contract, and pay to the OWNER the amount of damages as described in paragraph 6 in excess of the Balance of the Contract Price incurred by the OWNER resulting from the CONTRACTOR Default; or
- 4.4. Waive its right to perform and complete, arrange for completion, or obtain a new contractor and with reasonable promptness under the circumstances:
- 4.4.1. After investigation, determine the amount for which it may be liable to the OWNER and, as soon as practicable after the amount is determined, tender payment therefor to the OWNER; or
- 4.4.2. Deny liability in whole or in part and notify the OWNER citing reasons therefor.
- 5. If the Surety does not proceed as provided in paragraph 4 with reasonable promptness, the Surety shall be deemed to be in default on this Bond fifteen days after receipt of an additional written notice from the OWNER to the Surety demanding that the Surety perform its obligations under this Bond, and

- the OWNER shall be entitled to enforce any remedy available to the OWNER. If the Surety proceeds as provided in paragraph 4.4, and the OWNER refuses the payment tendered or the Surety has denied pliability, in whole or in part, without further notice the OWNER shall be entitled to enforce any remedy available to the OWNER.
- 6. After the OWNER has terminated the CONTRACTOR's right to complete the Contract, and if the Surety elects to act under paragraph 4.1, 4.2, or 4.3 above, then the responsibilities of the Surety to the OWNER shall not be greater than those of the CONTRACTOR under the Contract, and the responsibilities of the OWNER to the Surety shall not be greater than those of the OWNER under the Contract. To a limit of the amount of this Bond, but subject to commitment by the OWNER of the Balance of the Contract Price to mitigation of costs and damages on the Contract, the Surety is obligated without duplication for:
- 6.1. The responsibilities of the CONTRACTOR for correction of defective Work and completion of the Contract;
- 6.2. Additional legal, design professional and delay costs resulting from the CONTRACTOR's Default, and resulting from the actions or failure to act of the Surety under paragraph 4; and
- 6.3. Liquidated damages, or if no liquidated damages are specified in the Contract, actual damages caused by delayed performance or non-performance of the CONTRACTOR.
- 7. The Surety shall not be liable to the OWNER or others for obligations of the CONTRACTOR that are unrelated to the Contract, and the Balance of the Contract Price shall not be reduced or set off on account of any such unrelated obligations. No right of action shall accrue on this Bond to any person or entity other than the OWNER or its heirs, executors, administrators, or successors.
- 8. The Surety hereby waives notice of any change, including changes of time, to the Contract or to related subcontracts, purchase orders and other obligations.
- 9. Any proceeding, legal or equitable, under this Bond may be instituted in any court of competent jurisdiction in the location in which the Work or part of the Work is located and shall be instituted within two years after CONTRACTOR Default or within two years after the CONTRACTOR ceased working or within two years after the Surety refuses or fails to perform its obligations under this Bond, whichever occurs first. If the provisions of this paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.
- 10. Notice to the Surety, the OWNER or the CONTRACTOR shall be mailed or delivered to the address shown on the signature page.
- 11. When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the Contract was be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted here from and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. The intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

12. Definitions.

- 12.1. Balance of the Contract Price: The total amount payable by the OWNER to the CONTRACTOR under the Contract after all proper adjustments have been made, including allowance to the CONTRACTOR of any amounts received or to be received by the OWNER in settlement of insurance or other Claims for damages to which the CONTRACTOR is entitled, reduced by all valid and proper payments made to or on behalf of the CONTRACTOR under the Contract.
- 12.2. Contract: The agreement between the OWNER and the CONTRACTOR identified on the signature page, including all Contract Documents and changes thereto.
- 12.3. CONTRACTOR Default: Failure of the CONTRACTOR, which has neither been remedied nor waived, to perform or otherwise to comply with the terms of the Contract.

Performance Bond PB-3 of 6

Metropolitan Topeka Airport Authority Philip Billard Municipal Airport Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

12.4. OWNER Default: Failure of the OWNER, which has neither been remedied not waived, to pay the CONTRACTOR as required by the Contractor or to perform and complete or comply with the other terms thereof.

Performance Bond PB-4 of 6

(FOR INFORMATION ONLYName, Address :

AGENT or BROKER: OWNER'S REPRESENTATIVE (Engineer or other party):

Performance Bond PB-5 of 6

THIS PAGE INTENTIONALLY LEFT BLANK

Performance Bond PB-6 of 6

Payment Bond

Any singular reference to Contractor, Surety, Owner of other party shall be considered plural where applicable. SURETY (Name and Address of Principal Place of CONTRACTOR (Name and Address): Business): OWNER (Name and Address): Metropolitan Topeka Airport Authority 6510 SE Forbes Avenue, Suite 1 Topeka, KS 66619 **CONTRACT** Date: Amount: Description (Name and Location): AIP 3-20-0082-027 BIL-AIG 3-20-0082-028 Terminal Apron Rehabilitation Philip Billard Municipal Airport **BOND** Date (Not earlier than Contract Date): Amount: Modifications to this Bond Form: Surety and Contractor, intending to be legally bound hereby, subject to the terms printed on the reverse side hereof, do each cause this Performance Bond to be duly executed on its behalf by its authorized officer, agent or representative. CONTRACTOR AS PRINCIPAL **SURETY** Company: (Corp. Seal) Company: (Corp. Seal) Signature: _ Signature: _ Name and Title: Name and Title: (Attach Power of Attorney) (Space is provided below for signatures of additional parties, if required.) CONTRACTOR AS PRINCIPAL **SURETY** Company: (Corp. Seal) Company: (Corp. Seal) Signature: Signature: -Name and Title: Name and Title: EJCDC No. 1910-28-B (1996 Edition) Originally prepared through the joint efforts of the Surety Association of America, Engineers Joint Contract Documents Committee, the Associated General Contractors of America, and the American Institute of Architects.

Payment Bond PAY-1 of 6

THIS PAGE INTENTIONALLY LEFT BLANK

Payment Bond PAY-2 of 6

Metropolitan Topeka Airport Authority Philip Billard Municipal Airport

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

- 1. The CONTRACTOR and the Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the OWNER to pay for labor, materials and equipment furnished for use in the performance of the Contract, which is incorporated herein by reference.
- 2. With respect to the OWNER, this obligation shall be null and void if the CONTRACTOR:
- 2.1. Promptly makes payment, directly or indirectly, for all sums due Claimants, and
- 2.2. Defends, indemnifies and holds harmless the OWNER from all claims, demands, liens or suits by any person or entity who furnished labor, materials or equipment for use in the performance of the Contract, provided the OWNER has promptly notified the CONTRACTOR and the Surety (at the addresses described in paragraph 12) of any claims, demands, liens or suits and tendered defense of such claims, demands, liens or suits to the CONTRACTOR and the Surety, and provided there is no OWNER Default.
- With respect to Claimants, this obligation shall be null and void if the CONTRACTOR promptly makes payment, directly or indirectly, for all sums due.
- 4. The Surety shall have no obligation to Claimants under this Bond until:
- 4.1. Claimants who are employed by or have a direct contract with the CONTRACTOR have given notice to the Surety (at the addresses described in paragraph 12) and sent a copy, or notice thereof, to the OWNER, stating that a claim is being made under this Bond and, with substantial accuracy, the amount of the claim.
 - 4.2. Claimants who do not have a direct contract with the CONTRACTOR:
- 1. Have furnished written notice to the CONTRACTOR and sent a copy, or notice thereof, to the OWNER, within 90 days after having last performed labor or last furnished materials or equipment included in the claim stating, with substantial accuracy, the amount of the claim and the name of the party to whom the materials were furnished or supplied or for whom the labor was done or performed; and
- 2. Have either received a rejection in whole or in part from the CONTRACTOR, or not received within 30 days of furnishing the above notice any communication from the CONTRACTOR by which the CONTRACTOR had indicated the claim will be paid directly or indirectly; and
- 3. Not having been paid within the above 30 days, have sent a written notice to the Surety and sent a copy, or notice thereof, to the OWNER, stating that a claim is being made under this Bond and enclosing a copy of the previous written notice furnished to the CONTRACTOR.
- 5. If a notice required by paragraph 4 is given by the OWNER to the CONTRACTOR or to the Surety, that is sufficient compliance.
- 6. When the Claimant has satisfied the conditions of paragraph 4, the Surety shall promptly and at the Surety's expense take the following actions:
- 6.1. Send an answer to the Claimant, with a copy to the OWNER, within 45 days after receipt of the claim, stating the amounts that are undisputed and the basis for challenging any amounts that are disputed.
 - 6.2. Pay or arrange for payment of any undisputed amounts.
- 7. The Surety's total obligation shall not exceed the amount of this Bond, and the amount of this Bond shall be credited for any payments made in good faith by the Surety.

- 8. Amounts owed by the OWNER to the CONTRACTOR under the Contract shall be used for the performance of the Contract and to satisfy claims, if any, under any Performance Bond. By the CONTRACTOR furnishing and the OWNER accepting this Bond, they agree that all funds earned by the CONTRACTOR in the performance of the Contract are dedicated to satisfy obligations of the CONTRACTOR and the Surety under this Bond, subject to the OWNER's priority to use the funds for the completion of the Work.
- 9. The Surety shall not be liable to the OWNER, Claimants or others for obligations of the CONTRACTOR that are unrelated to the Contract. The OWNER shall not be liable for payment of any costs or expenses of any Claimant under this Bond, and shall have under this Bond no obligations to make payments to, give notices on behalf of, or otherwise have obligations to Claimants under this Bond.
- 10. The Surety hereby waives notice of any change, including changes of time, to the Contract or to related Subcontracts, purchase orders and other obligations.
- 11. No suit or action shall be commenced by a Claimant under this Bond other than a court of competent jurisdiction in the location in which the Work or part of the Work is located or after the expiration of one year from the date (1) on which the Claimant gave the notice required by paragraph 4.1 or paragraph 4.2.3, or (2) on which the last labor or service was performed by anyone or the last materials or equipment were furnished by anyone under the Construction Contract, whichever of (1) or (2) first occurs. If the provisions of this paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.
- 12. Notice to the Surety, the OWNER or the CONTRACTOR shall be mailed or delivered to the address shown on the signature page. Actual receipt of notice by Surety, the OWNER or the CONTRACTOR, however accomplished, shall be sufficient compliance as of the date received at the address shown on the signature page.
- 13. When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the Contract was be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. The intent is, that this Bond shall be construed as a statutory bond and not as a common law bond.
- 14. Upon request of any person or entity appearing to be a potential beneficiary of this Bond, the CONTRACTOR shall promptly furnish a copy of this Bond o shall permit a copy to me made.

15. DEFINITIONS.

- 15.1. Claimant: An individual or entity having a direct contract with the CONTRACTOR or with a Subcontractor of the CONTRACTOR to furnish labor, materials or equipment for use in the performance of the Contract. The intent of this Bond shall be to include without limitation in the terms "labor, materials or equipment" that part of water, gas, power, light, heat, oil, gasoline, telephone service or rental equipment used in the Contract, architectural and engineering services required for performance of the Work of the CONTRACTOR and the CONTRACTOR's Subcontractors, and all other items for which a mechanic's lien may be asserted in the jurisdiction where the labor, materials or equipment were furnished.
- 15.2. Contract: The agreement between the OWNER and the CONTRACTOR identified on the signature page, including all Contract Documents and changes thereto
- 15.3. OWNER Default: Failure of the OWNER, which has neither been remedied not waived, to pay the CONTRACTOR as required by the Contract or to perform and complete or comply with the other terms thereof.

Payment Bond PAY-3 of 6

THIS PAGE INTENTIONALLY LEFT BLANK

Payment Bond PAY-4 of 6

(FOR INFORMATION ONLYName, Address and Telephone)
AGENT or BROKER: OWNER'S REPRESENTATIVE (Engineer or other party):

Payment Bond PAY-5 of 6

THIS PAGE INTENTIONALLY LEFT BLANK

Payment Bond PAY-6 of 6

SUPPLEMENTARY PROVISIONS

These Supplementary Conditions amend and/or supplement the General Provision of the Contract and other provisions of the Contract Documents as indicated herein. All contract provisions that are not so amended or supplemented remain in full force and effect.

FEDERAL PROVISIONS

The provisions provided in the section "Contract Provision Guidelines for Obligated Sponsors and Airport Improvement Program Projects" (Federal Provisions) as provided for in this project manual are made a part of the project contract documents.

WARRANTY / GUARANTEE

All equipment and materials furnished and installed under this section shall be guaranteed against defects in materials and workmanship for a period of at least twelve (12) months from final acceptance by the Owner. The defective materials and/or equipment shall be repaired or replaced, at the Owner's discretion, with no additional cost to the Owner.

STORMWATER POLLUTION PREVENTION PLAN

Successful bidder shall assume ownership and responsibility of the project's Stormwater Pollution Prevention Plan from the Metropolitan Topeka Airport Authority. Successful bidder shall satisfactorily demonstrate to the MTAA/Engineer that the bidder has transferred the ownership of the SWPPP to himself at the start of the project. Contractor shall be responsible for installation, maintenance, and inspection of the stormwater pollution prevention installations during the course of the project. At the completion of the project, Contractor shall be responsible for the removal and disposal of stormwater pollution prevention devices from the project site.

STATE PROVISIONS - None

LOCAL PROVISIONS None

CONTRACTOR'S LIABILITY INSURANCE

- 1.1. Contractor shall purchase and maintain such commercial general liability and other insurance as is appropriate for the Project and as will provide protection from claims set forth below which may arise out of or result from Contractor's performance and furnishing of the Work and Contractor's other obligations under the Contract Documents, whether it is to be performed or furnished by Contractor, by any Subcontractor, by anyone directly or indirectly employed by any of them to perform or furnish any of the Work, or by anyone for whose acts any of them may be liable:
- 1.1.1. Claims under workers' or workmen's compensation, disability benefits and other similar employee benefit acts, as per state and federal statutory requirements.
- 1.1.2. Employers Liability Insurance covering claims for damages because of bodily injury, occupational sickness or disease, or death of Contractor's employees with a \$500,000.00 each person, limit.
- 1.1.3. Claims for damages because of bodily injury, sickness or disease, or death of any person other than Contractor's employees;

- 1.10.4. Claims for property damages, other than to the Work itself, because of injury to or destruction of tangible property wherever located, including loss of use resulting therefrom.
- 1.1.5. Claims arising out of operation of Laws or Regulations for damages because of bodily injury or death of any person or for damage to property; and
- 1.1.6. The commercial general liability insurance required under paragraphs 1.1.3 through 1.1.5 shall have the following specific coverages:

(1) General Liability:

1. Each Occurrence	\$1,000,000
2. Personal and Advertising Injury	\$1,000,000
3. Products and Completed Operations Aggregate	\$1,000,000
4. General Aggregate	\$2,000,000
5. Rented Premises	\$ 100,000
6. Medical Expenses	\$ 5,000

(2) Excess Liability:

Bodily Injury and Property Damage Combined:

\$1,000,000 Each Occurrence

\$1,000,000 Annual Aggregate

The commercial general liability insurance shall include completed operations insurance. Property Damage liability insurance shall be provided with coverages for explosion, collapse and underground hazards, where applicable. The Owner shall be named as an additional insured on the Contractor's general liability policy.

(3) Automobile Liability:

Claims for damages because of bodily injury or death of any person or property damage arising out of the ownership, maintenance or use of any motor vehicle. Coverages for hired car and employee non-owned auto liability shall also be provided. The coverage limits shall be:

Combined Single Limit for Each Occurrence \$1,000,000

(4) Contractual Liability Insurance:

1.2. The commercial general liability insurance required by paragraph 1.1 will include contractual liability insurance applicable to Contractor's obligations under the Contract Documents.

(5) Property Insurance:

1.3. Contractor shall purchase and maintain property insurance upon the Work at the site to the full insurable value thereof (subject to such deductible amounts as required by Laws and Regulations) for all projects which include construction of or modification to above ground structures. This insurance shall include the interests of Owner, Contractor and Subcontractors all of whom shall be listed as insured or additional insured parties, shall insure against the perils of fire and extended coverage and shall include "all risk" insurance for physical loss and damage including theft, vandalism and malicious mischief, collapse and water damage, and shall include damages, losses and expenses arising out of or resulting from any insured loss or incurred in the repair or replacement

of any insured property (including but not limited to fees and charges of engineers, architects, attorneys and other professionals). If not covered under the "all risk" insurance, Contractor shall purchase and maintain similar property insurance on portions of the Work stored on and off the site or in transit when such portions of the Work are to be included in an Application for Payment.

1.4. Contractor shall purchase and maintain such boiler and machinery insurance or additional property insurance as may be required by Laws and Regulations which will include the interests of Owner, Contractor and Subcontractors all of whom shall be listed as insured or additional insured parties.

Owners Liability Insurance

1.5. Contractor, at his sole expense, shall purchase Owner's Protective Liability Insurance and provide owner with the original policy. This insurance shall be maintained in full force and effect for the duration of the Contract by Contractor and shall name the Owner as the named Insured. This insurance shall have the following limits:

Each Occurrence \$1,000,000

General Aggregate \$1,000,000

This insurance shall protect Owner against any and all claims and liabilities for injury to or death of persons, or damage to property caused in whole or in part by, or alleged to have been caused in whole or in part by, the negligent acts or omissions of Contractor or Subcontractors or any agent, servant, worker or employee of Contractor or Subcontractor arising from the operations or Work for the project.

Notice of Cancellation

1.6. All of the policies of insurance so required to be purchased and maintained (or the certificates) in accordance with paragraphs 1.1 through 1.5 shall contain a provision or endorsement that the coverage afforded will not be canceled, materially changed or renewal refused until at least thirty (30) days prior written notice has been given to Owner. All such insurance shall remain in effect until final payment and at all times thereafter when Contractor may be correcting, removing or replacing defective Work in accordance with the Project Manual. In addition, Contractor shall maintain such completed operations insurance for one year after final payment and furnish Owner with evidence of continuation of such insurance at final payment.

Receipt and Application of Proceeds

- 1.7. Any insured loss under the policies of insurance required by paragraphs 1.3 and 1.4 will be adjusted with Owner and made payable to Owner as trustee for the insured, as their interests may appear, subject to the requirements of any applicable mortgage clause and of paragraph 1.10, Owner shall deposit in a separate account any money so received, and shall distribute it in accordance with such agreement as the parties in interest may reach. If no other special agreement is reached the damaged Work shall be repaired or replaced, the moneys so received applied on account thereof and the Work and the cost thereof covered by an appropriate Change Order.
- 1.8. Owner as trustee shall have power to adjust and settle any loss with the insurers unless one of the parties in interest shall object in writing within fifteen days after the occurrence of loss to Owner's exercise of this power. If such objection be made, Owner as trustee shall make settlement with the insurers in accordance with such agreement as the parties in interest may reach. If required in writing by any party in interest, Owner as trustee shall, upon the occurrence of an insured loss, give bond for the proper performance of such duties.

Acceptance of Insurance

1.9. If Owner has any objection to the coverage afforded by or other provisions of the insurance required to be purchased and maintained by Contractor in accordance with paragraphs 1.1 through 1.5 on the basis of its not complying with the Contract Documents, Owner shall notify Contractor in writing thereof within thirty days of the date of delivery of such certificates to Owner. Contractor shall provide to Owner such additional information in respect of insurance provided by Contractor as Owner may reasonably request. Failure by Owner to give any such notice of objection within the time provided shall constitute acceptance of such insurance purchased by Contractor as complying with the Contract Documents. All Certificates of Insurance shall utilize the ACORD 25-S form, most recent revision date.

Partial Utilization - Property Insurance

1.10. If Owner finds it necessary to occupy or use a portion or portions of the Work prior to Substantial Completion of all the Work, such use or occupancy may be accomplished in accordance with the Project Manual; provided that no such use or occupancy shall commence before the insurers providing the property insurance have acknowledged notice thereof and in writing effected the changes in coverage necessitated thereby. The insurers providing the property insurance shall consent by endorsement on the policy or policies, but the property insurance shall not be canceled or lapse on account of any such partial use or occupancy.

<u>WAGE RATES</u> Reference is made to 29 CFR 1 §1.6 Use and effectiveness of wage determinations, paragraph (c) (3) (iv).

The wage rates for the project are contained in the wage rate determination included in the project manual. The wage rates for the project may change and the current wage rate may be incorporated into the project under two conditions.

Condition 1:

If wage rate is updated 10 days before bid opens, the updated wage rate will be added to the project documents via an addendum and shall be used in the development of the bid.

Condition 2:

Wage rate is updated after bids are opened and the contract was not awarded within 90 days of bid opening, the contract will be amended to incorporate the wage rate as of the contract award date. The Notice to Proceed date will not be considered to be the contract award date.

ATTACHMENTS TO SUPPLEMENTARY CONDITIONS

A. <u>Department of Labor Wage Rate Determination</u> – See Section WR - Wage Rates Decision Number KS20240148 Modification Number 0 – 01/05/2024.

Information regarding civil construction items will be referred to the Federal Aviation Administration specifications.

Any references to Architect, Engineer, Construction Inspector, Resident Project Representative will be construed to be "Owner's Representative".

END OF SUPPLEMENTARY PROVISIONS

THIS PAGE INTENTIONALLY LEFT BLANK

"General Decision Number: KS20250148 02/07/2025

Superseded General Decision Number: KS20240148

State: Kansas

Construction Type: Highway

County: Shawnee County in Kansas.

HIGHWAY CONSTRUCTION PROJECTS

Note: Contracts subject to the Davis-Bacon Act are generally required to pay at least the applicable minimum wage rate required under Executive Order 14026 or Executive Order 13658. Please note that these Executive Orders apply to covered contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but do not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(1).

If the contract is entered	. Executive Order 14026
into on or after January 30,	generally applies to the
2022, or the contract is	contract.
renewed or extended (e.g., an	. The contractor must pay
option is exercised) on or	all covered workers at
after January 30, 2022:	least \$17.75 per hour (or
	the applicable wage rate
	listed on this wage
	determination, if it is
	higher) for all hours
	spent performing on the
	contract in 2025.
If the contract was awarded on	Executive Order 13658
or between January 1, 2015 and	generally applies to the
January 29, 2022, and the	contract.
contract is not renewed or	. The contractor must pay all
extended on or after January	covered workers at least
30, 2022:	\$13.30 per hour (or the
	applicable wage rate listed
	on this wage determination,
	if it is higher) for all
	hours spent performing on
	that contract in 2025.

The applicable Executive Order minimum wage rate will be adjusted annually. If this contract is covered by one of the Executive Orders and a classification considered necessary for

Wage Rates WR-1 of 8

performance of work on the contract does not appear on this wage determination, the contractor must still submit a conformance request.

Additional information on contractor requirements and worker protections under the Executive Orders is available at http://www.dol.gov/whd/govcontracts.

Modification Number	Publication Date
0	01/03/2025
1	02/07/2025

IRON0010-009 04/01/2024

	Rates	Fringes
IRONWORKER, STRUCTURAL	.\$ 38.00	33.56
* UAVG-KS-0006 01/01/2025		
	Rates	Fringes
LABORER: Pipelayer	\$ 32.12	14.73
* SUKS2019-087 05/09/2019		
	Rates	Fringes
CARPENTER, Includes Form Work	\$ 17.12 **	4.74
CEMENT MASON/CONCRETE FINISHER	.\$ 27.45	10.10
ELECTRICIAN	.\$ 29.93	14.14
IRONWORKER, REINFORCING	.\$ 30.50	27.05
LABORER: Common or General	\$ 17.30 **	8.37
LABORER: Concrete Saw (Hand Held/Walk Behind)	.\$ 29.21	14.63
LABORER: Flagger	.\$ 13.20 **	0.00
LABORER: Mason Tender - Cement/Concrete	.\$ 29.75	12.83
OPERATOR: Backhoe/Excavator/Trackhoe	\$ 26.78	11.94
OPERATOR: Bobcat/Skid		

Wage Rates WR-2 of 8

Steer/Skid Loader\$ 21.75	11.31
OPERATOR: Broom/Sweeper\$ 19.17	0.00
OPERATOR: Bulldozer\$ 19.35	5.41
OPERATOR: Concrete Finishing Machine\$ 24.26	0.00
OPERATOR: Crane\$21.18	6.96
OPERATOR: Grader/Blade\$ 25.14	9.03
OPERATOR: Loader\$ 18.87	4.26
OPERATOR: Material Transfer Vehicle\$ 14.65 **	0.00
OPERATOR: Mechanic\$ 25.45	9.49
OPERATOR: Paver (Asphalt, Aggregate, and Concrete)\$ 27.84	15.53
OPERATOR: Roller\$ 16.09 **	0.00
OPERATOR: Scraper\$ 17.67 **	0.00
OPERATOR: Screed\$ 16.93 **	0.00
OPERATOR: Tractor\$ 16.96 **	0.00
OPERATOR: Roto Mill Groundman\$ 18.43	0.00
OPERATOR: Roto Mill\$ 21.05	0.00
OPERATOR: Striping Machine\$ 27.27	12.25
TRAFFIC CONTROL: Service Driver	0.00
TRAFFIC SIGNALIZATION: Traffic Signal Installation (Groundman)\$ 16.54 **	0.00
TRUCK DRIVER: Water Truck\$ 22.45	11.51
TRUCK DRIVER: water Truck\$ 22.43 TRUCK DRIVER: Dump and Tandem\$ 23.23	11.51
TRUCK DRIVER: Dump and Tandem	11.31
Lowboy\$ 23.82	9.89

Wage Rates WR-3 of 8

TRUCK DRIVER: Off Road Truck\$ 19.06	0.00

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

** Workers in this classification may be entitled to a higher minimum wage under Executive Order 14026 (\$17.75) or 13658 (\$13.30). Please see the Note at the top of the wage determination for more information. Please also note that the minimum wage requirements of Executive Order 14026 are not currently being enforced as to any contract or subcontract to which the states of Texas, Louisiana, or Mississippi, including their agencies, are a party.

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at

https://www.dol.gov/agencies/whd/government-contracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (iii)).

.....

The body of each wage determination lists the classifications and wage rates that have been found to be prevailing for the type(s) of construction and geographic area covered by the wage determination. The classifications are listed in alphabetical order under rate identifiers indicating whether the particular rate is a union rate (current union negotiated rate), a survey rate, a weighted union average rate, a state adopted rate, or a

Wage Rates WR-4 of 8

supplemental classification rate.

Union Rate Identifiers

A four-letter identifier beginning with characters other than ""SU"", ""UAVG"", ?SA?, or ?SC? denotes that a union rate was prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2024. PLUM is an identifier of the union whose collectively bargained rate prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. The date, 07/01/2024 in the example, is the effective date of the most current negotiated rate.

Union prevailing wage rates are updated to reflect all changes over time that are reported to WHD in the rates in the collective bargaining agreement (CBA) governing the classification.

Union Average Rate Identifiers

The UAVG identifier indicates that no single rate prevailed for those classifications, but that 100% of the data reported for the classifications reflected union rates. EXAMPLE: UAVG-OH-0010 01/01/2024. UAVG indicates that the rate is a weighted union average rate. OH indicates the State of Ohio. The next number, 0010 in the example, is an internal number used in producing the wage determination. The date, 01/01/2024 in the example, indicates the date the wage determination was updated to reflect the most current union average rate.

A UAVG rate will be updated once a year, usually in January, to reflect a weighted average of the current rates in the collective bargaining agreements on which the rate is based.

Survey Rate Identifiers

The ""SU"" identifier indicates that either a single non-union rate prevailed (as defined in 29 CFR 1.2) for this classification in the survey or that the rate was derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As a weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SUFL2022-007 6/27/2024. SU indicates the rate is a single non-union prevailing rate or a weighted average of survey data for that classification. FL indicates the State of Florida. 2022 is the year of the survey on which these classifications and rates are

Wage Rates WR-5 of 8

based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 6/27/2024 in the example, indicates the survey completion date for the classifications and rates under that identifier.

?SU? wage rates typically remain in effect until a new survey is conducted. However, the Wage and Hour Division (WHD) has the discretion to update such rates under 29 CFR 1.6(c)(1).

State Adopted Rate Identifiers

The ""SA"" identifier indicates that the classifications and prevailing wage rates set by a state (or local) government were adopted under 29 C.F.R 1.3(g)-(h). Example: SAME2023-007 01/03/2024. SA reflects that the rates are state adopted. ME refers to the State of Maine. 2023 is the year during which the state completed the survey on which the listed classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 01/03/2024 in the example, reflects the date on which the classifications and rates under the ?SA? identifier took effect under state law in the state from which the rates were adopted.

WAGE DETERMINATION APPEALS PROCESS

1) Has there been an initial decision in the matter? This can be:

- a) a survey underlying a wage determination
- b) an existing published wage determination
- c) an initial WHD letter setting forth a position on a wage determination matter
- d) an initial conformance (additional classification and rate) determination

On survey related matters, initial contact, including requests for summaries of surveys, should be directed to the WHD Branch of Wage Surveys. Requests can be submitted via email to davisbaconinfo@dol.gov or by mail to:

Branch of Wage Surveys Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

Regarding any other wage determination matter such as conformance decisions, requests for initial decisions should be

Wage Rates WR-6 of 8

directed to the WHD Branch of Construction Wage Determinations. Requests can be submitted via email to BCWD-Office@dol.gov or by mail to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2) If an initial decision has been issued, then any interested party (those affected by the action) that disagrees with the decision can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Requests for review and reconsideration can be submitted via email to dba.reconsideration@dol.gov or by mail to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210.

END OF GENERAL DECISION"

Wage Rates WR-7 of 8

THIS PAGE INTENTIONALLY LEFT BLANK

Wage Rates WR-8 of 8



Contract Provision Guidelines for Obligated Sponsors and Airport Improvement Program Projects

(Issued on May 24, 2023)

Contents

Current	Changes	3
Contrac	et Guidance	4
1.	Purpose of this Document	4
2.	Sponsor Actions	4
3.	Typical Procurement Steps	5
4.	Applicability Matrix for Contract Provisions	6
Append	dix A – CONTRACT PROVISIONS	9
A1	ACCESS TO RECORDS AND REPORTS	9
A2	AFFIRMATIVE ACTION REQUIREMENT	10
A3	BREACH OF CONTRACT TERMS	12
A4	BUY AMERICAN PREFERENCE	13
A5	CIVIL RIGHTS - GENERAL	23
A6	CIVIL RIGHTS – TITLE VI ASSURANCE	25
A7	CLEAN AIR AND WATER POLLUTION CONTROL	34
A8	CONTRACT WORKHOURS AND SAFETY STANDARDS ACT REQUIREMENTS	35
A9	COPELAND "ANTI-KICKBACK" ACT	37
A1	0 DAVIS-BACON REQUIREMENTS	39
A1	1 DEBARMENT AND SUSPENSION	46
A1	2 DISADVANTAGED BUSINESS ENTERPRISE	48
A1	3 DISTRACTED DRIVING	52
A1 SU	4 PROHIBITION ON CERTAIN TELECOMMUNICATIONS AND VIDEO RVEILLANCE SERVICES OR EQUIPMENT	53
A1		
Δ1		55

A17	FEDERAL FAIR LABOR STANDARDS ACT (FEDERAL MINIMUM WAGE)	62
A18	LOBBYING AND INFLUENCING FEDERAL EMPLOYEES	63
A19	PROHIBITION of SEGREGATED FACILITIES	65
A20	OCCUPATIONAL SAFETY AND HEALTH ACT OF 1970	67
A21	PROCUREMENT OF RECOVERED MATERIALS	68
A22	RIGHT TO INVENTIONS	70
A23	SEISMIC SAFETY	71
A24	TAX DELINQUENCY AND FELONY CONVICTIONS	73
A25	TERMINATION OF CONTRACT	75
A26	TRADE RESTRICTION CERTIFICATION	79
A27	VETERAN'S PREFERENCE	81
A28	DOMESTIC PREFERENCES FOR PROCUREMENTS	82

CURRENT CHANGES

Item	Change
Editorial update made to the January 23, 2023 version (effective May 24, 2023)	The link on page 35 was updated to reflect changes to the Department of Labor website.
Editorial updates made to the November 17, 2022 version (effective January 23, 2023)	Pages 7, 16, 19, 20, 25, and 42 of Appendix A were edited to correct grammatical mistakes, update internal document links, and correct the name of the Title VI List of Pertinent Nondiscrimination Acts and Authorities.

CONTRACT GUIDANCE

1. Purpose of this Document

- The purpose of this document is to establish a convenient resource for Sponsors that consolidates federal contract provisions and clauses into one document that includes an applicability matrix. This document itself does not create, revise or delete requirements for participation in the Airport Improvement Program (AIP). The source of requirements addressed within this document are identified within the section for each individual clause.
- 2) While this document is intended to assist Sponsors with their compliance efforts, it does not alter or modify the terms of any applicable statute or regulation, is not a substitute for reading the regulation and the applicability matrix, and each corresponding document section, nor does it constitute legal advice.
- 3) Federal laws and regulations require that a Sponsor (a recipient of federal assistance) include specific clauses in certain contracts, solicitations, or specifications regardless of whether or not the project is federally funded.
- 4) For purposes of remaining compliant with its obligations, a Sponsor must incorporate applicable contract provisions in all its procurements and contract documents. Unless otherwise stated, these provisions flow down to subcontracts and sub-tier agreements.
- 5) Terminology:
 - a. The term **"Sponsor"** is used in this document to mean either an obligated Sponsor on a project that is not federally funded, or a Sponsor on an AIP funded project. A Sponsor is a "recipient" of federal assistance when receiving AIP or other FAA grant funds.
 - b. The term "Owner" of a public use airport is generally used in the solicitation or contract clauses because of its common use in public contracts. An Owner becomes an obligated Sponsor upon acceptance of the AIP grant assurances associated with current or prior AIP grant funded projects.
 - c. For purposes of determining requirements for contract provisions, the term "contract" includes professional services, and subcontracts and supplier contracts such as purchase orders.
 - d. The term "contractor" is understood to mean a contractor, subcontractor, or consultant; and means one who participates, through a contract or subcontract (at any tier).
 - e. The term "bid" is understood to mean a bid, an offer, or a proposal.
 - f. The term "applicant" is understood to mean the following in different contexts:
 - i. For the Equal Employment Opportunity (EEO) clause, the term "applicant" means an applicant for employment (whether or not the phrase, *for employment*, follows the word applicant or applicants).
 - ii. For all other clauses, the term "applicant" means a bidder, offeror, or proposer for a contract.

2. Sponsor Actions

In general, Sponsor's actions consistent with obligations:

- 1) Include in its procurements the provisions that are applicable to its project.
- 2) Not incorporate the entire contract provisions guidelines in its solicitation or contract documents, whether by reference or by inclusion in whole. Incorporation of this entire guidance document creates potential for ambiguous interpretation and may lead to improper application that unnecessarily increases price. A Sponsor that fails to properly incorporate applicable contract clauses may place themselves at risk for audit findings or denial of Federal funding.
- 3) Incorporate applicable contract provisions using mandatory language as required. The subheading entitled *Applicability* advises whether a particular clause or provision has mandatory language that a Sponsor must use.
 - (a) Mandatory Language Whenever a clause or provision has mandatory text, the Sponsor must incorporate the text of the provision <u>without change</u>, except where specific adaptive input is necessary (e.g., such as the Sponsor's name).
 - (b) No Mandatory Language For provisions without mandatory language, this guidance provides model language acceptable to the FAA. Some Sponsors may have standard procurement language that is equivalent to those federal provisions. In these cases, Sponsors may use their existing standard procurement provision language provided the text meets the intent and purpose of the Federal law or regulation.
- 4) Require the contractor (including all subcontractors) to insert these contract provisions in each lower tier contract (e.g., subcontract or sub-agreement).
- 5) Require the contractor (including all subcontractors) to incorporate the requirements of these contract provisions by reference for work done under any purchase orders, rental agreements, and other agreements for supplies or services.
- 6) Require that the prime contractor be responsible for compliance with these contract provisions by any subcontractor, lower-tier subcontractor, or service provider.
- 7) Verify that any required local or State provision does not conflict with or alter a Federal law or regulation.

3. Typical Procurement Steps

The typical procurement steps in a project are:

- 1) Solicitation, Request for Bids, or Request for Proposals This is also called the Advertisement or Notice to Bidders.
- 2) Bidding or Accepting Proposals In this stage, the bidders receive a complete set of the procurement documents, also known as the project manual. The project manual will typically include a copy of the solicitation, instructions-to-bidders, bid forms, certifications and representations, general provisions, contract conditions, copy of contract, project drawings, technical specifications, and related project documents.
- 3) Bid/Proposal Evaluation Period when Sponsor tabulates, reviews, and evaluates all proposals for bid responsiveness and bidder responsibility.
- 4) Award Point when the Sponsor formally awards the contract to the successful bidder.

5) Execution of Contract – Point at which the Sponsor formally enters into a legally binding agreement with bidder to perform services or provide goods.

4. Applicability Matrix for Contract Provisions

<u>Table 1</u> Matrix summarizes the applicability of contract provisions based upon the type of contract or agreement. The dollar threshold represents the value at which, when equal to or exceeded, the Sponsor must incorporate the provision in the contract or agreement.

Supplemental information addressing applicability and use for each provision is located in Appendix A. Appendix A and the Matrix include notes indicating when the Sponsor may incorporate references in the solicitation in lieu of including the entire text.

Sponsors are responsible for reviewing both the Matrix and each corresponding section to determine applicability of specific contract provisions.

Meaning of cell values in table below:

- Info –Sponsor has discretion on whether to include clause in its contracts.
- Limited Provision with limited applicability depending on circumstances of the procurement.
- n/a Provision that is not applicable for that procurement type.
- NIS Provision that does not need to be included or referenced in the solicitation document
- REF Provision to be incorporated into the solicitation by reference.
- REQD Provision the Sponsor must incorporate into procurement documents.

Table 1 – Applicability of Provisions

Provisions/Clauses	Dollar Threshold	Solicitation	Professional Services	Construction	Equipment	Property (Land)	Non-AIP Contracts
					2502	2502	,
Access to Records and Reports	\$0	NIS	REQD	REQD	REQD	REQD	n/a
Affirmative Action Requirement	\$10,000	REQD	Limited	REQD	Limited	Limited	n/a
Breach of Contract	\$250,000	NIS	REQD	REQD	REQD	REQD	n/a
Buy American Preferences	\$ 0	REF	Limited	REQD	REQD	Limited	n/a
(1) Buy American Statement	\$ 0	NIS	Limited	REQD	REQD	Limited	n/a
(2) <u>Construction</u>	\$ 0	NIS	Limited	REQD	REQD	Limited	n/a
(3) Equipment/Building Projects	\$ 0	NIS	Limited	REQD	REQD	Limited	n/a
<u>Civil Rights – General</u>	\$ 0	NIS	REQD	REQD	REQD	REQD	REQD
<u>Civil Rights - Title VI Assurances</u>	\$ 0	REF	REQD	REQD	REQD	REQD	REQD
(1) Notice - Solicitation	\$ 0	REQD	REQD	REQD	REQD	REQD	REQD
(2) <u>Clause - Contracts</u>	\$ 0	NIS	REQD	REQD	REQD	REQD	REQD
(3) <u>Clause – Transfer of U.S. Property</u>	\$ 0	NIS	n/a	n/a	n/a	Limited	REQD
(4) <u>Clause – Transfer of Real Property</u>	\$ 0	NIS	n/a	n/a	n/a	REQD	REQD
(5) <u>Clause - Construct/Use/Access to</u>	\$ 0	NIS	n/a	n/a	n/a	REQD	REQD
Real Property							
(6) <u>List – Pertinent Authorities</u>	\$0	NIS	REQD	REQD	REQD	REQD	REQD
Clean Air/Water Pollution Control	\$150,000	NIS	REQD	REQD	REQD	REQD	n/a
Contract Work Hours and Safety Standards	\$100,000	NIS	Limited	REQD	Limited	Limited	n/a
Copeland Anti-Kickback	\$ 2,000	NIS	Limited	REQD	Limited	Limited	n/a
<u>Davis Bacon Requirements</u>	\$ 2,000	REF	Limited	REQD	Limited	Limited	n/a
<u>Debarment and Suspension</u>	\$25,000	REF	REQD	REQD	REQD	Limited	n/a
<u>Disadvantaged Business Enterprise</u>	\$ 250,000	REQD	REQD	REQD	REQD	REQD	n/a
<u>Distracted Driving</u>	\$10,000	NIS	REQD	REQD	REQD	REQD	n/a
<u>Domestic Preferences for Procurements</u>	\$0	NIS	REQD	REQD	REQD	REQD	Info
Equal Employment Opportunity	\$10,000	NIS	Limited	REQD	Limited	Limited	n/a
(1) EEO Contract Clause	\$10,000	NIS	Limited	REQD	Limited	Limited	n/a
(2) EEO Specification	\$10,000	NIS	Limited	REQD	Limited	Limited	n/a
Federal Fair Labor Standards Act	\$ 0	REQD	REQD	REQD	REQD	REQD	Info
Foreign Trade Restriction	\$ 0	REQD	REQD	REQD	REQD	REQD	n/a
<u>Lobbying Federal Employees</u>	\$ 100,000	REF	REQD	REQD	REQD	REQD	n/a
Occupational Safety and Health Act	\$ 0	NIS	REQD	REQD	REQD	REQD	Info
Prohibition on Certain Telecommunications	\$0	NIS	REQD	REQD	REQD	REQD	Info
and Video Surveillance Services or							
<u>Equipment</u>							
Prohibition of Segregated Facilities	\$0	NIS	Limited	REQD	Limited	Limited	n/a
Recovered Materials	\$10,000	REF	Limited	REQD	REQD	Limited	n/a
Right to Inventions	\$ 0	NIS	Limited	Limited	Limited	n/a	n/a
Seismic Safety	\$ 0	NIS	Limited	Limited	Limited	n/a	n/a
Tax Delinquency and Felony Conviction	\$ 0	NIS	REQD	REQD	REQD	REQD	n/a
Termination of Contract	\$10,000	NIS	REQD	REQD	REQD	REQD	n/a
<u>Veteran's Preference</u>	\$ 0	NIS	REQD	REQD	REQD	REQD	n/a

Airport Concessions Disadvantage Business Enterprise (ACDBE) Notes:

- 1. Language relative to solicitation for ACDBEs does not need to be included in AIP funded solicitations, since in no case are concessions activities funded with federal funds.
- 2. Airport Sponsors must include the appropriate Civil Rights Title VI language in their solicitation notices when they seek proposals for concessions.
- 3. For ACDBE agreements, use the column for *Non-AIP Contracts*.

APPENDIX A - CONTRACT PROVISIONS

A1 ACCESS TO RECORDS AND REPORTS

A1.1 SOURCE

2 CFR § 200.334

2 CFR § 200.337

FAA Order 5100.38

A1.2 APPLICABILITY

2 CFR § 200.334 requires a Sponsor to retain records pertinent to a Federal award for a period of three years from submission of final closure documents. 2 CFR § 200.337 establishes that Sponsors must provide Federal entities the right to access records pertinent to the Federal award. FAA policy extends these requirements to the Sponsor's contracts and subcontracts of AIP funded projects.

Contract Types – The Sponsor must include this provision in all contracts and subcontracts of AIP funded projects.

Use of Provision – No mandatory language provided. The following language is acceptable to the FAA with meeting the intent of this requirement. If the Sponsor prefers to use different language, the Sponsor's language must fully satisfy the requirements of 2 CFR §§ 200.334 and 200.337.

A1.3 MODEL CONTRACT CLAUSE

ACCESS TO RECORDS AND REPORTS

The Contractor must maintain an acceptable cost accounting system. The Contractor agrees to provide the Owner, the Federal Aviation Administration and the Comptroller General of the United States or any of their duly authorized representatives access to any books, documents, papers and records of the Contractor which are directly pertinent to the specific contract for the purpose of making audit, examination, excerpts and transcriptions. The Contractor agrees to maintain all books, records and reports required under this contract for a period of not less than three years after final payment is made and all pending matters are closed.

A2 AFFIRMATIVE ACTION REQUIREMENT

A2.1 SOURCE

41 CFR Part 60-4

Executive Order 11246

A2.2 APPLICABILITY

Minority Participation. Sponsors are required to set goals for minority participation in AIP funded projects exceeding \$10,000. The goals for minority participation derive from Economic Area (EA) and Standard Metropolitan Statistical Area (SMSA) as established in Volume 45 of the Federal Register dated 10/3/80. Page 65984 contains a table of all EAs and SMSAs and the associated minority participation goals.

To find the goals for minority participation, a Sponsor must either refer to the Federal Register Notice or to the Department of Labor online document, "Participation Goals for Minorities and Females". EAs and SMSAs span state boundaries. A Sponsor may have to refer to entries for adjacent states in order to locate the goal for the project location.

Female Participation. Executive Order 11246 has set a goal of 6.9% nationally for female participation for all construction projects. This value remains constant for all counties and states.

Contract Types –

Construction – The Sponsor must incorporate this notice in all solicitations for bids or requests for proposals for AIP funded construction work contracts and subcontracts that exceed \$10,000. Construction work means construction, rehabilitation, alteration, conversion, extension, demolition or repair of buildings, highways or other changes or improvements to real property, including facilities providing utility services. The term also includes the supervision, inspection and other onsite functions incidental to the actual construction.

Equipment – The Sponsor must incorporate this notice in any equipment project exceeding \$10,000 that involves installation of equipment onsite (e.g., electrical vault equipment). This provision does not apply to equipment acquisition projects where the manufacture of the equipment takes place offsite at a manufacturer's plant (e.g., firefighting and snow removal vehicles).

Professional Services – The Sponsor must incorporate this notice in any professional service agreement if the professional services agreement includes tasks that meet the definition of construction work [as defined by the U.S. Department of Labor (DOL)] and exceeds \$10,000. Examples include installation of monitoring systems (e.g., noise, environmental, etc.).

Property/Land – The Sponsor must incorporate this notice in any agreement associated with land acquisition if the agreement includes construction work (defined above) that exceeds \$10,000. Examples include demolition of structures or installation of boundary fencing.

Use of Provision – MANDATORY TEXT. The Sponsor must:

- (a) Incorporate the text of this provision in its solicitations without modification.
- (b) Incorporate the applicable minority participation goal and the covered area by geographic name.
- (c) Not simply insert a reference to the 1980 Federal Register Notice.

A2.3 MANDATORY SOLICITATION CLAUSE

NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE EQUAL EMPLOYMENT OPPORTUNITY

- 1. The Offeror's or Bidder's attention is called to the "Equal Opportunity Clause" and the "Standard Federal Equal Employment Opportunity Construction Contract Specifications" set forth herein.
- 2. The goals and timetables for minority and female participation, expressed in percentage terms for the Contractor's aggregate workforce in each trade on all construction work in the covered area, are as follows:

Timetables

Goals for minority participation for each trade: [Sponsor must insert established goal]

Goals for female participation in each trade: 6.9%

These goals are applicable to all of the Contractor's construction work (whether or not it is Federal or federally assisted) performed in the covered area. If the Contractor performs construction work in a geographical area located outside of the covered area, it shall apply the goals established for such geographical area where the work is actually performed. With regard to this second area, the Contractor also is subject to the goals for both its federally involved and nonfederally involved construction.

The Contractor's compliance with the Executive Order and the regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the specifications set forth in 41 CFR 60-4.3(a) and its efforts to meet the goals. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade, and the Contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from Contractor to Contractor or from project to project for the sole purpose of meeting the Contractor's goals shall be a violation of the contract, the Executive Order and the regulations in 41 CFR Part 60-4. Compliance with the goals will be measured against the total work hours performed.

- 3. The Contractor shall provide written notification to the Director of the Office of Federal Contract Compliance Programs (OFCCP) within 10 working days of award of any construction subcontract in excess of \$10,000 at any tier for construction work under the contract resulting from this solicitation. The notification shall list the name, address, and telephone number of the subcontractor; employer identification number of the subcontractor; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the subcontract is to be performed.
- 4. As used in this notice and in the contract resulting from this solicitation, the "covered area" is [Sponsor must insert state, county, and city].

A3 BREACH OF CONTRACT TERMS

A3.1 SOURCE

2 CFR Part 200, Appendix II(A)

A3.2 APPLICABILITY

This provision requires Sponsors to incorporate administrative, contractual or legal remedies in the event that a contractor violates or breaches contract terms. The Sponsor must also include appropriate sanctions and penalties.

Contract Types – This provision is required for all contracts that exceed the simplified acquisition threshold as stated in 2 CFR Part 200, Appendix II (A). This threshold is occasionally adjusted for inflation and is \$250,000.

Use of Provision – No mandatory language provided. The following language is acceptable to the FAA as meeting the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of 2 CFR Part 200. Select either "contractor" or "consultant" as applicable.

A3.3 MODEL CONTRACT CLAUSE

BREACH OF CONTRACT TERMS

Any violation or breach of terms of this contract on the part of the [Contractor / Consultant] or its subcontractors may result in the suspension or termination of this contract or such other action that may be necessary to enforce the rights of the parties of this agreement.

Owner will provide [Contractor | Consultant] written notice that describes the nature of the breach and corrective actions the [Contractor | Consultant] must undertake in order to avoid termination of the contract. Owner reserves the right to withhold payments to Contractor until such time the Contractor corrects the breach or the Owner elects to terminate the contract. The Owner's notice will identify a specific date by which the [Contractor | Consultant] must correct the breach. Owner may proceed with termination of the contract if the [Contractor | Consultant] fails to correct the breach by the deadline indicated in the Owner's notice.

The duties and obligations imposed by the Contract Documents and the rights and remedies available thereunder are in addition to, and not a limitation of, any duties, obligations, rights and remedies otherwise imposed or available by law.

A4 BUY AMERICAN PREFERENCE

A4.1 SOURCE

Title 49 USC § 50101

Executive Order 14005, Ensuring the Future is Made in All of America by All of America's Workers Bipartisan Infrastructure Law (Pub. L. No. 117-58), Build America, Buy America (BABA)

A4.2 APPLICABILITY

The Buy American Preference incorporates statutory requirements and policies outlined in the in 49 USC § 50101, Executive Order 14005, and BABA.

Section 50101 of 49 USC requires that all steel and manufactured goods used on AIP projects be produced in the United States. This section also gives the FAA the ability to issue a waiver to a Sponsor to use non-domestic material on an AIP funded project subject to meeting certain conditions. A Sponsor may request that the FAA issue a waiver from the Buy American Preference requirements if the FAA finds that:

- 1) Applying the provision is not in the public interest.
- 2) The steel or manufactured goods are not available in sufficient quantity or quality in the United States
- 3) The cost of components and subcomponents produced in the United States is more than 60 percent of the total components of a facility or equipment, and final assembly has taken place in the United States. Items that have an FAA standard specification item number (such as specific airport lighting equipment) are considered the equipment.
- 4) Applying this provision would increase the cost of the overall project by more than 25 percent.

Executive Order 14005 advances the Administration's priority to use terms and conditions of Federal financial assistance awards to maximize the use of goods, products, and materials produced in, and services offered in, the United States. The Order directs, to the extent appropriate and consistent with applicable law, agencies shall partner with the Hollings Manufacturing Extension Partnership (MEP) to conduct supplier scouting in order to identify American companies that are able to produce goods, products, and materials in the United States that meet Federal procurement needs, prior to consideration of using non-domestic products.

The Bipartisan Infrastructure Law, Build America, Buy America (BABA) Act strengthens Made in America Laws and bolsters America's industrial base, protects national security, and supports high-paying jobs. Under BABA, iron, steel and certain construction materials are required to be 100% produced in the United States.

Under the Bipartisan Infrastructure Law (Pub. L. No. 117-58) BABA three waivers are available for iron and steel, manufactured products, and construction materials when a Federal agency finds that –

1) Applying the domestic content procurement preference would be inconsistent with the public interest (a "public interest waiver");

- 2) Types of iron, steel, manufactured products, or construction materials are not produced in the United States in sufficient and reasonably available quantities or of a satisfactory quality (a "nonavailability waiver"); or
- 3) The inclusion of iron, steel, manufactured products, or construction materials produced in the United States will increase the cost of the overall project by more than 25 percent (an "unreasonable cost waiver").

BABA defines construction materials, items that are or consists primarily of non-ferrous metals, plastic and polymer-based products (including polyvinylchloride, composite building materials, and polymers used in fiber optic cables), glass (including optic glass), lumber or drywall.

Items that consist of two or more of the aforementioned materials that have been combined together through a manufacturing process, and items that include at least one of the listed materials combined with a material that is not listed through a manufacturing process, should be treated as manufactured products, rather than as construction materials. For example, a plastic framed sliding window should be treated as a manufactured product while plate glass should be treated as a construction material.

The Buy America Preference requirements flow down from the Sponsor to first tier contractors, who are responsible for ensuring that lower tier contractors and subcontractors are also in compliance.

Note: The Buy American Preference does not apply to temporary equipment a contractor uses as a tool of its trade and which does not remain as part of the project.

Required Documentation

The FAA Buy American Requests. All applications (requests) for an FAA Buy American Preference Waiver includes, at minimum, a completed Content Percentage Worksheet and Final Assembly Questionnaire. Additional information may be requested from the applicant by the FAA. Airport Sponsors, consultants, construction contractors, or equipment manufacturers are responsible for completing and submitting waiver applications. The FAA is unable to make a determination on waiver requests with incomplete information. Sponsors must confirm with the bidder or offeror to assess the adequacy of the waiver request and associated information prior to forwarding a waiver request to the FAA for action. All FAA waivers forms are available from the FAA Buy American Requirements webpage.

Proprietary Confidentiality. Exemption 4 of the Freedom of Information Act protects "trade secrets and commercial or financial information obtained from a person [that is] privileged or confidential. Proprietary manufacturing and design information submitted to the Federal Aviation Administration for the purposes of receiving a Buy American Waiver shall not be disclosed outside the FAA. The FAA will provide a written notification to the Airport Sponsor, manufacturer(s), contractor(s) or supplier(s) when a waiver determination is complete.

Timing of Waiver Requests. Sponsors desiring a Type 2 waiver should submit their waiver request, with justification, *before* issuing a solicitation for bids or a request for proposal for a project.

The Sponsor must submit a Type 2, Type 3, or Type 4 waiver request *prior* to executing the contract. The FAA will generally not consider waiver requests after execution of the contract except where extraordinary and extenuating circumstances exist.

The Buy American Notice of Determination (NOD) Process. The FAA Reauthorization Act of 2018 requires that all approved waivers must be posted to the FAA's website and remain posted for public comment for 10 days, before becoming effective. All FAA waivers must complete the NOD process. Sponsors are encouraged to wait until approved waivers become effective before executing AIP projects.

Buy American Conformance Lists. The FAA Office of Airports maintains listings of projects and products that have received a waiver from the Buy American Preference requirements for project specific and nationwide use. Each of these conformance lists is available online at www.faa.gov/airports/aip/buy_american/. Products listed on the FAA Nationwide Buy American Conformance list do not require additional submittal of domestic content information. Nationwide waivers expire five years from the date issued, unless revoked earlier by the FAA.

Facility Waiver Requests. For construction of a facility, the Sponsor may submit the waiver request after bid opening, but prior to contract execution. Examples of facility construction include terminal buildings, terminal renovation, and snow removal equipment buildings.

Contract Types –

Construction and Equipment – The Sponsor must meet the Buy American Preference requirements of 49 USC § 50101 and BABA for all AIP funded projects that require materials that are or consists primarily of iron, steel or manufactured goods and construction materials.

Professional Services – Professional service agreements (PSAs) do not normally result in a deliverable that meets the definition of a manufactured product. However, the emergence of various project delivery methods has created situations where task deliverables under a PSA may include a manufactured product. If a PSA includes providing a manufactured good as a deliverable under the contract, the Sponsor must include the Buy American Preference provision in the agreement.

Property – Most land transactions do not involve acquiring a manufactured product. However, under certain circumstances, a property acquisition project could result in the installation of a manufactured product. For example, the installation of property fencing, gates, doors and locks, etc. represent manufactured products acquired under an AIP funded land project that must comply with Buy American Preferences.

Use of Provisions – No mandatory language provided. The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's revised language must fully comply with 49 USC § 50101 and BABA.

There are two types of FAA Buy American certifications. The Sponsor must incorporate the appropriate certifications of compliance with FAA Buy American Preference in the solicitation:

- Construction Projects involving the replacement, rehabilitation, reconstruction of airfield surfaces such as on runways, taxiways, taxilanes, aprons, roadways, parking lots, etc. Insert the Certificate of compliance to FAA Buy American Preference based on Construction Projects.
- Equipment and Buildings Projects involving and including the acquisition of equipment such as snow removal equipment, navigational aids, wind cones, and the construction of buildings such as hangars, terminal development, lighting vaults, aircraft rescue & firefighting buildings, etc. -

Insert the Certificate of Compliance with FAA Buy American Preference Based on Equipment/Building Projects.

A4.3 MODEL SOLICITATION CLAUSES

A4.3.1 Certification of Compliance with FAA Buy American Preference Statement

FAA BUY AMERICAN PREFERENCE

The Contractor certifies that its bid/offer is in compliance with 49 USC § 50101, BABA and other related Made in America Laws, U.S. statutes, guidance, and FAA policies, which provide that Federal funds may not be obligated unless all iron, steel and manufactured goods used in AIP funded projects are produced in the United States, unless the Federal Aviation Administration has issued a waiver for the product; the product is listed as an Excepted Article, Material Or Supply in Federal Acquisition Regulation subpart 25.108; or is included in the FAA Nationwide Buy American Waivers Issued list.

The bidder or offeror must complete and submit the certification of compliance with FAA's Buy American Preference, BABA and Made in America laws included herein with their bid or offer. The Airport Sponsor/Owner will reject as nonresponsive any bid or offer that does not include a completed certification of compliance with FAA's Buy American Preference and BABA.

The bidder or offeror certifies that all constructions materials, defined to mean an article, material, or supply other than an item of primarily iron or steel; a manufactured product; cement and cementitious materials; aggregates such as stone, sand, or gravel; or aggregate binding agents or additives that are or consist primarily of: non-ferrous metals; plastic and polymer-based products (including polyvinylchloride, composite building materials, and polymers used in fiber optic cables); glass (including optic glass); lumber; or drywall used in the project are manufactured in the U.S.

Guidelines for Contract Provisions for Obligated Sponsors and Airport Improvement Program Projects

¹ Per Executive Order 14005 "Made in America Laws" means all statutes, regulations, rules, and Executive Orders relating to federal financial assistance awards or federal procurement, including those that refer to "Buy America" or "Buy American," that require, or provide a preference for, the purchase or acquisition of goods, products, or materials produced in the United States, including iron, steel, and manufactured products offered in the United States.

A4.3.2 Certification of Compliance with FAA Buy American Preference – Construction Projects

As a matter of bid responsiveness, the bidder or offeror must complete, sign, date, and submit this certification statement with its proposal. The bidder or offeror must indicate how it intends to comply with 49 USC \S 50101, BABA and other related Made in America Laws, U.S. statutes, guidance, and FAA policies, by selecting one of the following certification statements. These statements are mutually exclusive. Bidder must select one or the other (i.e., not both) by inserting a checkmark (\checkmark) or the letter "X".

Bidder or offeror hereby certifies that it will comply with 49 USC § 50101, BABA and other
related U.S. statutes, guidance, and policies of the FAA by:

- a) Only installing iron, steel and manufactured products produced in the United States;
- b) Only installing construction materials defined as: an article, material, or supply other than an item of primarily iron or steel; a manufactured product; cement and cementitious materials; aggregates such as stone, sand, or gravel; or aggregate binding agents or additives that are or consist primarily of non-ferrous metals; plastic and polymer-based products (including polyvinylchloride, composite building materials, and polymers used in fiber optic cables); glass (including optic glass); lumber or drywall that have been manufactured in the United States.
- c) Installing manufactured products for which the Federal Aviation Administration (FAA)
 has issued a waiver as indicated by inclusion on the current FAA Nationwide Buy
 American Waivers Issued listing; or
- d) Installing products listed as an Excepted Article, Material or Supply in Federal Acquisition Regulation Subpart 25.108.

By selecting this certification statement, the bidder or offeror agrees:

- a) To provide to the Airport Sponsor or the FAA evidence that documents the source and origin of the iron, steel, and/or manufactured product.
- b) To faithfully comply with providing U.S. domestic products.
- c) To refrain from seeking a waiver request after establishment of the contract, unless extenuating circumstances emerge that the FAA determines justified.
- d) Certify that all construction materials used in the project are manufactured in the U.S.
- ☐ The bidder or offeror hereby certifies it cannot comply with the 100 percent Buy American Preferences of 49 USC § 50101(a) but may qualify for a Type 3 or Type 4 waiver under 49 USC § 50101(b). By selecting this certification statement, the apparent bidder or offeror with the apparent low bid agrees:
 - a) To the submit to the Airport Sponsor or FAA within 15 calendar days of being selected as the responsive bidder, a formal waiver request and required documentation that supports the type of waiver being requested.
 - b) That failure to submit the required documentation within the specified timeframe is cause for a non-responsive determination that may result in rejection of the proposal.

- c) To faithfully comply with providing U.S. domestic products at or above the approved U.S. domestic content percentage as approved by the FAA.
- d) To furnish U.S. domestic product for any waiver request that the FAA rejects.
- e) To refrain from seeking a waiver request after establishment of the contract, unless extenuating circumstances emerge that the FAA determines justified.

Required Documentation

Type 2 Waiver (Nonavailability) - The iron, steel, manufactured goods or construction materials or manufactured goods are not available in sufficient quantity or quality in the United States. The required documentation for the Nonavailability waiver is

- a) Completed Content Percentage Worksheet and Final Assembly Questionnaire
- b) Record of thorough market research, consideration where appropriate of qualifying alternate items, products, or materials including;
- c) A description of the market research activities and methods used to identify domestically manufactured items capable of satisfying the requirement, including the timing of the research and conclusions reached on the availability of sources.

Type 3 Waiver – The cost of components and subcomponents produced in the United States is more than 60 percent of the cost of all components and subcomponents of the "facility/project." The required documentation for a Type 3 waiver is:

- a) Completed Content Percentage Worksheet and Final Assembly Questionnaire including;
- b) Listing of all manufactured products that are not comprised of 100 percent U.S. domestic content (excludes products listed on the FAA Nationwide Buy American Waivers Issued listing and products excluded by Federal Acquisition Regulation Subpart 25.108; products of unknown origin must be considered as non-domestic products in their entirety).
- c) Cost of non-domestic components and subcomponents, excluding labor costs associated with final assembly and installation at project location.
- d) Percentage of non-domestic component and subcomponent cost as compared to total "facility" component and subcomponent costs, excluding labor costs associated with final assembly and installation at project location.

Type 4 Waiver (Unreasonable Costs) - Applying this provision for iron, steel, manufactured goods or construction materials would increase the cost of the overall project by more than 25 percent. The required documentation for this waiver is:

- a) A completed Content Percentage Worksheet and Final Assembly Questionnaire from
- b) At minimum two comparable equal bids and/or offers;
- c) Receipt or record that demonstrates that supplier scouting called for in Executive Order 14005, indicates that no domestic source exists for the project and/or component;
- d) Completed waiver applications for each comparable bid and/or offer.

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

False Statements: Per 49 USC § 47126, this certification concerns a matter within the jurisdiction of the Federal Aviation Administration and the making of a false, fictitious, or fraudulent certification may render the maker subject to prosecution under Title 18, United States Code.			
Date	Signature		
Company Name	Title		

A4.3.3 Certification of Compliance with FAA Buy American Preference – Equipment/Building Projects

As a matter of bid responsiveness, the bidder or offeror must complete, sign, date, and submit this certification statement with their proposal. The bidder or offeror must indicate how they intend to comply with 49 USC § 50101, and other Made in America Laws, U.S. statutes, guidance, and FAA policies by selecting one on the following certification statements. These statements are mutually exclusive. Bidder must select one or the other (not both) by inserting a checkmark (\checkmark) or the letter "X".

Bidder or offeror hereby certifies that it will comply with 49 USC § 50101, BABA and other
related U.S. statutes, guidance, and policies of the FAA by:

- a) Only installing steel and manufactured products produced in the United States;
- b) Only installing construction materials defined as: an article, material, or supply other than an item of primarily iron or steel; a manufactured product; cement and cementitious materials; aggregates such as stone, sand, or gravel; or aggregate binding agents or additives that are or consist primarily of non-ferrous metals; plastic and polymer-based products (including polyvinylchloride, composite building materials, and polymers used in fiber optic cables); glass (including optic glass); lumber or drywall that have been manufactured in the United States.
- Installing manufactured products for which the Federal Aviation Administration (FAA)
 has issued a waiver as indicated by inclusion on the current FAA Nationwide Buy
 American Waivers Issued listing; or
- d) Installing products listed as an Excepted Article, Material or Supply in Federal Acquisition Regulation Subpart 25.108.

By selecting this certification statement, the bidder or offeror agrees:

- a) To provide to the Airport Sponsor or FAA evidence that documents the source and origin of the steel and manufactured product.
- b) To faithfully comply with providing U.S. domestic product.
- c) To furnish U.S. domestic product for any waiver request that the FAA rejects.
- d) To refrain from seeking a waiver request after establishment of the contract, unless extenuating circumstances emerge that the FAA determines justified.
- The bidder or offeror hereby certifies it cannot comply with the 100 percent Buy American Preferences of 49 USC § 50101(a) but may qualify for a Type 3 waiver under 49 USC § 50101(b). By selecting this certification statement, the apparent bidder or offeror with the apparent low bid agrees:
 - a) To submit to the Airport Sponsor or FAA within 15 calendar days of being selected as the responsive bidder, a formal waiver request and required documentation that supports the type of waiver being requested.
 - b) That failure to submit the required documentation within the specified timeframe is cause for a non-responsive determination that may result in rejection of the proposal.

- c) To faithfully comply with providing U.S. domestic products at or above the approved U.S. domestic content percentage as approved by the FAA.
- d) To refrain from seeking a waiver request after establishment of the contract, unless extenuating circumstances emerge that the FAA determines justified.

Required Documentation

Type 2 Waiver (**Nonavailability**) - The iron, steel, manufactured goods or construction materials are not available in sufficient quantity or quality in the United States. The required documentation for the Nonavailability waiver is:

- a) Completed Content Percentage Worksheet and Final Assembly Questionnaire
- b) Record of thorough market research, consideration where appropriate of qualifying alternate items, products, or materials including;
- c) A description of the market research activities and methods used to identify domestically manufactured items capable of satisfying the requirement, including the timing of the research and conclusions reached on the availability of sources.

Type 3 Waiver – The cost of the item components and subcomponents produced in the United States is more that 60 percent of the cost of all components and subcomponents of the "item". The required documentation for a Type 3 waiver is:

- a) Completed Content Percentage Worksheet and Final Assembly Questionnaire including;
- b) Listing of all product components and subcomponents that are not comprised of 100 percent U.S. domestic content (Excludes products listed on the FAA Nationwide Buy American Waivers Issued listing and products excluded by Federal Acquisition Regulation Subpart 25.108 (products of unknown origin must be considered as non-domestic products in their entirety).
- c) Cost of non-domestic components and subcomponents, excluding labor costs associated with final assembly at place of manufacture.
- d) Percentage of non-domestic component and subcomponent cost as compared to total "item" component and subcomponent costs, excluding labor costs associated with final assembly at place of manufacture.

Type 4 Waiver (Unreasonable Costs) - Applying this provision for iron, steel, manufactured goods or construction materials, would increase the cost of the overall project by more than 25 percent. The required documentation for this waiver is:

- a) Completed Content Percentage Worksheet and Final Assembly Questionnaire from
- b) At minimum two comparable equal bidders and/or offerors;
- c) Receipt or record that demonstrates that supplier scouting called for in Executive Order 14005, indicates that no domestic source exists for the project and/or component;
- d) Completed waiver applications for each comparable bid and/or offer.

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

False Statements: Per 49 USC § 47126, this certifica	ation concerns a matter within the jurisdiction of
the Federal Aviation Administration and the making or render the maker subject to prosecution under Title 18	•
Date	Signature
Company Name	Title

A5 CIVIL RIGHTS - GENERAL

A5.1 SOURCE

49 USC § 47123

A5.2 APPLICABILITY

There are two separate civil rights provisions that apply to projects:

- 1. FAA General Civil Rights Provision and,
- 2. Title VI provisions, which are addressed in Appendix A6.

Contract Types – The General Civil Rights Provisions found in 49 USC § 47123, derived from the Airport and Airway Improvement Act of 1982, Section 520, apply to all Sponsor contracts *regardless* of funding source.

Use of Provision – MANDATORY TEXT. Each contract must include two civil rights provisions. The first general clause must be included in all contracts, lease agreements, or transfer agreements. An additional specific provision must be included; the applicable text is based on whether the contract is a general contract or whether the contract is a lease or transfer agreement. The Sponsor must incorporate the text of the appropriate general clause and specific clause without modification into the contract, lease, or transfer agreement.

The required clauses for each type of contact are summarized in the table below:

Contract Clause	The Sponsor must include the contract clause in:	Clause Text is Included in Paragraph
Clause that is used for all contracts, lease agreements and transfer agreements	Every contract or agreement regardless of funding source .	A5.3.1
Clause that is used for general contract agreements	This applies to all contracts that do not involve property agreements. It applies to all contracts not covered by A5.3.3 regardless of funding source.	A5.3.2
Clause that is used for lease agreements and transfer agreements	This applies to all property agreements such leases of concession space in a terminal and leases where a physical portion of the airport is transferred for use. It applies to all contracts not covered by A5.3.2 regardless of funding source.	A5.3.3

A5.3 MANDATORY CONTRACT CLAUSES

A5.3.1 General Clause that is used for Contracts, Lease Agreements, and Transfer Agreements

GENERAL CIVIL RIGHTS PROVISIONS

In all its activities within the scope of its airport program, the Contractor agrees to comply with pertinent statutes, Executive Orders, and such rules as identified in Title VI List of Pertinent Nondiscrimination Acts and Authorities to ensure that no person shall, on the grounds of race, color, national origin (including limited English proficiency), creed, sex (including sexual orientation and gender identity), age, or disability be excluded from participating in any activity conducted with or benefiting from Federal assistance.

This provision is in addition to that required by Title VI of the Civil Rights Act of 1964.

A5.3.2 Specific Clause that is used for General Contract Agreements

The above provision binds the Contractor and subcontractors from the bid solicitation period through the completion of the contract.

A5.3.3 Specific Clause that is used for Lease Agreements or Transfer Agreements

If the Contractor transfers its obligation to another, the transferee is obligated in the same manner as the Contractor.

The above provision obligates the Contractor for the period during which the property is owned, used or possessed by the Contractor and the airport remains obligated to the Federal Aviation Administration.

A6 CIVIL RIGHTS - TITLE VI ASSURANCE

A6.1 SOURCE

49 USC § 47123

FAA Order 1400.11

A6.2 APPLICABILITY

Title VI of the Civil Rights Act of 1964, as amended, (Title VI) prohibits discrimination on the grounds of race, color, or national origin under any program or activity receiving Federal financial assistance. Sponsors must include appropriate clauses from the Standard DOT Title VI Assurances in all contracts and solicitations.

The text of each individual clause comes from the U.S. Department of Transportation <u>Order DOT 1050.2</u>, Standard Title VI Assurances and Nondiscrimination Provisions, effective April 24, 2013. These assurances require that the Recipient (the Sponsor) insert the appropriate clauses in the form provided by the DOT. Where the clause refers to the applicable activity, project, or program, it means the AIP project.

The clauses are as follows:

A6.2.1 Applicability of Title VI Solicitation Notice

Contract Clause	The Sponsor must include the contract clause in:	Clause Text is Included in Paragraph
 Title VI Solicitation Notice – Assurance 2 of the DOT Standard Title VI Assurances and Nondiscrimination Clauses Assurance 30(d) of the Airport Sponsors Assurances 	 All AIP funded solicitations for bids, requests for proposals, or any work subject to Title VI regulations; and All Sponsor proposals for negotiated agreements regardless of funding source. 	A6.3.1
Title VI Clauses for Compliance with Nondiscrimination Requirements • Assurance 3 of the DOT Standard Title VI Assurances and Nondiscrimination Clauses • Assurance 30(e)(1) of the Airport Sponsor Assurances	Every contract or agreement (unless the Sponsor has determined, and the FAA concurs, that the contract or agreement is not subject to the Nondiscrimination Acts and Authorities, which is a rare occurrence). It has been determined that service contracts with utility companies that are not already subject to substantively identical nondiscrimination requirements must include this clause.	A6.4.2

Contract Clause	The Sponsor must include the contract clause in:	Clause Text is Included in Paragraph
Title VI Required Clause for Property Interests Transferred from the United States • Assurance 4 of the DOT Standard Title VI Assurances and Nondiscrimination Clauses • Assurance 30e.3 of the Airport Sponsor Assurances	As a covenant running with the land, in any deed from the United States effecting or recording a transfer of real property, structures, use, or improvements thereon or interest therein to a Sponsor. This is a rare occurrence, and it will be the responsibility of the United States government to include the clause in the contract.	A6.4.3
Title VI Required Clause for Transfer of Real Property Acquired or Improved Under the Activity, Facility or Program – • Assurance 5 of the DOT Standard Title VI Assurances and Nondiscrimination Clauses • Assurance 30(e)(4)(a) of the Airport Sponsor Assurances	As a covenant running with the land, in any future deeds, leases, licenses, permits, or similar instruments entered into by the Sponsor with other parties for all transfers of real property acquired or improved under Airport Improvement Program This applies to agreements such as leases where a physical portion of the airport is transferred for use, for example a fuel farm, apron space, or a parking facility. It applies to agreements not covered by A6.4.4.	A6.4.4
Clause for Construction/Use/Access to Real Property Acquired Under the Activity, Facility or Program • Assurance 6 of the DOT Standard Title VI Assurances and Nondiscrimination Clauses • Assurance 30(e)(4)(b) of the Airport Sponsor Assurances	In any future (deeds, leases, licenses, permits, or similar instruments) entered into by the Sponsor with other parties for the construction or use of, or access to, space on, over, or under real property acquired or improved under Airport Improvement Program This applies to agreements such as leases of concession space in a terminal not covered by A6.4.3.	A6.4.5

Contract Clause	The Sponsor must include the contract clause in:	Clause Text is Included in Paragraph
Title VI List of Pertinent Nondiscrimination Acts and Authorities • Assurance 3 of the DOT Standard Title VI Assurances and Nondiscrimination Clauses • Assurance 30(e)(2) of the Airport Sponsor Assurances	Insert this list in every contract or agreement, unless the Sponsor has determined, and the FAA concurs, that the contract or agreement is not subject to the Nondiscrimination Acts and Authorities, which is a rare occurrence. This list can only be omitted if the FAA has determined that the contractor or company is already subject to substantively identical nondiscrimination requirements.	A6.4.1 List must be included in all applicable contracts.

A6.3 MANDATORY SOLICITATION CLAUSE

The Sponsor must include this clause in:

- All AIP funded solicitations for bids, requests for proposals, or any work subject to Title VI regulations; and
- 2) All Sponsor proposals for negotiated agreements **regardless of funding source.**

A6.3.1 Title VI Solicitation Notice

Title VI Solicitation Notice:

The (Name of Sponsor), in accordance with the provisions of Title VI of the Civil Rights Act of 1964 (78 Stat. 252, 42 USC §§ 2000d to 2000d-4) and the Regulations, hereby notifies all bidders or offerors that it will affirmatively ensure that for any contract entered into pursuant to this advertisement, [select businesses, or disadvantaged business enterprises or airport concession disadvantaged business enterprises] will be afforded full and fair opportunity to submit bids in response to this invitation and no businesses will be discriminated against on the grounds of race, color, national origin (including limited English proficiency), creed, sex (including sexual orientation and gender identity), age, or disability in consideration for an award.

A6.4 MANDATORY CONTRACT CLAUSES

A6.4.1 Title VI List of Pertinent Nondiscrimination and Authorities

Insert this list in every contract or agreement, unless the Sponsor has determined and the FAA concurs, that the contract or agreement is not subject to the Nondiscrimination Acts and Authorities. This list can be omitted if the FAA has determined that the contractor or company is already subject to nondiscrimination requirements, which is a rare occurrence.

Title VI List of Pertinent Nondiscrimination Acts and Authorities

During the performance of this contract, the Contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "Contractor") agrees to comply with the following non-discrimination statutes and authorities; including but not limited to:

- Title VI of the Civil Rights Act of 1964 (42 USC § 2000d *et seq.*, 78 stat. 252) (prohibits discrimination on the basis of race, color, national origin);
- 49 CFR part 21 (Non-discrimination in Federally-Assisted programs of the Department of Transportation—Effectuation of Title VI of the Civil Rights Act of 1964);
- The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 USC § 4601) (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects);
- Section 504 of the Rehabilitation Act of 1973 (29 USC § 794 *et seq.*), as amended (prohibits discrimination on the basis of disability); and 49 CFR part 27 (Nondiscrimination on the Basis of Disability in Programs or Activities Receiving Federal Financial Assistance);
- The Age Discrimination Act of 1975, as amended (42 USC § 6101 *et seq.*) (prohibits discrimination on the basis of age);
- Airport and Airway Improvement Act of 1982 (49 USC § 47123), as amended (prohibits discrimination based on race, creed, color, national origin, or sex);
- The Civil Rights Restoration Act of 1987 (PL 100-259) (broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, the Age Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition of the terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, subrecipients and contractors, whether such programs or activities are Federally funded or not);
- Titles II and III of the Americans with Disabilities Act of 1990 (42 USC § 12101, et seq) (prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities) as implemented by U.S. Department of Transportation regulations at 49 CFR parts 37 and 38;
- The Federal Aviation Administration's Nondiscrimination statute (49 USC § 47123) (prohibits discrimination on the basis of race, color, national origin, and sex);
- Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations (ensures nondiscrimination against minority populations by discouraging programs, policies, and activities with disproportionately high and adverse human health or environmental effects on minority and low-income populations);
- Executive Order 13166, Improving Access to Services for Persons with Limited English
 Proficiency, and resulting agency guidance, national origin discrimination includes discrimination
 because of limited English proficiency (LEP). To ensure compliance with Title VI, you must
 take reasonable steps to ensure that LEP persons have meaningful access to your programs [70
 Fed. Reg. 74087 (2005)];
- Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 USC § 1681, et seq).

A6.4.2 Nondiscrimination Requirements/Title VI Clauses for Compliance

The Sponsor must include this contract clause in:

- 1) Every contract or agreement (unless the Sponsor has determined, and the FAA concurs, that the contract or agreement is not subject to the Nondiscrimination Acts and Authorities); and
- 2) Service contracts with utility companies that are not already subject to substantively identical nondiscrimination requirements.
- 3) Other types of contracts with utility companies involving property covered by A6.4.2, A6.4.3, or A6.4.4.

Compliance with Nondiscrimination Requirements:

During the performance of this contract, the Contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "Contractor"), agrees as follows:

- Compliance with Regulations: The Contractor (hereinafter includes consultants) will
 comply with the Title VI List of Pertinent Nondiscrimination Acts and Authorities, as they
 may be amended from time to time, which are herein incorporated by reference and made a
 part of this contract.
- 2. **Nondiscrimination:** The Contractor, with regard to the work performed by it during the contract, will not discriminate on the grounds of race, color, national origin (including limited English proficiency), creed, sex (including sexual orientation and gender identity), age, or disability in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The Contractor will not participate directly or indirectly in the discrimination prohibited by the Nondiscrimination Acts and Authorities, including employment practices when the contract covers any activity, project, or program set forth in Appendix B of 49 CFR part 21.
- 3. Solicitations for Subcontracts, including Procurements of Materials and Equipment: In all solicitations, either by competitive bidding or negotiation made by the Contractor for work to be performed under a subcontract, including procurements of materials, or leases of equipment, each potential subcontractor or supplier will be notified by the Contractor of the contractor's obligations under this contract and the Nondiscrimination Acts and Authorities on the grounds of race, color, or national origin.
- 4. **Information and Reports:** The Contractor will provide all information and reports required by the Acts, the Regulations, and directives issued pursuant thereto and will permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Sponsor or the Federal Aviation Administration to be pertinent to ascertain compliance with such Nondiscrimination Acts and Authorities and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish the information, the Contractor will so certify to the Sponsor or the Federal Aviation Administration, as appropriate, and will set forth what efforts it has made to obtain the information.
- 5. **Sanctions for Noncompliance:** In the event of a Contractor's noncompliance with the non-discrimination provisions of this contract, the Sponsor will impose such contract sanctions as it or the Federal Aviation Administration may determine to be appropriate, including, but not limited to:
 - a. Withholding payments to the Contractor under the contract until the Contractor complies; and/or
 - b. Cancelling, terminating, or suspending a contract, in whole or in part.

6. **Incorporation of Provisions:** The Contractor will include the provisions of paragraphs one through six in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Acts, the Regulations, and directives issued pursuant thereto. The Contractor will take action with respect to any subcontract or procurement as the Sponsor or the Federal Aviation Administration may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, that if the Contractor becomes involved in, or is threatened with litigation by a subcontractor, or supplier because of such direction, the Contractor may request the Sponsor to enter into any litigation to protect the interests of the Sponsor. In addition, the Contractor may request the United States to enter into the litigation to protect the interests of the United States.

A6.4.3 Title VI Clauses for Deeds Transferring United States Property

This is a rare occurrence, and it will be the responsibility of the United States government to include the clause in the contract. It will be included as a covenant running with the land, in any deed from the United States effecting or recording a transfer of real property, structures, use, or improvements thereon or interest therein to a Sponsor.

CLAUSES FOR DEEDS TRANSFERRING UNITED STATES PROPERTY

The following clauses will be included in deeds effecting or recording the transfer of real property, structures, or improvements thereon, or granting interest therein from the United States pursuant to the provisions of the Airport Improvement Program grant assurances:

NOW, THEREFORE, the Federal Aviation Administration as authorized by law and upon the condition that the (*Title of Sponsor*) will accept title to the lands and maintain the project constructed thereon in accordance with (*Name of Appropriate Legislative Authority*), for the (Airport Improvement Program or other program for which land is transferred), and the policies and procedures prescribed by the Federal Aviation Administration of the U.S. Department of Transportation in accordance and in compliance with all requirements imposed by Title 49, Code of Federal Regulations, U.S. Department of Transportation, Subtitle A, Office of the Secretary, Part 21, Non-discrimination in Federally-assisted programs of the U.S. Department of Transportation pertaining to and effectuating the provisions of Title VI of the Civil Rights Act of 1964 (78 Stat. 252; 42 USC §§ 2000d to 2000d-4), does hereby remise, release, quitclaim and convey unto the (*Title of Sponsor*) all the right, title and interest of the U.S. Department of Transportation/Federal Aviation Administration in and to said lands described in (*Exhibit A attached hereto or other exhibit describing the transferred property*) and made a part hereof.

(HABENDUM CLAUSE)

TO HAVE AND TO HOLD said lands and interests therein unto (*Title of Sponsor*) and its successors forever, subject, however, to the covenants, conditions, restrictions and reservations herein contained as follows, which will remain in effect for the period during which the real property or structures are used for a purpose for which Federal financial assistance is extended or for another purpose involving the provision of similar services or benefits and will be binding on the (*Title of Sponsor*), its successors and assigns.

The (*Title of Sponsor*), in consideration of the conveyance of said lands and interests in lands, does hereby covenant and agree as a covenant running with the land for itself, its successors and assigns, that (1) no person will on the grounds of race, color, or national origin, be excluded from participation in, be denied the benefits of, or be otherwise subjected to discrimination with regard to any facility located wholly or in part on, over, or under such lands hereby conveyed [,] [and]* (2) that the (*Title of Sponsor*) will use the lands and interests in lands and interests in lands so conveyed, in compliance with all requirements imposed by or pursuant to Title 49, Code of Federal Regulations, U.S. Department of Transportation, Subtitle A, Office of the Secretary, Part 21, Non-discrimination in Federally-assisted programs of the U.S. Department of Transportation, Effectuation of Title VI of the Civil Rights Act of 1964, and as said Regulations and Acts may be amended[, and (3) that in the event of breach of any of the above-mentioned nondiscrimination conditions, the Department will have a right to enter or re-enter said lands and facilities on said land, and that above described land and facilities will thereon revert to and vest in and become the absolute property of the Federal Aviation Administration and its assigns as such interest existed prior to this instruction].*

(*Reverter clause and related language to be used only when it is determined that such a clause is necessary in order to make clear the purpose of Title VI.)

A6.4.4 Title VI Clauses for Transfer of Real Property Acquired or Improved Under the Activity, Facility, or Program

This applies to agreements such as leases where a physical portion of the airport is transferred for use—for example a fuel farm, apron space, or a parking facility—and will be included as a covenant running with the land, in any future deeds, leases, licenses, permits, or similar instruments entered into by the Sponsor with other parties for all transfers of real property acquired or improved under the Airport Improvement Program.

CLAUSES FOR TRANSFER OF REAL PROPERTY ACQUIRED OR IMPROVED UNDER THE AIRPORT IMPROVEMENT PROGRAM

The following clauses will be included in deeds, licenses, leases, permits, or similar instruments entered into by the Sponsor pursuant to the provisions of the Airport Improvement Program grant assurances:

- A. The (grantee, lessee, permittee, etc. as appropriate) for himself/herself, his/her heirs, personal representatives, successors in interest, and assigns, as a part of the consideration hereof, does hereby covenant and agree [in the case of deeds and leases add "as a covenant running with the land"] that:
 - 1. In the event facilities are constructed, maintained, or otherwise operated on the property described in this (deed, license, lease, permit, etc.) for a purpose for which a Federal Aviation Administration activity, facility, or program is extended or for another purpose involving the provision of similar services or benefits, the (grantee, licensee, lessee, permittee, etc.) will maintain and operate such facilities and services

in compliance with all requirements imposed by the Nondiscrimination Acts and Regulations listed in the Title VI List of Pertinent Nondiscrimination Acts and Authorities (as may be amended) such that no person on the grounds of race, color, or national origin, will be excluded from participation in, denied the benefits of, or be otherwise subjected to discrimination in the use of said facilities.

- B. With respect to licenses, leases, permits, etc., in the event of breach of any of the above Nondiscrimination covenants, (*Title of Sponsor*) will have the right to terminate the (lease, license, permit, etc.) and to enter, re-enter, and repossess said lands and facilities thereon, and hold the same as if the (lease, license, permit, etc.) had never been made or issued.*
- C. With respect to a deed, in the event of breach of any of the above Nondiscrimination covenants, the (*Title of Sponsor*) will have the right to enter or re-enter the lands and facilities thereon, and the above-described lands and facilities will there upon revert to and vest in and become the absolute property of the (*Title of Sponsor*) and its assigns.*

(*Reverter clause and related language to be used only when it is determined that such a clause is necessary to make clear the purpose of Title VI.)

A6.4.5 Title VI Clauses for Construction/Use/Access to Real Property Acquired Under the Activity, Facility or Program

This applies to agreements such as leases of concession space in a terminal and any future deeds, leases, licenses, permits, or similar instruments entered into by the Sponsor with other parties for the construction or use of, or access to, space on, over, or under real property acquired or improved under the Airport Improvement Program.

CLAUSES FOR CONSTRUCTION/USE/ACCESS TO REAL PROPERTY ACQUIRED UNDER THE ACTIVITY, FACILITY OR PROGRAM

The following clauses will be included in deeds, licenses, permits, or similar instruments/agreements entered into by (*Title of Sponsor*) pursuant to the provisions of the Airport Improvement Program grant assurances.

- A. The (grantee, licensee, permittee, etc., as appropriate) for himself/herself, his/her heirs, personal representatives, successors in interest, and assigns, as a part of the consideration hereof, does hereby covenant and agree (in the case of deeds and leases add, "as a covenant running with the land") that (1) no person on the ground of race, color, or national origin, will be excluded from participation in, denied the benefits of, or be otherwise subjected to discrimination in the use of said facilities, (2) that in the construction of any improvements on, over, or under such land, and the furnishing of services thereon, no person on the ground of race, color, or national origin, will be excluded from participation in, denied the benefits of, or otherwise be subjected to discrimination, (3) that the (grantee, licensee, lessee, permittee, etc.) will use the premises in compliance with all other requirements imposed by or pursuant to the Title VI List of Pertinent Nondiscrimination Acts and Authorities.
- B. With respect to (licenses, leases, permits, etc.), in the event of breach of any of the above Non-discrimination covenants, (*Title of Sponsor*) will have the right to terminate the (license, permit, etc., as appropriate) and to enter or re-enter and repossess said land and the facilities

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

- thereon, and hold the same as if said (license, permit, etc., as appropriate) had never been made or issued.*
- C. With respect to deeds, in the event of breach of any of the above Non-discrimination covenants, (*Title of Sponsor*) will there upon revert to and vest in and become the absolute property of (*Title of Sponsor*) and its assigns.*

(*Reverter clause and related language to be used only when it is determined that such a clause is necessary to make clear the purpose of Title VI.)

A7 CLEAN AIR AND WATER POLLUTION CONTROL

A7.1 SOURCE

2 CFR Part 200, Appendix II(G)

42 USC § 7401, et seq

33 USC § 1251, et seq

A7.2 APPLICABILITY

Contract Types – This provision is required for all contracts and lower tier contracts that exceed \$150,000.

Use of Provision – No mandatory language provided. The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of Appendix II to 2 CFR § 200.

A7.3 MODEL CONTRACT CLAUSE

CLEAN AIR AND WATER POLLUTION CONTROL

Contractor agrees to comply with all applicable standards, orders, and regulations issued pursuant to the Clean Air Act (42 USC §§ 7401-7671q) and the Federal Water Pollution Control Act as amended (33 USC §§ 1251-1387). The Contractor agrees to report any violation to the Owner immediately upon discovery. The Owner assumes responsibility for notifying the Environmental Protection Agency (EPA) and the Federal Aviation Administration.

Contractor must include this requirement in all subcontracts that exceed \$150,000.

A8 CONTRACT WORKHOURS AND SAFETY STANDARDS ACT REQUIREMENTS

A8.1 SOURCE

2 CFR Part 200, Appendix II(E)

2 CFR § 5.5(b)

40 USC § 3702

40 USC § 3704

A8.2 APPLICABILITY

Contract Work Hours and Safety Standards Act Requirements (CWHSSA) (40 USC §§ 3702 & 3704) requires contractors and subcontractors on covered contracts to pay laborers and mechanics employed in the performance of the contracts not less than one and one-half times their basic rate of pay for all hours worked over 40 in a workweek. CWHSSA prohibits unsanitary, hazardous, or dangerous working conditions on federally-assisted projects. The Wage and Hour Division (WHD) within the U.S. Department of Labor (DOL) enforces the compensation requirements of this Act, while DOL's Occupational Safety and Health Administration (OSHA) enforces the safety and health requirements.

Contract Types –

Construction – This provision applies to all contracts and lower tier contracts that exceed \$100,000, and employ laborers, mechanics, watchmen, and guards.

Equipment – This provision applies to any equipment project exceeding \$100,000 that involves installation of equipment onsite (e.g., electrical vault equipment). This provision does not apply to equipment acquisition projects where the manufacture of the equipment takes place offsite at the vendor plant (e.g., ARFF and SRE vehicles).

Professional Services – This provision applies to professional service agreements that exceed \$100,000 and employs laborers, mechanics, watchmen, and guards. This includes members of survey crews and exploratory drilling operations.

Property – While most land transactions do not involve employment of laborers, mechanics, watchmen, and guards, under certain circumstances, a property acquisition project could require such employment. Examples include the installation of property fencing or testing for environmental contamination

Use of Provision – MANDATORY TEXT. Sponsors must incorporate this text without modification.

A8.3 MANDATORY CONTRACT CLAUSE

CONTRACT WORKHOURS AND SAFETY STANDARDS ACT REQUIREMENTS

1. Overtime Requirements.

No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic, including watchmen and guards, in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek.

2. Violation; Liability for Unpaid Wages; Liquidated Damages.

In the event of any violation of the clause set forth in paragraph (1) of this clause, the Contractor and any subcontractor responsible therefor shall be liable for the unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the clause set forth in paragraph (1) of this clause, in the sum of \$29 for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph (1) of this clause.

3. Withholding for Unpaid Wages and Liquidated Damages.

The Federal Aviation Administration (FAA) or the Owner shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph (2) of this clause.

4. Subcontractors.

The Contractor or subcontractor shall insert in any subcontracts the clauses set forth in paragraphs (1) through (4) and also a clause requiring the subcontractor to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs (1) through (4) of this clause.

A9 COPELAND "ANTI-KICKBACK" ACT

A9.1 SOURCE

2 CFR Part 200, Appendix II(D)

29 CFR Parts 3 and 5

A9.2 APPLICABILITY and PURPOSE

The Copeland (Anti-Kickback) Act (18 USC § 874 and 40 USC § 3145) makes it unlawful to induce by force, intimidation, threat of dismissal from employment, or by any other manner, any person employed in the construction or repair of public buildings or public works, financed in whole or in part by the United States, to give up any part of the compensation to which that person is entitled under a contract of employment. The Copeland Act also requires each contractor and subcontractor to furnish weekly a statement of compliance with respect to the wages paid each employee during the preceding week.

Contract Types –

Construction – This provision applies to all construction contracts and subcontracts financed under the AIP that exceed \$2,000.

Equipment – This provision applies to all equipment installation projects (e.g., electrical vault improvements) financed under the AIP that exceed \$2,000. This provision does not apply to equipment acquisitions where the equipment is manufactured at the vendor's plant (e.g., SRE and ARFF vehicles).

Professional Services –The emergence of different project delivery methods has created situations where Professional Service Agreements (PSAs) include tasks that meet the definition of construction, alteration, or repair as defined in 29 CFR Part 5. If such tasks result in work that qualifies as construction, alteration, or repair and it exceeds \$2,000, the PSA must incorporate the Copeland Anti-kickback provision.

Property –Ordinarily, land acquisition projects would not involve employment of laborers or mechanics and thus the Copeland Anti-Kickback provision would not apply. However, land projects that involve installation of boundary fencing and demolition of structures would involve laborers and mechanics. The Sponsor must include this provision if the land acquisition project involves employment of laborers or mechanics for a contract exceeding \$2,000.

Use of Provision – No mandatory language provided. The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of 29 CFR Part 5.

A9.3 MODEL CONTRACT CLAUSE

COPELAND "ANTI-KICKBACK" ACT

Contractor must comply with the requirements of the Copeland "Anti-Kickback" Act (18 USC 874 and 40 USC 3145), as supplemented by Department of Labor regulation 29 CFR part 3. Contractor and

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

subcontractors are prohibited from inducing, by any means, any person employed on the project to give up any part of the compensation to which the employee is entitled. The Contractor and each Subcontractor must submit to the Owner, a weekly statement on the wages paid to each employee performing on covered work during the prior week. Owner must report any violations of the Act to the Federal Aviation Administration.

A10 DAVIS-BACON REQUIREMENTS

A10.1 SOURCE

2 CFR Part 200, Appendix II(D)

29 CFR Part 5

49 USC § 47112(b)

40 USC §§ 3141-3144, 3146, and 3147

A10.2 APPLICABILITY

The Davis-Bacon Act (40 USC §§ 3141-3144, 3146, and 3147) ensures that laborers and mechanics employed under the contract receive pay no less than the locally prevailing wages and fringe benefits as determined by the Department of Labor.

Contract Types –

Construction – Incorporate into all construction contracts and subcontracts that exceed \$2,000 and include funding from the AIP.

Equipment – This provision applies to all equipment installation projects (e.g., electrical vault improvements) financed under the AIP that exceed \$ 2,000. This provision does not apply to equipment acquisitions where the equipment is manufactured at the vendor's plant (e.g., SRE and ARFF vehicles)

Professional Services – The emergence of different project delivery methods has created situations where Professional Service Agreements (PSAs) includes tasks that meet the definition of construction, alteration, or repair as defined in 29 CFR Part 5. If such tasks result in work that qualifies as construction, alteration, or repair and it exceeds \$2,000, the PSA must incorporate this clause.

Property – Ordinarily, land acquisition projects would not involve employment of laborers or mechanics and thus the provision would not apply. However, land projects that involve installation of boundary fencing and demolition of structures would involve laborers and mechanics. The Sponsor must include this provision if the land acquisition project involves employment of laborers or mechanics for a contract exceeding \$2,000.

Fencing Projects – Fencing projects that exceed \$2,000 must include this provision.

Use of Provision – **MANDATORY TEXT.** 29 CFR part 5 establishes specific language a Sponsor must use. The Sponsor may not make any modification to the standard language. A/E firms that employ laborers and mechanics on a task that meets the definition of construction, alteration, or repair are acting as a contractor. The Sponsor may not substitute the term "Contractor" for "Consultant" in such instances.

A10.3 MANDATORY CONTRACT CLAUSE

DAVIS-BACON REQUIREMENTS

1. Minimum Wages.

(i) All laborers and mechanics employed or working upon the site of the work will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by the Secretary of Labor under the Copeland Act (29 CFR Part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalent thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the Contractor and such laborers and mechanics.

Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph (1)(iv) of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in 29 CFR § 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: *Provided*, that the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under (1)(ii) of this section) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the Contractor and its subcontractors at the site of the work in a prominent and accessible place where it can easily be seen by the workers.

- (ii)(A) The contracting officer shall require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The contracting officer shall approve an additional classification and wage rate and fringe benefits therefore only when the following criteria have been met:
- (1) The work to be performed by the classification requested is not performed by a classification in the wage determination;
- (2) The classification is utilized in the area by the construction industry; and
- (3) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.
- (B) If the Contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the Administrator of the Wage and Hour Division, U.S. Department of Labor,

Washington, DC 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

- (C) In the event the Contractor, the laborers, or mechanics to be employed in the classification, or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Administrator for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.
- (D) The wage rate (including fringe benefits where appropriate) determined pursuant to subparagraphs (1)(ii) (B) or (C) of this paragraph, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.
- (iii) Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.
- (iv) If the Contractor does not make payments to a trustee or other third person, the Contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, *Provided*, that the Secretary of Labor has found, upon the written request of the Contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the Contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.
- 2. Withholding. The Federal Aviation Administration or the Sponsor shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld from the Contractor under this contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the Contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the Federal Aviation Administration may, after written notice to the Contractor, Sponsor, Applicant, or Owner, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.
- 3. Payrolls and Basic Records.
- (i) Payrolls and basic records relating thereto shall be maintained by the Contractor during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker; his or her correct classification; hourly rates of wages paid (including rates of

contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in 1(b)(2)(B) of the Davis-Bacon Act); daily and weekly number of hours worked; deductions made; and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5(a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-Bacon Act, the Contractor shall maintain records that show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual costs incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.

- (ii)(A) The Contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the Federal Aviation Administration if the agency is a party to the contract, but if the agency is not such a party, the Contractor will submit the payrolls to the applicant, Sponsor, or Owner, as the case may be, for transmission to the Federal Aviation Administration. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under 29 CFR § 5.5(a)(3)(i), except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall only need to include an individually identifying number for each employee (e.g., the last four digits of the employee's social security number). The required weekly payroll information may be submitted in any form desired. Optional Form WH-347 is available for this purpose from the Wage and Hour Division Web site at https://www.dol.gov/agencies/whd/government-contracts/construction/payroll-certification or its successor site. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors. Contractors and subcontractors shall maintain the full social security number and current address of each covered worker and shall provide them upon request to the Federal Aviation Administration if the agency is a party to the contract, but if the agency is not such a party, the Contractor will submit them to the applicant, Sponsor, or Owner, as the case may be, for transmission to the Federal Aviation Administration, the Contractor, or the Wage and Hour Division of the Department of Labor for purposes of an investigation or audit of compliance with prevailing wage requirements. It is not a violation of this section for a prime contractor to require a subcontractor to provide addresses and social security numbers to the prime contractor for its own records, without weekly submission to the sponsoring government agency (or the applicant, Sponsor, or Owner).
- (B) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the Contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:
- (1) That the payroll for the payroll period contains the information required to be provided under 29 CFR § 5.5(a)(3)(ii), the appropriate information is being maintained under 29 CFR § 5.5 (a)(3)(i), and that such information is correct and complete;
- (2) That each laborer and mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either

directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in Regulations, 29 CFR Part 3;

- (3) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.
- (C) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph (3)(ii)(B) of this section.
- (D) The falsification of any of the above certifications may subject the Contractor or subcontractor to civil or criminal prosecution under Section 1001 of Title 18 and Section 231 of Title 31 of the United States Code.
- (iii) The Contractor or subcontractor shall make the records required under paragraph (3)(i) of this section available for inspection, copying, or transcription by authorized representatives of the Sponsor, the Federal Aviation Administration, or the Department of Labor and shall permit such representatives to interview employees during working hours on the job. If the Contractor or subcontractor fails to submit the required records or to make them available, the Federal agency may, after written notice to the Contractor, Sponsor, applicant, or Owner, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR § 5.12.
- 4. Apprentices and Trainees.
- (i) Apprentices. Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer and Labor Services, or with a State Apprenticeship Agency recognized by the Office, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Office of Apprenticeship Training, Employer and Labor Services or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice. The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the Contractor's or subcontractor's registered program shall be observed. Every apprentice must be paid at not less than the rate specified in the registered program for

the apprentice's level of progress, expressed as a percentage of the journeymen hourly rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination. In the event the Office of Apprenticeship Training, Employer and Labor Services, or a State Apprenticeship Agency recognized by the Office, withdraws approval of an apprenticeship program, the Contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

- (ii) Trainees. Except as provided in 29 CFR § 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration. The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration. Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate on the wage determination that provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate that is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. In the event the Employment and Training Administration withdraws approval of a training program, the Contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.
- (iii) Equal Employment Opportunity. The utilization of apprentices, trainees, and journeymen under this part shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR Part 30.
- 5. Compliance with Copeland Act Requirements.

The Contractor shall comply with the requirements of 29 CFR Part 3, which are incorporated by reference in this contract.

6. Subcontracts.

The Contractor or subcontractor shall insert in any subcontracts the clauses contained in 29 CFR §\$ 5.5(a)(1) through (10) and such other clauses as the Federal Aviation Administration may by

appropriate instructions require, and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in 29 CFR § 5.5.

7. Contract Termination: Debarment.

A breach of the contract clauses in paragraph 1 through 10 of this section may be grounds for termination of the contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR § 5.12.

8. Compliance with Davis-Bacon and Related Act Requirements.

All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR Parts 1, 3, and 5 are herein incorporated by reference in this contract.

9. Disputes Concerning Labor Standards.

Disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR Parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the Contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

- 10. Certification of Eligibility.
- (i) By entering into this contract, the Contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the Contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR § 5.12(a)(1).
- (ii) No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR § 5.12(a)(1).
- (iii) The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 USC § 1001.

A11 DEBARMENT AND SUSPENSION

A11.1 SOURCE

2 CFR Part 180 (Subpart B)

2 CFR Part 200, Appendix II(H)

2 CFR Part 1200

DOT Order 4200.5

Executive Orders 12549 and 12689

A11.2 APPLICABILITY

The Sponsor must verify that the firm or individual that it is entering into a contract with is not presently suspended, excluded, or debarred by any Federal department or agency from participating in federally-assisted projects. The Sponsor accomplishes this by:

- 1) Checking the System for Award Management (SAM.gov) to verify that the firm or individual is not listed in SAM.gov as being suspended, debarred, or excluded;
- 2) Collecting a certification from the firm or individual that it is not suspended, debarred, or excluded; and
- 3) Incorporating a clause in the contract that requires lower tier contracts to verify that no suspended, debarred, or excluded firm or individual is included in the project.

Contract Types – This requirement applies to *covered transactions*, which are defined in 2 CFR part 180 (Subpart B). AIP funded contracts are non-procurement transactions, as defined by 2 CFR § 180.970. Covered transactions include any AIP-funded contract, regardless of tier, that is awarded by a contractor, subcontractor, supplier, consultant, or its agent or representative in any transaction, if the amount of the contract is expected to equal or exceed \$25,000. This includes contracts associated with land acquisition projects.

Use of Provision – No mandatory language provided. The following language is acceptable to the FAA in meeting the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of 2 CFR part 180. For professional service agreements, Sponsor may substitute "bidder/offeror" with "consultant."

A11.3 MODEL BID/PROPOSAL CERTIFICATION CLAUSES

A11.3.1 Bidder or Offeror Certification

CERTIFICATION OF OFFEROR/BIDDER REGARDING DEBARMENT

By submitting a bid/proposal under this solicitation, the bidder or offeror certifies that neither it nor its principals are presently debarred or suspended by any Federal department or agency from participation in this transaction.

A11.3.2 Lower Tier Contract Certification

CERTIFICATION OF LOWER TIER CONTRACTORS REGARDING DEBARMENT

The successful bidder, by administering each lower tier subcontract that exceeds \$25,000 as a "covered transaction", must confirm each lower tier participant of a "covered transaction" under the project is not presently debarred or otherwise disqualified from participation in this federally-assisted project. The successful bidder will accomplish this by:

- 1. Checking the System for Award Management at website: http://www.sam.gov.
- 2. Collecting a certification statement similar to the Certification of Offeror /Bidder Regarding Debarment, above.
- 3. Inserting a clause or condition in the covered transaction with the lower tier contract.

If the Federal Aviation Administration later determines that a lower tier participant failed to disclose to a higher tier participant that it was excluded or disqualified at the time it entered the covered transaction, the FAA may pursue any available remedies, including suspension and debarment of the non-compliant participant.

A12 DISADVANTAGED BUSINESS ENTERPRISE

A12.1 SOURCE

49 CFR Part 26

A12.2 APPLICABILITY

A Sponsor that anticipates awarding \$250,000 or more in AIP funded prime contracts in a federal fiscal year must have an approved Disadvantaged Business Enterprise (DBE) program on file with the FAA Office of Civil Rights (49 CFR § 26.21). The approved DBE program will identify a 3-year overall program goal that the Sponsor bases on the availability of ready, willing, and able DBEs relative to all businesses ready, willing, and able to participate on the project (49 CFR § 26.45).

Contract Types – Sponsors with a DBE program on file with the FAA must include the following provisions, if applicable:

- 1) Clause in all solicitations for proposals for which a contract goal has been established,
- 2) Clause in each prime contract, and
- 3) Clause in solicitations that are obtaining DBE participation through race/gender neutral means.

Use of Provision -

- 1. Solicitations with a DBE Contract Goal No mandatory language provided. 49 CFR §26.53 requires a Sponsor's solicitation to address what a contractor must submit on proposed DBE participation. The language of A12.3.1 is acceptable to the FAA in meeting the intent of this requirement. If the Sponsor uses different language, the Sponsor's revised language must fully satisfy these requirements. The Sponsor may require the contractor's submittal on proposed DBE participation either at bid opening as a matter of responsiveness or within five days of bid opening as a matter of responsibility.
- 2. Solicitations Relying on Race/Gender Neutral Means No mandatory language provided. The language of A12.3.2 is acceptable to the FAA in meeting the intent of this requirement. If the Sponsor uses different language, the Sponsor's revised language must fully satisfy requirements for a Sponsor that is not applying a project specific contract goal but is covered by a DBE program on file with the FAA.
- 3. Assurance for Contracts Covered by DBE Program MANDATORY TEXT PROVIDED. Sponsors must incorporate this language if they have a DBE program on file with the FAA. This includes projects where DBE participation is obtained through race/gender neutral means (i.e., no DBE contract goal). Section 26.13 of 49 CFR establishes mandatory language for contractor assurance. The Sponsor must not modify the language. Part 26 of 49 CFR requires Sponsors ensure this clause also flows down into subcontracts (i.e., must be included verbatim in subcontracts).
- 4. *Prompt Payment for Contracts Covered by DBE Program* No mandatory language provided. Section 26.29 of 49 CFR requires Sponsors to include a contract clause requiring

prompt payment to subcontractors no later than thirty (30) days after the prime contractor receives payment from the Sponsor. The requirement applies to all subcontractors, not just DBEs. The prompt payment language of A12.3.3 is acceptable to the FAA in meeting the intent of this requirement. If the Sponsor uses different language, such as a specific clause identified in the Sponsor's approved DBE program plan, the Sponsor's revised language must fully satisfy these requirements.

- 5. Termination of DBE Subcontractors on Contracts with a DBE Contract Goal No mandatory language provided. Section 26.53 of 49 CFR prohibits unauthorized removal or replacement of DBE firms listed in response to a solicitation that had a DBE contract goal and sets forth the specific enforcement mechanism recipients must include in prime contracts. The language of A12.3.3 is acceptable to the FAA in meeting the intent of this requirement.
- 6. Sponsors that are not required to have a DBE program on file with the FAA are not required to include DBE provisions and clauses.

A12.3 REQUIRED PROVISIONS

A12.3.1 Solicitation Language (Solicitations that include a Contract Goal)

Bid Information Submitted as a matter of **responsiveness**:

The Owner's award of this contract is conditioned upon Bidder or Offeror satisfying the good faith effort requirements of 49 CFR § 26.53.

As a condition of responsiveness, the Bidder or Offeror must submit the following information with its proposal on the forms provided herein:

- 1) The names and addresses of Disadvantaged Business Enterprise (DBE) firms that will participate in the contract;
- 2) A description of the work that each DBE firm will perform;
- 3) The dollar amount of the participation of each DBE firm listed under (1);
- 4) Written statement from Bidder or Offeror that attests their commitment to use the DBE firm(s) listed under (1) to meet the Owner's project goal
- 5) Written confirmation from each listed DBE firm that it is participating in the contract in the kind and amount of work provided in the prime contractor's commitment; and
- 6) If Bidder or Offeror cannot meet the advertised project DBE goal, evidence of good faith efforts undertaken by the Bidder or Offeror as described in appendix A to 49 CFR part 26. The documentation of good faith efforts must include copies of each DBE and non-DBE subcontractor quote submitted to the bidder when a non-DBE subcontractor was selected over a DBE for work on the contract.

Bid Information submitted as a matter of **responsibility**:

The Owner's award of this contract is conditioned upon Bidder or Offeror satisfying the good faith effort requirements of 49 CFR § 26.53.

As a condition of responsibility, every Bidder or Offeror must submit the following information on the forms provided herein within five days after bid opening.

- 1) The names and addresses of Disadvantaged Business Enterprise (DBE) firms that will participate in the contract:
- 2) A description of the work that each DBE firm will perform;
- 3) The dollar amount of the participation of each DBE firm listed under (1);
- 4) Written statement from Bidder or Offeror that attests their commitment to use the DBE firm(s) listed under (1) to meet the Owner's project goal;
- 5) Written confirmation from each listed DBE firm that it is participating in the contract in the kind and amount of work provided in the prime contractor's commitment; and
- 6) If Bidder or Offeror cannot meet the advertised project DBE goal, evidence of good faith efforts undertaken by the Bidder or Offeror as described in appendix A to 49 CFR part 26. The documentation of good faith efforts must include copies of each DBE and non-DBE subcontractor quote submitted to the bidder when a non-DBE subcontractor was selected over a DBE for work on the contract.

A12.3.2 Solicitation Language (Race/Gender Neutral Means)

The requirements of 49 CFR part 26 apply to this contract. It is the policy of the [Insert Name of Owner] to practice nondiscrimination based on race, color, sex, or national origin in the award or performance of this contract. The Owner encourages participation by all firms qualifying under this solicitation regardless of business size or ownership.

A12.3.3 Prime Contracts (Contracts Covered by a DBE Program)

Contract Assurance (49 CFR § 26.13; mandatory text provided) –

The Contractor, subrecipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The Contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of DOT-assisted contracts. Failure by the Contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate, which may include, but is not limited to:

- 1) Withholding monthly progress payments;
- 2) Assessing sanctions;
- 3) Liquidated damages; and/or
- 4) Disqualifying the Contractor from future bidding as non-responsible.

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

Prompt Payment (49 CFR § 26.29; acceptable/sample text provided) –

The prime contractor agrees to pay each subcontractor under this prime contract for satisfactory performance of its contract no later than [specify number of days, not to exceed 30] days from the receipt of each payment the prime contractor receives from [Name of recipient]. The prime contractor agrees further to return retainage payments to each subcontractor within [specify number of days, not to exceed 30] days after the subcontractor's work is satisfactorily completed. Any delay or postponement of payment from the above referenced time frame may occur only for good cause following written approval of the [Name of Recipient]. This clause applies to both DBE and non-DBE subcontractors.

Termination of DBE Subcontracts (49 CFR § 26.53(f); acceptable/sample text provided) –

The prime contractor must not terminate a DBE subcontractor listed in response to [include Solicitation paragraph number where paragraph 12.3.1, Solicitation Language appears] (or an approved substitute DBE firm) without prior written consent of [Name of Recipient]. This includes, but is not limited to, instances in which the prime contractor seeks to perform work originally designated for a DBE subcontractor with its own forces or those of an affiliate, a non-DBE firm, or with another DBE firm.

The prime contractor shall utilize the specific DBEs listed to perform the work and supply the materials for which each is listed unless the contractor obtains written consent [Name of Recipient]. Unless [Name of Recipient] consent is provided, the prime contractor shall not be entitled to any payment for work or material unless it is performed or supplied by the listed DBE.

[Name of Recipient] may provide such written consent only if [Name of Recipient] agrees, for reasons stated in the concurrence document, that the prime contractor has good cause to terminate the DBE firm. For purposes of this paragraph, good cause includes the circumstances listed in 49 CFR §26.53.

Before transmitting to [Name of Recipient] its request to terminate and/or substitute a DBE subcontractor, the prime contractor must give notice in writing to the DBE subcontractor, with a copy to [Name of Recipient], of its intent to request to terminate and/or substitute, and the reason for the request.

The prime contractor must give the DBE five days to respond to the prime contractor's notice and advise [Name of Recipient] and the contractor of the reasons, if any, why it objects to the proposed termination of its subcontract and why [Name of Recipient] should not approve the prime contractor's action. If required in a particular case as a matter of public necessity (e.g., safety), [Name of Recipient] may provide a response period shorter than five days.

In addition to post-award terminations, the provisions of this section apply to preaward deletions of or substitutions for DBE firms put forward by offerors in negotiated procurements.

A13 DISTRACTED DRIVING

A13.1 SOURCE

Executive Order 13513

DOT Order 3902.10

A13.2 APPLICABILITY

The FAA encourages recipients of Federal grant funds to adopt and enforce safety policies that decrease crashes by distracted drivers, including policies to ban text messaging while driving when performing work related to a grant or subgrant.

Contract Types – Sponsors must insert this provision in all AIP funded contracts that exceed the micropurchase threshold of 2 CFR § 200.320 (currently set at \$10,000).

Use of Provision – No mandatory text provided. The following language is acceptable to the FAA in meeting the intent of this requirement. If the Sponsor uses different language, the Sponsor's revised language must fully satisfy these requirements.

A13.3 MODEL CONTRACT CLAUSE

TEXTING WHEN DRIVING

In accordance with Executive Order 13513, "Federal Leadership on Reducing Text Messaging While Driving", (10/1/2009) and DOT Order 3902.10, "Text Messaging While Driving", (12/30/2009), the Federal Aviation Administration encourages recipients of Federal grant funds to adopt and enforce safety policies that decrease crashes by distracted drivers, including policies to ban text messaging while driving when performing work related to a grant or subgrant.

In support of this initiative, the Owner encourages the Contractor to promote policies and initiatives for its employees and other work personnel that decrease crashes by distracted drivers, including policies that ban text messaging while driving motor vehicles while performing work activities associated with the project. The Contractor must include the substance of this clause in all sub-tier contracts exceeding \$10,000 that involve driving a motor vehicle in performance of work activities associated with the project.

A14 PROHIBITION ON CERTAIN TELECOMMUNICATIONS AND VIDEO SURVEILLANCE SERVICES OR EQUIPMENT

A14.1 SOURCE

2 CFR § 200, Appendix II(K)

2 CFR § 200.216

A14.2 APPLICABILITY

Sponsors and subgrant recipients are prohibited from using AIP grant funds to:

- a) Procure or obtain,
- b) Extend or renew a contract to procure or obtain, or
- c) Enter into a contract to procure or obtain certain covered telecommunications equipment.

These restrictions apply to telecommunication equipment, services, or systems that use covered telecommunications equipment or services as a substantial or essential component of any system or as critical technology as part of any system. Covered telecommunications equipment is equipment produced or provided by Huawei Technologies Company or ZTE Corporation (or any subsidiary or affiliate of either).

Contract Types – The Sponsor must include this provision in all AIP funded contracts and lower-tier contracts.

Use of Provision – No mandatory text provided. The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's revised language must fully satisfy these requirements. Sponsor may substitute "Contractor and subcontractor" with "Consultant and sub-consultant" for professional service agreements.

A14.3 MODEL CERTIFICATION CLAUSE

PROHIBITION ON CERTAIN TELECOMMUNICATIONS AND VIDEO SURVEILLANCE SERVICES OR EQUIPMENT

Contractor and Subcontractor agree to comply with mandatory standards and policies relating to use and procurement of certain telecommunications and video surveillance services or equipment in compliance with the National Defense Authorization Act [Public Law 115-232 § 889(f)(1)].

A15 DRUG FREE WORKPLACE REQUIREMENTS

A15.1 SOURCE

49 CFR Part 32

Drug-Free Workplace Act of 1988 (41 USC § 8101-8106, as amended)

A15.2 APPLICABILITY

The Drug-Free Workplace Act of 1988 requires some Federal contractors and *all* Federal grantees to agree that they will provide drug-free workplaces as a condition of receiving a contract or grant from a Federal agency. The Act does *not* apply to contractors, subcontractors, or subgrantees, although the Federal grantees workplace may be where the contractors, subcontractors, or subgrantees are working.

Contract Types – This provision applies to all AIP funded projects, but not to the contracts between the grantee (the Sponsor) and a contractor, subcontractors, suppliers, or subgrantees.

Use of Provision – No mandatory or recommended text provided because the requirements do not extend beyond the Sponsor level.

A15.3 CONTRACT CLAUSE

None.

A16 EQUAL EMPLOYMENT OPPORTUNITY (EEO)

A16.1 SOURCE

2 CFR Part 200, Appendix II(C)

41 CFR § 60-1.4

41 CFR § 60-4.3

Executive Order 11246

A16.2 APPLICABILITY

The purpose of this provision is to provide equal opportunity for all persons, without regard to race, color, religion, sex, or national origin who are employed or seeking employment with contractors performing under a federally-assisted construction contract. There are two provisions — a construction clause and a specification clause.

The equal opportunity contract clause must be included in any contract or subcontract when the amount exceeds \$10,000. Once the equal opportunity clause is determined to be applicable, the contract or subcontract must include the clause for the remainder of the year, regardless of the amount or the contract.

Contract Types –

Construction – The Sponsor must incorporate contract and specification language in all construction contracts and subcontracts as required above.

Equipment – The Sponsor must incorporate contract and specification language into all equipment contracts as required above that involves installation of equipment onsite (e.g., electrical vault equipment). This provision does not apply to equipment acquisition projects where the manufacture of the equipment takes place offsite at the vendor plant (e.g., ARFF and SRE vehicles).

Professional Services – The Sponsor must include contract and specification language into all professional service agreements as required above.

Property – The Sponsor must include contract and specification language into all land acquisition projects that include work that qualifies as construction work as defined by 41 CFR part 60 as required above. An example is installation of boundary fencing.

Use of Provision – **MANDATORY TEXT.** 41 CFR § 60-1.4 provides the mandatory *contract* language. 41 CFR § 60-4.3 provides the mandatory *specification* language. The Sponsor must incorporate these clauses without modification.

A16.3 MANDATORY CONTRACT CLAUSE

A16.3.1 EEO Contract Clause

EQUAL OPPORTUNITY CLAUSE

During the performance of this contract, the Contractor agrees as follows:

- (1) The Contractor will not discriminate against any employee or applicant for employment because of race, color, religion, sex, sexual orientation, gender identity, or national origin. The Contractor will take affirmative action to ensure that applicants are employed, and that employees are treated during employment, without regard to their race, color, religion, sex, sexual orientation, gender identify, or national origin. Such action shall include, but not be limited to, the following: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff, or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The Contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided setting forth the provisions of this nondiscrimination clause.
- (2) The Contractor will, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, color, religion, sex, sexual orientation, gender identity, or national origin.
- (3) The contractor will not discharge or in any other manner discriminate against any employee or applicant for employment because such employee or applicant has inquired about, discussed, or disclosed the compensation of the employee or applicant or another employee or applicant. This provision shall not apply to instances in which an employee who has access to the compensation information of other employees or applicants as a part of such employee's essential job functions discloses the compensation of such other employees or applicants to individuals who do not otherwise have access to such information, unless such disclosure is in response to a formal complaint or charge, in furtherance of an investigation, proceeding, hearing, or action, including an investigation conducted by the employer, or is consistent with the contractor's legal duty to furnish information.
- (4) The Contractor will send to each labor union or representative of workers with which it has a collective bargaining agreement or other contract or understanding, a notice to be provided by the agency contracting officer, advising the labor union or workers' representative of the Contractor's commitments under this section 202 of Executive Order 11246 of September 24, 1965, and shall post copies of the notice in conspicuous places available to employees and applicants for employment.
- (5) The Contractor will comply with all provisions of Executive Order 11246 of September 24, 1965, and of the rules, regulations, and relevant orders of the Secretary of Labor.
- (6) The Contractor will furnish all information and reports required by Executive Order 11246 of September 24, 1965, and by the rules, regulations, and orders of the Secretary of Labor, or pursuant thereto, and will permit access to his books, records, and accounts by the contracting agency and the Secretary of Labor for purposes of investigation to ascertain compliance with such rules, regulations, and orders.

- (7) In the event of the Contractor's noncompliance with the nondiscrimination clauses of this contract or with any such rules, regulations, or orders, this contract may be canceled, terminated, or suspended in whole or in part and the Contractor may be declared ineligible for further Government contracts in accordance with procedures authorized in Executive Order 11246 of September 24, 1965, and such other sanctions may be imposed and remedies invoked as provided in Executive Order 11246 of September 24, 1965, or by rule, regulation, or order of the Secretary of Labor, or as otherwise provided by law.
- (8) The Contractor will include the provisions of paragraphs (1) through (8) in every subcontract or purchase order unless exempted by rules, regulations, or orders of the Secretary of Labor issued pursuant to section 204 of Executive Order 11246 of September 24, 1965, so that such provisions will be binding upon each subcontractor or vendor. The Contractor will take such action with respect to any subcontract or purchase order as may be directed by the Secretary of Labor as a means of enforcing such provisions, including sanctions for noncompliance: *Provided*, however, that in the event the contractor becomes involved in, or is threatened with, litigation with a subcontractor or vendor as a result of such direction, the Contractor may request the United States to enter into such litigation to protect the interests of the United States.

A16.3.2 EEO Specification

STANDARD FEDERAL EQUAL EMPLOYMENT OPPORTUNITY CONSTRUCTION CONTRACT SPECIFICATIONS

- 1. As used in these specifications:
 - a. "Covered area" means the geographical area described in the solicitation from which this contract resulted;
 - b. "Director" means Director, Office of Federal Contract Compliance Programs (OFCCP), U.S. Department of Labor, or any person to whom the Director delegates authority;
 - c. "Employer identification number" means the Federal social security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department Form 941;
 - d. "Minority" includes:
 - (1) Black (all persons having origins in any of the Black African racial groups not of Hispanic origin);
 - (2) Hispanic (all persons of Mexican, Puerto Rican, Cuban, Central or South American, or other Spanish culture or origin, regardless of race);
 - (3) Asian and Pacific Islander (all persons having origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent, or the Pacific Islands); and
 - (4) American Indian or Alaskan native (all persons having origins in any of the original peoples of North America and maintaining identifiable tribal affiliations through membership and participation or community identification).

- 2. Whenever the Contractor, or any subcontractor at any tier, subcontracts a portion of the work involving any construction trade, it shall physically include in each subcontract in excess of \$10,000 the provisions of these specifications and the Notice which contains the applicable goals for minority and female participation and which is set forth in the solicitations from which this contract resulted.
- 3. If the Contractor is participating (pursuant to 41 CFR part 60-4.5) in a Hometown Plan approved by the U.S. Department of Labor in the covered area either individually or through an association, its affirmative action obligations on all work in the Plan area (including goals and timetables) shall be in accordance with that Plan for those trades which have unions participating in the Plan. Contractors must be able to demonstrate their participation in and compliance with the provisions of any such Hometown Plan. Each contractor or subcontractor participating in an approved plan is individually required to comply with its obligations under the EEO clause and to make a good faith effort to achieve each goal under the Plan in each trade in which it has employees. The overall good faith performance by other contractors or subcontractors toward a goal in an approved Plan does not excuse any covered contractor's or subcontractor's failure to take good faith efforts to achieve the Plan goals and timetables.
- 4. The Contractor shall implement the specific affirmative action standards provided in paragraphs 7a through 7p of these specifications. The goals set forth in the solicitation from which this contract resulted are expressed as percentages of the total hours of employment and training of minority and female utilization the Contractor should reasonably be able to achieve in each construction trade in which it has employees in the covered area. Covered construction contractors performing construction work in a geographical areas where they do not have a Federal or federally assisted construction contract shall apply the minority and female goals established for the geographical area where the work is being performed. Goals are published periodically in the Federal Register in notice form, and such notices may be obtained from any Office of Federal Contract Compliance Programs office or from Federal procurement contracting officers. The Contractor is expected to make substantially uniform progress in meeting its goals in each craft during the period specified.
- 5. Neither the provisions of any collective bargaining agreement, nor the failure by a union with whom the Contractor has a collective bargaining agreement, to refer either minorities or women shall excuse the Contractor's obligations under these specifications, Executive Order 11246, or the regulations promulgated pursuant thereto.
- 6. In order for the nonworking training hours of apprentices and trainees to be counted in meeting the goals, such apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor.
- 7. The Contractor shall take specific affirmative actions to ensure equal employment opportunity. The evaluation of the Contractor's compliance with these specifications shall be based upon its effort to achieve maximum results from its actions. The Contractor shall document these efforts fully, and shall implement affirmative action steps at least as extensive as the following:
 - a. Ensure and maintain a working environment free of harassment, intimidation, and coercion at all sites, and in all facilities at which the Contractor's employees are assigned to work. The Contractor,

where possible, will assign two or more women to each construction project. The Contractor shall specifically ensure that all foremen, superintendents, and other onsite supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working at such sites or in such facilities.

- b. Establish and maintain a current list of minority and female recruitment sources, provide written notification to minority and female recruitment sources and to community organizations when the Contractor or its unions have employment opportunities available, and maintain a record of the organizations' responses.
- c. Maintain a current file of the names, addresses, and telephone numbers of each minority and female off-the-street applicant and minority or female referral from a union, a recruitment source, or community organization and of what action was taken with respect to each such individual. If such individual was sent to the union hiring hall for referral and was not referred back to the Contractor by the union or, if referred, not employed by the Contractor, this shall be documented in the file with the reason therefor, along with whatever additional actions the Contractor may have taken.
- d. Provide immediate written notification to the Director when the union or unions with which the Contractor has a collective bargaining agreement has not referred to the Contractor a minority person or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.
- e. Develop on-the-job training opportunities and/or participate in training programs for the area which expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the Department of Labor. The Contractor shall provide notice of these programs to the sources compiled under 7b above.
- f. Disseminate the Contractor's EEO policy by providing notice of the policy to unions and training programs and requesting their cooperation in assisting the Contractor in meeting its EEO obligations; by including it in any policy manual and collective bargaining agreement; by publicizing it in the company newspaper, annual report, etc.; by specific review of the policy with all management personnel and with all minority and female employees at least once a year; and by posting the company EEO policy on bulletin boards accessible to all employees at each location where construction work is performed.
- g. Review, at least annually, the company's EEO policy and affirmative action obligations under these specifications with all employees having any responsibility for hiring, assignment, layoff, termination, or other employment decisions including specific review of these items with onsite supervisory personnel such superintendents, general foremen, etc., prior to the initiation of construction work at any job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.
- h. Disseminate the Contractor's EEO policy externally by including it in any advertising in the news media, specifically including minority and female news media, and providing written notification to

and discussing the Contractor's EEO policy with other contractors and subcontractors with whom the Contractor does or anticipates doing business.

- i. Direct its recruitment efforts, both oral and written, to minority, female, and community organizations, to schools with minority and female students and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than one month prior to the date for the acceptance of applications for apprenticeship or other training by any recruitment source, the Contractor shall send written notification to organizations such as the above, describing the openings, screening procedures, and tests to be used in the selection process.
- j. Encourage present minority and female employees to recruit other minority persons and women and, where reasonable, provide after school, summer, and vacation employment to minority and female youth both on the site and in other areas of a contractor's work force.
- k. Validate all tests and other selection requirements where there is an obligation to do so under 41 CFR part 60-3.
- 1. Conduct, at least annually, an inventory and evaluation at least of all minority and female personnel, for promotional opportunities and encourage these employees to seek or to prepare for, through appropriate training, etc., such opportunities.
- m. Ensure that seniority practices, job classifications, work assignments, and other personnel practices do not have a discriminatory effect by continually monitoring all personnel and employment related activities to ensure that the EEO policy and the Contractor's obligations under these specifications are being carried out.
- n. Ensure that all facilities and company activities are nonsegregated except that separate or single-user toilet and necessary changing facilities shall be provided to assure privacy between the sexes.
- o. Document and maintain a record of all solicitations of offers for subcontracts from minority and female construction contractors and suppliers, including circulation of solicitations to minority and female contractor associations and other business associations.
- p. Conduct a review, at least annually, of all supervisor's adherence to and performance under the Contractor's EEO policies and affirmative action obligations.
- 8. Contractors are encouraged to participate in voluntary associations, which assist in fulfilling one or more of their affirmative action obligations (7a through 7p). The efforts of a contractor association, joint contractor-union, contractor-community, or other similar group of which the Contractor is a member and participant may be asserted as fulfilling any one or more of its obligations under 7a through 7p of these specifications provided that the Contractor actively participates in the group, makes every effort to assure that the group has a positive impact on the employment of minorities and women in the industry, ensures that the concrete benefits of the program are reflected in the Contractor's minority and female workforce participation, makes a good faith effort to meet its individual goals and timetables, and can provide access to documentation which demonstrates the effectiveness of actions taken on behalf of the Contractor. The obligation to comply, however, is the Contractor's and failure of such a group to fulfill an obligation shall not be a defense for the Contractor's noncompliance.

- 9. A single goal for minorities and a separate single goal for women have been established. The Contractor, however, is required to provide equal employment opportunity and to take affirmative action for all minority groups, both male and female, and all women, both minority and non-minority. Consequently, the Contractor may be in violation of the Executive Order if a particular group is employed in a substantially disparate manner (for example, even though the Contractor has achieved its goals for women generally, the Contractor may be in violation of the Executive Order if a specific minority group of women is underutilized).
- 10. The Contractor shall not use the goals and timetables or affirmative action standards to discriminate against any person because of race, color, religion, sex, sexual orientation, gender identity, or national origin.
- 11. The Contractor shall not enter into any subcontract with any person or firm debarred from Government contracts pursuant to Executive Order 11246.
- 12. The Contractor shall carry out such sanctions and penalties for violation of these specifications and of the Equal Opportunity Clause, including suspension, termination, and cancellation of existing subcontracts as may be imposed or ordered pursuant to Executive Order 11246, as amended, and its implementing regulations, by the Office of Federal Contract Compliance Programs. Any contractor who fails to carry out such sanctions and penalties shall be in violation of these specifications and Executive Order 11246, as amended.
- 13. The Contractor, in fulfilling its obligations under these specifications, shall implement specific affirmative action steps, at least as extensive as those standards prescribed in paragraph 7 of these specifications, so as to achieve maximum results from its efforts to ensure equal employment opportunity. If the Contractor fails to comply with the requirements of the Executive Order, the implementing regulations, or these specifications, the Director shall proceed in accordance with 41 CFR part 60-4.8.
- 14. The Contractor shall designate a responsible official to monitor all employment related activity to ensure that the company EEO policy is being carried out, to submit reports relating to the provisions hereof as may be required by the Government, and to keep records. Records shall at least include for each employee, the name, address, telephone numbers, construction trade, union affiliation if any, employee identification number when assigned, social security number, race, sex, status (e.g., mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily understandable and retrievable form; however, to the degree that existing records satisfy this requirement, contractors shall not be required to maintain separate records.
- 15. Nothing herein provided shall be construed as a limitation upon the application of other laws which establish different standards of compliance or upon the application of requirements for the hiring of local or other area residents (e.g. those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).

A17 FEDERAL FAIR LABOR STANDARDS ACT (FEDERAL MINIMUM WAGE)

A17.1 SOURCE

29 USC § 201, et seq

2 CFR § 200.430

A17.2 APPLICABILITY

The U.S. Department of Labor (DOL) Wage and Hour Division administers the Fair Labor Standards Act (FLSA). This act prescribes federal standards for basic minimum wage, overtime pay, record keeping, and child labor standards.

Contract Types – Per the Department of Labor, all employees of certain enterprises having workers engaged in interstate commerce; producing goods for interstate commerce; or handling, selling, or otherwise working on goods or materials that have been moved in or produced for such commerce by any person are covered by the FLSA.

All consultants, sub-consultants, contractors, and subcontractors employed under this federally assisted project must comply with the FLSA.

Professional Services – 29 CFR § 213 exempts employees in a bona fide executive, administrative or professional capacity. Because professional firms employ individuals that are not covered by this exemption, the Sponsor's agreement with a professional services firm must include the FLSA provision.

Use of Provision – No mandatory text provided. The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of 29 USC § 201, et seq. The Sponsor must select *contractor* or *consultant*, as appropriate for the contract.

A17.3 MODEL SOLICITATION CLAUSE

All contracts and subcontracts that result from this solicitation incorporate by reference the provisions of 29 CFR part 201, et seq, the Federal Fair Labor Standards Act (FLSA), with the same force and effect as if given in full text. The FLSA sets minimum wage, overtime pay, recordkeeping, and child labor standards for full and part-time workers.

The [Contractor / Consultant] has full responsibility to monitor compliance to the referenced statute or regulation. The [Contractor / Consultant] must address any claims or disputes that arise from this requirement directly with the U.S. Department of Labor – Wage and Hour Division.

A18 LOBBYING AND INFLUENCING FEDERAL EMPLOYEES

A18.1 SOURCE

31 USC § 1352 – Byrd Anti-Lobbying Amendment

2 CFR Part 200, Appendix II(I)

49 CFR Part 20, Appendix A

A18.2 APPLICABILITY

Consultants and contractors that apply or bid for an award of \$100,000 or more must certify that it will not and has not used Federal appropriated funds to pay any person or organization for influencing or attempting to influence an officer or employee of any agency, a member of Congress, officer or employee of Congress, or an employee of a member of Congress in connection with obtaining any Federal contract, grant, or another award covered by 31 USC § 1352. Each tier must also disclose any lobbying with non-Federal funds that takes place in connection with obtaining any Federal award.

Contract Types – The Sponsor must incorporate this provision into all contracts exceeding \$100,000.

Use of Provision – MANDATORY TEXT. Appendix A to 49 CFR Part 20 prescribes language the Sponsor must use. The Sponsor must incorporate this provision without modification.

A18.3 MANDATORY CERTIFICATION CLAUSE

CERTIFICATION REGARDING LOBBYING

The Bidder or Offeror certifies by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

- (1) No Federal appropriated funds have been paid or will be paid, by or on behalf of the Bidder or Offeror, to any person for influencing or attempting to influence an officer or employee of an agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
- (2) If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.
- (3) The undersigned shall require that the language of this certification be included in the award documents for all sub-awards at all tiers (including subcontracts, subgrants, and contracts under

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

grants, loans, and cooperative agreements) and that all sub-recipients shall certify and disclose accordingly.

This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by section 1352, title 31, U.S. Code. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

A19 PROHIBITION OF SEGREGATED FACILITIES

A19.1 SOURCE

2 CFR Part 200, Appendix II(C)

41 CFR Part 60-1

A19.2 APPLICABILITY

The contractor must comply with the requirements of the EEO clause by ensuring that facilities they provide for employees are free of segregation on the basis of race, color, religion, sex, sexual orientation, gender identity, or national origin. This clause must be included in all contracts that include the equal opportunity clause, regardless of the amount of the contract.

Contract Types – AIP Sponsors must incorporate the Prohibition of Segregated Facilities clause (41 CFR § 60-1.8) in any contract containing the Equal Employment Opportunity clause of 41 CFR § 60-1.4. This obligation flows down to subcontract and sub-tier purchase orders containing the Equal Employment Opportunity clause.

Construction – Construction work means construction, rehabilitation, alteration, conversion, extension, demolition or repair of buildings, highways, or other changes or improvements to real property, including facilities providing utility services. The term also includes the supervision, inspection, and other onsite functions incidental to the actual construction.

Equipment – On site installation of equipment such as airfield lighting control equipment meets the definition of construction and thus this provision would apply. This provision does not apply to equipment projects involving manufacture of the item at a vendor's manufacturing plant. An example would be the manufacture of a SRE or ARFF vehicle.

Professional Services – Professional services that include tasks that qualify as construction work as defined by 41 CFR part 60-1. Examples include the installation of noise monitoring equipment.

Property/Land – Land acquisition contracts that include tasks that qualify as construction work as defined by 41 CFR part 60-1. Examples include demolition of structures or installation of boundary fencing.

Use of Provision – No mandatory text provided. The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of 41 CFR Part 60-1.

A19.3 MODEL CONTRACT CLAUSE

PROHIBITION OF SEGREGATED FACILITIES

(a) The Contractor agrees that it does not and will not maintain or provide for its employees any segregated facilities at any of its establishments, and that it does not and will not permit its employees to perform their services at any location under its control where segregated facilities are maintained. The Contractor agrees that a breach of this clause is a violation of the Equal Employment Opportunity clause in this contract.

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

- (b) "Segregated facilities," as used in this clause, means any waiting rooms, work areas, rest rooms and wash rooms, restaurants and other eating areas, time clocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees that are segregated by explicit directive or are in fact segregated on the basis of race, color, religion, sex, sexual orientation, gender identity, or national origin because of written or oral policies or employee custom. The term does not include separate or single-user rest rooms or necessary dressing or sleeping areas provided to assure privacy between the sexes.
- (c) The Contractor shall include this clause in every subcontract and purchase order that is subject to the Equal Employment Opportunity clause of this contract.

A20 OCCUPATIONAL SAFETY AND HEALTH ACT OF 1970

A20.1 SOURCE

29 CFR Part 1910

A20.2 APPLICABILITY

Contract Types – All contracts and subcontracts must comply with the Occupational Safety and Health Act of 1970 (OSH). The U.S. Department of Labor Occupational Safety and Health Administration (OSHA) oversees the workplace health and safety standards wage provisions from OSH.

Use of Provision – No mandatory text provided. The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of 29 CFR Part 1910.

A20.3 MODEL CONTRACT CLAUSE

All contracts and subcontracts that result from this solicitation incorporate by reference the requirements of 29 CFR Part 1910 with the same force and effect as if given in full text. The employer must provide a work environment that is free from recognized hazards that may cause death or serious physical harm to the employee. The employer retains full responsibility to monitor its compliance and their subcontractor's compliance with the applicable requirements of the Occupational Safety and Health Act of 1970 (29 CFR Part 1910). The employer must address any claims or disputes that pertain to a referenced requirement directly with the U.S. Department of Labor – Occupational Safety and Health Administration.

A21 PROCUREMENT OF RECOVERED MATERIALS

A21.1 SOURCE

2 CFR § 200.323

2 CFR Part 200, Appendix II(J)

40 CFR Part 247

42 USC § 6901, et seq (Resource Conservation and Recovery Act (RCRA))

A21.2 APPLICABILITY

Sponsors of AIP funded development and equipment projects must comply with Section 6002 of the Solid Waste Disposal Act, as amended by the Resource Conservation and Recovery Act. Section 6002 emphasizes maximizing energy and resource recovery through use of affirmative procurement actions for recovered materials identified in the Environmental Protection Agency (EPA) guidelines codified at 40 CFR part 247. When acquiring items designated in the guidelines, the Sponsor must procure items that contain the highest percentage of recovered materials practicable, consistent with maintaining a satisfactory level of competition.

Contract Types – This provision applies to any contracts that include procurement of products designated in subpart B of 40 CFR part 247 where the purchase price of the item exceeds \$10,000 or the value of the quantity acquired by the preceding fiscal year exceeded \$10,000.

Construction and Equipment – Include this provision in all construction and equipment projects.

Professional Services and Property – Include this provision if the agreement includes procurement of a product that exceeds \$10,000.

Use of Provision – No mandatory text provided. The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of 2 CFR Part 200.

A21.3 MODEL CONTRACT CLAUSE

PROCUREMENT OF RECOVERED MATERIALS

Contractor and subcontractor agree to comply with Section 6002 of the Solid Waste Disposal Act, as amended by the Resource Conservation and Recovery Act, and the regulatory provisions of 40 CFR Part 247. In the performance of this contract and to the extent practicable, the Contractor and subcontractors are to use products containing the highest percentage of recovered materials for items designated by the Environmental Protection Agency (EPA) under 40 CFR Part 247 whenever:

- 1) The contract requires procurement of \$10,000 or more of a designated item during the fiscal year; or
- 2) The contractor has procured \$10,000 or more of a designated item using Federal funding during the previous fiscal year.

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

The list of EPA-designated items is available at www.epa.gov/smm/comprehensive-procurement-guidelines-construction-products.

Section 6002(c) establishes exceptions to the preference for recovery of EPA-designated products if the contractor can demonstrate the item is:

- a) Not reasonably available within a timeframe providing for compliance with the contract performance schedule;
- b) Fails to meet reasonable contract performance requirements; or
- c) Is only available at an unreasonable price.

A22 RIGHT TO INVENTIONS

A22.1 SOURCE

2 CFR Part 200, Appendix II(F)

37 CFR Part 401

A22.2 APPLICABILITY

Contract Types – This provision applies to all contracts and subcontracts with small business firms or nonprofit organizations that include performance of *experimental*, *developmental*, *or research work*. This clause is not applicable to construction, equipment, or professional service contracts unless the contract includes *experimental*, *developmental*, *or research work*.

Use of Provision – No mandatory text provided. The following language is acceptable to the FAA and meets the intent of this requirement. If the sponsor uses different language, the Sponsor's language must fully satisfy the requirements of 2 CFR Part 200, Appendix II.

A22.3 MODEL CONTRACT CLAUSE

RIGHTS TO INVENTIONS

Contracts or agreements that include the performance of experimental, developmental, or research work must provide for the rights of the Federal Government and the Owner in any resulting invention as established by 37 CFR part 401, Rights to Inventions Made by Non-profit Organizations and Small Business Firms under Government Grants, Contracts, and Cooperative Agreements. This contract incorporates by reference the patent and inventions rights as specified within 37 CFR § 401.14. Contractor must include this requirement in all sub-tier contracts involving experimental, developmental, or research work.

A23 SEISMIC SAFETY

A23.1 SOURCE

49 CFR Part 41

A23.2 APPLICABILITY

Contract Types – This provision applies to construction of new buildings and additions to existing buildings financed in whole or in part through the Airport Improvement Program.

Professional Services– Sponsor must incorporate this clause in any contract involved in the construction of new buildings or structural addition to existing buildings.

Construction – Sponsor must incorporate this clause in any contract involved in the construction of new buildings or structural addition to existing buildings.

Equipment – Sponsor must include the construction provision if the project involves construction or structural addition to a building such as an electrical vault project to accommodate or install equipment.

Land – This provision will not typically apply to a property/land project.

Use of Provision – No mandatory text provided. The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of 49 CFR part 41.

A23.3 MODEL CONTRACT CLAUSE

A23.3.1 Professional Service Agreements for Design

SEISMIC SAFETY

In the performance of design services, the Consultant agrees to furnish a building design and associated construction specification that conform to a building code standard that provides a level of seismic safety substantially equivalent to standards as established by the National Earthquake Hazards Reduction Program (NEHRP). Local building codes that model their building code after the current version of the International Building Code (IBC) meet the NEHRP equivalency level for seismic safety. At the conclusion of the design services, the Consultant agrees to furnish the Owner a "certification of compliance" that attests conformance of the building design and the construction specifications with the seismic standards of NEHRP or an equivalent building code.

A23.3.2 Construction Contracts

SEISMIC SAFETY

The Contractor agrees to ensure that all work performed under this contract, including work performed by subcontractors, conforms to a building code standard that provides a level of seismic safety substantially equivalent to standards established by the National Earthquake Hazards Reduction

Metropolitan Topeka Airport Authority Philip Billard Municipal Airport Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

Program (NEHRP). Local building codes that model their code after the current version of the International Building Code (IBC) meet the NEHRP equivalency level for seismic safety.

A24 TAX DELINQUENCY AND FELONY CONVICTIONS

A24.1 SOURCE

Section 8113 of the Consolidated Appropriations Act, 2022 (Public Law 117-103) and similar provisions in subsequent appropriations acts.

DOT Order 4200.6 – Appropriations Act Requirements for Procurement and Non-Procurement Regarding Tax Delinquency and Felony Convictions

A24.2 APPLICABILITY

The Sponsor must ensure that no funding goes to any contractor who:

- Has been convicted of a Federal felony within the last 24 months; or
- Has any outstanding tax liability for which all judicial and administrative remedies have lapsed or been exhausted.

Contract Types – This provision applies to all contracts funded in whole or part with AIP.

Use of Provision – No mandatory text provided. The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of DOT Order 4200.6.

A24.3 MODEL CERTIFICATION CLAUSE

CERTIFICATION OF OFFEROR/BIDDER REGARDING TAX DELINQUENCY AND FELONY CONVICTIONS

The applicant must complete the following two certification statements. The applicant must indicate its current status as it relates to tax delinquency and felony conviction by inserting a checkmark (\checkmark) in the space following the applicable response. The applicant agrees that, if awarded a contract resulting from this solicitation, it will incorporate this provision for certification in all lower tier subcontracts.

Certifications

- 1) The applicant represents that it is () is not () a corporation that has any unpaid Federal tax liability that has been assessed, for which all judicial and administrative remedies have been exhausted or have lapsed, and that is not being paid in a timely manner pursuant to an agreement with the authority responsible for collecting the tax liability.
- 2) The applicant represents that it is () is not () a corporation that was convicted of a criminal violation under any Federal law within the preceding 24 months.

Note

If an applicant responds in the affirmative to either of the above representations, the applicant is ineligible to receive an award unless the Sponsor has received notification from the agency suspension and debarment official (SDO) that the SDO has considered suspension or debarment and determined that further action is not required to protect the Government's interests. The applicant therefore must provide information to the owner about its tax liability or conviction to the Owner, who will then notify

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

the FAA Airports District Office, which will then notify the agency's SDO to facilitate completion of the required considerations before award decisions are made.

Term Definitions

Felony conviction: Felony conviction means a conviction within the preceding twenty four (24) months of a felony criminal violation under any Federal law and includes conviction of an offense defined in a section of the U.S. Code that specifically classifies the offense as a felony and conviction of an offense that is classified as a felony under 18 USC § 3559.

Tax Delinquency: A tax delinquency is any unpaid Federal tax liability that has been assessed, for which all judicial and administrative remedies have been exhausted, or have lapsed, and that is not being paid in a timely manner pursuant to an agreement with the authority responsible for collecting the tax liability.

A25 TERMINATION OF CONTRACT

A25.1 SOURCE

2 CFR Part 200, Appendix II(B)

FAA Advisory Circular 150/5370-10, Section 80-09

A25.2 APPLICABILITY

Contract Types – All contracts and subcontracts in excess of \$10,000 must address *termination for cause* and *termination for convenience* by the Sponsor. The provision must address the manner (i.e., notice, opportunity to cure, and effective date) by which the Sponsor's contract will be affected and the basis for settlement (e.g., incurred expenses, completed work, profit, etc.).

Use of Provision -

Termination for Convenience – No mandatory text provided. The Sponsor must include a clause for termination for convenience. The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of Appendix II to 2 CFR § 200.

Termination for Cause – No mandatory text provided. The Sponsor must include a clause for termination for cause (includes default). The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of 2 CFR Part 200, Appendix II.

Equipment, Professional Services, and Property – No mandatory text provided. The Sponsor may use their established clause language provided that it adequately addresses the intent of 2 CFR Part 200 Appendix II(B), which addresses termination for cause and for convenience.

A25.3 MODEL CONTRACT CLAUSES

A25.3.1 Termination for Convenience

TERMINATION FOR CONVENIENCE (CONSTRUCTION & EQUIPMENT CONTRACTS)

The Owner may terminate this contract in whole or in part at any time by providing written notice to the Contractor. Such action may be without cause and without prejudice to any other right or remedy of Owner. Upon receipt of a written notice of termination, except as explicitly directed by the Owner, the Contractor shall immediately proceed with the following obligations regardless of any delay in determining or adjusting amounts due under this clause:

- 1. Contractor must immediately discontinue work as specified in the written notice.
- 2. Terminate all subcontracts to the extent they relate to the work terminated under the notice.
- 3. Discontinue orders for materials and services except as directed by the written notice.
- 4. Deliver to the Owner all fabricated and partially fabricated parts, completed and partially completed work, supplies, equipment and materials acquired prior to termination of the work, and as directed in the written notice.

- 5. Complete performance of the work not terminated by the notice.
- 6. Take action as directed by the Owner to protect and preserve property and work related to this contract that Owner will take possession.

Owner agrees to pay Contractor for:

- 1. Completed and acceptable work executed in accordance with the contract documents prior to the effective date of termination:
- Documented expenses sustained prior to the effective date of termination in performing work and furnishing labor, materials, or equipment as required by the contract documents in connection with uncompleted work;
- 3. Reasonable and substantiated claims, costs, and damages incurred in settlement of terminated contracts with Subcontractors and Suppliers; and
- 4. Reasonable and substantiated expenses to the Contractor directly attributable to Owner's termination action.

Owner will not pay Contractor for loss of anticipated profits or revenue or other economic loss arising out of or resulting from the Owner's termination action.

The rights and remedies this clause provides are in addition to any other rights and remedies provided by law or under this contract.

TERMINATION FOR CONVENIENCE (PROFESSIONAL SERVICES)

The Owner may, by written notice to the Consultant, terminate this Agreement for its convenience and without cause or default on the part of Consultant. Upon receipt of the notice of termination, except as explicitly directed by the Owner, the Contractor must immediately discontinue all services affected.

Upon termination of the Agreement, the Consultant must deliver to the Owner all data, surveys, models, drawings, specifications, reports, maps, photographs, estimates, summaries, and other documents and materials prepared by the Engineer under this contract, whether complete or partially complete.

Owner agrees to make just and equitable compensation to the Consultant for satisfactory work completed up through the date the Consultant receives the termination notice. Compensation will not include anticipated profit on non-performed services.

Owner further agrees to hold Consultant harmless for errors or omissions in documents that are incomplete as a result of the termination action under this clause.

A25.3.2 Termination for Default

TERMINATION FOR CAUSE (CONSTRUCTION)

Section 80-09 of FAA Advisory Circular 150/5370-10 establishes standard language for conditions, rights, and remedies associated with Owner termination of this contract for cause due to default of the Contractor.

TERMINATION FOR CAUSE (EQUIPMENT)

The Owner may, by written notice of default to the Contractor, terminate all or part of this Contract for cause if the Contractor:

- 1. Fails to begin the Work under the Contract within the time specified in the Notice- to-Proceed;
- 2. Fails to make adequate progress as to endanger performance of this Contract in accordance with its terms;
- 3. Fails to make delivery of the equipment within the time specified in the Contract, including any Owner approved extensions;
- 4. Fails to comply with material provisions of the Contract;
- 5. Submits certifications made under the Contract and as part of their proposal that include false or fraudulent statements; or
- 6. Becomes insolvent or declares bankruptcy.

If one or more of the stated events occur, the Owner will give notice in writing to the Contractor and Surety of its intent to terminate the contract for cause. At the Owner's discretion, the notice may allow the Contractor and Surety an opportunity to cure the breach or default.

If within [10] days of the receipt of notice, the Contractor or Surety fails to remedy the breach or default to the satisfaction of the Owner, the Owner has authority to acquire equipment by other procurement action. The Contractor will be liable to the Owner for any excess costs the Owner incurs for acquiring such similar equipment.

Payment for completed equipment delivered to and accepted by the Owner shall be at the Contract price. The Owner may withhold from amounts otherwise due the Contractor for such completed equipment, such sum as the Owner determines to be necessary to protect the Owner against loss because of Contractor default.

Owner will not terminate the Contractor's right to proceed with the work under this clause if the delay in completing the work arises from unforeseeable causes beyond the control and without the fault or negligence of the Contractor. Examples of such acceptable causes include: acts of God, acts of the Owner, acts of another Contractor in the performance of a contract with the Owner, and severe weather events that substantially exceed normal conditions for the location.

If, after termination of the Contractor's right to proceed, the Owner determines that the Contractor was not in default, or that the delay was excusable, the rights and obligations of the parties will be the same as if the Owner issued the termination for the convenience the Owner.

The rights and remedies of the Owner in this clause are in addition to any other rights and remedies provided by law or under this contract.

TERMINATION FOR CAUSE (PROFESSIONAL SERVICES)

Either party may terminate this Agreement for cause if the other party fails to fulfill its obligations that are essential to the completion of the work per the terms and conditions of the Agreement. The party initiating the termination action must allow the breaching party an opportunity to dispute or cure the breach.

The terminating party must provide the breaching party [7] days advance written notice of its intent to terminate the Agreement. The notice must specify the nature and extent of the breach, the conditions

necessary to cure the breach, and the effective date of the termination action. The rights and remedies in this clause are in addition to any other rights and remedies provided by law or under this agreement.

- a) **Termination by Owner**: The Owner may terminate this Agreement for cause in whole or in part, for the failure of the Consultant to:
 - 1. Perform the services within the time specified in this contract or by Owner approved extension;
 - 2. Make adequate progress so as to endanger satisfactory performance of the Project; or
 - 3. Fulfill the obligations of the Agreement that are essential to the completion of the Project.

Upon receipt of the notice of termination, the Consultant must immediately discontinue all services affected unless the notice directs otherwise. Upon termination of the Agreement, the Consultant must deliver to the Owner all data, surveys, models, drawings, specifications, reports, maps, photographs, estimates, summaries, and other documents and materials prepared by the Engineer under this contract, whether complete or partially complete.

Owner agrees to make just and equitable compensation to the Consultant for satisfactory work completed up through the date the Consultant receives the termination notice. Compensation will not include anticipated profit on non-performed services.

Owner further agrees to hold Consultant harmless for errors or omissions in documents that are incomplete as a result of the termination action under this clause.

If, after finalization of the termination action, the Owner determines the Consultant was not in default of the Agreement, the rights and obligations of the parties shall be the same as if the Owner issued the termination for the convenience of the Owner.

- b) **Termination by Consultant**: The Consultant may terminate this Agreement for cause in whole or in part, if the Owner:
 - 1. Defaults on its obligations under this Agreement;
 - 2. Fails to make payment to the Consultant in accordance with the terms of this Agreement;
 - 3. Suspends the project for more than [180] days due to reasons beyond the control of the Consultant.

Upon receipt of a notice of termination from the Consultant, Owner agrees to cooperate with Consultant for the purpose of terminating the agreement or portion thereof, by mutual consent. If Owner and Consultant cannot reach mutual agreement on the termination settlement, the Consultant may, without prejudice to any rights and remedies it may have, proceed with terminating all or parts of this Agreement based upon the Owner's breach of the contract.

In the event of termination due to Owner breach, the Consultant is entitled to invoice Owner and to receive full payment for all services performed or furnished in accordance with this Agreement and all justified reimbursable expenses incurred by the Consultant through the effective date of termination action. Owner agrees to hold Consultant harmless for errors or omissions in documents that are incomplete as a result of the termination action under this clause.

A26 TRADE RESTRICTION CERTIFICATION

A26.1 SOURCE

49 USC § 50104

49 CFR Part 30

A26.2 APPLICABILITY

Unless waived by the Secretary of Transportation, Sponsors may not use AIP funds on a product or service from a foreign country included in the current list of countries that discriminate against U.S. firms as published by the Office of the United States Trade Representative (USTR).

Contract Types – The trade restriction certification and clause apply to all AIP funded projects.

Use of Provision – **MANDATORY TEXT.** 49 CFR Part 30 prescribes the language for this model clause. The Sponsor must include this certification language in all contracts and subcontracts without modification.

A26.3 MANDATORY SOLICITATION CLAUSE

TRADE RESTRICTION CERTIFICATION

By submission of an offer, the Offeror certifies that with respect to this solicitation and any resultant contract, the Offeror –

- 1) is not owned or controlled by one or more citizens of a foreign country included in the list of countries that discriminate against U.S. firms as published by the Office of the United States Trade Representative (USTR);
- 2) has not knowingly entered into any contract or subcontract for this project with a person that is a citizen or national of a foreign country included on the list of countries that discriminate against U.S. firms as published by the USTR; and
- 3) has not entered into any subcontract for any product to be used on the Federal project that is produced in a foreign country included on the list of countries that discriminate against U.S. firms published by the USTR.

This certification concerns a matter within the jurisdiction of an agency of the United States of America and the making of a false, fictitious, or fraudulent certification may render the maker subject to prosecution under Title 18 USC § 1001.

The Offeror/Contractor must provide immediate written notice to the Owner if the Offeror/Contractor learns that its certification or that of a subcontractor was erroneous when submitted or has become erroneous by reason of changed circumstances. The Contractor must require subcontractors provide immediate written notice to the Contractor if at any time it learns that its certification was erroneous by reason of changed circumstances.

Unless the restrictions of this clause are waived by the Secretary of Transportation in accordance with 49 CFR § 30.17, no contract shall be awarded to an Offeror or subcontractor:

- 1) who is owned or controlled by one or more citizens or nationals of a foreign country included on the list of countries that discriminate against U.S. firms published by the USTR; or
- 2) whose subcontractors are owned or controlled by one or more citizens or nationals of a foreign country on such USTR list; or
- 3) who incorporates in the public works project any product of a foreign country on such USTR list.

Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render, in good faith, the certification required by this provision. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

The Offeror agrees that, if awarded a contract resulting from this solicitation, it will incorporate this provision for certification without modification in all lower tier subcontracts. The Contractor may rely on the certification of a prospective subcontractor that it is not a firm from a foreign country included on the list of countries that discriminate against U.S. firms as published by USTR, unless the Offeror has knowledge that the certification is erroneous.

This certification is a material representation of fact upon which reliance was placed when making an award. If it is later determined that the Contractor or subcontractor knowingly rendered an erroneous certification, the Federal Aviation Administration (FAA) may direct through the Owner cancellation of the contract or subcontract for default at no cost to the Owner or the FAA.

A27 VETERAN'S PREFERENCE

A27.1 SOURCE

49 USC § 47112(c)

A27.2 APPLICABILITY

Contract Types – This provision applies to all AIP funded projects that involve labor to carry out the project. This preference, which excludes executive, administrative, and supervisory positions, applies to covered veterans [as defined under § 47112(c)] only when they are readily available and qualified to accomplish the work required by the project.

Use of Provision – No mandatory text provided. The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of 49 USC § 47112.

A27.3 MODEL CONTRACT CLAUSE

VETERAN'S PREFERENCE

In the employment of labor (excluding executive, administrative, and supervisory positions), the Contractor and all sub-tier contractors must give preference to covered veterans as defined within Title 49 United States Code Section 47112. Covered veterans include Vietnam-era veterans, Persian Gulf veterans, Afghanistan-Iraq war veterans, disabled veterans, and small business concerns (as defined by 15 USC § 632) owned and controlled by disabled veterans. This preference only applies when there are covered veterans readily available and qualified to perform the work to which the employment relates.

A28 DOMESTIC PREFERENCES FOR PROCUREMENTS

A28.1 SOURCE

2 CFR § 200.322

2 CFR Part 200, Appendix II(L)

A28.2 APPLICABILITY

To the greatest extent "practicable," Sponsors must provide a preference for the purchase, acquisition, or use of goods, products, or materials produced in the U.S., including, but not limited to iron, aluminum, steel, cement, or other manufactured products.

Contract Types – Must be included in all subawards, including all contracts and purchase orders for work or products under the grant.

Use of Provision – No mandatory text provided. The following language is acceptable to the FAA and meets the intent of this requirement. If the Sponsor uses different language, the Sponsor's language must fully satisfy the requirements of 2 CFR § 200.322.

A28.3 MODEL CERTIFICATION CLAUSE

CERTIFICATION REGARDING DOMESTIC PREFERENCES FOR PROCUREMENTS

The Bidder or Offeror certifies by signing and submitting this bid or proposal that, to the greatest extent practicable, the Bidder or Offeror has provided a preference for the purchase, acquisition, or use of goods, products, or materials produced in the United States (including, but not limited to, iron, aluminum, steel, cement, and other manufactured products) in compliance with 2 CFR § 200.322.

END OF GUIDELINES FOR CONTRACT PROVISIONS FOR OBLIGATED SPONSORS AND AIRPORT IMPROVEMENT PROGRAM PROJECTS

SECTION 10 DEFINITION OF TERMS

When the following terms are used in these specifications, in the contract, or in any documents or other instruments pertaining to construction where these specifications govern, the intent and meaning shall be defined as follows:

Paragraph Number	Term	Definition
10-01	AASHTO	The American Association of State Highway and Transportation Officials.
10-02	Access Road	The right-of-way, the roadway and all improvements constructed thereon connecting the airport to a public roadway.
10-03	Advertisement	A public announcement, as required by local law, inviting bids for work to be performed and materials to be furnished.
10-04	Airport	Airport means an area of land or water which is used or intended to be used for the landing and takeoff of aircraft; an appurtenant area used or intended to be used for airport buildings or other airport facilities or rights of way; airport buildings and facilities located in any of these areas, and a heliport.
10-05	Airport Improvement Program (AIP)	A grant-in-aid program, administered by the Federal Aviation Administration (FAA).
10-06	Air Operations Area (AOA)	The term air operations area (AOA) shall mean any area of the airport used or intended to be used for the landing, takeoff, or surface maneuvering of aircraft. An air operation area shall include such paved or unpaved areas that are used or intended to be used for the unobstructed movement of aircraft in addition to its associated runway, taxiway, or apron.
10-07	Apron	Area where aircraft are parked, unloaded or loaded, fueled and/or serviced.
10-08	ASTM International (ASTM)	Formerly known as the American Society for Testing and Materials (ASTM).
10-09	Award	The Owner's notice to the successful bidder of the acceptance of the submitted bid.

GP-10 Definition of Terms GP-10-1 of 8

Paragraph Number	Term	Definition
10-10	Bidder	Any individual, partnership, firm, or corporation, acting directly or through a duly authorized representative, who submits a proposal for the work contemplated.
10-11	Building Area	An area on the airport to be used, considered, or intended to be used for airport buildings or other airport facilities or rights-of-way together with all airport buildings and facilities located thereon.
10-12	Calendar Day	Every day shown on the calendar.
10-13	Certificate of Analysis (COA)	The COA is the manufacturer's Certificate of Compliance (COC) including all applicable test results required by the specifications.
10-14	Certificate of Compliance (COC)	The manufacturer's certification stating that materials or assemblies furnished fully comply with the requirements of the contract. The certificate shall be signed by the manufacturer's authorized representative.
10-15	Change Order	A written order to the Contractor covering changes in the plans, specifications, or proposal quantities and establishing the basis of payment and contract time adjustment, if any, for work within the scope of the contract and necessary to complete the project.
10-16	Contract	A written agreement between the Owner and the Contractor that establishes the obligations of the parties including but not limited to performance of work, furnishing of labor, equipment and materials and the basis of payment. The awarded contract includes but may not be limited to: Advertisement, Contract form, Proposal, Performance bond, payment bond, General provisions, certifications and representations, Technical Specifications, Plans, Supplemental Provisions, standards incorporated by reference and issued addenda.
10-17	Contract Item (Pay Item)	A specific unit of work for which a price is provided in the contract.
10-18	Contract Time	The number of calendar days or working days, stated in the proposal, allowed for completion of the contract, including authorized time extensions. If a calendar date of completion is stated in the proposal, in lieu of a number of calendar or working days, the contract shall be completed by that date.

GP-10 Definition of Terms GP-10-2 of 8

Paragraph Number	Term	Definition
10-19	Contractor	The individual, partnership, firm, or corporation primarily liable for the acceptable performance of the work contracted and for the payment of all legal debts pertaining to the work who acts directly or through lawful agents or employees to complete the contract work.
10-20	Contractors Quality Control (QC) Facilities	The Contractor's QC facilities in accordance with the Contractor Quality Control Program (CQCP).
10-21	Contractor Quality Control Program (CQCP)	Details the methods and procedures that will be taken to assure that all materials and completed construction required by the contract conform to contract plans, technical specifications and other requirements, whether manufactured by the Contractor, or procured from subcontractors or vendors.
10-22	Control Strip	A demonstration by the Contractor that the materials, equipment, and construction processes results in a product meeting the requirements of the specification.
10-23	Construction Safety and Phasing Plan (CSPP)	The overall plan for safety and phasing of a construction project developed by the airport operator, or developed by the airport operator's consultant and approved by the airport operator. It is included in the invitation for bids and becomes part of the project specifications.
10-24	Drainage System	The system of pipes, ditches, and structures by which surface or subsurface waters are collected and conducted from the airport area.
10-25	Engineer	The individual, partnership, firm, or corporation duly authorized by the Owner to be responsible for engineering, inspection, and/or observation of the contract work and acting directly or through an authorized representative.
10-26	Equipment	All machinery, together with the necessary supplies for upkeep and maintenance; and all tools and apparatus necessary for the proper construction and acceptable completion of the work.
10-27	Extra Work	An item of work not provided for in the awarded contract as previously modified by change order or supplemental agreement, but which is found by the Owner's Engineer or Resident Project Representative (RPR) to be necessary to complete the work within the intended scope of the contract as previously modified.

GP-10 Definition of Terms GP-10-3 of 8

Paragraph Number	Term	Definition
10-28	FAA	The Federal Aviation Administration. When used to designate a person, FAA shall mean the Administrator or their duly authorized representative.
10-29	Federal Specifications	The federal specifications and standards, commercial item descriptions, and supplements, amendments, and indices prepared and issued by the General Services Administration.
10-30	Force Account	a. Contract Force Account - A method of payment that addresses extra work performed by the Contractor on a time and material basis.
		b. Owner Force Account - Work performed for the project by the Owner's employees.
10-31	Intention of Terms	Whenever, in these specifications or on the plans, the words "directed," "required," "permitted," "ordered," "designated," "prescribed," or words of like import are used, it shall be understood that the direction, requirement, permission, order, designation, or prescription of the Engineer and/or Resident Project Representative (RPR) is intended; and similarly, the words "approved," "acceptable," "satisfactory," or words of like import, shall mean approved by, or acceptable to, or satisfactory to the Engineer and/or RPR, subject in each case to the final determination of the Owner. Any reference to a specific requirement of a numbered
		paragraph of the contract specifications or a cited standard shall be interpreted to include all general requirements of the entire section, specification item, or cited standard that may be pertinent to such specific reference.
10-32	Lighting	A system of fixtures providing or controlling the light sources used on or near the airport or within the airport buildings. The field lighting includes all luminous signals, markers, floodlights, and illuminating devices used on or near the airport or to aid in the operation of aircraft landing at, taking off from, or taxiing on the airport surface.
10-33	Major and Minor Contract Items	A major contract item shall be any item that is listed in the proposal, the total cost of which is equal to or greater than 20% of the total amount of the award contract. All other items shall be considered minor contract items.
10-34	Materials	Any substance specified for use in the construction of the contract work.

GP-10 Definition of Terms GP-10-4 of 8

Paragraph Number	Term	Definition
10-35	Modification of Standards (MOS)	Any deviation from standard specifications applicable to material and construction methods in accordance with FAA Order 5300.1.
10-36	Notice to Proceed (NTP)	A written notice to the Contractor to begin the actual contract work on a previously agreed to date. If applicable, the Notice to Proceed shall state the date on which the contract time begins.
10-37	Owner	The term "Owner" shall mean the party of the first part or the contracting agency signatory to the contract. Where the term "Owner" is capitalized in this document, it shall mean airport Sponsor only. The Owner for this project is the Metropolitan Topeka Airport Authority (MTAA).
10-38	Passenger Facility Charge (PFC)	Per 14 Code of Federal Regulations (CFR) Part 158 and 49 United States Code (USC) § 40117, a PFC is a charge imposed by a public agency on passengers enplaned at a commercial service airport it controls.
10-39	Pavement Structure	The combined surface course, base course(s), and subbase course(s), if any, considered as a single unit.
10-40	Payment bond	The approved form of security furnished by the Contractor and their own surety as a guaranty that the Contractor will pay in full all bills and accounts for materials and labor used in the construction of the work.
10-41	Performance bond	The approved form of security furnished by the Contractor and their own surety as a guaranty that the Contractor will complete the work in accordance with the terms of the contract.
10-42	Plans	The official drawings or exact reproductions which show the location, character, dimensions and details of the airport and the work to be done and which are to be considered as a part of the contract, supplementary to the specifications. Plans may also be referred to as 'contract drawings.'
10-43	Project	The agreed scope of work for accomplishing specific airport development with respect to a particular airport.
10-44	Proposal	The written offer of the bidder (when submitted on the approved proposal form) to perform the contemplated work

GP-10 Definition of Terms GP-10-5 of 8

Paragraph Number	Term	Definition
		and furnish the necessary materials in accordance with the provisions of the plans and specifications.
10-45	Proposal guaranty	The security furnished with a proposal to guarantee that the bidder will enter into a contract if their own proposal is accepted by the Owner.
10-46	Quality Assurance (QA)	Owner's responsibility to assure that construction work completed complies with specifications for payment.
10-47	Quality Control (QC)	Contractor's responsibility to control material(s) and construction processes to complete construction in accordance with project specifications.
10-48	Quality Assurance (QA) Inspector	An authorized representative of the Engineer and/or Resident Project Representative (RPR) assigned to make all necessary inspections, observations, tests, and/or observation of tests of the work performed or being performed, or of the materials furnished or being furnished by the Contractor.
10-49	Quality Assurance (QA) Laboratory	The official quality assurance testing laboratories of the Owner or such other laboratories as may be designated by the Engineer or RPR. May also be referred to as Engineer's, Owner's, or QA Laboratory.
10-50	Resident Project Representative (RPR)	The individual, partnership, firm, or corporation duly authorized by the Owner to be responsible for all necessary inspections, observations, tests, and/or observations of tests of the contract work performed or being performed, or of the materials furnished or being furnished by the Contractor, and acting directly or through an authorized representative.
10-51	Runway	The area on the airport prepared for the landing and takeoff of aircraft.
10-52	Runway Safety Area (RSA)	A defined surface surrounding the runway prepared or suitable for reducing the risk of damage to aircraft. See the construction safety and phasing plan (CSPP) for limits of the RSA.
10-53	Safety Plan Compliance Document (SPCD)	Details how the Contractor will comply with the CSPP.
10-54	Specifications	A part of the contract containing the written directions and requirements for completing the contract work. Standards for specifying materials or testing which are cited in the

GP-10 Definition of Terms GP-10-6 of 8

Paragraph Number	Term	Definition
		contract specifications by reference shall have the same force and effect as if included in the contract physically.
10-55	Sponsor	A Sponsor is defined in 49 USC § 47102(24) as a public agency that submits to the FAA for an AIP grant; or a private Owner of a public-use airport that submits to the FAA an application for an AIP grant for the airport.
10-56	Structures	Airport facilities such as bridges; culverts; catch basins, inlets, retaining walls, cribbing; storm and sanitary sewer lines; water lines; underdrains; electrical ducts, manholes, handholes, lighting fixtures and bases; transformers; navigational aids; buildings; vaults; and, other manmade features of the airport that may be encountered in the work and not otherwise classified herein.
10-57	Subgrade	The soil that forms the pavement foundation.
10-58	Superintendent	The Contractor's executive representative who is present on the work during progress, authorized to receive and fulfill instructions from the RPR, and who shall supervise and direct the construction.
10-59	Supplemental Agreement	A written agreement between the Contractor and the Owner that establishes the basis of payment and contract time adjustment, if any, for the work affected by the supplemental agreement. A supplemental agreement is required if: (1) in scope work would increase or decrease the total amount of the awarded contract by more than 25%: (2) in scope work would increase or decrease the total of any major contract item by more than 25%; (3) work that is not within the scope of the originally awarded contract; or (4) adding or deleting of a major contract item.
10-60	Surety	The corporation, partnership, or individual, other than the Contractor, executing payment or performance bonds that are furnished to the Owner by the Contractor.
10-61	Taxilane	A taxiway designed for low speed movement of aircraft between aircraft parking areas and terminal areas.
10-62	Taxiway	The portion of the air operations area of an airport that has been designated by competent airport authority for movement of aircraft to and from the airport's runways, aircraft parking areas, and terminal areas.
10-63	Taxiway/Taxilane Safety Area (TSA)	A defined surface alongside the taxiway prepared or suitable for reducing the risk of damage to an aircraft. See

GP-10 Definition of Terms GP-10-7 of 8

Paragraph Number	Term	Definition
		the construction safety and phasing plan (CSPP) for limits of the TSA.
10-64	Work	The furnishing of all labor, materials, tools, equipment, and incidentals necessary or convenient to the Contractor's performance of all duties and obligations imposed by the contract, plans, and specifications.
10-65	Working day	A working day shall be any day other than a legal holiday, Saturday, or Sunday on which the normal working forces of the Contractor may proceed with regular work for at least six (6) hours toward completion of the contract. When work is suspended for causes beyond the Contractor's control, it will not be counted as a working day. Saturdays, Sundays and holidays on which the Contractor's forces engage in regular work will be considered as working days.
10-66	Owner Defined terms	None

END OF SECTION 10

GP-10 Definition of Terms GP-10-8 of 8

SECTION 20 PROPOSAL REQUIREMENTS AND CONDITIONS

20-01 Advertisement (Notice to Bidders). See Section NTB – Notice to Bidders

20-02 Qualification of bidders. Each bidder shall submit evidence of competency and evidence of financial responsibility to perform the work to the Owner at the time of bid opening.

Evidence of competency, unless otherwise specified, shall consist of statements covering the bidder's past experience on similar work, and a list of equipment and a list of key personnel that would be available for the work.

Each bidder shall furnish the Owner satisfactory evidence of their financial responsibility. Evidence of financial responsibility, unless otherwise specified, shall consist of a confidential statement or report of the bidder's financial resources and liabilities as of the last calendar year or the bidder's last fiscal year. Such statements or reports shall be certified by a public accountant. At the time of submitting such financial statements or reports, the bidder shall further certify whether their financial responsibility is approximately the same as stated or reported by the public accountant. If the bidder's financial responsibility has changed, the bidder shall qualify the public accountant's statement or report to reflect the bidder's true financial condition at the time such qualified statement or report is submitted to the Owner.

Unless otherwise specified, a bidder may submit evidence that they are prequalified with the State Highway Division and are on the current "bidder's list" of the state in which the proposed work is located. Evidence of State Highway Division prequalification may be submitted as evidence of financial responsibility in lieu of the certified statements or reports specified above.

20-03 Contents of proposal forms. The Owner's proposal forms state the location and description of the proposed construction; the place, date, and time of opening of the proposals; and the estimated quantities of the various items of work to be performed and materials to be furnished for which unit bid prices are asked. The proposal form states the time in which the work must be completed, and the amount of the proposal guaranty that must accompany the proposal. The Owner will accept only those Proposals properly executed on physical forms or electronic forms provided by the Owner. Bidder actions that may cause the Owner to deem a proposal irregular are given in paragraph 20-09 Irregular proposals.

Mobilization is limited to 5 percent of the total project cost.

20-04 Issuance of proposal forms. The Owner reserves the right to refuse to issue a proposal form to a prospective bidder if the bidder is in default for any of the following reasons:

- **a.** Failure to comply with any prequalification regulations of the Owner, if such regulations are cited, or otherwise included, in the proposal as a requirement for bidding.
- **b.** Failure to pay, or satisfactorily settle, all bills due for labor and materials on former contracts in force with the Owner at the time the Owner issues the proposal to a prospective bidder.
 - **c.** Documented record of Contractor default under previous contracts with the Owner.
 - **d.** Documented record of unsatisfactory work on previous contracts with the Owner.

20-05 Interpretation of estimated proposal quantities. An estimate of quantities of work to be done and materials to be furnished under these specifications is given in the proposal. It is the result of careful calculations and is believed to be correct. It is given only as a basis for comparison of proposals and the award of the contract. The Owner does not expressly, or by implication, agree that the actual quantities involved will correspond exactly therewith; nor shall the bidder plead misunderstanding or deception because of such estimates of quantities, or of the character, location, or other conditions pertaining to the work. Payment to the Contractor will be made only for the actual quantities of work performed or materials

furnished in accordance with the plans and specifications. It is understood that the quantities may be increased or decreased as provided in the Section 40, paragraph 40-02, Alteration of Work and Quantities, without in any way invalidating the unit bid prices.

20-06 Examination of plans, specifications, and site. The bidder is expected to carefully examine the site of the proposed work, the proposal, plans, specifications, and contract forms. Bidders shall satisfy themselves to the character, quality, and quantities of work to be performed, materials to be furnished, and to the requirements of the proposed contract. The submission of a proposal shall be prima facie evidence that the bidder has made such examination and is satisfied to the conditions to be encountered in performing the work and the requirements of the proposed contract, plans, and specifications.

Boring logs and other records of subsurface investigations and tests are available for inspection of bidders. It is understood and agreed that such subsurface information, whether included in the plans, specifications, or otherwise made available to the bidder, was obtained and is intended for the Owner's design and estimating purposes only. Such information has been made available for the convenience of all bidders. It is further understood and agreed that each bidder is solely responsible for all assumptions, deductions, or conclusions which the bidder may make or obtain from their own examination of the boring logs and other records of subsurface investigations and tests that are furnished by the Owner.

20-07 Preparation of proposal. The bidder shall submit their proposal on the forms furnished by the Owner. All blank spaces in the proposal forms, unless explicitly stated otherwise, must be correctly filled in where indicated for each and every item for which a quantity is given. The bidder shall state the price (written in ink or typed) both in words and numerals which they propose for each pay item furnished in the proposal. In case of conflict between words and numerals, the words, unless obviously incorrect, shall govern.

The bidder shall correctly sign the proposal in ink. If the proposal is made by an individual, their name and post office address must be shown. If made by a partnership, the name and post office address of each member of the partnership must be shown. If made by a corporation, the person signing the proposal shall give the name of the state where the corporation was chartered and the name, titles, and business address of the president, secretary, and the treasurer. Anyone signing a proposal as an agent shall file evidence of their authority to do so and that the signature is binding upon the firm or corporation.

20-08 Responsive and responsible bidder. A responsive bid conforms to all significant terms and conditions contained in the Owner's invitation for bid. It is the Owner's responsibility to decide if the exceptions taken by a bidder to the solicitation are material or not and the extent of deviation it is willing to accept.

A responsible bidder has the ability to perform successfully under the terms and conditions of a proposed procurement, as defined in 2 CFR § 200.318(h). This includes such matters as Contractor integrity, compliance with public policy, record of past performance, and financial and technical resources.

- **20-09 Irregular proposals.** Proposals shall be considered irregular for the following reasons:
- **a.** If the proposal is on a form other than that furnished by the Owner, or if the Owner's form is altered, or if any part of the proposal form is detached.
- **b.** If there are unauthorized additions, conditional or alternate pay items, or irregularities of any kind that make the proposal incomplete, indefinite, or otherwise ambiguous.
- **c.** If the proposal does not contain a unit price for each pay item listed in the proposal, except in the case of authorized alternate pay items, for which the bidder is not required to furnish a unit price.
 - **d.** If the proposal contains unit prices that are obviously unbalanced.
 - **e.** If the proposal is not accompanied by the proposal guaranty specified by the Owner.
 - **f.** If the applicable Disadvantaged Business Enterprise information is incomplete.

The Owner reserves the right to reject any irregular proposal and the right to waive technicalities if such waiver is in the best interest of the Owner and conforms to local laws and ordinances pertaining to the letting of construction contracts.

- **20-10 Bid guarantee**. Each separate proposal shall be accompanied by a bid bond, certified check, or other specified acceptable collateral, in the amount specified in the proposal form. Such bond, check, or collateral, shall be made payable to the Owner.
- **20-11 Delivery of proposal.** Each proposal submitted shall be placed in a sealed envelope plainly marked with the project number, location of airport, and name and business address of the bidder on the outside. When sent by mail, preferably registered, the sealed proposal, marked as indicated above, should be enclosed in an additional envelope. No proposal will be considered unless received at the place specified in the advertisement or as modified by Addendum before the time specified for opening all bids. Proposals received after the bid opening time shall be returned to the bidder unopened.
- **20-12 Withdrawal or revision of proposals**. A bidder may withdraw or revise (by withdrawal of one proposal and submission of another) a proposal provided that the bidder's request for withdrawal is received by the Owner in writing, by fax or by email before the time specified for opening bids. Revised proposals must be received at the place specified in the advertisement before the time specified for opening all bids.
- **20-13 Public opening of proposals**. Proposals shall be opened, and read, publicly at the time and place specified in the advertisement. Bidders, their authorized agents, and other interested persons are invited to attend. Proposals that have been withdrawn (by written or telegraphic request) or received after the time specified for opening bids shall be returned to the bidder unopened.
- **20-14 Disqualification of bidders**. A bidder shall be considered disqualified for any of the following reasons:
- **a.** Submitting more than one proposal from the same partnership, firm, or corporation under the same or different name.
- **b.** Evidence of collusion among bidders. Bidders participating in such collusion shall be disqualified as bidders for any future work of the Owner until any such participating bidder has been reinstated by the Owner as a qualified bidder.
- **c.** If the bidder is considered to be in "default" for any reason specified in paragraph 20-04, *Issuance of Proposal Forms*, of this section.
- **20-15 Discrepancies and Omissions.** A Bidder who discovers discrepancies or omissions with the project bid documents shall immediately notify the Owner's Engineer of the matter. A bidder that has doubt as to the true meaning of a project requirement may submit to the Owner's Engineer a written request for interpretation no later than 7 days prior to bid opening.

Any interpretation of the project bid documents by the Owner's Engineer will be by written addendum issued by the Owner. The Owner will not consider any instructions, clarifications or interpretations of the bidding documents in any manner other than written addendum.

END OF SECTION 20

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 30 AWARD AND EXECUTION OF CONTRACT

30-01 Consideration of proposals. After the proposals are publicly opened and read, they will be compared on the basis of the summation of the products obtained by multiplying the estimated quantities shown in the proposal by the unit bid prices. If a bidder's proposal contains a discrepancy between unit bid prices written in words and unit bid prices written in numbers, the unit bid price written in words shall govern.

Until the award of a contract is made, the Owner reserves the right to reject a bidder's proposal for any of the following reasons:

- **a.** If the proposal is irregular as specified in Section 20, paragraph 20-09, *Irregular Proposals*.
- **b.** If the bidder is disqualified for any of the reasons specified Section 20, paragraph 20-14, *Disqualification of Bidders*.

In addition, until the award of a contract is made, the Owner reserves the right to reject any or all proposals, waive technicalities, if such waiver is in the best interest of the Owner and is in conformance with applicable state and local laws or regulations pertaining to the letting of construction contracts; advertise for new proposals; or proceed with the work otherwise. All such actions shall promote the Owner's best interests.

30-02 Award of contract. The award of a contract, if it is to be awarded, shall be made within 90 calendar days of the date specified for publicly opening proposals, unless otherwise specified herein.

If the Owner elects to proceed with an award of contract, the Owner will make award to the responsible bidder whose bid, conforming with all the material terms and conditions of the bid documents, is the lowest in price.

- **30-03 Cancellation of award**. The Owner reserves the right to cancel the award without liability to the bidder, except return of proposal guaranty, at any time before a contract has been fully executed by all parties and is approved by the Owner in accordance with paragraph 30-07 *Approval of Contract*.
- **30-04 Return of proposal guaranty**. All proposal guaranties, except those of the two lowest bidders, will be returned immediately after the Owner has made a comparison of bids as specified in the paragraph 30-01, *Consideration of Proposals*. Proposal guaranties of the two lowest bidders will be retained by the Owner until such time as an award is made, at which time, the unsuccessful bidder's proposal guaranty will be returned. The successful bidder's proposal guaranty will be returned as soon as the Owner receives the contract bonds as specified in paragraph 30-05, *Requirements of Contract Bonds*.
- **30-05 Requirements of contract bonds**. At the time of the execution of the contract, the successful bidder shall furnish the Owner a surety bond or bonds that have been fully executed by the bidder and the surety guaranteeing the performance of the work and the payment of all legal debts that may be incurred by reason of the Contractor's performance of the work. The surety and the form of the bond or bonds shall be acceptable to the Owner. Unless otherwise specified in this subsection, the surety bond or bonds shall be in a sum equal to the full amount of the contract.
- **30-06 Execution of contract**. The successful bidder shall sign (execute) the necessary agreements for entering into the contract and return the signed contract to the Owner, along with the fully executed surety bond or bonds specified in paragraph 30-05, *Requirements of Contract Bonds*, of this section, within 15 calendar days from the date mailed or otherwise delivered to the successful bidder.
- **30-07 Approval of contract**. Upon receipt of the contract and contract bond or bonds that have been executed by the successful bidder, the Owner shall complete the execution of the contract in accordance with local laws or ordinances, and return the fully executed contract to the Contractor. Delivery of the fully executed contract to the Contractor shall constitute the Owner's approval to be bound by the successful bidder's proposal and the terms of the contract.

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

30-08 Failure to execute contract. Failure of the successful bidder to execute the contract and furnish an acceptable surety bond or bonds within the period specified in paragraph 30-06, *Execution of Contract*, of this section shall be just cause for cancellation of the award and forfeiture of the proposal guaranty, not as a penalty, but as liquidated damages to the Owner.

END OF SECTION 30

SECTION 40 SCOPE OF WORK

40-01 Intent of contract. The intent of the contract is to provide for construction and completion, in every detail, of the work described. It is further intended that the Contractor shall furnish all labor, materials, equipment, tools, transportation, and supplies required to complete the work in accordance with the plans, specifications, and terms of the contract.

40-02 Alteration of work and quantities. The Owner reserves the right to make such changes in quantities and work as may be necessary or desirable to complete, in a satisfactory manner, the original intended work. Unless otherwise specified in the Contract, the Owner's Engineer or RPR shall be and is hereby authorized to make, in writing, such in-scope alterations in the work and variation of quantities as may be necessary to complete the work, provided such action does not represent a significant change in the character of the work.

For purpose of this section, a significant change in character of work means: any change that is outside the current contract scope of work; any change (increase or decrease) in the total contract cost by more than 25%; or any change in the total cost of a major contract item by more than 25%.

Work alterations and quantity variances that do not meet the definition of significant change in character of work shall not invalidate the contract nor release the surety. Contractor agrees to accept payment for such work alterations and quantity variances in accordance with Section 90, paragraph 90-03, Compensation for Altered Quantities.

Should the value of altered work or quantity variance meet the criteria for significant change in character of work, such altered work and quantity variance shall be covered by a supplemental agreement. Supplemental agreements shall also require consent of the Contractor's surety and separate performance and payment bonds. If the Owner and the Contractor are unable to agree on a unit adjustment for any contract item that requires a supplemental agreement, the Owner reserves the right to terminate the contract with respect to the item and make other arrangements for its completion.

40-03 Omitted items. The Owner, the Owner's Engineer or the RPR may provide written notice to the Contractor to omit from the work any contract item that does not meet the definition of major contract item. Major contract items may be omitted by a supplemental agreement. Such omission of contract items shall not invalidate any other contract provision or requirement.

Should a contract item be omitted or otherwise ordered to be non-performed, the Contractor shall be paid for all work performed toward completion of such item prior to the date of the order to omit such item. Payment for work performed shall be in accordance with Section 90, paragraph 90-04, *Payment for Omitted Items*.

40-04 Extra work. Should acceptable completion of the contract require the Contractor to perform an item of work not provided for in the awarded contract as previously modified by change order or supplemental agreement, Owner may issue a Change Order to cover the necessary extra work. Change orders for extra work shall contain agreed unit prices for performing the change order work in accordance with the requirements specified in the order, and shall contain any adjustment to the contract time that, in the RPR's opinion, is necessary for completion of the extra work.

When determined by the RPR to be in the Owner's best interest, the RPR may order the Contractor to proceed with extra work as provided in Section 90, paragraph 90-05, *Payment for Extra Work*. Extra work that is necessary for acceptable completion of the project, but is not within the general scope of the work covered by the original contract shall be covered by a supplemental agreement as defined in Section 10, paragraph 10-59, *Supplemental Agreement*.

GP-40 Scope of Work GP-40-1 of 4

If extra work is essential to maintaining the project critical path, RPR may order the Contractor to commence the extra work under a Time and Material contract method. Once sufficient detail is available to establish the level of effort necessary for the extra work, the Owner shall initiate a change order or supplemental agreement to cover the extra work.

Any claim for payment of extra work that is not covered by written agreement (change order or supplemental agreement) shall be rejected by the Owner.

- **40-05 Maintenance of traffic.** It is the explicit intention of the contract that the safety of aircraft, as well as the Contractor's equipment and personnel, is the most important consideration. The Contractor shall maintain traffic in the manner detailed in the Construction Safety and Phasing Plan (CSPP).
- **a.** It is understood and agreed that the Contractor shall provide for the free and unobstructed movement of aircraft in the air operations areas (AOAs) of the airport with respect to their own operations and the operations of all subcontractors as specified in Section 80, paragraph 80-04, *Limitation of Operations*. It is further understood and agreed that the Contractor shall provide for the uninterrupted operation of visual and electronic signals (including power supplies thereto) used in the guidance of aircraft while operating to, from, and upon the airport as specified in Section 70, paragraph 70-15, *Contractor's Responsibility for Utility Service and Facilities of Others*.
- **b.** With respect to their own operations and the operations of all subcontractors, the Contractor shall provide marking, lighting, and other acceptable means of identifying personnel, equipment, vehicles, storage areas, and any work area or condition that may be hazardous to the operation of aircraft, fire-rescue equipment, or maintenance vehicles at the airport in accordance with the construction safety and phasing plan (CSPP) and the safety plan compliance document (SPCD).
- c. When the contract requires the maintenance of an existing road, street, or highway during the Contractor's performance of work that is otherwise provided for in the contract, plans, and specifications, the Contractor shall keep the road, street, or highway open to all traffic and shall provide maintenance as may be required to accommodate traffic. The Contractor, at their expense, shall be responsible for the repair to equal or better than preconstruction conditions of any damage caused by the Contractor's equipment and personnel. The Contractor shall furnish, erect, and maintain barricades, warning signs, flag person, and other traffic control devices in reasonable conformity with the Manual on Uniform Traffic Control Devices (MUTCD) (http://mutcd.fhwa.dot.gov/), unless otherwise specified. The Contractor shall also construct and maintain in a safe condition any temporary connections necessary for ingress to and egress from abutting property or intersecting roads, streets or highways. Unless otherwise specified herein, the Contractor will not be required to furnish snow removal for such existing road, street, or highway.
- **40-06 Removal of existing structures**. All existing structures encountered within the established lines, grades, or grading sections shall be removed by the Contractor, unless such existing structures are otherwise specified to be relocated, adjusted up or down, salvaged, abandoned in place, reused in the work or to remain in place. The cost of removing such existing structures shall not be measured or paid for directly, but shall be included in the various contract items.

Should the Contractor encounter an existing structure (above or below ground) in the work for which the disposition is not indicated on the plans, the Resident Project Representative (RPR) shall be notified prior to disturbing such structure. The disposition of existing structures so encountered shall be immediately determined by the RPR in accordance with the provisions of the contract.

Except as provided in Section 40, paragraph 40-07, *Rights in and Use of Materials Found in the Work*, it is intended that all existing materials or structures that may be encountered (within the lines, grades, or grading sections established for completion of the work) shall be used in the work as otherwise provided for in the contract and shall remain the property of the Owner when so used in the work.

GP-40 Scope of Work GP-40-2 of 4

40-07 Rights in and use of materials found in the work. Should the Contractor encounter any material such as (but not restricted to) sand, stone, gravel, slag, or concrete slabs within the established lines, grades, or grading sections, the use of which is intended by the terms of the contract to be embankment, the Contractor may at their own option either:

- **a.** Use such material in another contract item, providing such use is approved by the RPR and is in conformance with the contract specifications applicable to such use; or,
 - **b.** Remove such material from the site, upon written approval of the RPR; or
 - c. Use such material for the Contractor's own temporary construction on site; or,
 - **d.** Use such material as intended by the terms of the contract.

Should the Contractor wish to exercise option a., b., or c., the Contractor shall request the RPR's approval in advance of such use.

Should the RPR approve the Contractor's request to exercise option a., b., or c., the Contractor shall be paid for the excavation or removal of such material at the applicable contract price. The Contractor shall replace, at their expense, such removed or excavated material with an agreed equal volume of material that is acceptable for use in constructing embankment, backfills, or otherwise to the extent that such replacement material is needed to complete the contract work. The Contractor shall not be charged for use of such material used in the work or removed from the site.

Should the RPR approve the Contractor's exercise of option a., the Contractor shall be paid, at the applicable contract price, for furnishing and installing such material in accordance with requirements of the contract item in which the material is used.

It is understood and agreed that the Contractor shall make no claim for delays by reason of their own exercise of option a., b., or c.

The Contractor shall not excavate, remove, or otherwise disturb any material, structure, or part of a structure which is located outside the lines, grades, or grading sections established for the work, except where such excavation or removal is provided for in the contract, plans, or specifications.

40-08 Final cleanup. Upon completion of the work and before acceptance and final payment will be made, the Contractor shall remove from the site all machinery, equipment, surplus and discarded materials, rubbish, temporary structures, and stumps or portions of trees. The Contractor shall cut all brush and woods within the limits indicated and shall leave the site in a neat and presentable condition. Material cleared from the site and deposited on adjacent property will not be considered as having been disposed of satisfactorily, unless the Contractor has obtained the written permission of the property Owner.

END OF SECTION 40

GP-40 Scope of Work GP-40-3 of 4

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

THIS PAGE INTENTIONALLY LEFT BLANK

GP-40 Scope of Work GP-40-4 of 4

SECTION 50 CONTROL OF WORK

50-01 Authority of the Resident Project Representative (RPR). The RPR has final authority regarding the interpretation of project specification requirements. The RPR shall determine acceptability of the quality of materials furnished, method of performance of work performed, and the manner and rate of performance of the work. The RPR does not have the authority to accept work that does not conform to specification requirements.

50-02 Conformity with plans and specifications. All work and all materials furnished shall be in reasonably close conformity with the lines, grades, grading sections, cross-sections, dimensions, material requirements, and testing requirements that are specified (including specified tolerances) in the contract, plans, or specifications.

If the RPR finds the materials furnished, work performed, or the finished product not within reasonably close conformity with the plans and specifications, but that the portion of the work affected will, in their opinion, result in a finished product having a level of safety, economy, durability, and workmanship acceptable to the Owner, the RPR will advise the Owner of their determination that the affected work be accepted and remain in place. The RPR will document the determination and recommend to the Owner a basis of acceptance that will provide for an adjustment in the contract price for the affected portion of the work. Changes in the contract price must be covered by contract change order or supplemental agreement as applicable.

If the RPR finds the materials furnished, work performed, or the finished product are not in reasonably close conformity with the plans and specifications and have resulted in an unacceptable finished product, the affected work or materials shall be removed and replaced or otherwise corrected by and at the expense of the Contractor in accordance with the RPR's written orders.

The term "reasonably close conformity" shall not be construed as waiving the Contractor's responsibility to complete the work in accordance with the contract, plans, and specifications. The term shall not be construed as waiving the RPR's responsibility to insist on strict compliance with the requirements of the contract, plans, and specifications during the Contractor's execution of the work, when, in the RPR's opinion, such compliance is essential to provide an acceptable finished portion of the work.

The term "reasonably close conformity" is also intended to provide the RPR with the authority, after consultation with the Sponsor and FAA, to use sound engineering judgment in their determinations to accept work that is not in strict conformity, but will provide a finished product equal to or better than that required by the requirements of the contract, plans and specifications.

The RPR will not be responsible for the Contractor's means, methods, techniques, sequences, or procedures of construction or the safety precautions incident thereto.

50-03 Coordination of contract, plans, and specifications. The contract, plans, specifications, and all referenced standards cited are essential parts of the contract requirements. If electronic files are provided and used on the project and there is a conflict between the electronic files and hard copy plans, the hard copy plans shall govern. A requirement occurring in one is as binding as though occurring in all. They are intended to be complementary and to describe and provide for a complete work. In case of discrepancy, calculated dimensions will govern over scaled dimensions; contract technical specifications shall govern over contract general provisions, plans, cited standards for materials or testing, and cited advisory circulars (ACs); contract general provisions shall govern over plans, cited standards for materials or testing, and cited ACs; plans shall govern over cited standards for materials or testing and cited ACs. If any paragraphs contained in the Special Provisions conflict with General Provisions or Technical Specifications, the Special Provisions shall govern.

GP-50 Control of Work GP-50-1 of 6

From time to time, discrepancies within cited testing standards occur due to the timing of the change, edits, and/or replacement of the standards. If the Contractor discovers any apparent discrepancy within standard test methods, the Contractor shall immediately ask the RPR for an interpretation and decision, and such decision shall be final.

The Contractor shall not take advantage of any apparent error or omission on the plans or specifications. In the event the Contractor discovers any apparent error or discrepancy, Contractor shall immediately notify the Owner or the designated representative in writing requesting their written interpretation and decision.

50-04 List of Special Provisions. None

50-05 Cooperation of Contractor. The Contractor shall be supplied with five hard copies or an electronic PDF of the plans and specifications. The Contractor shall have available on the construction site at all times one hardcopy each of the plans and specifications. Additional hard copies of plans and specifications may be obtained by the Contractor for the cost of reproduction.

The Contractor shall give constant attention to the work to facilitate the progress thereof, and shall cooperate with the RPR and their inspectors and with other Contractors in every way possible. The Contractor shall have a competent superintendent on the work at all times who is fully authorized as their agent on the work. The superintendent shall be capable of reading and thoroughly understanding the plans and specifications and shall receive and fulfill instructions from the RPR or their authorized representative.

50-06 Cooperation between Contractors. The Owner reserves the right to contract for and perform other or additional work on or near the work covered by this contract.

When separate contracts are let within the limits of any one project, each Contractor shall conduct the work not to interfere with or hinder the progress of completion of the work being performed by other Contractors. Contractors working on the same project shall cooperate with each other as directed.

Each Contractor involved shall assume all liability, financial or otherwise, in connection with their own contract and shall protect and hold harmless the Owner from any and all damages or claims that may arise because of inconvenience, delays, or loss experienced because of the presence and operations of other Contractors working within the limits of the same project.

The Contractor shall arrange their work and shall place and dispose of the materials being used to not interfere with the operations of the other Contractors within the limits of the same project. The Contractor shall join their work with that of the others in an acceptable manner and shall perform it in proper sequence to that of the others.

50-07 Construction layout and stakes. The Engineer/RPR shall establish necessary horizontal and vertical control. The establishment of Survey Control and/or reestablishment of survey control shall be by a State Licensed Land Surveyor. Contractor is responsible for preserving integrity of horizontal and vertical controls established by Engineer/RPR. In case of negligence on the part of the Contractor or their employees, resulting in the destruction of any horizontal and vertical control, the resulting costs will be deducted as a liquidated damage against the Contractor.

Prior to the start of construction, the Contractor will check all control points for horizontal and vertical accuracy and certify in writing to the RPR that the Contractor concurs with survey control established for the project. All lines, grades and measurements from control points necessary for the proper execution and control of the work on this project will be provided to the RPR. The Contractor is responsible to establish all layout required for the construction of the project.

Copies of survey notes will be provided to the RPR for each area of construction and for each placement of material as specified to allow the RPR to make periodic checks for conformance with plan grades, alignments and grade tolerances required by the applicable material specifications. Surveys will be provided to the RPR prior to commencing work items that cover or disturb the survey staking. Survey(s) and notes shall be provided in the following format(s): hard copy and electronic text files.

GP-50 Control of Work GP-50-2 of 6

Laser, GPS, String line, or other automatic control shall be checked with temporary control as necessary. In the case of error, on the part of the Contractor, their surveyor, employees or subcontractors, resulting in established grades, alignment or grade tolerances that do not concur with those specified or shown on the plans, the Contractor is solely responsible for correction, removal, replacement and all associated costs at no additional cost to the Owner.

No direct payment will be made, unless otherwise specified in contract documents, for this labor, materials, or other expenses. The cost shall be included in the price of the bid for the various items of the Contract.

50-08 Authority and duties of Quality Assurance (QA) inspectors. QA inspectors shall be authorized to inspect all work done and all material furnished. Such QA inspection may extend to all or any part of the work and to the preparation, fabrication, or manufacture of the materials to be used. QA inspectors are not authorized to revoke, alter, or waive any provision of the contract. QA inspectors are not authorized to issue instructions contrary to the plans and specifications or to act as foreman for the Contractor.

QA Inspectors are authorized to notify the Contractor or their representatives of any failure of the work or materials to conform to the requirements of the contract, plans, or specifications and to reject such nonconforming materials in question until such issues can be referred to the RPR for a decision.

50-09 Inspection of the work. All materials and each part or detail of the work shall be subject to inspection. The RPR shall be allowed access to all parts of the work and shall be furnished with such information and assistance by the Contractor as is required to make a complete and detailed inspection.

If the RPR requests it, the Contractor, at any time before acceptance of the work, shall remove or uncover such portions of the finished work as may be directed. After examination, the Contractor shall restore said portions of the work to the standard required by the specifications. Should the work thus exposed or examined prove acceptable, the uncovering, or removing, and the replacing of the covering or making good of the parts removed will be paid for as extra work; but should the work so exposed or examined prove unacceptable, the uncovering, or removing, and the replacing of the covering or making good of the parts removed will be at the Contractor's expense.

Provide advance written notice to the RPR of work the Contractor plans to perform each week and each day. Any work done or materials used without written notice and allowing opportunity for inspection by the RPR may be ordered removed and replaced at the Contractor's expense.

Should the contract work include relocation, adjustment, or any other modification to existing facilities, not the property of the (contract) Owner, authorized representatives of the Owners of such facilities shall have the right to inspect such work. Such inspection shall in no sense make any facility owner a party to the contract, and shall in no way interfere with the rights of the parties to this contract.

50-10 Removal of unacceptable and unauthorized work. All work that does not conform to the requirements of the contract, plans, and specifications will be considered unacceptable, unless otherwise determined acceptable by the RPR as provided in paragraph 50-02, *Conformity with Plans and Specifications*.

Unacceptable work, whether the result of poor workmanship, use of defective materials, damage through carelessness, or any other cause found to exist prior to the final acceptance of the work, shall be removed immediately and replaced in an acceptable manner in accordance with the provisions of Section 70, paragraph 70-14, *Contractor's Responsibility for Work*.

No removal work made under provision of this paragraph shall be done without lines and grades having been established by the RPR. Work done contrary to the instructions of the RPR, work done beyond the lines shown on the plans or as established by the RPR, except as herein specified, or any extra work done without authority, will be considered as unauthorized and will not be paid for under the provisions of the contract. Work so done may be ordered removed or replaced at the Contractor's expense.

GP-50 Control of Work GP-50-3 of 6

Upon failure on the part of the Contractor to comply with any order of the RPR made under the provisions of this subsection, the RPR will have authority to cause unacceptable work to be remedied or removed and replaced; and unauthorized work to be removed and recover the resulting costs as a liquidated damage against the Contractor.

50-11 Load restrictions. The Contractor shall comply with all legal load restrictions in the hauling of materials on public roads beyond the limits of the work. A special permit will not relieve the Contractor of liability for damage that may result from the moving of material or equipment.

The operation of equipment of such weight or so loaded as to cause damage to structures or to any other type of construction will not be permitted. Hauling of materials over the base course or surface course under construction shall be limited as directed. No loads will be permitted on a concrete pavement, base, or structure before the expiration of the curing period. The Contractor, at their own expense, shall be responsible for the repair to equal or better than preconstruction conditions of any damage caused by the Contractor's equipment and personnel.

50-12 Maintenance during construction. The Contractor shall maintain the work during construction and until the work is accepted. Maintenance shall constitute continuous and effective work prosecuted day by day, with adequate equipment and forces so that the work is maintained in satisfactory condition at all times.

In the case of a contract for the placing of a course upon a course or subgrade previously constructed, the Contractor shall maintain the previous course or subgrade during all construction operations.

All costs of maintenance work during construction and before the project is accepted shall be included in the unit prices bid on the various contract items, and the Contractor will not be paid an additional amount for such work.

50-13 Failure to maintain the work. Should the Contractor at any time fail to maintain the work as provided in paragraph 50-12, *Maintenance during Construction*, the RPR shall immediately notify the Contractor of such noncompliance. Such notification shall specify a reasonable time within which the Contractor shall be required to remedy such unsatisfactory maintenance condition. The time specified will give due consideration to the exigency that exists.

Should the Contractor fail to respond to the RPR's notification, the Owner may suspend any work necessary for the Owner to correct such unsatisfactory maintenance condition, depending on the exigency that exists. Any maintenance cost incurred by the Owner, shall be recovered as a liquidated damage against the Contractor.

- **50-14 Partial acceptance**. If at any time during the execution of the project the Contractor substantially completes a usable unit or portion of the work, the occupancy of which will benefit the Owner, the Contractor may request the RPR to make final inspection of that unit. If the RPR finds upon inspection that the unit has been satisfactorily completed in compliance with the contract, the RPR may accept it as being complete, and the Contractor may be relieved of further responsibility for that unit. Such partial acceptance and beneficial occupancy by the Owner shall not void or alter any provision of the contract.
- **50-15 Final acceptance.** Upon due notice from the Contractor of presumptive completion of the entire project, the RPR and Owner will make an inspection. If all construction provided for and contemplated by the contract is found to be complete in accordance with the contract, plans, and specifications, such inspection shall constitute the final inspection. The RPR shall notify the Contractor in writing of final acceptance as of the date of the final inspection.

If, however, the inspection discloses any work, in whole or in part, as being unsatisfactory, the RPR will notify the Contractor and the Contractor shall correct the unsatisfactory work. Upon correction of the work, another inspection will be made which shall constitute the final inspection, provided the work has been satisfactorily completed. In such event, the RPR will make the final acceptance and notify the Contractor in writing of this acceptance as of the date of final inspection.

GP-50 Control of Work GP-50-4 of 6

50-16 Claims for adjustment and disputes. If for any reason the Contractor deems that additional compensation is due for work or materials not clearly provided for in the contract, plans, or specifications or previously authorized as extra work, the Contractor shall notify the RPR in writing of their intention to claim such additional compensation before the Contractor begins the work on which the Contractor bases the claim. If such notification is not given or the RPR is not afforded proper opportunity by the Contractor for keeping strict account of actual cost as required, then the Contractor hereby agrees to waive any claim for such additional compensation. Such notice by the Contractor and the fact that the RPR has kept account of the cost of the work shall not in any way be construed as proving or substantiating the validity of the claim. When the work on which the claim for additional compensation is based has been completed, the Contractor shall, within 10 calendar days, submit a written claim to the RPR who will present it to the Owner for consideration in accordance with local laws or ordinances.

Nothing in this subsection shall be construed as a waiver of the Contractor's right to dispute final payment based on differences in measurements or computations.

50-17 Value Engineering Cost Proposal. The provisions of this paragraph will apply only to contracts awarded to the lowest bidder pursuant to competitive bidding.

On projects with original contract amounts in excess of \$100,000, the Contractor may submit to the RPR, in writing, proposals for modifying the plans, specifications or other requirements of the contract for the sole purpose of reducing the cost of construction. The value engineering cost proposal shall not impair, in any manner, the essential functions or characteristics of the project, including but not limited to service life, economy of operation, ease of maintenance, desired appearance, design and safety standards. This provision shall not apply unless the proposal submitted is specifically identified by the Contractor as being presented for consideration as a value engineering proposal.

Not eligible for value engineering cost proposals are changes in the basic design of a pavement type, runway and taxiway lighting, visual aids, hydraulic capacity of drainage facilities, or changes in grade or alignment that reduce the geometric standards of the project.

As a minimum, the following information shall be submitted by the Contractor with each proposal:

- a. A description of both existing contract requirements for performing the work and the proposed changes, with a discussion of the comparative advantages and disadvantages of each.
 - b. An itemization of the contract requirements that must be changed if the proposal is adopted.
- c. A detailed estimate of the cost of performing the work under the existing contract and under the proposed changes.
 - d. A statement of the time by which a change order adopting the proposal must be issued.
 - e. A statement of the effect adoption of the proposal will have on the time for completion of the contract.
- f. The contract items of work affected by the proposed changes, including any quantity variation attributable to them.

The Contractor may withdraw, in whole or in part, any value engineering cost proposal not accepted by the RPR, within the period specified in the proposal. The provisions of this subsection shall not be construed to require the RPR to consider any value engineering cost proposal that may be submitted.

The Contractor shall continue to perform the work in accordance with the requirements of the contract until a change order incorporating the value engineering cost proposal has been issued. If a change order has not been issued by the date upon which the Contractor's value engineering cost proposal specifies that a decision should be made, or such other date as the Contractor may subsequently have requested in writing, such value engineering cost proposal shall be deemed rejected.

GP-50 Control of Work GP-50-5 of 6

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

The RPR shall be the sole judge of the acceptability of a value engineering cost proposal and of the estimated net savings from the adoption of all or any part of such proposal. In determining the estimated net savings, the RPR may disregard the contract bid prices if, in the RPR's judgment such prices do not represent a fair measure of the value of the work to be performed or deleted.

The Owner may require the Contractor to share in the Owner's costs of investigating a value engineering cost proposal submitted by the Contractor as a condition of considering such proposal. Where such a condition is imposed, the Contractor shall acknowledge acceptance of it in writing. Such acceptance shall constitute full authority for the Owner to deduct the cost of investigating a value engineering cost proposal from amounts payable to the Contractor under the contract.

If the Contractor's value engineering cost proposal is accepted in whole or in part, such acceptance will be by a contract change order that shall specifically state that it is executed pursuant to this paragraph. Such change order shall incorporate the changes in the plans and specifications which are necessary to permit the value engineering cost proposal or such part of it as has been accepted and shall include any conditions upon which the RPR's approval is based. The change order shall also set forth the estimated net savings attributable to the value engineering cost proposal. The net savings shall be determined as the difference in costs between the original contract costs for the involved work items and the costs occurring as a result of the proposed change. The change order shall also establish the net savings agreed upon and shall provide for adjustment in the contract price that will divide the net savings equally between the Contractor and the Owner.

The Contractor's 50% share of the net savings shall constitute full compensation to the Contractor for the value engineering cost proposal and the performance of the work.

Acceptance of the value engineering cost proposal and performance of the work shall not extend the time of completion of the contract unless specifically provided for in the contract change order.

END OF SECTION 50

GP-50 Control of Work GP-50-6 of 6

SECTION 60 CONTROL OF MATERIALS

60-01 Source of supply and quality requirements. The materials used in the work shall conform to the requirements of the contract, plans, and specifications. Unless otherwise specified, such materials that are manufactured or processed shall be new (as compared to used or reprocessed).

In order to expedite the inspection and testing of materials, the Contractor shall furnish documentation to the RPR as to the origin, composition, and manufacture of all materials to be used in the work. Documentation shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials.

At the RPR's option, materials may be approved at the source of supply before delivery. If it is found after trial that sources of supply for previously approved materials do not produce specified products, the Contractor shall furnish materials from other sources.

The Contractor shall furnish airport lighting equipment that meets the requirements of the specifications; and is listed in AC 150/5345-53, *Airport Lighting Equipment Certification Program* and *Addendum*, that is in effect on the date of advertisement.

60-02 Samples, tests, and cited specifications. All materials used in the work shall be inspected, tested, and approved by the RPR before incorporation in the work unless otherwise designated. Any work in which untested materials are used without approval or written permission of the RPR shall be performed at the Contractor's risk. Materials found to be unacceptable and unauthorized will not be paid for and, if directed by the RPR, shall be removed at the Contractor's expense.

Unless otherwise designated, quality assurance tests will be made by and at the expense of the Owner in accordance with the cited standard methods of ASTM, American Association of State Highway and Transportation Officials (AASHTO), federal specifications, Commercial Item Descriptions, and all other cited methods, which are current on the date of advertisement for bids.

The testing organizations performing on-site quality assurance field tests shall have copies of all referenced standards on the construction site for use by all technicians and other personnel. Unless otherwise designated, samples for quality assurance will be taken by a qualified representative of the RPR. All materials being used are subject to inspection, test, or rejection at any time prior to or during incorporation into the work. Copies of all tests will be furnished to the Contractor's representative at their request after review and approval of the RPR.

A copy of all Contractor QC test data shall be provided to the RPR daily, along with printed reports, in an approved format, on a weekly basis. After completion of the project, and prior to final payment, the Contractor shall submit a final report to the RPR showing all test data reports, plus an analysis of all results showing ranges, averages, and corrective action taken on all failing tests.

The Contractor shall employ a Quality Control (QC) testing organization to perform all Contractor required QC tests in accordance with Item C-100 Contractor Quality Control Program (CQCP).

60-03 Certification of compliance/analysis (COC/COA). The RPR may permit the use, prior to sampling and testing, of certain materials or assemblies when accompanied by manufacturer's COC stating that such materials or assemblies fully comply with the requirements of the contract. The certificate shall be signed by the manufacturer. Each lot of such materials or assemblies delivered to the work must be accompanied by a certificate of compliance in which the lot is clearly identified. The COA is the manufacturer's COC and includes all applicable test results.

GP-60 Control of Materials GP-60-1 of 4

Materials or assemblies used on the basis of certificates of compliance may be sampled and tested at any time and if found not to be in conformity with contract requirements will be subject to rejection whether in place or not.

The form and distribution of certificates of compliance shall be as approved by the RPR.

When a material or assembly is specified by "brand name or equal" and the Contractor elects to furnish the specified "or equal," the Contractor shall be required to furnish the manufacturer's certificate of compliance for each lot of such material or assembly delivered to the work. Such certificate of compliance shall clearly identify each lot delivered and shall certify as to:

- a. Conformance to the specified performance, testing, quality or dimensional requirements; and,
- **b.** Suitability of the material or assembly for the use intended in the contract work.

The RPR shall be the sole judge as to whether the proposed "or equal" is suitable for use in the work.

The RPR reserves the right to refuse permission for use of materials or assemblies on the basis of certificates of compliance.

60-04 Plant inspection. The RPR or their authorized representative may inspect, at its source, any specified material or assembly to be used in the work. Manufacturing plants may be inspected from time to time for the purpose of determining compliance with specified manufacturing methods or materials to be used in the work and to obtain samples required for acceptance of the material or assembly.

Should the RPR conduct plant inspections, the following conditions shall exist:

- **a.** The RPR shall have the cooperation and assistance of the Contractor and the producer with whom the Contractor has contracted for materials.
- **b.** The RPR shall have full entry at all reasonable times to such parts of the plant that concern the manufacture or production of the materials being furnished.
- **c.** If required by the RPR, the Contractor shall arrange for adequate office or working space that may be reasonably needed for conducting plant inspections. Place office or working space in a convenient location with respect to the plant.

It is understood and agreed that the Owner shall have the right to retest any material that has been tested and approved at the source of supply after it has been delivered to the site. The RPR shall have the right to reject only material which, when retested, does not meet the requirements of the contract, plans, or specifications.

60-05 Engineer/ Resident Project Representative (RPR) field office. An Engineer/RPR field office is not required.

60-06 Storage of materials. Materials shall be stored to assure the preservation of their quality and fitness for the work. Stored materials, even though approved before storage, may again be inspected prior to their use in the work. Stored materials shall be located to facilitate their prompt inspection. The Contractor shall coordinate the storage of all materials with the RPR. Materials to be stored on airport property shall not create an obstruction to air navigation nor shall they interfere with the free and unobstructed movement of aircraft. Unless otherwise shown on the plans and/or CSPP, the storage of materials and the location of the Contractor's plant and parked equipment or vehicles shall be as directed by the RPR. Private property shall not be used for storage purposes without written permission of the Owner or lessee of such property. The Contractor shall make all arrangements and bear all expenses for the storage of materials on private property. Upon request, the Contractor shall furnish the RPR a copy of the property Owner's permission.

All storage sites on private or airport property shall be restored to their original condition by the Contractor at their expense, except as otherwise agreed to (in writing) by the Owner or lessee of the property.

GP-60 Control of Materials GP-60-2 of 4

60-07 Unacceptable materials. Any material or assembly that does not conform to the requirements of the contract, plans, or specifications shall be considered unacceptable and shall be rejected. The Contractor shall remove any rejected material or assembly from the site of the work, unless otherwise instructed by the RPR.

Rejected material or assembly, the defects of which have been corrected by the Contractor, shall not be returned to the site of the work until such time as the RPR has approved its use in the work.

60-08 Owner furnished materials. The Contractor shall furnish all materials required to complete the work, except those specified, if any, to be furnished by the Owner. Owner-furnished materials shall be made available to the Contractor at the location specified.

All costs of handling, transportation from the specified location to the site of work, storage, and installing Owner-furnished materials shall be included in the unit price bid for the contract item in which such Owner-furnished material is used.

After any Owner-furnished material has been delivered to the location specified, the Contractor shall be responsible for any demurrage, damage, loss, or other deficiencies that may occur during the Contractor's handling, storage, or use of such Owner-furnished material. The Owner will deduct from any monies due or to become due the Contractor any cost incurred by the Owner in making good such loss due to the Contractor's handling, storage, or use of Owner-furnished materials.

END OF SECTION 60

GP-60 Control of Materials GP-60-3 of 4

THIS PAGE INTENTIONALLY LEFT BLANK

GP-60 Control of Materials GP-60-4 of 4

SECTION 70 LEGAL REGULATIONS AND RESPONSIBILITY TO PUBLIC

70-01 Laws to be observed. The Contractor shall keep fully informed of all federal and state laws, all local laws, ordinances, and regulations and all orders and decrees of bodies or tribunals having any jurisdiction or authority, which in any manner affect those engaged or employed on the work, or which in any way affect the conduct of the work. The Contractor shall at all times observe and comply with all such laws, ordinances, regulations, orders, and decrees; and shall protect and indemnify the Owner and all their officers, agents, or servants against any claim or liability arising from or based on the violation of any such law, ordinance, regulation, order, or decree, whether by the Contractor or the Contractor's employees.

70-02 Permits, licenses, and taxes. The Contractor shall procure all permits and licenses, pay all charges, fees, and taxes, and give all notices necessary and incidental to the due and lawful execution of the work.

70-03 Patented devices, materials, and processes. If the Contractor is required or desires to use any design, device, material, or process covered by letters of patent or copyright, the Contractor shall provide for such use by suitable legal agreement with the Patentee or Owner. The Contractor and the surety shall indemnify and hold harmless the Owner, any third party, or political subdivision from any and all claims for infringement by reason of the use of any such patented design, device, material or process, or any trademark or copyright, and shall indemnify the Owner for any costs, expenses, and damages which it may be obliged to pay by reason of an infringement, at any time during the execution or after the completion of the work.

70-04 Restoration of surfaces disturbed by others. The Owner reserves the right to authorize the construction, reconstruction, or maintenance of any public or private utility service, FAA or National Oceanic and Atmospheric Administration (NOAA) facility, or a utility service of another government agency at any time during the progress of the work. To the extent that such construction, reconstruction, or maintenance has been coordinated with the Owner, such authorized work (by others) must be shown on the plans and is indicated as follows:

- Owner (Utility or Other Facility): Not Applicable
- Location (See Plan Sheet No.)
- Person to Contact (Name, Title, Address and Phone)

Except as listed above, the Contractor shall not permit any individual, firm, or corporation to excavate or otherwise disturb such utility services or facilities located within the limits of the work without the written permission of the RPR.

Should the Owner of public or private utility service, FAA, or NOAA facility, or a utility service of another government agency be authorized to construct, reconstruct, or maintain such utility service or facility during the progress of the work, the Contractor shall cooperate with such Owners by arranging and performing the work in this contract to facilitate such construction, reconstruction or maintenance by others whether or not such work by others is listed above. When ordered as extra work by the RPR, the Contractor shall make all necessary repairs to the work which are due to such authorized work by others, unless otherwise provided for in the contract, plans, or specifications. It is understood and agreed that the Contractor shall not be entitled to make any claim for damages due to such authorized work by others or for any delay to the work resulting from such authorized work.

70-05 Federal Participation. The United States Government has agreed to reimburse the Owner for some portion of the contract costs. The contract work is subject to the inspection and approval of duly authorized representatives of the FAA Administrator. No requirement of this contract shall be construed as making

the United States a party to the contract nor will any such requirement interfere, in any way, with the rights of either party to the contract.

70-06 Sanitary, health, and safety provisions. The Contractor's worksite and facilities shall comply with applicable federal, state, and local requirements for health, safety and sanitary provisions.

70-07 Public convenience and safety. The Contractor shall control their operations and those of their subcontractors and all suppliers, to assure the least inconvenience to the traveling public. Under all circumstances, safety shall be the most important consideration.

The Contractor shall maintain the free and unobstructed movement of aircraft and vehicular traffic with respect to their own operations and those of their own subcontractors and all suppliers in accordance with Section 40, paragraph 40-05, *Maintenance of Traffic*, and shall limit such operations for the convenience and safety of the traveling public as specified in Section 80, paragraph 80-04, *Limitation of Operations*.

The Contractor shall remove or control debris and rubbish resulting from its work operations at frequent intervals, and upon the order of the RPR. If the RPR determines the existence of Contractor debris in the work site represents a hazard to airport operations and the Contractor is unable to respond in a prompt and reasonable manner, the RPR reserves the right to assign the task of debris removal to a third party and recover the resulting costs as a liquidated damage against the Contractor.

70-08 Construction Safety and Phasing Plan (CSPP). The Contractor shall complete the work in accordance with the approved Construction Safety and Phasing Plan (CSPP) developed in accordance with AC 150/5370-2, Operational Safety on Airports During Construction. The CSPP is included within the project plans.

70-09 Use of explosives. The use of explosives is not permitted on this project.

70-10 Protection and restoration of property and landscape. The Contractor shall be responsible for the preservation of all public and private property, and shall protect carefully from disturbance or damage all land monuments and property markers until the Engineer/RPR has witnessed or otherwise referenced their location and shall not move them until directed.

The Contractor shall be responsible for all damage or injury to property of any character, during the execution of the work, resulting from any act, omission, neglect, or misconduct in manner or method of executing the work, or at any time due to defective work or materials, and said responsibility shall not be released until the project has been completed and accepted.

When or where any direct or indirect damage or injury is done to public or private property by or on account of any act, omission, neglect, or misconduct in the execution of the work, or in consequence of the non-execution thereof by the Contractor, the Contractor shall restore, at their expense, such property to a condition similar or equal to that existing before such damage or injury was done, by repairing, or otherwise restoring as may be directed, or the Contractor shall make good such damage or injury in an acceptable manner.

70-11 Responsibility for damage claims. The Contractor shall indemnify and hold harmless the Engineer/RPR and the Owner and their officers, agents, and employees from all suits, actions, or claims, of any character, brought because of any injuries or damage received or sustained by any person, persons, or property on account of the operations of the Contractor; or on account of or in consequence of any neglect in safeguarding the work; or through use of unacceptable materials in constructing the work; or because of any act or omission, neglect, or misconduct of said Contractor; or because of any claims or amounts recovered from any infringements of patent, trademark, or copyright; or from any claims or amounts arising or recovered under the "Workmen's Compensation Act," or any other law, ordinance, order, or decree. Money due the Contractor under and by virtue of their own contract considered necessary by the Owner for such purpose may be retained for the use of the Owner or, in case no money is due, their own surety may be held until such suits, actions, or claims for injuries or damages shall have been settled and suitable

evidence to that effect furnished to the Owner, except that money due the Contractor will not be withheld when the Contractor produces satisfactory evidence that he or she is adequately protected by public liability and property damage insurance.

70-12 Third party beneficiary clause. It is specifically agreed between the parties executing the contract that it is not intended by any of the provisions of any part of the contract to create for the public or any member thereof, a third-party beneficiary or to authorize anyone not a party to the contract to maintain a suit for personal injuries or property damage pursuant to the terms or provisions of the contract.

70-13 Opening sections of the work to traffic. If it is necessary for the Contractor to complete portions of the contract work for the beneficial occupancy of the Owner prior to completion of the entire contract, such "phasing" of the work must be specified below and indicated on the approved Construction Safety and Phasing Plan (CSPP) and the project plans. When so specified, the Contractor shall complete such portions of the work on or before the date specified or as otherwise specified.

Upon completion of any portion of work listed above, such portion shall be accepted by the Owner in accordance with Section 50, paragraph 50-14, *Partial Acceptance*.

No portion of the work may be opened by the Contractor until directed by the Owner in writing. Should it become necessary to open a portion of the work to traffic on a temporary or intermittent basis, such openings shall be made when, in the opinion of the RPR, such portion of the work is in an acceptable condition to support the intended traffic. Temporary or intermittent openings are considered to be inherent in the work and shall not constitute either acceptance of the portion of the work so opened or a waiver of any provision of the contract. Any damage to the portion of the work so opened that is not attributable to traffic which is permitted by the Owner shall be repaired by the Contractor at their expense.

The Contractor shall make their own estimate of the inherent difficulties involved in completing the work under the conditions herein described and shall not claim any added compensation by reason of delay or increased cost due to opening a portion of the contract work.

The Contractor must conform to safety standards contained AC 150/5370-2 and the approved CSPP.

Contractor shall refer to the plans, specifications, and the approved CSPP to identify barricade requirements, temporary and/or permanent markings, airfield lighting, guidance signs and other safety requirements prior to opening up sections of work to traffic.

70-14 Contractor's responsibility for work. Until the RPR's final written acceptance of the entire completed work, excepting only those portions of the work accepted in accordance with Section 50, paragraph 50-14, *Partial Acceptance*, the Contractor shall have the charge and care thereof and shall take every precaution against injury or damage to any part due to the action of the elements or from any other cause, whether arising from the execution or from the non-execution of the work. The Contractor shall rebuild, repair, restore, and make good all injuries or damages to any portion of the work occasioned by any of the above causes before final acceptance and shall bear the expense thereof except damage to the work due to unforeseeable causes beyond the control of and without the fault or negligence of the Contractor, including but not restricted to acts of God such as earthquake, tidal wave, tornado, hurricane or other cataclysmic phenomenon of nature, or acts of the public enemy or of government authorities.

If the work is suspended for any cause whatever, the Contractor shall be responsible for the work and shall take such precautions necessary to prevent damage to the work. The Contractor shall provide for normal drainage and shall erect necessary temporary structures, signs, or other facilities at their own expense. During such period of suspension of work, the Contractor shall properly and continuously maintain in an acceptable growing condition all living material in newly established planting, seeding, and sodding furnished under the contract, and shall take adequate precautions to protect new tree growth and other important vegetative growth against injury.

70-15 Contractor's responsibility for utility service and facilities of others. As provided in paragraph 70-04, *Restoration of Surfaces Disturbed by Others*, the Contractor shall cooperate with the owner of any public or private utility service, FAA or NOAA, or a utility service of another government agency that may be authorized by the Owner to construct, reconstruct or maintain such utility services or facilities during the progress of the work. In addition, the Contractor shall control their operations to prevent the unscheduled interruption of such utility services and facilities.

To the extent that such public or private utility services, FAA, or NOAA facilities, or utility services of another governmental agency are known to exist within the limits of the contract work, the approximate locations have been indicated on the plans and/or in the contract documents and the owners are indicated as follows:

Federal Aviation Administration – Forbes FCT Rick Stadler Building 620, P.O. Box 19305 Forbes Field Airport Topeka, Kansas 66619 Office Number: 785-862-9421

AT & T Doug Holthaus 823 SE Quincy Street, Room 1050 Topeka, Kansas 66612 Office Number: 785-276-6146

It is understood and agreed that the Owner does not guarantee the accuracy or the completeness of the location information relating to existing utility services, facilities, or structures that may be shown on the plans or encountered in the work. Any inaccuracy or omission in such information shall not relieve the Contractor of the responsibility to protect such existing features from damage or unscheduled interruption of service.

It is further understood and agreed that the Contractor shall, upon execution of the contract, notify the Owners of all utility services or other facilities of their plan of operations. Such notification shall be in writing addressed to "The Person to Contact" as provided in this paragraph and paragraph 70-04, *Restoration of Surfaces Disturbed By Others*. A copy of each notification shall be given to the RPR.

In addition to the general written notification provided, it shall be the responsibility of the Contractor to keep such individual Owners advised of changes in their plan of operations that would affect such Owners.

Prior to beginning the work in the general vicinity of an existing utility service or facility, the Contractor shall again notify each such Owner of their plan of operation. If, in the Contractor's opinion, the Owner's assistance is needed to locate the utility service or facility or the presence of a representative of the Owner is desirable to observe the work, such advice should be included in the notification. Such notification shall be given by the most expeditious means to reach the utility owner's "Person to Contact" no later than two normal business days prior to the Contractor's commencement of operations in such general vicinity. The Contractor shall furnish a written summary of the notification to the RPR.

The Contractor's failure to give the two days' notice shall be cause for the Owner to suspend the Contractor's operations in the general vicinity of a utility service or facility.

Where the outside limits of an underground utility service have been located and staked on the ground, the Contractor shall be required to use hand excavation methods within 3 feet (1 m) of such outside limits at such points as may be required to ensure protection from damage due to the Contractor's operations.

Should the Contractor damage or interrupt the operation of a utility service or facility by accident or otherwise, the Contractor shall immediately notify the proper authority and the RPR and shall take all reasonable measures to prevent further damage or interruption of service. The Contractor, in such events, shall cooperate with the utility service or facility owner and the RPR continuously until such damage has been repaired and service restored to the satisfaction of the utility or facility owner.

The Contractor shall bear all costs of damage and restoration of service to any utility service or facility due to their operations whether due to negligence or accident. The Owner reserves the right to deduct such costs from any monies due or which may become due the Contractor, or their own surety.

- **70-15.1 FAA facilities and cable runs**. The Contractor is hereby advised that the construction limits of the project include existing facilities and buried cable runs that are owned, operated and maintained by the FAA. The Contractor, during the execution of the project work, shall comply with the following:
- a. The Contractor shall permit FAA maintenance personnel the right of access to the project work site for purposes of inspecting and maintaining all existing FAA owned facilities.
- b. The Contractor shall provide notice to the FAA Air Traffic Organization (ATO)/Technical Operations/System Support Center (SSC) Point-of-Contact through the airport Owner a minimum of seven (7) calendar days prior to commencement of construction activities in order to permit sufficient time to locate and mark existing buried cables and to schedule any required facility outages.
- c. If execution of the project work requires a facility outage, the Contractor shall contact the FAA Point-of-Contact a minimum of 72 hours prior to the time of the required outage.
- d. Any damage to FAA cables, access roads, or FAA facilities during construction caused by the Contractor's equipment or personnel whether by negligence or accident will require the Contractor to repair or replace the damaged cables, access road, or FAA facilities to FAA requirements. The Contractor shall not bear the cost to repair damage to underground facilities or utilities improperly located by the FAA.
- e. If the project work requires the cutting or splicing of FAA owned cables, the FAA Point-of-Contact shall be contacted a minimum of 72 hours prior to the time the cable work commences. The FAA reserves the right to have a FAA representative on site to observe the splicing of the cables as a condition of acceptance. All cable splices are to be accomplished in accordance with FAA specifications and require approval by the FAA Point-of-Contact as a condition of acceptance by the Owner. The Contractor is hereby advised that FAA restricts the location of where splices may be installed. If a cable splice is required in a location that is not permitted by FAA, the Contractor shall furnish and install a sufficient length of new cable that eliminates the need for any splice.
- **70-16 Furnishing rights-of-way**. The Owner will be responsible for furnishing all rights-of-way upon which the work is to be constructed in advance of the Contractor's operations.
- **70-17 Personal liability of public officials**. In carrying out any of the contract provisions or in exercising any power or authority granted by this contract, there shall be no liability upon the Engineer, RPR, their authorized representatives, or any officials of the Owner either personally or as an official of the Owner. It is understood that in such matters they act solely as agents and representatives of the Owner.
- **70-18** No waiver of legal rights. Upon completion of the work, the Owner will expeditiously make final inspection and notify the Contractor of final acceptance. Such final acceptance, however, shall not preclude or stop the Owner from correcting any measurement, estimate, or certificate made before or after completion of the work, nor shall the Owner be precluded or stopped from recovering from the Contractor or their surety, or both, such overpayment as may be sustained, or by failure on the part of the Contractor to fulfill their obligations under the contract. A waiver on the part of the Owner of any breach of any part of the contract shall not be held to be a waiver of any other or subsequent breach.

The Contractor, without prejudice to the terms of the contract, shall be liable to the Owner for latent defects, fraud, or such gross mistakes as may amount to fraud, or as regards the Owner's rights under any warranty or guaranty.

70-19 Environmental protection. The Contractor shall comply with all federal, state, and local laws and regulations controlling pollution of the environment. The Contractor shall take necessary precautions to prevent pollution of streams, lakes, ponds, and reservoirs with fuels, oils, asphalts, chemicals, or other harmful materials and to prevent pollution of the atmosphere from particulate and gaseous matter.

70-20 Archaeological and historical findings. Unless otherwise specified in this subsection, the Contractor is advised that the site of the work is not within any property, district, or site, and does not contain any building, structure, or object listed in the current National Register of Historic Places published by the United States Department of Interior.

Should the Contractor encounter, during their operations, any building, part of a building, structure, or object that is incongruous with its surroundings, the Contractor shall immediately cease operations in that location and notify the RPR. The RPR will immediately investigate the Contractor's finding and the Owner will direct the Contractor to either resume operations or to suspend operations as directed.

Should the Owner order suspension of the Contractor's operations in order to protect an archaeological or historical finding, or order the Contractor to perform extra work, such shall be covered by an appropriate contract change order or supplemental agreement as provided in Section 40, paragraph 40-04, *Extra Work*, and Section 90, paragraph 90-05, *Payment for Extra Work*. If appropriate, the contract change order or supplemental agreement shall include an extension of contract time in accordance with Section 80, paragraph 80-07, *Determination and Extension of Contract Time*.

70-21 Insurance Requirements. See the Supplementary Provisions for Insurance requirements.

END OF SECTION 70

SECTION 80 EXECUTION AND PROGRESS

80-01 Subletting of contract. The Owner will not recognize any subcontractor on the work. The Contractor shall at all times when work is in progress be represented either in person, by a qualified superintendent, or by other designated, qualified representative who is duly authorized to receive and execute orders of the Resident Project Representative (RPR).

The Contractor shall perform, with his organization, an amount of work equal to at least 30 percent of the total contract cost.

Should the Contractor elect to assign their contract, said assignment shall be concurred in by the surety, shall be presented for the consideration and approval of the Owner, and shall be consummated only on the written approval of the Owner.

The Contractor shall provide copies of all subcontracts to the RPR 14 days prior to being utilized on the project. As a minimum, the information shall include the following:

- Subcontractor's legal company name.
- Subcontractor's legal company address, including County name.
- Principal contact person's name, telephone and fax number.
- Complete narrative description, and dollar value of the work to be performed by the subcontractor.
- Copies of required insurance certificates in accordance with the specifications.
- Minority/ non-minority status.

80-02 Notice to proceed (NTP). The Owners notice to proceed will state the date on which contract time commences. The Contractor is expected to commence project operations within 10 days of the NTP date. The Contractor shall notify the RPR at least 24 hours in advance of the time contract operations begins. The Contractor shall not commence any actual operations prior to the date on which the notice to proceed is issued by the Owner.

80-03 Execution and progress. Unless otherwise specified, the Contractor shall submit their coordinated construction schedule showing all work activities for the RPR's review and acceptance at least 10 days prior to the start of work. The Contractor's progress schedule, once accepted by the RPR, will represent the Contractor's baseline plan to accomplish the project in accordance with the terms and conditions of the Contract. The RPR will compare actual Contractor progress against the baseline schedule to determine that status of the Contractor's performance. The Contractor shall provide sufficient materials, equipment, and labor to guarantee the completion of the project in accordance with the plans and specifications within the time set forth in the proposal.

If the Contractor falls significantly behind the submitted schedule, the Contractor shall, upon the RPR's request, submit a revised schedule for completion of the work within the contract time and modify their operations to provide such additional materials, equipment, and labor necessary to meet the revised schedule. Should the execution of the work be discontinued for any reason, the Contractor shall notify the RPR at least 24 hours in advance of resuming operations.

The Contractor shall not commence any actual construction prior to the date on which the NTP is issued by the Owner.

The project schedule shall be prepared as a network diagram in Critical Path Method (CPM), Program Evaluation and Review Technique (PERT), or other format, or as otherwise specified. It shall include information on the sequence of work activities, milestone dates, and activity duration. The schedule shall show all work items identified in the project proposal for each work area and shall include the project start date and end date.

The Contractor shall maintain the work schedule and provide an update and analysis of the progress schedule on a twice monthly basis, or as otherwise specified in the contract. Submission of the work schedule shall not relieve the Contractor of overall responsibility for scheduling, sequencing, and coordinating all work to comply with the requirements of the contract.

80-04 Limitation of operations. The Contractor shall control their operations and the operations of their subcontractors and all suppliers to provide for the free and unobstructed movement of aircraft in the air operations areas (AOA) of the airport.

When the work requires the Contractor to conduct their operations within an AOA of the airport, the work shall be coordinated with airport operations (through the RPR) at least 48 hours prior to commencement of such work. The Contractor shall not close an AOA until so authorized by the RPR and until the necessary temporary marking, signage and associated lighting is in place as provided in Section 70, paragraph 70-08, *Construction Safety and Phasing Plan (CSPP)*.

When the contract work requires the Contractor to work within an AOA of the airport on an intermittent basis (intermittent opening and closing of the AOA), the Contractor shall maintain constant communications as specified; immediately obey all instructions to vacate the AOA; and immediately obey all instructions to resume work in such AOA. Failure to maintain the specified communications or to obey instructions shall be cause for suspension of the Contractor's operations in the AOA until satisfactory conditions are provided. The areas of the AOA identified in the Construction Safety Phasing Plan (CSPP) and as listed below, cannot be closed to operating aircraft to permit the Contractor's operations on a continuous basis and will therefore be closed to aircraft operations intermittently as follows: See CSPP sheets included within the project plans for AOA closures, time periods they can be closed, type of communications required and the control authority necessary.

The Contractor shall be required to conform to safety standards contained in AC 150/5370-2, Operational Safety on Airports During Construction and the approved CSPP.

80-04.1 Operational safety on airport during construction. All Contractors' operations shall be conducted in accordance with the approved project Construction Safety and Phasing Plan (CSPP) and the Safety Plan Compliance Document (SPCD) and the provisions set forth within the current version of AC 150/5370-2, Operational Safety on Airports During Construction. The CSPP included within the contract documents conveys minimum requirements for operational safety on the airport during construction activities. The Contractor shall prepare and submit a SPCD that details how it proposes to comply with the requirements presented within the CSPP.

The Contractor shall implement all necessary safety plan measures prior to commencement of any work activity. The Contractor shall conduct routine checks to assure compliance with the safety plan measures.

The Contractor is responsible to the Owner for the conduct of all subcontractors it employs on the project. The Contractor shall assure that all subcontractors are made aware of the requirements of the CSPP and SPCD and that they implement and maintain all necessary measures.

No deviation or modifications may be made to the approved CSPP and SPCD unless approved in writing by the Owner. The necessary coordination actions to review Contractor proposed modifications to an approved CSPP or approved SPCD can require a significant amount of time.

80-05 Character of workers, methods, and equipment. The Contractor shall, at all times, employ sufficient labor and equipment for prosecuting the work to full completion in the manner and time required by the contract, plans, and specifications.

All workers shall have sufficient skill and experience to perform properly the work assigned to them. Workers engaged in special work or skilled work shall have sufficient experience in such work and in the operation of the equipment required to perform the work satisfactorily.

Any person employed by the Contractor or by any subcontractor who violates any operational regulations or operational safety requirements and, in the opinion of the RPR, does not perform his work in a proper and skillful manner or is intemperate or disorderly shall, at the written request of the RPR, be removed immediately by the Contractor or subcontractor employing such person, and shall not be employed again in any portion of the work without approval of the RPR.

Should the Contractor fail to remove such person or persons, or fail to furnish suitable and sufficient personnel for the proper execution of the work, the RPR may suspend the work by written notice until compliance with such orders.

All equipment that is proposed to be used on the work shall be of sufficient size and in such mechanical condition as to meet requirements of the work and to produce a satisfactory quality of work. Equipment used on any portion of the work shall not cause injury to previously completed work, adjacent property, or existing airport facilities due to its use.

When the methods and equipment to be used by the Contractor in accomplishing the work are not prescribed in the contract, the Contractor is free to use any methods or equipment that will accomplish the work in conformity with the requirements of the contract, plans, and specifications.

When the contract specifies the use of certain methods and equipment, such methods and equipment shall be used unless otherwise authorized by the RPR. If the Contractor desires to use a method or type of equipment other than specified in the contract, the Contractor may request authority from the RPR to do so. The request shall be in writing and shall include a full description of the methods and equipment proposed and of the reasons for desiring to make the change. If approval is given, it will be on the condition that the Contractor will be fully responsible for producing work in conformity with contract requirements. If, after trial use of the substituted methods or equipment, the RPR determines that the work produced does not meet contract requirements, the Contractor shall discontinue the use of the substitute method or equipment and shall complete the remaining work with the specified methods and equipment. The Contractor shall remove any deficient work and replace it with work of specified quality, or take such other corrective action as the RPR may direct. No change will be made in basis of payment for the contract items involved nor in contract time as a result of authorizing a change in methods or equipment under this paragraph.

80-06 Temporary suspension of the work. The Owner shall have the authority to suspend the work wholly, or in part, for such period or periods the Owner may deem necessary, due to unsuitable weather, or other conditions considered unfavorable for the execution of the work, or for such time necessary due to the failure on the part of the Contractor to carry out orders given or perform any or all provisions of the contract.

In the event that the Contractor is ordered by the Owner, in writing, to suspend work for some unforeseen cause not otherwise provided for in the contract and over which the Contractor has no control, the Contractor may be reimbursed for actual money expended on the work during the period of shutdown. No allowance will be made for anticipated profits. The period of shutdown shall be computed from the effective date of the written order to suspend work to the effective date of the written order to resume the work. Claims for such compensation shall be filed with the RPR within the time period stated in the RPR's order to resume work. The Contractor shall submit with their own claim information substantiating the amount shown on the claim. The RPR will forward the Contractor's claim to the Owner for consideration in accordance with local laws or ordinances. No provision of this article shall be construed as entitling the

Contractor to compensation for delays due to inclement weather or for any other delay provided for in the contract, plans, or specifications.

If it becomes necessary to suspend work for an indefinite period, the Contractor shall store all materials in such manner that they will not become an obstruction nor become damaged in any way. The Contractor shall take every precaution to prevent damage or deterioration of the work performed and provide for normal drainage of the work. The Contractor shall erect temporary structures where necessary to provide for traffic on, to, or from the airport.

80-07 Determination and extension of contract time. The number of calendar days shall be stated in the proposal and contract and shall be known as the Contract Time.

If the contract time requires extension for reasons beyond the Contractor's control, it shall be adjusted as follows:

80-07.1 Contract time based on calendar days. Contract Time based on calendar days shall consist of the number of calendar days stated in the contract counting from the effective date of the Notice to Proceed and including all Saturdays, Sundays, holidays, and non-work days. All calendar days elapsing between the effective dates of the Owner's orders to suspend and resume all work, due to causes not the fault of the Contractor, shall be excluded.

At the time of final payment, the contract time shall be increased in the same proportion as the cost of the actually completed quantities bears to the cost of the originally estimated quantities in the proposal. Such increase in the contract time shall not consider either cost of work or the extension of contract time that has been covered by a change order or supplemental agreement. Charges against the contract time will cease as of the date of final acceptance.

80-08 Failure to complete on time. For each calendar day or working day, as specified in the contract, that any work remains uncompleted after the contract time (including all extensions and adjustments as provided in paragraph 80-07, *Determination and Extension of Contract Time*) the sum specified in the contract and proposal as liquidated damages (LD) will be deducted from any money due or to become due the Contractor or their own surety. Such deducted sums shall not be deducted as a penalty but shall be considered as liquidation of a reasonable portion of damages including but not limited to additional engineering services that will be incurred by the Owner should the Contractor fail to complete the work in the time provided in their contract.

80-09 Default and termination of contract. The Contractor shall be considered in default of their contract and such default will be considered as cause for the Owner to terminate the contract for any of the following reasons, if the Contractor:

- a. Fails to begin the work under the contract within the time specified in the Notice to Proceed, or
- **b.** Fails to perform the work or fails to provide sufficient workers, equipment and/or materials to assure completion of work in accordance with the terms of the contract, or
- **c.** Performs the work unsuitably or neglects or refuses to remove materials or to perform anew such work as may be rejected as unacceptable and unsuitable, or
 - **d.** Discontinues the execution of the work, or
 - e. Fails to resume work which has been discontinued within a reasonable time after notice to do so, or
 - **f.** Becomes insolvent or is declared bankrupt, or commits any act of bankruptcy or insolvency, or
 - g. Allows any final judgment to stand against the Contractor unsatisfied for a period of 10 days, or
 - **h.** Makes an assignment for the benefit of creditors, or
 - i. For any other cause whatsoever, fails to carry on the work in an acceptable manner.

Should the Owner consider the Contractor in default of the contract for any reason above, the Owner shall immediately give written notice to the Contractor and the Contractor's surety as to the reasons for considering the Contractor in default and the Owner's intentions to terminate the contract.

If the Contractor or surety, within a period of 10 days after such notice, does not proceed in accordance therewith, then the Owner will, upon written notification from the RPR of the facts of such delay, neglect, or default and the Contractor's failure to comply with such notice, have full power and authority without violating the contract, to take the execution of the work out of the hands of the Contractor. The Owner may appropriate or use any or all materials and equipment that have been mobilized for use in the work and are acceptable and may enter into an agreement for the completion of said contract according to the terms and provisions thereof, or use such other methods as in the opinion of the RPR will be required for the completion of said contract in an acceptable manner.

All costs and charges incurred by the Owner, together with the cost of completing the work under contract, will be deducted from any monies due or which may become due the Contractor. If such expense exceeds the sum which would have been payable under the contract, then the Contractor and the surety shall be liable and shall pay to the Owner the amount of such excess.

80-10 Termination for national emergencies. The Owner shall terminate the contract or portion thereof by written notice when the Contractor is prevented from proceeding with the construction contract as a direct result of an Executive Order of the President with respect to the execution of war or in the interest of national defense.

When the contract, or any portion thereof, is terminated before completion of all items of work in the contract, payment will be made for the actual number of units or items of work completed at the contract price or as mutually agreed for items of work partially completed or not started. No claims or loss of anticipated profits shall be considered.

Reimbursement for organization of the work, and other overhead expenses, (when not otherwise included in the contract) and moving equipment and materials to and from the job will be considered, the intent being that an equitable settlement will be made with the Contractor.

Acceptable materials, obtained or ordered by the Contractor for the work and that are not incorporated in the work shall, at the option of the Contractor, be purchased from the Contractor at actual cost as shown by receipted bills and actual cost records at such points of delivery as may be designated by the RPR.

Termination of the contract or a portion thereof shall neither relieve the Contractor of their responsibilities for the completed work nor shall it relieve their surety of its obligation for and concerning any just claim arising out of the work performed.

80-11 Work area, storage area and sequence of operations. The Contractor shall obtain approval from the RPR prior to beginning any work in all areas of the airport. No operating runway, taxiway, or air operations area (AOA) shall be crossed, entered, or obstructed while it is operational. The Contractor shall plan and coordinate work in accordance with the approved CSPP and SPCD.

END OF SECTION 80

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 90 MEASUREMENT AND PAYMENT

90-01 Measurement of quantities. All work completed under the contract will be measured by the RPR, or their authorized representatives, using United States Customary Units of Measurement.

The method of measurement and computations to be used in determination of quantities of material furnished and of work performed under the contract will be those methods generally recognized as conforming to good engineering practice.

Unless otherwise specified, longitudinal measurements for area computations will be made horizontally, and no deductions will be made for individual fixtures (or leave-outs) having an area of 9 square feet (0.8 square meters) or less. Unless otherwise specified, transverse measurements for area computations will be the neat dimensions shown on the plans or ordered in writing by the RPR.

Unless otherwise specified, all contract items which are measured by the linear foot such as electrical ducts, conduits, pipe culverts, underdrains, and similar items shall be measured parallel to the base or foundation upon which such items are placed.

The term "lump sum" when used as an item of payment will mean complete payment for the work described in the contract. When a complete structure or structural unit (in effect, "lump sum" work) is specified as the unit of measurement, the unit will be construed to include all necessary fittings and accessories.

When requested by the Contractor and approved by the RPR in writing, material specified to be measured by the cubic yard (cubic meter) may be weighed, and such weights will be converted to cubic yards (cubic meters) for payment purposes. Factors for conversion from weight measurement to volume measurement will be determined by the RPR and shall be agreed to by the Contractor before such method of measurement of pay quantities is used.

Measurement and Payment Terms

Term	Description
Excavation and Embankment Volume	In computing volumes of excavation, the average end area method will be used unless otherwise specified.
Measurement and Proportion by Weight	The term "ton" will mean the short ton consisting of 2,000 pounds (907 km) avoirdupois. All materials that are measured or proportioned by weights shall be weighed on accurate, independently certified scales by competent, qualified personnel at locations designated by the RPR. If material is shipped by rail, the car weight may be accepted provided that only the actual weight of material is paid for. However, car weights will not be acceptable for material to be passed through mixing plants. Trucks used to haul material being paid for by weight shall be weighed empty daily at such times as the RPR directs, and each truck shall bear a plainly legible identification mark.
Measurement by Volume	Materials to be measured by volume in the hauling vehicle shall be hauled in approved vehicles and measured therein at the point of delivery. Vehicles for this purpose may be of any size or type acceptable for the materials hauled, provided that the body is of such shape that the actual contents may be readily and accurately determined. All vehicles shall be loaded to at least their water level

Term	Description
	capacity, and all loads shall be leveled when the vehicles arrive at the point of delivery.
Asphalt Material	Asphalt materials will be measured by the gallon (liter) or ton (kg). When measured by volume, such volumes will be measured at 60°F (16°C) or will be corrected to the volume at 60°F (16°C) using ASTM D1250 for asphalts. Net certified scale weights or weights based on certified volumes in the case of rail shipments will be used as a basis of measurement, subject to correction when asphalt material has been lost from the car or the distributor, wasted, or otherwise not incorporated in the work. When asphalt materials are shipped by truck or transport, net certified weights by volume, subject to correction for loss or foaming, will be used for computing quantities.
Cement	Cement will be measured by the ton (kg) or hundredweight (km).
Structure	Structures will be measured according to neat lines shown on the plans or as altered to fit field conditions.
Timber	Timber will be measured by the thousand feet board measure (MFBM) actually incorporated in the structure. Measurement will be based on nominal widths and thicknesses and the extreme length of each piece.
Plates and Sheets	The thickness of plates and galvanized sheet used in the manufacture of corrugated metal pipe, metal plate pipe culverts and arches, and metal cribbing will be specified and measured in decimal fraction of inch.
Miscellaneous Items	When standard manufactured items are specified such as fence, wire, plates, rolled shapes, pipe conduit, etc., and these items are identified by gauge, unit weight, section dimensions, etc., such identification will be considered to be nominal weights or dimensions. Unless more stringently controlled by tolerances in cited specifications, manufacturing tolerances established by the industries involved will be accepted.
Scales	Scales must be tested for accuracy and serviced before use. Scales for weighing materials which are required to be proportioned or measured and paid for by weight shall be furnished, erected, and maintained by the Contractor, or be certified permanently installed commercial scales. Platform scales shall be installed and maintained with the platform level and rigid bulkheads at each end.
	Scales shall be accurate within 0.5% of the correct weight throughout the range of use. The Contractor shall have the scales checked under the observation of the RPR before beginning work and at such other times as requested. The intervals shall be uniform in spacing throughout the graduated or marked length of the beam or dial and shall not exceed 0.1% of the nominal rated capacity of the scale, but not less than one pound (454 grams). The use of spring balances will not be permitted.
	In the event inspection reveals the scales have been "overweighing" (indicating more than correct weight) they will be immediately adjusted. All materials

Term	Description
	received subsequent to the last previous correct weighting-accuracy test will be reduced by the percentage of error in excess of 0.5%.
	In the event inspection reveals the scales have been under-weighing (indicating less than correct weight), they shall be immediately adjusted. No additional payment to the Contractor will be allowed for materials previously weighed and recorded.
	Beams, dials, platforms, and other scale equipment shall be so arranged that the operator and the RPR can safely and conveniently view them.
	Scale installations shall have available ten standard 50-pound (2.3 km) weights for testing the weighing equipment or suitable weights and devices for other approved equipment.
	All costs in connection with furnishing, installing, certifying, testing, and maintaining scales; for furnishing check weights and scale house; and for all other items specified in this subsection, for the weighing of materials for proportioning or payment, shall be included in the unit contract prices for the various items of the project.
Rental Equipment	Rental of equipment will be measured by time in hours of actual working time and necessary traveling time of the equipment within the limits of the work. Special equipment ordered in connection with extra work will be measured as agreed in the change order or supplemental agreement authorizing such work as provided in paragraph 90-05 <i>Payment for Extra Work</i> .
Pay Quantities	When the estimated quantities for a specific portion of the work are designated as the pay quantities in the contract, they shall be the final quantities for which payment for such specific portion of the work will be made, unless the dimensions of said portions of the work shown on the plans are revised by the RPR. If revised dimensions result in an increase or decrease in the quantities of such work, the final quantities for payment will be revised in the amount represented by the authorized changes in the dimensions.

90-02 Scope of payment. The Contractor shall receive and accept compensation provided for in the contract as full payment for furnishing all materials, for performing all work under the contract in a complete and acceptable manner, and for all risk, loss, damage, or expense of whatever character arising out of the nature of the work or the execution thereof, subject to the provisions of Section 70, paragraph 70-18, *No Waiver of Legal Rights*.

When the "basis of payment" subsection of a technical specification requires that the contract price (price bid) include compensation for certain work or material essential to the item, this same work or material will not also be measured for payment under any other contract item which may appear elsewhere in the contract, plans, or specifications.

90-03 Compensation for altered quantities. When the accepted quantities of work vary from the quantities in the proposal, the Contractor shall accept as payment in full, so far as contract items are concerned, payment at the original contract price for the accepted quantities of work actually completed and accepted. No allowance, except as provided for in Section 40, paragraph 40-02, *Alteration of Work and Quantities*, will be made for any increased expense, loss of expected reimbursement, or loss of anticipated

profits suffered or claimed by the Contractor which results directly from such alterations or indirectly from their own unbalanced allocation of overhead and profit among the contract items, or from any other cause.

90-04 Payment for omitted items. As specified in Section 40, paragraph 40-03, *Omitted Items*, the RPR shall have the right to omit from the work (order nonperformance) any contract item, except major contract items, in the best interest of the Owner.

Should the RPR omit or order nonperformance of a contract item or portion of such item from the work, the Contractor shall accept payment in full at the contract prices for any work actually completed and acceptable prior to the RPR's order to omit or non-perform such contract item.

Acceptable materials ordered by the Contractor or delivered on the work prior to the date of the RPR's order will be paid for at the actual cost to the Contractor and shall thereupon become the property of the Owner.

In addition to the reimbursement hereinbefore provided, the Contractor shall be reimbursed for all actual costs incurred for the purpose of performing the omitted contract item prior to the date of the RPR's order. Such additional costs incurred by the Contractor must be directly related to the deleted contract item and shall be supported by certified statements by the Contractor as to the nature the amount of such costs.

90-05 Payment for extra work. Extra work, performed in accordance with Section 40, paragraph 40-04, *Extra Work*, will be paid for at the contract prices or agreed prices specified in the change order or supplemental agreement authorizing the extra work.

90-06 Partial payments. Partial payments will be made to the Contractor at least once each month as the work progresses. Said payments will be based upon estimates, prepared by the RPR, of the value of the work performed and materials complete and in place, in accordance with the contract, plans, and specifications. Such partial payments may also include the delivered actual cost of those materials stockpiled and stored in accordance with paragraph 90-07, *Payment for Materials on Hand*. No partial payment will be made when the amount due to the Contractor since the last estimate amounts to less than five hundred dollars.

- **a.** From the total of the amount determined to be payable on a partial payment, 10% percent of such total amount will be deducted and retained by the Owner for protection of the Owner's interests. Unless otherwise instructed by the Owner, the amount retained by the Owner will be in effect until the final payment is made except as follows:
- (1) Contractor may request release of retainage on work that has been partially accepted by the Owner in accordance with Section 50-14. Contractor must provide a certified invoice to the RPR that supports the value of retainage held by the Owner for partially accepted work.
- (2) In lieu of retainage, the Contractor may exercise at its option the establishment of an escrow account per paragraph 90-08.
- b. The Contractor is required to pay all subcontractors for satisfactory performance of their contracts no later than 30 days after the Contractor has received a partial payment. Contractor must provide the Owner evidence of prompt and full payment of retainage held by the prime Contractor to the subcontractor within 30 days after the subcontractor's work is satisfactorily completed. A subcontractor's work is satisfactorily completed when all the tasks called for in the subcontract have been accomplished and documented as required by the Owner. When the Owner has made an incremental acceptance of a portion of a prime contract, the work of a subcontractor covered by that acceptance is deemed to be satisfactorily completed.

It is understood and agreed that the Contractor shall not be entitled to demand or receive partial payment based on quantities of work in excess of those provided in the proposal or covered by approved change orders or supplemental agreements, except when such excess quantities have been determined by the RPR to be a part of the final quantity for the item of work in question.

No partial payment shall bind the Owner to the acceptance of any materials or work in place as to quality or quantity. All partial payments are subject to correction at the time of final payment as provided in paragraph 90-09, *Acceptance and Final Payment*.

The Contractor shall deliver to the Owner a complete release of all claims for labor and material arising out of this contract before the final payment is made. If any subcontractor or supplier fails to furnish such a release in full, the Contractor may furnish a bond or other collateral satisfactory to the Owner to indemnify the Owner against any potential lien or other such claim. The bond or collateral shall include all costs, expenses, and attorney fees the Owner may be compelled to pay in discharging any such lien or claim.

- **90-07 Payment for materials on hand.** Partial payments may be made to the extent of the delivered cost of materials to be incorporated in the work, provided that such materials meet the requirements of the contract, plans, and specifications and are delivered to acceptable sites on the airport property or at other sites in the vicinity that are acceptable to the Owner. Such delivered costs of stored or stockpiled materials may be included in the next partial payment after the following conditions are met:
- **a.** The material has been stored or stockpiled in a manner acceptable to the RPR at or on an approved site.
- **b.** The Contractor has furnished the RPR with acceptable evidence of the quantity and quality of such stored or stockpiled materials.
- **c.** The Contractor has furnished the RPR with satisfactory evidence that the material and transportation costs have been paid.
- **d.** The Contractor has furnished the Owner legal title (free of liens or encumbrances of any kind) to the material stored or stockpiled.
- **e.** The Contractor has furnished the Owner evidence that the material stored or stockpiled is insured against loss by damage to or disappearance of such materials at any time prior to use in the work.

It is understood and agreed that the transfer of title and the Owner's payment for such stored or stockpiled materials shall in no way relieve the Contractor of their responsibility for furnishing and placing such materials in accordance with the requirements of the contract, plans, and specifications.

In no case will the amount of partial payments for materials on hand exceed the contract price for such materials or the contract price for the contract item in which the material is intended to be used.

No partial payment will be made for stored or stockpiled living or perishable plant materials.

The Contractor shall bear all costs associated with the partial payment of stored or stockpiled materials in accordance with the provisions of this paragraph.

- **90-08 Payment of withheld funds**. At the Contractor's option, if an Owner withholds retainage in accordance with the methods described in paragraph 90-06 *Partial Payments*, the Contractor may request that the Owner deposit the retainage into an escrow account. The Owner's deposit of retainage into an escrow account is subject to the following conditions:
- **a.** The Contractor shall bear all expenses of establishing and maintaining an escrow account and escrow agreement acceptable to the Owner.
- **b.** The Contractor shall deposit to and maintain in such escrow only those securities or bank certificates of deposit as are acceptable to the Owner and having a value not less than the retainage that would otherwise be withheld from partial payment.

- **c.** The Contractor shall enter into an escrow agreement satisfactory to the Owner.
- **d.** The Contractor shall obtain the written consent of the surety to such agreement.

90-09 Acceptance and final payment. When the contract work has been accepted in accordance with the requirements of Section 50, paragraph 50-15, *Final Acceptance*, the RPR will prepare the final estimate of the items of work actually performed. The Contractor shall approve the RPR's final estimate or advise the RPR of the Contractor's objections to the final estimate which are based on disputes in measurements or computations of the final quantities to be paid under the contract as amended by change order or supplemental agreement. The Contractor and the RPR shall resolve all disputes (if any) in the measurement and computation of final quantities to be paid within 30 calendar days of the Contractor's receipt of the RPR's final estimate. If, after such 30-day period, a dispute still exists, the Contractor may approve the RPR's estimate under protest of the quantities in dispute, and such disputed quantities shall be considered by the Owner as a claim in accordance with Section 50, paragraph 50-16, *Claims for Adjustment and Disputes*.

After the Contractor has approved, or approved under protest, the RPR's final estimate, and after the RPR's receipt of the project closeout documentation required in paragraph 90-11, *Contractor Final Project Documentation*, final payment will be processed based on the entire sum, or the undisputed sum in case of approval under protest, determined to be due the Contractor less all previous payments and all amounts to be deducted under the provisions of the contract. All prior partial estimates and payments shall be subject to correction in the final estimate and payment.

If the Contractor has filed a claim for additional compensation under the provisions of Section 50, paragraph 50-16, *Claims for Adjustments and Disputes*, or under the provisions of this paragraph, such claims will be considered by the Owner in accordance with local laws or ordinances. Upon final adjudication of such claims, any additional payment determined to be due the Contractor will be paid pursuant to a supplemental final estimate.

90-10 Construction warranty.

- **a.** In addition to any other warranties in this contract, the Contractor warrants that work performed under this contract conforms to the contract requirements and is free of any defect in equipment, material, workmanship, or design furnished, or performed by the Contractor or any subcontractor or supplier at any tier.
- **b.** This warranty shall continue for a period of one year from the date of final acceptance of the work, except as noted. If the Owner takes possession of any part of the work before final acceptance, this warranty shall continue for a period of one year from the date the Owner takes possession.
- **c.** The Contractor shall remedy at the Contractor's expense any failure to conform, or any defect. In addition, the Contractor shall remedy at the Contractor's expense any damage to Owner real or personal property, when that damage is the result of the Contractor's failure to conform to contract requirements; or any defect of equipment, material, workmanship, or design furnished by the Contractor.
- **d.** The Contractor shall restore any work damaged in fulfilling the terms and conditions of this clause. The Contractor's warranty with respect to work repaired or replaced will run for one year from the date of repair or replacement.
- **e.** The Owner will notify the Contractor, in writing, within, seven (7) days after the discovery of any failure, defect, or damage.
- **f.** If the Contractor fails to remedy any failure, defect, or damage within 14 days after receipt of notice, the Owner shall have the right to replace, repair, or otherwise remedy the failure, defect, or damage at the Contractor's expense.

- **g.** With respect to all warranties, express or implied, from subcontractors, manufacturers, or suppliers for work performed and materials furnished under this contract, the Contractor shall: (1) Obtain all warranties that would be given in normal commercial practice; (2) Require all warranties to be executed, in writing, for the benefit of the Owner, as directed by the Owner, and (3) Enforce all warranties for the benefit of the Owner.
- **h.** This warranty shall not limit the Owner's rights with respect to latent defects, gross mistakes, or fraud.
- **90-11 Contractor Final Project Documentation.** Approval of final payment to the Contractor is contingent upon completion and submittal of the items listed below. The final payment will not be approved until the RPR approves the Contractor's final submittal. The Contractor shall:
- **a.** Provide two (2) copies of all manufacturers warranties specified for materials, equipment, and installations.
- **b.** Provide weekly payroll records (not previously received) from the general Contractor and all subcontractors.
 - c. Complete final cleanup in accordance with Section 40, paragraph 40-08, Final Cleanup.
 - **d.** Complete all punch list items identified during the Final Inspection.
 - e. Provide complete release of all claims for labor and material arising out of the Contract.
- **f.** Provide a certified statement signed by the subcontractors, indicating actual amounts paid to the Disadvantaged Business Enterprise (DBE) subcontractors and/or suppliers associated with the project.
 - g. When applicable per state requirements, return copies of sales tax completion forms.
 - **h.** Manufacturer's certifications for all items incorporated in the work.
 - i. All required record drawings, as-built drawings or as-constructed drawings.
 - **j.** Project Operation and Maintenance (O&M) Manual(s).
 - k. Security for Construction Warranty.
 - **l.** Equipment commissioning documentation submitted, if

END OF SECTION 90

THIS PAGE INTENTIONALLY BLANK

ITEM C-100 CONTRACTOR QUALITY CONTROL PROGRAM (CQCP)

100-1 General. Quality is more than test results. Quality is the combination of proper materials, testing, workmanship, equipment, inspection, and documentation of the project. Establishing and maintaining a culture of quality is key to achieving a quality project. The Contractor shall establish, provide, and maintain an effective Contractor Quality Control Program (CQCP) that details the methods and procedures that will be taken to assure that all materials and completed construction required by this contract conform to contract plans, technical specifications and other requirements, whether manufactured by the Contractor, or procured from subcontractors or vendors. Although guidelines are established and certain minimum requirements are specified here and elsewhere in the contract technical specifications, the Contractor shall assume full responsibility for accomplishing the stated purpose.

The Contractor shall establish a CQCP that will:

- **a.** Provide qualified personnel to develop and implement the CQCP.
- **b.** Provide for the production of acceptable quality materials.
- **c.** Provide sufficient information to assure that the specification requirements can be met.
- **d.** Document the CQCP process.

The Contractor shall not begin any construction or production of materials to be incorporated into the completed work until the CQCP has been reviewed and approved by the Resident Project Representative (RPR). No partial payment will be made for materials subject to specific quality control (QC) requirements until the CQCP has been reviewed and approved.

The QC requirements contained in this section and elsewhere in the contract technical specifications are in addition to and separate from the quality assurance (QA) testing requirements. QA testing requirements are the responsibility of the RPR or Contractor as specified in the specifications.

A Quality Control (QC)/Quality Assurance (QA) workshop with the Engineer, Resident Project Representative (RPR), Contractor, subcontractors, testing laboratories, and Owner's representative must be held prior to start of construction. The QC/QA workshop will be facilitated by the Contractor. The Contractor shall coordinate with the Airport and the RPR on time and location of the QC/QA workshop. Items to be addressed, at a minimum, will include:

- **a.** Review of the CQCP including submittals, QC Testing, Action & Suspension Limits for Production, Corrective Action Plans, Distribution of QC reports, and Control Charts.
 - **b.** Discussion of the QA program.
- ${f c.}$ Discussion of the QC and QA Organization and authority including coordination and information exchange between QC and QA.
 - **d.** Establish regular meetings to discuss control of materials, methods and testing.
 - e. Establishment of the overall QC culture.

100-2 Description of program.

a. General description. The Contractor shall establish a CQCP to perform QC inspection and testing of all items of work required by the technical specifications, including those performed by subcontractors. The CQCP shall ensure conformance to applicable specifications and plans with respect to materials, offsite fabrication, workmanship, construction, finish, and functional performance. The CQCP shall be effective for control of all construction work performed under this Contract and shall specifically include

surveillance and tests required by the technical specifications, in addition to other requirements of this section and any other activities deemed necessary by the Contractor to establish an effective level of QC.

b. Contractor Quality Control Program (CQCP). The Contractor shall describe the CQCP in a written document that shall be reviewed and approved by the RPR prior to the start of any production, construction, or off-site fabrication. The written CQCP shall be submitted to the RPR for review and approval at least 10 calendar days before the CQCP Workshop. The Contractor's CQCP and QC testing laboratory must be approved in writing by the RPR prior to the Notice to Proceed (NTP).

The CQCP shall be organized to address, as a minimum, the following:

- 1. QC organization and resumes of key staff
- 2. Project progress schedule
- 3. Submittals schedule
- 4. Inspection requirements
- 5. QC testing plan
- 6. Documentation of QC activities and distribution of QC reports
- 7. Requirements for corrective action when QC and/or QA acceptance criteria are not met
- 8. Material quality and construction means and methods. Address all elements applicable to the project that affect the quality of the pavement structure including subgrade, subbase, base, and surface course. Some elements that must be addressed include, but is not limited to mix design, aggregate grading, stockpile management, mixing and transporting, placing and finishing, quality control testing and inspection, smoothness, laydown plan, equipment, and temperature management plan.

The Contractor must add any additional elements to the CQCP that is necessary to adequately control all production and/or construction processes required by this contract.

100-3 CQCP organization. The CQCP shall be implemented by the establishment of a QC organization. An organizational chart shall be developed to show all QC personnel, their authority, and how these personnel integrate with other management/production and construction functions and personnel.

The organizational chart shall identify all QC staff by name and function, and shall indicate the total staff required to implement all elements of the CQCP, including inspection and testing for each item of work. If necessary, different technicians can be used for specific inspection and testing functions for different items of work. If an outside organization or independent testing laboratory is used for implementation of all or part of the CQCP, the personnel assigned shall be subject to the qualification requirements of paragraphs 100-03a and 100-03b. The organizational chart shall indicate which personnel are Contractor employees and which are provided by an outside organization.

The QC organization shall, as a minimum, consist of the following personnel:

a. Program Administrator. The Contractor Quality Control Program Administrator (CQCPA) must be a full-time employee of the Contractor, or a consultant engaged by the Contractor. The CQCPA must have a minimum of five (5) years of experience in QC pavement construction with prior QC experience on a project of comparable size and scope as the contract.

Included in the five (5) years of paving/QC experience, the CQCPA must meet at least one of the following requirements:

- (1) Professional Engineer with one (1) year of airport paving experience.
- (2) Engineer-in-training with two (2) years of airport paving experience.

- (3) National Institute for Certification in Engineering Technologies (NICET) Civil Engineering Technology Level IV with three (3) years of airport paving experience.
- (4) An individual with four (4) years of airport paving experience, with a Bachelor of Science Degree in Civil Engineering, Civil Engineering Technology or Construction.

The CQCPA must have full authority to institute any and all actions necessary for the successful implementation of the CQCP to ensure compliance with the contract plans and technical specifications. The CQCPA authority must include the ability to immediately stop production until materials and/or processes are in compliance with contract specifications. The CQCPA must report directly to a principal officer of the construction firm. The CQCPA may supervise the Quality Control Program on more than one project provided that person can be at the job site within two (2) hours after being notified of a problem.

b. QC technicians. A sufficient number of QC technicians necessary to adequately implement the CQCP must be provided. These personnel must be either Engineers, engineering technicians, or experienced craftsman with qualifications in the appropriate field equivalent to NICET Level II in Civil Engineering Technology or higher, and shall have a minimum of two (2) years of experience in their area of expertise.

The QC technicians must report directly to the CQCPA and shall perform the following functions:

- (1) Inspection of all materials, construction, plant, and equipment for conformance to the technical specifications, and as required by paragraph 100-6.
 - (2) Performance of all QC tests as required by the technical specifications and paragraph 100-8.
 - (3) Performance of tests for the RPR when required by the technical specifications.

Certification at an equivalent level of qualification and experience by a state or nationally recognized organization will be acceptable in lieu of NICET certification.

- **c. Staffing levels.** The Contractor shall provide sufficient qualified QC personnel to monitor each work activity at all times. Where material is being produced in a plant for incorporation into the work, separate plant and field technicians shall be provided at each plant and field placement location. The scheduling and coordinating of all inspection and testing must match the type and pace of work activity. The CQCP shall state where different technicians will be required for different work elements.
- **100-4 Project progress schedule.** Critical QC activities must be shown on the project schedule as required by Section 80, paragraph 80-03, *Execution and Progress*.
- **100-5 Submittals schedule.** The Contractor shall submit a detailed listing of all submittals (for example, mix designs, material certifications) and shop drawings required by the technical specifications. The listing can be developed in a spreadsheet format and shall include as a minimum:
 - a. Specification item number
 - **b.** Item description
 - c. Description of submittal
 - d. Specification paragraph requiring submittal
 - e. Scheduled date of submittal

100-6 Inspection requirements. QC inspection functions shall be organized to provide inspections for all definable features of work, as detailed below. All inspections shall be documented by the Contractor as specified by paragraph 100-9.

Inspections shall be performed as needed to ensure continuing compliance with contract requirements until completion of the particular feature of work. Inspections shall include the following minimum requirements:

- **a.** During plant operation for material production, QC test results and periodic inspections shall be used to ensure the quality of aggregates and other mix components, and to adjust and control mix proportioning to meet the approved mix design and other requirements of the technical specifications. All equipment used in proportioning and mixing shall be inspected to ensure its proper operating condition. The CQCP shall detail how these and other QC functions will be accomplished and used.
- **b.** During field operations, QC test results and periodic inspections shall be used to ensure the quality of all materials and workmanship. All equipment used in placing, finishing, and compacting shall be inspected to ensure its proper operating condition and to ensure that all such operations are in conformance to the technical specifications and are within the plan dimensions, lines, grades, and tolerances specified. The CQCP shall document how these and other QC functions will be accomplished and used.

100-7 Contractor QC testing facility.

- **a.** For projects that include Item P-401, Item P-403, and Item P-404, the Contractor shall ensure facilities, including all necessary equipment, materials, and current reference standards, are provided that meet requirements in the following paragraphs of ASTM D3666, *Standard Specification for Minimum Requirements for Agencies Testing and Inspecting Road and Paving Materials*:
 - 8.1.3 Equipment Calibration and Checks;
 - 8.1.9 Equipment Calibration, Standardization, and Check Records;
 - 8.1.12 Test Methods and Procedures
- **b.** For projects that include P-501, the Contractor shall ensure facilities, including all necessary equipment, materials, and current reference standards, are provided that meet requirements in the following paragraphs of ASTM C1077, Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation:
 - 7 Test Methods and Procedures
 - 8 Facilities, Equipment, and Supplemental Procedures
- **100-8 QC testing plan.** As a part of the overall CQCP, the Contractor shall implement a QC testing plan, as required by the technical specifications. The testing plan shall include the minimum tests and test frequencies required by each technical specification Item, as well as any additional QC tests that the Contractor deems necessary to adequately control production and/or construction processes.

The QC testing plan can be developed in a spreadsheet fashion and shall, as a minimum, include the following:

- a. Specification item number (e.g., P-401)
- **b.** Item description (e.g., Hot Mix Asphalt Pavements)
- **c.** Test type (e.g., gradation, grade, asphalt content)
- **d.** Test standard (e.g., ASTM or American Association of State Highway and Transportation Officials (AASHTO) test number, as applicable)
- **e.** Test frequency (e.g., as required by technical specifications or minimum frequency when requirements are not stated)
 - **f.** Responsibility (e.g., plant technician)
 - **g.** Control requirements (e.g., target, permissible deviations)

The QC testing plan shall contain a statistically-based procedure of random sampling for acquiring test samples in accordance with ASTM D3665. The RPR shall be provided the opportunity to witness QC sampling and testing.

All QC test results shall be documented by the Contractor as required by paragraph 100-9.

100-9 Documentation. The Contractor shall maintain current QC records of all inspections and tests performed. These records shall include factual evidence that the required QC inspections or tests have been performed, including type and number of inspections or tests involved; results of inspections or tests; nature of defects, deviations, causes for rejection, etc.; proposed remedial action; and corrective actions taken.

These records must cover both conforming and defective or deficient features, and must include a statement that all supplies and materials incorporated in the work are in full compliance with the terms of the contract. Legible copies of these records shall be furnished to the RPR daily. The records shall cover all work placed subsequent to the previously furnished records and shall be verified and signed by the CQCPA.

Contractor QC records required for the contract shall include, but are not necessarily limited to, the following records:

- **a. Daily inspection reports.** Each Contractor QC technician shall maintain a daily log of all inspections performed for both Contractor and subcontractor operations. These technician's daily reports shall provide factual evidence that continuous QC inspections have been performed and shall, as a minimum, include the following:
 - (1) Technical specification item number and description
 - (2) Compliance with approved submittals
 - (3) Proper storage of materials and equipment
 - (4) Proper operation of all equipment
 - (5) Adherence to plans and technical specifications
 - (6) Summary of any necessary corrective actions
 - (7) Safety inspection.
 - (8) Photographs and/or video

The daily inspection reports shall identify all QC inspections and QC tests conducted, results of inspections, location and nature of defects found, causes for rejection, and remedial or corrective actions taken or proposed.

The daily inspection reports shall be signed by the responsible QC technician and the CQCPA. The RPR shall be provided at least one copy of each daily inspection report on the work day following the day of record. When QC inspection and test results are recorded and transmitted electronically, the results must be archived.

- **b. Daily test reports.** The Contractor shall be responsible for establishing a system that will record all QC test results. Daily test reports shall document the following information:
 - (1) Technical specification item number and description
 - (2) Test designation
 - (3) Location
 - (4) Date of test
 - (5) Control requirements
 - (6) Test results
 - (7) Causes for rejection
 - (8) Recommended remedial actions
 - (9) Retests

Test results from each day's work period shall be submitted to the RPR prior to the start of the next day's work period. When required by the technical specifications, the Contractor shall maintain statistical QC charts. When QC daily test results are recorded and transmitted electronically, the results must be archived.

100-10 Corrective action requirements. The CQCP shall indicate the appropriate action to be taken when a process is deemed, or believed, to be out of control (out of tolerance) and detail what action will be taken to bring the process into control. The requirements for corrective action shall include both general requirements for operation of the CQCP as a whole, and for individual items of work contained in the technical specifications.

The CQCP shall detail how the results of QC inspections and tests will be used for determining the need for corrective action and shall contain clear rules to gauge when a process is out of control and the type of correction to be taken to regain process control.

When applicable or required by the technical specifications, the Contractor shall establish and use statistical QC charts for individual QC tests. The requirements for corrective action shall be linked to the control charts.

100-11 Inspection and/or observations by the RPR. All items of material and equipment are subject to inspection and/or observation by the RPR at the point of production, manufacture or shipment to determine if the Contractor, producer, manufacturer or shipper maintains an adequate QC system in conformance with the requirements detailed here and the applicable technical specifications and plans. In addition, all items of materials, equipment and work in place shall be subject to inspection and/or observation by the RPR at the site for the same purpose.

Inspection and/or observations by the RPR does not relieve the Contractor of performing QC inspections of either on-site or off-site Contractor's or subcontractor's work.

100-12 Noncompliance.

- **a.** The Resident Project Representative (RPR) will provide written notice to the Contractor of any noncompliance with their CQCP. After receipt of such notice, the Contractor must take corrective action.
- **b.** When QC activities do not comply with either the CQCP or the contract provisions or when the Contractor fails to properly operate and maintain an effective CQCP, and no effective corrective actions have been taken after notification of non-compliance, the RPR will recommend the Owner take the following actions:
 - (1) Order the Contractor to replace ineffective or unqualified QC personnel or subcontractors and/or
 - (2) Order the Contractor to stop operations until appropriate corrective actions are taken.

METHOD OF MEASUREMENT

100-13 Basis of measurement and payment. Contractor Quality Control Program (CQCP) is for the personnel, tests, facilities and documentation required to implement the CQCP. No separate measurement for payment shall be made for the CQCP. CQCP shall be considered necessary and incidental to the work of this Contract.

BASIS OF PAYMENT

100-14 Payment.

No payment will be made separately or directly for Contractor Quality Control Program (CQCP). CQCP shall be considered necessary and incidental to the work of this Contract.

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

National Institute for Certification in Engineering Technologies (NICET)

ASTM International (ASTM)

ASTM C1077 Standard Practice for Agencies Testing Concrete and Concrete Aggregates

for Use in Construction and Criteria for Testing Agency Evaluation

ASTM D3665 Standard Practice for Random Sampling of Construction Materials

ASTM D3666 Standard Specification for Minimum Requirements for Agencies Testing

and Inspecting Road and Paving Materials

END OF ITEM C-100

THIS PAGE INTENTIONALLY LEFT BLANK

ITEM C-102 TEMPORARY AIR AND WATER POLLUTION, SOIL EROSION, AND SILTATION CONTROL

DESCRIPTION

102-1. This item shall consist of temporary control measures as shown on the plans or as ordered by the Resident Project Representative (RPR) during the life of a contract to control pollution of air and water, soil erosion, and siltation through the use of silt fences, berms, dikes, dams, sediment basins, fiber mats, gravel, mulches, grasses, slope drains, and other erosion control devices or methods.

Temporary erosion control shall be in accordance with the approved erosion control plan; the approved Construction Safety and Phasing Plan (CSPP) and AC 150/5370-2, *Operational Safety on Airports During Construction*. The temporary erosion control measures contained herein shall be coordinated with the permanent erosion control measures specified as part of this contract to the extent practical to assure economical, effective, and continuous erosion control throughout the construction period.

Temporary control may include work outside the construction limits such as borrow pit operations, equipment and material storage sites, waste areas, and temporary plant sites.

Temporary control measures shall be designed, installed and maintained to minimize the creation of wildlife attractants that have the potential to attract hazardous wildlife on or near public-use airports.

MATERIALS

- **102-2.1 Grass.** Grass that will not compete with the grasses sown later for permanent cover per Item T-901shall be a quick-growing species (such as ryegrass, Italian ryegrass, or cereal grasses) suitable to the area providing a temporary cover. Selected grass species shall not create a wildlife attractant.
- **102-2.2 Mulches.** Mulches may be hay, straw, fiber mats, netting, bark, wood chips, or other suitable material reasonably clean and free of noxious weeds and deleterious materials per Item T-908. Mulches shall not create a wildlife attractant.
- **102-2.3 Fertilizer.** Fertilizer shall be a standard commercial grade and shall conform to all federal and state regulations and to the standards of the Association of Official Agricultural Chemists.
- **102-2.4 Slope drains.** Slope drains may be constructed of pipe, fiber mats, rubble, concrete, asphalt, or other materials that will adequately control erosion.
- **102-2.5 Silt fence.** Silt fence shall consist of polymeric filaments which are formed into a stable network such that filaments retain their relative positions. Synthetic filter fabric shall contain ultraviolet ray inhibitors and stabilizers to provide a minimum of six months of expected usable construction life. Silt fence shall meet the requirements of ASTM D6461.
- **102-2.6 Other.** All other materials shall meet commercial grade standards and shall be approved by the RPR before being incorporated into the project.

CONSTRUCTION REQUIREMENTS

102-3.1 General. In the event of conflict between these requirements and pollution control laws, rules, or regulations of other federal, state, or local agencies, the more restrictive laws, rules, or regulations shall apply.

The RPR shall be responsible for assuring compliance to the extent that construction practices, construction operations, and construction work are involved.

102-3.2 Schedule. Prior to the start of construction, the Contractor shall submit schedules in accordance with the approved Construction Safety and Phasing Plan (CSPP) and the plans for accomplishment of temporary and permanent erosion control work for clearing and grubbing; grading; construction; paving; and structures at watercourses. The Contractor shall also submit a proposed method of erosion and dust control on haul roads and borrow pits and a plan for disposal of waste materials. Work shall not be started until the erosion control schedules and methods of operation for the applicable construction have been accepted by the RPR.

102-3.3 Construction details. The Contractor will be required to incorporate all permanent erosion control features into the project at the earliest practicable time as outlined in the plans and approved CSPP. Except where future construction operations will damage slopes, the Contractor shall perform the permanent seeding and mulching and other specified slope protection work in stages, as soon as substantial areas of exposed slopes can be made available. Temporary erosion and pollution control measures will be used to correct conditions that develop during construction that were not foreseen during the design stage; that are needed prior to installation of permanent control features; or that are needed temporarily to control erosion that develops during normal construction practices, but are not associated with permanent control features on the project.

Where erosion may be a problem, schedule and perform clearing and grubbing operations so that grading operations and permanent erosion control features can follow immediately if project conditions permit. Temporary erosion control measures are required if permanent measures cannot immediately follow grading operations. The RPR shall limit the area of clearing and grubbing, excavation, borrow, and embankment operations in progress, commensurate with the Contractor's capability and progress in keeping the finish grading, mulching, seeding, and other such permanent control measures current with the accepted schedule. If seasonal limitations make such coordination unrealistic, temporary erosion control measures shall be taken immediately to the extent feasible and justified as directed by the RPR.

The Contractor shall provide immediate permanent or temporary pollution control measures to minimize contamination of adjacent streams or other watercourses, lakes, ponds, or other areas of water impoundment as directed by the RPR. If temporary erosion and pollution control measures are required due to the Contractor's negligence, carelessness, or failure to install permanent controls as a part of the work as scheduled or directed by the RPR, the work shall be performed by the Contractor and the cost shall be incidental to this item.

The RPR may increase or decrease the area of erodible earth material that can be exposed at any time based on an analysis of project conditions.

The erosion control features installed by the Contractor shall be maintained by the Contractor during the construction period.

Provide temporary structures whenever construction equipment must cross watercourses at frequent intervals. Pollutants such as fuels, lubricants, bitumen, raw sewage, wash water from concrete mixing operations, and other harmful materials shall not be discharged into any waterways, impoundments or into natural or manmade channels.

102-3.4 Installation, maintenance and removal of silt fence. Silt fences shall extend a minimum of 16 inches (41 cm) and a maximum of 34 inches (86 cm) above the ground surface. Posts shall be set no more than 10 feet (3 m) on center. Filter fabric shall be cut from a continuous roll to the length required minimizing joints where possible. When joints are necessary, the fabric shall be spliced at a support post with a minimum 12-inch (300-mm) overlap and securely sealed. A trench shall be excavated approximately 4 inches (100 mm) deep by 4 inches (100 mm) wide on the upslope side of the silt fence. The trench shall be backfilled and the soil compacted over the silt fence fabric. The Contractor shall remove and dispose of

silt that accumulates during construction and prior to establishment of permanent erosion control. The fence shall be maintained in good working condition until permanent erosion control is established. Silt fence shall be removed upon approval of the RPR.

METHOD OF MEASUREMENT

- **102-4.1** Temporary erosion and pollution control work required will be performed as scheduled or directed by the RPR. Completed and accepted work will be measured per lump sum
- **102-4.2** Control work performed for protection of construction areas outside the construction limits, such as borrow and waste areas, haul roads, equipment and material storage sites, and temporary plant sites, will not be measured and paid for directly but shall be considered as a subsidiary obligation of the Contractor.

BASIS OF PAYMENT

102-5.1 Accepted quantities of temporary water pollution, soil erosion, and siltation control work ordered by the RPR and measured as provided in paragraph 102-4.1 will be paid for under:

Item C-102-5.1 Temporary Erosion Control – per lump sum

Where other directed work falls within the specifications for a work item that has a contract price, the units of work shall be measured and paid for at the contract unit price bid for the various items.

Temporary control features not covered by contract items that are ordered by the RPR will be paid for in accordance with Section 90, paragraph 90-05 *Payment for Extra Work*.

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

Advisory Circulars (AC)

AC 150/5200-33 Hazardous Wildlife Attractants on or Near Airports
AC 150/5370-2 Operational Safety on Airports During Construction

ASTM International (ASTM)

ASTM D6461 Standard Specification for Silt Fence Materials

United States Department of Agriculture (USDA)

FAA/USDA Wildlife Hazard Management at Airports, A Manual for Airport Personnel

END OF ITEM C-102

THIS PAGE INTENTIONALLY LEFT BLANK

ITEM C-105 MOBILIZATION

DESCRIPTION

- **105-1 Description.** This item of work shall consist of, but is not limited to, work and operations necessary for the movement of personnel, equipment, material and supplies to and from the project site for work on the project except as provided in the contract as separate pay items.
- **105-2 Mobilization limit.** Mobilization shall be limited to **ten percent** (**10%**) percent of the total project cost.
- **105-3 Posted notices.** Prior to commencement of construction activities, the Contractor must post the following documents in a prominent and accessible place where they may be easily viewed by all employees of the prime Contractor and by all employees of subcontractors engaged by the prime Contractor: Equal Employment Opportunity (EEO) Poster "Equal Employment Opportunity is the Law" in accordance with the Office of Federal Contract Compliance Programs Executive Order 11246, as amended; Davis Bacon Wage Poster (WH 1321) DOL "Notice to All Employees" Poster; and Applicable Davis-Bacon Wage Rate Determination. These notices must remain posted until final acceptance of the work by the Owner.
- 105-4 Engineer/RPR field office. An Engineer/RPR field office is not required.

METHOD OF MEASUREMENT

- **105-5 Basis of measurement and payment.** Based upon the contract lump sum price for "Mobilization" partial payments will be allowed as follows:
 - a. With first pay request, 25%.
 - b. When 25% or more of the original contract is earned, an additional 25%.
 - c. When 50% or more of the original contract is earned, an additional 40%.
 - d. After Final Inspection, Staging area clean-up and delivery of all Project Closeout materials as required by Section 90, paragraph 90-11, Contractor Final Project Documentation, the final 10%.

BASIS OF PAYMENT

105-6 Payment will be made under:

Item C-105-6.1 Mobilization – per lump sum

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

Office of Federal Contract Compliance Programs (OFCCP)

Executive Order 11246, as amended

EEOC-P/E-1 – Equal Employment Opportunity is the Law Poster

C-105 Mobilization C-105-1 of 2

United States Department of Labor, Wage and Hour Division (WHD)

WH 1321 – Employee Rights under the Davis-Bacon Act Poster

END OF ITEM C-105

C-105 Mobilization C-105-2 of 2

ITEM C-106 TRAFFIC CONTROL

DESCRIPTION

106-1.1 This item shall consist of the installation, relocation, maintenance and removal of all painting over centerline markings, temporary taxiway closure markers, and barricades, and modify airfield lighting and signage, at the locations shown on the plans, or as directed by the Owner/Engineer, and required in accordance with FAA AC 150/5370-2, Operational Safety On Airports During Construction (current edition).

CONSTRUCTION METHODS

- **106-2.1** Prior to starting any work the Contractor shall install temporary taxiway closure markers, and modify airfield lighting and signage, and barricades at the locations shown in the plans.
- 106-2.2 RUNWAY CLOSURE MARKERS. Not used.
- 106-2.3 TEMPORARY PAVEMENT MARKING OBLITERATION. Not used.
- **106-2.4 RESTORATION OF TEMPORARY PAVEMENT MARKING OBLITERATION.** Not used.

METHOD OF MEASUREMENT

- **106-3.1 MEASUREMENT.** If there is no quantity shown in the bidding schedule, the work covered by this section shall be considered as a subsidiary obligation of the Contractor covered under the other contract items. Only accepted work in accordance with the specifications and accepted by the Engineer will be measured.
- **a. Traffic Control.** The unit of measurement for traffic control shall be a Lump Sum amount, based upon a specific percentage of the original contract amount.

BASIS OF PAYMENT

106-4.1 PAYMENT.

a. Payment shall be based on the contract lump sum price for "Traffic Control" and partial payments will be made on every partial pay estimate based on the estimated completion of the project. This price shall be full compensation for furnishing all materials, including but not limited to paint, taxiway closure markers, airfield lighting and signage conduit, cable, and covers, traffic cones, and low-profile barricades and for all labor, equipment, tools, and incidentals necessary to complete the item. No additional payment for this item shall be made if the contract time is exceeded for any reason.

Payment will be made under:

Item C-106-4.1 Traffic Control – per lump sum

END OF ITEM C-106

C-106 Traffic Control C-106-1 of 2

THIS PAGE INTENTIONALL LEFT BLANK

C-106 Traffic Control C-106-2 of 2

ITEM C-110 METHOD OF ESTIMATING PERCENTAGE OF MATERIAL WITHIN SPECIFICATION LIMITS (PWL)

110-1 General. When the specifications provide for acceptance of material based on the method of estimating percentage of material within specification limits (PWL), the PWL will be determined in accordance with this section. All test results for a lot will be analyzed statistically to determine the total estimated percent of the lot that is within specification limits. The PWL is computed using the sample average (X) and sample standard deviation (S_n) of the specified number (n) of sublots for the lot and the specification tolerance limits, L for lower and U for upper, for the particular acceptance parameter. From these values, the respective Quality index, Q_L for Lower Quality Index and/or Q_U for Upper Quality Index, is computed and the PWL for the lot for the specified n is determined from Table 1. All specification limits specified in the technical sections shall be absolute values. Test results used in the calculations shall be to the significant figure given in the test procedure.

There is some degree of uncertainty (risk) in the measurement for acceptance because only a small fraction of production material (the population) is sampled and tested. This uncertainty exists because all portions of the production material have the same probability to be randomly sampled. The Contractor's risk is the probability that material produced at the acceptable quality level is rejected or subjected to a pay adjustment. The Owner's risk is the probability that material produced at the rejectable quality level is accepted.

It is the intent of this section to inform the Contractor that, in order to consistently offset the Contractor's risk for material evaluated, production quality (using population average and population standard deviation) must be maintained at the acceptable quality specified or higher. In all cases, it is the responsibility of the Contractor to produce at quality levels that will meet the specified acceptance criteria when sampled and tested at the frequencies specified.

110-2 Method for computing PWL. The computational sequence for computing PWL is as follows:

- **a.** Divide the lot into n sublots in accordance with the acceptance requirements of the specification.
- **b**. Locate the random sampling position within the sublot in accordance with the requirements of the specification.
- **c.** Make a measurement at each location, or take a test portion and make the measurement on the test portion in accordance with the testing requirements of the specification.
 - **d.** Find the sample average (X) for all sublot test values within the lot by using the following formula:

$$X = (x_1 + x_2 + x_3 + ... x_n) / n$$

Where: X =Sample average of all sublot test values within a lot $x_1, x_2, \dots x_n =$ Individual sublot test values n =Number of sublot test values

e. Find the sample standard deviation (S_n) by use of the following formula:

$$S_n = [(d_1^2 + d_2^2 + d_3^2 + \dots d_n^2)/(n-1)]^{1/2}$$

Where: $S_n =$ Sample standard deviation of the number of sublot test values in the set $d_1, d_2, \ldots d_n =$ Deviations of the individual sublot test values x_1, x_2, \ldots from the average value X

that is:
$$d_1 = (x_1 - X)$$
, $d_2 = (x_2 - X)$... $d_n = (x_n - X)$
 $n = Number of sublot test values$

f. For single sided specification limits (i.e., L only), compute the Lower Quality Index Q_L by use of the following formula:

$$Q_L = (X - L) / S_n$$

Where: L = specification lower tolerance limit

Estimate the percentage of material within limits (PWL) by entering Table 1 with Q_L , using the column appropriate to the total number (n) of measurements. If the value of Q_L falls between values shown on the table, use the next higher value of PWL.

g. For double-sided specification limits (i.e., L and U), compute the Quality Indexes Q_L and Q_U by use of the following formulas:

$$Q_L = (X - L) \ / \ S_n$$
 and
$$Q_U = (U - X) \ / \ S_n$$

Where: L and U = specification lower and upper tolerance limits

Estimate the percentage of material between the lower (L) and upper (U) tolerance limits (PWL) by entering Table 1 separately with Q_L and Q_U , using the column appropriate to the total number (n) of measurements, and determining the percent of material above P_L and percent of material below P_U for each tolerance limit. If the values of Q_L fall between values shown on the table, use the next higher value of P_L or P_U . Determine the PWL by use of the following formula:

$$PWL = (P_U + P_L) - 100$$

Where: P_L = percent within lower specification limit P_U = percent within upper specification limit

EXAMPLE OF PWL CALCULATION

Project: Example Project

Test Item: Item P-401, Lot A.

A. PWL Determination for Mat Density.

1. Density of four random cores taken from Lot A.

$$A-1 = 96.60$$

$$A-2 = 97.55$$

$$A-3 = 99.30$$

$$A-4 = 98.35$$

$$n = 4$$

2. Calculate average density for the lot.

$$X = (x_1 + x_2 + x_3 + ... x_n) / n$$

$$X = (96.60 + 97.55 + 99.30 + 98.35) / 4$$

 $X = 97.95\%$ density

3. Calculate the standard deviation for the lot.

$$\begin{split} S_n &= \left[\left((96.60 - 97.95)^2 + (97.55 - 97.95)^2 + (99.30 - 97.95)^2 + (98.35 - 97.95)^2 \right) \right) / \left(4 - 1 \right) \right]^{1/2} \\ S_n &= \left[\left(1.82 + 0.16 + 1.82 + 0.16 \right) / 3 \right]^{1/2} \\ S_n &= 1.15 \end{split}$$

4. Calculate the Lower Quality Index Q_L for the lot. (L=96.3)

$$\begin{aligned} Q_L &= (X \text{ -}L) \, / \, S_n \\ Q_L &= (97.95 \text{ -} 96.30) \, / \, 1.15 \\ Q_L &= 1.4348 \end{aligned}$$

5. Determine PWL by entering Table 1 with $Q_L = 1.44$ and n = 4.

$$PWL = 98$$

B. PWL Determination for Air Voids.

1. Air Voids of four random samples taken from Lot A.

$$A-1 = 5.00$$

 $A-2 = 3.74$
 $A-3 = 2.30$
 $A-4 = 3.25$

2. Calculate the average air voids for the lot.

$$X = (x_1 + x_2 + x_3 ...n) / n$$

 $X = (5.00 + 3.74 + 2.30 + 3.25) / 4$
 $X = 3.57\%$

3. Calculate the standard deviation S_n for the lot.

$$\begin{split} S_n &= \left[\left((3.57 - 5.00)^2 + (3.57 - 3.74)^2 + (3.57 - 2.30)^2 + (3.57 - 3.25)^2 \right) / \left(4 - 1 \right) \right]^{1/2} \\ S_n &= \left[\left(2.04 + 0.03 + 1.62 + 0.10 \right) / 3 \right]^{1/2} \\ S_n &= 1.12 \end{split}$$

4. Calculate the Lower Quality Index Q_L for the lot. (L= 2.0)

$$\begin{aligned} Q_L &= (X - L) \, / \, S_n \\ Q_L &= (3.57 - 2.00) \, / \, 1.12 \\ Q_L &= 1.3992 \end{aligned}$$

5. Determine P_L by entering Table 1 with $Q_L = 1.41$ and n = 4.

$$P_{L} = 97$$

6. Calculate the Upper Quality Index Q_U for the lot. (U= 5.0)

$$\begin{aligned} Q_U &= (U - X) \, / \, S_n \\ Q_U &= (5.00 - 3.57) \, / \, 1.12 \\ Q_U &= 1.2702 \end{aligned}$$

7. Determine P_U by entering Table 1 with $Q_U = 1.29$ and n = 4.

$$P_{U} = 93$$

8. Calculate Air Voids PWL

$$PWL = (P_L + P_U) - 100$$

$$PWL = (97 + 93) - 100 = 90$$

EXAMPLE OF OUTLIER CALCULATION (REFERENCE ASTM E178)

Project: Example Project

Test Item: Item P-401, Lot A.

A. Outlier Determination for Mat Density.

1. Density of four random cores taken from Lot A arranged in descending order.

A-3 = 99.30

A-4 = 98.35

A-2 = 97.55

A-1 = 96.60

- **2.** From ASTM E178, Table 1, for n=4 an upper 5% significance level, the critical value for test criterion = 1.463.
 - **3.** Use average density, standard deviation, and test criterion value to evaluate density measurements.
 - **a.** For measurements greater than the average:

If (measurement - average)/(standard deviation) is less than test criterion, then the measurement is not considered an outlier.

For A-3, check if (99.30 - 97.95) / 1.15 is greater than 1.463.

Since 1.174 is less than 1.463, the value is not an outlier.

b. For measurements less than the average:

If (average - measurement)/(standard deviation) is less than test criterion, then the measurement is not considered an outlier.

For A-1, check if (97.95 - 96.60) / 1.15 is greater than 1.463.

Since 1.435 is less than 1.463, the value is not an outlier.

Note: In this example, a measurement would be considered an outlier if the density were:

Greater than $(97.95 + 1.463 \times 1.15) = 99.63\%$

OR

less than $(97.95 - 1.463 \times 1.15) = 96.27\%$.

Table 1. Table for Estimating Percent of Lot Within Limits (PWL)

Percent Within	Positive Values of Q (Q _L and Q _U)							
$\begin{array}{c} Limits \\ (P_L \ and \ P_U) \end{array}$	n=3	n=4	n=5	n=6	n=7	n=8	n=9	n=10
99	1.1541	1.4700	1.6714	1.8008	1.8888	1.9520	1.9994	2.0362
98	1.1524	1.4400	1.6016	1.6982	1.7612	1.8053	1.8379	1.8630
97	1.1496	1.4100	1.5427	1.6181	1.6661	1.6993	1.7235	1.7420
96	1.1456	1.3800	1.4897	1.5497	1.5871	1.6127	1.6313	1.6454
95	1.1405	1.3500	1.4407	1.4887	1.5181	1.5381	1.5525	1.5635
94	1.1342	1.3200	1.3946	1.4329	1.4561	1.4717	1.4829	1.4914
93	1.1269	1.2900	1.3508	1.3810	1.3991	1.4112	1.4199	1.4265
92	1.1184	1.2600	1.3088	1.3323	1.3461	1.3554	1.3620	1.3670
91	1.1089	1.2300	1.2683	1.2860	1.2964	1.3032	1.3081	1.3118
90	1.0982	1.2000	1.2290	1.2419	1.2492	1.2541	1.2576	1.2602
89	1.0864	1.1700	1.1909	1.1995	1.2043	1.2075	1.2098	1.2115
88	1.0736	1.1400	1.1537	1.1587	1.1613	1.1630	1.1643	1.1653
87	1.0597	1.1100	1.1173	1.1192	1.1199	1.1204	1.1208	1.1212
86	1.0448	1.0800	1.0817	1.0808	1.0800	1.0794	1.0791	1.0789
85	1.0288	1.0500	1.0467	1.0435	1.0413	1.0399	1.0389	1.0382
84	1.0119	1.0200	1.0124	1.0071	1.0037	1.0015	1.0000	0.9990
83	0.9939	0.9900	0.9785	0.9715	0.9671	0.9643	0.9624	0.9610
82	0.9749	0.9600	0.9452	0.9367	0.9315	0.9281	0.9258	0.9241
81	0.9550	0.9300	0.9123	0.9025	0.8966	0.8928	0.8901	0.8882
80	0.9342	0.9000	0.8799	0.8690	0.8625	0.8583	0.8554	0.8533
79	0.9124	0.8700	0.8478	0.8360	0.8291	0.8245	0.8214	0.8192
78	0.8897	0.8400	0.8160	0.8036	0.7962	0.7915	0.7882	0.7858
77	0.8662	0.8100	0.7846	0.7716	0.7640	0.7590	0.7556	0.7531
76	0.8417	0.7800	0.7535	0.7401	0.7322	0.7271	0.7336	0.7211
75	0.8165	0.7500	0.7333	0.7089	0.7009	0.6958	0.6922	0.6896
74	0.7904	0.7200	0.6921	0.6781	0.6701	0.6649	0.6613	0.6587
73	0.7636	0.6900	0.6617	0.6477	0.6396	0.6344	0.6308	0.6282
72	0.7360	0.6600	0.6316	0.6176	0.6095	0.6044	0.6008	0.5982
71	0.7077	0.6300	0.6016	0.5878	0.5798	0.5747	0.5712	0.5686
70	0.6787	0.6000	0.5719	0.5582	0.5798	0.5454	0.5712	0.5394
69	0.6490	0.5700	0.5423	0.5290	0.5213	0.5454	0.5130	0.5394
68	0.6187	0.5400	0.5423	0.3290	0.3213	0.3104	0.3130	0.4820
67	0.5878	0.5100	0.3129	0.4999	0.4924	0.4577	0.4560	0.4620
66	0.5563	0.4800	0.4545	0.4710	0.4355	0.4392	0.4300	0.4337
65	0.5242	0.4500	0.4343	0.4424	0.4333	0.4030	0.4280	0.4237
64	0.3242	0.4300	0.4233	0.4139	0.4073	0.4030	0.4001	0.3705
	0.4586	0.3900	0.3679	0.3575	0.3793	0.3477	0.3723	0.3703
63			_	_		_		
62	0.4251	0.3600	0.3392	0.3295	0.3239	0.3203	0.3179	0.3161
61	0.3911	0.3300	0.3107	0.3016	0.2964	0.2931	0.2908	0.2892
60	0.3568	0.3000	0.2822	0.2738	0.2691	0.2660	0.2639	0.2624
59	0.3222	0.2700	0.2537	0.2461	0.2418	0.2391	0.2372	0.2358
58 57	0.2872	0.2400	0.2254	0.2186	0.2147	0.2122	0.2105	0.2093
	0.2519	0.2100	0.1971	0.1911	0.1877	0.1855	0.1840	0.1829 0.1566
56	0.2164	0.1800	0.1688	0.1636	0.1607	0.1588	0.1575	
55	0.1806	0.1500	0.1406	0.1363	0.1338	0.1322	0.1312	0.1304
54	0.1447	0.1200	0.1125	0.1090	0.1070	0.1057	0.1049	0.1042
53	0.1087	0.0900	0.0843	0.0817	0.0802	0.0793	0.0786	0.0781
52	0.0725	0.0600	0.0562	0.0544	0.0534	0.0528	0.0524	0.0521
51	0.0363	0.0300	0.0281	0.0272	0.0267	0.0264	0.0262	0.0260
50	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000

Percent	Negative Values of Q (Q _L and Q _U)							
Within Limits	n=3	n=4	n=5	n=6	n=7	n=8	n=9	n=10
(P _L and P _U)								
49	-0.0363	-0.0300	-0.0281	-0.0272	-0.0267	-0.0264	-0.0262	-0.0260
48	-0.0725	-0.0600	-0.0562	-0.0544	-0.0534	-0.0528	-0.0524	-0.0521
47	-0.1087	-0.0900	-0.0843	-0.0817	-0.0802	-0.0793	-0.0786	-0.0781
46	-0.1447	-0.1200	-0.1125	-0.1090	-0.1070	-0.1057	-0.1049	-0.1042
45	-0.1806	-0.1500	-0.1406	-0.1363	-0.1338	-0.1322	-0.1312	-0.1304
44	-0.2164	-0.1800	-0.1688	-0.1636	-0.1607	-0.1588	-0.1575	-0.1566
43	-0.2519	-0.2100	-0.1971	-0.1911	-0.1877	-0.1855	-0.1840	-0.1829
42	-0.2872	-0.2400	-0.2254	-0.2186	-0.2147	-0.2122	-0.2105	-0.2093
41	-0.3222	-0.2700	-0.2537	-0.2461	-0.2418	-0.2391	-0.2372	-0.2358
40	-0.3568	-0.3000	-0.2822	-0.2738	-0.2691	-0.2660	-0.2639	-0.2624
39	-0.3911	-0.3300	-0.3107	-0.3016	-0.2964	-0.2931	-0.2908	-0.2892
38	-0.4251	-0.3600	-0.3392	-0.3295	-0.3239	-0.3203	-0.3179	-0.3161
37	-0.4586	-0.3900	-0.3679	-0.3575	-0.3515	-0.3477	-0.3451	-0.3432
36	-0.4916	-0.4200	-0.3967	-0.3856	-0.3793	-0.3753	-0.3725	-0.3705
35	-0.5242	-0.4500	-0.4255	-0.4139	-0.4073	-0.4030	-0.4001	-0.3980
34	-0.5563	-0.4800	-0.4545	-0.4424	-0.4355	-0.4310	-0.4280	-0.4257
33	-0.5878	-0.5100	-0.4836	-0.4710	-0.4638	-0.4592	-0.4560	-0.4537
32	-0.6187	-0.5400	-0.5129	-0.4999	-0.4924	-0.4877	-0.4844	-0.4820
31	-0.6490	-0.5700	-0.5423	-0.5290	-0.5213	-0.5164	-0.5130	-0.5105
30	-0.6787	-0.6000	-0.5719	-0.5582	-0.5504	-0.5454	-0.5419	-0.5394
29	-0.7077	-0.6300	-0.6016	-0.5878	-0.5798	-0.5747	-0.5712	-0.5686
28	-0.7360	-0.6600	-0.6316	-0.6176	-0.6095	-0.6044	-0.6008	-0.5982
27	-0.7636	-0.6900	-0.6617	-0.6477	-0.6396	-0.6344	-0.6308	-0.6282
26	-0.7904	-0.7200	-0.6921	-0.6781	-0.6701	-0.6649	-0.6613	-0.6587
25	-0.8165	-0.7500	-0.7226	-0.7089	-0.7009	-0.6958	-0.6922	-0.6896
24	-0.8417	-0.7800	-0.7535	-0.7401	-0.7322	-0.7271	-0.7236	-0.7211
23	-0.8662	-0.8100	-0.7846	-0.7716	-0.7640	-0.7590	-0.7556	-0.7531
22	-0.8897	-0.8400	-0.8160	-0.8036	-0.7962	-0.7915	-0.7882	-0.7858
21	-0.9124	-0.8700	-0.8478	-0.8360	-0.8291	-0.8245	-0.8214	-0.8192
20	-0.9342	-0.9000	-0.8799	-0.8690	-0.8625	-0.8583	-0.8554	-0.8533
19	-0.9550	-0.9300	-0.9123	-0.9025	-0.8966	-0.8928	-0.8901	-0.8882
18	-0.9749	-0.9600	-0.9452	-0.9367	-0.9315	-0.9281	-0.9258	-0.9241
17	-0.9939	-0.9900	-0.9785	-0.9715	-0.9671	-0.9643	-0.9624	-0.9610
16	-1.0119	-1.0200	-1.0124	-1.0071	-1.0037	-1.0015	-1.0000	-0.9990
15	-1.0288	-1.0500	-1.0467	-1.0435	-1.0413	-1.0399	-1.0389	-1.0382
14	-1.0448	-1.0800	-1.0817	-1.0808	-1.0800	-1.0794	-1.0791	-1.0789
13	-1.0597	-1.1100	-1.1173	-1.1192	-1.1199	-1.1204	-1.1208	-1.1212
12	-1.0736	-1.1400	-1.1537	-1.1587	-1.1613	-1.1630	-1.1643	-1.1653
11	-1.0864	-1.1700	-1.1909	-1.1995	-1.2043	-1.2075	-1.2098	-1.2115
10	-1.0982	-1.2000	-1.2290	-1.2419	-1.2492	-1.2541	-1.2576	-1.2602
9	-1.1089	-1.2300	-1.2683	-1.2860	-1.2964	-1.3032	-1.3081	-1.3118
8	-1.1184	-1.2600	-1.3088	-1.3323	-1.3461	-1.3554	-1.3620	-1.3670
7	-1.1269	-1.2900	-1.3508	-1.3810	-1.3991	-1.4112	-1.4199	-1.4265
6	-1.1342	-1.3200	-1.3946	-1.4329	-1.4561	-1.4717	-1.4829	-1.4914
5	-1.1405	-1.3500	-1.4407	-1.4887	-1.5181	-1.5381	-1.5525	-1.5635
4	-1.1456	-1.3800	-1.4897	-1.5497	-1.5871	-1.6127	-1.6313	-1.6454
3	-1.1496	-1.4100	-1.5427	-1.6181	-1.6661	-1.6993	-1.7235	-1.7420
2	-1.1524	-1.4400	-1.6016	-1.6982	-1.7612	-1.8053	-1.8379	-1.8630
1	-1.1541	-1.4700	-1.6714	-1.8008	-1.8888	-1.9520	-1.9994	-2.0362

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM E178

Standard Practice for Dealing with Outlying Observations

END OF ITEM C-110

THIS PAGE INTENTIONALLY LEFT BLANK

ITEM P-101 PREPARATION/REMOVAL OF EXISTING PAVEMENTS

DESCRIPTION

101-1 This item shall consist of preparation of existing pavement surfaces for overlay, surface treatments, removal of existing pavement, and other miscellaneous items. The work shall be accomplished in accordance with these specifications and the applicable plans.

EQUIPMENT AND MATERIALS

101-2 All equipment and materials shall be specified here and in the following paragraphs or approved by the Resident Project Representative (RPR). The equipment shall not cause damage to the pavement to remain in place.

CONSTRUCTION

101-3.1 Removal of existing pavement.

The Contractor's removal operation shall be controlled to not damage adjacent pavement structure, and base material, cables, utility ducts, pipelines, or drainage structures which are to remain under the pavement.

a. Concrete pavement removal. Full depth saw cuts shall be made perpendicular to the slab surface. The Contractor shall saw through the full depth of the slab including any dowels at the joint, removing the pavement and installing new dowels as shown on the plans and per the specifications. Where the perimeter of the removal limits is not located on the joint and there are no dowels present, the perimeter shall be saw cut the full depth of the pavement. The pavement inside the saw cut shall be removed by methods which will not cause distress in the pavement which is to remain in place. Concrete slabs that are damaged by under breaking shall be repaired or removed and replaced as directed by the RPR.

The edge of existing concrete pavement against which new pavement abuts shall be protected from damage at all times. Spall and underbreak repair shall be in accordance with the plans. Any underlaying material that is to remain in place, shall be recompacted and/or replaced as shown on the plans. Adjacent areas damaged during repair shall be repaired or replaced at the Contractor's expense.

- **b. Asphalt pavement removal.** Asphalt pavement to be removed shall be cut to the full depth of the asphalt pavement around the perimeter of the area to be removed.
- **c. Repair or removal of Base, Subbase, and/or Subgrade.** All failed material including surface, base course, subbase course, and subgrade shall be removed and repaired as shown on the plans or as directed by the RPR. Materials and methods of construction shall comply with the applicable sections of these specifications. Any damage caused by Contractor's removal process shall be repaired at the Contractor's expense.
- 101-3.2 Preparation of joints and cracks prior to overlay/surface treatment. Remove all vegetation and debris from cracks to a minimum depth of 1 inch. If extensive vegetation exists, treat the specific area with a concentrated solution of a water-based herbicide approved by the RPR. Fill all cracks greater than 1/4 inch with a crack sealant per ASTM D6690. The crack sealant, preparation, and application shall be compatible with the surface treatment/overlay to be used. To minimize contamination of the asphalt with the crack sealant, underfill the crack sealant a minimum of 1/8 inch, not to exceed 1/4 inch. Any excess joint or crack sealer shall be removed from the pavement surface.

Wider cracks (over 1-1/2 inch wide), along with soft or sunken spots, indicate that the pavement or the pavement base should be repaired or replaced as stated below.

Cracks and joints may be filled with a mixture of emulsified asphalt and aggregate. The aggregate shall consist of limestone, volcanic ash, sand, or other material that will cure to form a hard substance. The combined gradation shall be as shown in the following table.

Gradation

Sieve Size	e Percent Passing	
No. 4	100	
No. 8	90-100	
No. 16	65-90	
No. 30	40-60	
No. 50	0. 50 25-42	
No. 100	15-30	
No. 200	10-20	

Up to 3% cement can be added to accelerate the set time. The mixture shall not contain more than 20% natural sand without approval in writing from the RPR.

The proportions of asphalt emulsion and aggregate shall be determined in the field and may be varied to facilitate construction requirements. Normally, these proportions will be approximately one part asphalt emulsion to five parts aggregate by volume. The material shall be poured or placed into the joints or cracks and compacted to form a void less mass. The joint or crack shall be filled to within +0 to -1/8 inches of the surface. Any material spilled outside the width of the joint shall be removed from the pavement surface prior to constructing the overlay. Where concrete overlays are to be constructed, only the excess joint material on the pavement surface and vegetation in the joints need to be removed.

101-3.3 Removal of Foreign Substances/contaminates prior to overlay. Removal of foreign substances/contaminates from existing pavement that will affect the bond of the new treatment shall consist of removal of rubber, fuel spills, oil, crack sealer, at least 90% of paint, and other foreign substances from the surface of the pavement. Areas that require removal are designated on the plans and as directed by the RPR in the field during construction.

High-pressure water may be used. If chemicals are used, they shall comply with the state's environmental protection regulations. Removal methods used shall not cause major damage to the pavement, or to any structure or utility within or adjacent to the work area. Major damage is defined as changing the properties of the pavement, removal of asphalt causing the aggregate to ravel, or removing pavement over 1/8 inch deep. If it is deemed by the RPR that damage to the existing pavement is caused by operational error, such as permitting the application method to dwell in one location for too long, the Contractor shall repair the damaged area without compensation and as directed by the RPR.

Removal of foreign substances shall not proceed until approved by the RPR. Water used for high-pressure water equipment shall be provided by the Contractor at the Contractor's expense. No material shall be deposited on the pavement shoulders. All wastes shall be disposed of in areas indicated in this specification or shown on the plans.

101-3.4 Concrete spall or failed asphaltic concrete pavement repair.

a. Repair of concrete spalls in areas to be overlaid with asphalt. The Contractor shall repair all spalled concrete as shown on the plans or as directed by the RPR. The perimeter of the repair shall be saw cut a minimum of 2 inches outside the affected area and 2 inches deep. The deteriorated material shall be removed to a depth where the existing material is firm or cannot be easily removed with a geologist pick. The removed area shall be filled with asphalt mixture with aggregate sized appropriately for the depth of

the patch. The material shall be compacted with equipment approved by the RPR until the material is dense and no movement or marks are visible. The material shall not be placed in lifts over 4 inches in depth. This method of repair applies only to pavement to be overlaid.

- **b. Asphalt pavement repair.** The Contractor shall repair all spalled concrete as shown on the plans or as directed by the RPR. The failed areas shall be removed as specified in paragraph 101-3.1b. All failed material including surface, base course, subbase course, and subgrade shall be removed. Materials and methods of construction shall comply with the applicable sections of these specifications.
- **101-3.5** Cold milling. Milling shall be performed with a power-operated milling machine or grinder, capable of producing a uniform finished surface. The milling machine or grinder shall operate without tearing or gouging the underlaying surface. The milling machine or grinder shall be equipped with grade and slope controls, and a positive means of dust control. All millings shall be removed and disposed off Airport property. If the Contractor mills or grinds deeper or wider than the plans specify, the Contractor shall replace the material removed with new material at the Contractor's Expense.
- **a. Patching.** The milling machine shall be capable of cutting a vertical edge without chipping or spalling the edges of the remaining pavement and it shall have a positive method of controlling the depth of cut. The RPR shall layout the area to be milled with a straightedge in increments of 1-foot widths. The area to be milled shall cover only the failed area. Any excessive area that is milled because the Contractor doesn't have the appropriate milling machine, or areas that are damaged because of his negligence, shall be repaired by the Contractor at the Contractor's Expense.
- **b. Profiling, grade correction, or surface correction.** The milling machine shall have a minimum width of 7 feet and it shall be equipped with electronic grade control devices that will cut the surface to the grade specified. The tolerances shall be maintained within +0 inch and -1/4 inch of the specified grade. The machine must cut vertical edges and have a positive method of dust control. The machine must have the ability to remove the millings or cuttings from the pavement and load them into a truck. All millings shall be removed and disposed of off the airport.
- **c. Clean-up.** The Contractor shall sweep the milled surface daily and immediately after the milling until all residual materials are removed from the pavement surface. Prior to paving, the Contractor shall wet down the milled pavement and thoroughly sweep and/or blow the surface to remove loose residual material. Waste materials shall be collected and removed from the pavement surface and adjacent areas by sweeping or vacuuming. Waste materials shall be removed and disposed off Airport property.
- **101-3.6. Preparation of asphalt pavement surfaces prior to surface treatment.** Existing asphalt pavements to be treated with a surface treatment shall be prepared as follows:
- **a.** Patch asphalt pavement surfaces that have been softened by petroleum derivatives or have failed due to any other cause. Remove damaged pavement to the full depth of the damage and replace with new asphalt pavement similar to that of the existing pavement in accordance with paragraph 101-3.4b.
 - **b.** Repair joints and cracks in accordance with paragraph 101-3.2.
- **c.** Remove oil or grease that has not penetrated the asphalt pavement by scrubbing with a detergent and washing thoroughly with clean water.
- **d.** Clean pavement surface immediately prior to placing the surface treatment so that it is free of dust, dirt, grease, vegetation, oil or any type of objectionable surface film.
- **101-3.7 Maintenance**. The Contractor shall perform all maintenance work necessary to keep the pavement in a satisfactory condition until the full section is complete and accepted by the RPR. The surface shall be kept clean and free from foreign material. The pavement shall be properly drained at all times. If cleaning is necessary or if the pavement becomes disturbed, any work repairs necessary shall be performed at the Contractor's expense.

- **101-3.8 Preparation of Joints in Rigid Pavement prior to resealing.** Prior to application of sealant material, clean and dry the joints of all scale, dirt, dust, old sealant, curing compound, moisture and other foreign matter. The Contractor shall demonstrate, in the presence of the RPR, that the method used cleans the joint and does not damage the joint.
- **101-3.8.1 Removal of Existing Joint Sealant**. All existing joint sealants will be removed by plowing or use of hand tools. Any remaining sealant and or debris will be removed by use of wire brushes or other tools as necessary. Resaw joints removing no more than 1/16 inch from each joint face. Immediately after sawing, flush out joint with water and other tools as necessary to completely remove the slurry.
- **101-3.8.2 Cleaning prior to sealing**. Immediately before sealing, joints shall be cleaned by removing any remaining laitance and other foreign material. Allow sufficient time to dry out joints prior to sealing. Joint surfaces will be surface-dry prior to installation of sealant.
- 101-3.8.3 Joint sealant. Joint material and installation will be in accordance with Item P-605.
- **101-3.9 Preparation of Cracks in Flexible Pavement prior to sealing.** Prior to application of sealant material, clean and dry the joints of all scale, dirt, dust, old sealant, curing compound, moisture and other foreign matter. The Contractor shall demonstrate, in the presence of the RPR, that the method used cleans the cracks and does not damage the pavement.
- **101-3.9.1 Preparation of Crack**. Widen crack with router by removing a minimum of 1/16 inch from each side of crack. Immediately before sealing, cracks will be blown out with a hot air lance combined with oil and water-free compressed air.
- **101-3.9.2 Removal of Existing Crack Sealant**. Existing sealants will be removed by routing. Following routing any remaining debris will be removed by use of a hot lance combined with oil and water-free compressed air.
- 101-3.9.3 Crack Sealant. Crack sealant material and installation will be in accordance with Item P-605.

101-3.9.4 Removal of Pipe and other Buried Structures.

- **a.** Removal of Existing Pipe Material. Remove the types of pipe as indicated on the plans. The pipe material shall be legally disposed of off-site in a timely manner following removal. Trenches shall be backfilled with material equal to or better in quality than adjacent embankment. Trenches under paved areas must be compacted to 95% of ASTM D698.
- **b.** Removal of Inlets/Manholes. Where indicated on the plans or as directed by the RPR, inlets and/or manholes shall be removed and legally disposed of off-site in a timely fashion after removal. Excavations after removal shall be backfilled with material equal or better in quality than adjacent embankment. When under paved areas must be compacted to 95% of ASTM D698, when outside of paved areas must be compacted to 95% of ASTM D698.

METHOD OF MEASUREMENT

- **101-4.1 Pavement removal**. The unit of measurement for pavement removal shall be the number of square yards removed by the Contractor. Any pavement removed outside the limits of removal because the pavement was damaged by negligence on the part of the Contractor shall not be included in the measurement for payment. No direct measurement or payment shall be made for saw cutting. Saw cutting shall be incidental to pavement removal. Dowel bar installation shall be incidental to pavement removal.
- **101-4.2 Joint and crack repair.** The unit of measurement for joint and crack repair shall be the linear foot of joint.
- **101-4.3 Removal of foreign substances/contaminates**. The unit of measurement for foreign Substances/contaminates removal shall be the square foot.

- 101-4.4 Spalled and failed asphalt pavement repair. The unit of measure for failed asphalt pavement repair shall be square foot.
- 101-4.5 Concrete spall repair. The unit of measure for concrete spall repair shall be the number of square feet (square meter). The location and average depth of the patch shall be determined and agreed upon by the RPR and the Contractor.
- **101-4.6 Cold milling.** The unit of measure for cold milling shall be 0 to 3 inches of milling per square yard. The location and average depth of the cold milling shall be as shown on the plans. If the initial cut does not correct the condition, the Contractor shall re-mill the area and will be paid for the total depth of milling.
- 101-4.7 Tie down abandonment. The unit of measure for tie down abandonment, by type, shall be each.
- 101-4.8 Pavement patching. The unit of measure for pavement patching shall be square yard. This shall include, but not limited to, saw cut, payement removal and concrete patch in accordance to the details in the plans.

BASIS OF PAYMENT

101-5.1 Payment. Payment shall be made at contract unit price for the unit of measurement as specified above. This price shall be full compensation for furnishing all materials and for all preparation, hauling, and placing of the material and for all labor, equipment, tools, and incidentals necessary to complete this item.

Item P 101-5.1	Joint and Crack Repair – per linear foot
Item P-101-5.2	Cold Milling (0" – 3") – per square yard
Item P-101-5.3	Tie-Down Abandonment Type 1 – per each
Item P-101-5.4	Tie-Down Abandonment Type 2 – per each
Item P-101-5.5	Pavement Patching – per square yards

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

Advisory Circulars (AC)

Guidelines and Procedures for Maintenance of Airport Pavements. AC 150/5380-6

ASTM International (ASTM)

ASTM D6690 Standard Specification for Joint and Crack Sealants, Hot Applied, for

Concrete and Asphalt Pavements

END OF ITEM P-101

THIS PAGE INTENTIONALLY LEFT BLANK

ITEM P-152 EXCAVATION, SUBGRADE, AND EMBANKMENT

DESCRIPTION

- **152-1.1** This item covers excavation, disposal, placement, and compaction of all materials within the limits of the work required to construct safety areas, runways, taxiways, aprons, and intermediate areas as well as other areas for drainage, building construction, parking, or other purposes in accordance with these specifications and in conformity to the dimensions and typical sections shown on the plans.
- **152-1.2 Classification.** All material excavated shall be classified as defined below:
- **a.** Unclassified excavation. Unclassified excavation shall consist of the excavation and disposal of all material, regardless of its nature.
- **152-1.3 Unsuitable excavation.** Unsuitable material shall be disposed in designated waste areas as shown on the plans. Materials containing vegetable or organic matter, such as muck, peat, organic silt, or sod shall be considered unsuitable for use in embankment construction. Material suitable for topsoil may be used on the embankment slope when approved by the RPR.

CONSTRUCTION METHODS

152-2.1 General. Before beginning excavation, grading, and embankment operations in any area, the area shall be cleared or cleared and grubbed in accordance with Item P-151.

The suitability of material to be placed in embankments shall be subject to approval by the RPR. All unsuitable material shall be disposed of in waste areas as shown on the plans. All waste areas shall be graded to allow positive drainage of the area and adjacent areas. The surface elevation of waste areas shall be specified on the plans or approved by the RPR.

When the Contractor's excavating operations encounter artifacts of historical or archaeological significance, the operations shall be temporarily discontinued and the RPR notified per Section 70, paragraph 70-20. At the direction of the RPR, the Contractor shall excavate the site in such a manner as to preserve the artifacts encountered and allow for their removal. Such excavation will be paid for as extra work.

Areas outside the limits of the pavement areas where the top layer of soil has become compacted by hauling or other Contractor activities shall be scarified and disked to a depth of 4 inches, to loosen and pulverize the soil. Stones or rock fragments larger than 4 inches in their greatest dimension will not be permitted in the top 6 inches of the subgrade.

If it is necessary to interrupt existing surface drainage, sewers or under-drainage, conduits, utilities, or similar underground structures, the Contractor shall be responsible for and shall take all necessary precautions to preserve them or provide temporary services. When such facilities are encountered, the Contractor shall notify the RPR, who shall arrange for their removal if necessary. The Contractor, at their own expense, shall satisfactorily repair or pay the cost of all damage to such facilities or structures that may result from any of the Contractor's operations during the period of the contract.

- **a. Blasting.** Blasting shall not be allowed.
- **152-2.2 Excavation.** No excavation shall be started until the work has been staked out by the Contractor and the RPR has obtained from the Contractor, the survey notes of the elevations and measurements of the ground surface. The Contractor and RPR shall agree that the original ground lines shown on the original topographic mapping are accurate, or agree to any adjustments made to the original ground lines.

All areas to be excavated shall be stripped of vegetation and topsoil. Topsoil shall be stockpiled for future use in areas designated on the plans or by the RPR. All suitable excavated material shall be used in the formation of embankment, subgrade, or other purposes as shown on the plans. All unsuitable material shall be disposed of as shown on the plans.

The grade shall be maintained so that the surface is well drained at all times.

When the volume of the excavation exceeds that required to construct the embankments to the grades as indicated on the plans, the excess shall be used to grade the areas of ultimate development or disposed as directed by the RPR. When the volume of excavation is not sufficient for constructing the embankments to the grades indicated, the deficiency shall be obtained from borrow areas.

- **a. Selective grading.** When selective grading is indicated on the plans, the more suitable material designated by the RPR shall be used in constructing the embankment or in capping the pavement subgrade. If, at the time of excavation, it is not possible to place this material in its final location, it shall be stockpiled in approved areas until it can be placed. The more suitable material shall then be placed and compacted as specified. Selective grading shall be considered incidental to the work involved. The cost of stockpiling and placing the material shall be included in the various pay items of work involved.
- **b. Undercutting.** Rock, shale, hardpan, loose rock, boulders, or other material unsatisfactory for safety areas, subgrades, roads, shoulders, or any areas intended for turf shall be excavated to a minimum depth of 12 inches below the subgrade or to the depth specified by the RPR. Muck, peat, matted roots, or other yielding material, unsatisfactory for subgrade foundation, shall be removed to the depth specified. Unsuitable materials shall be disposed off the airport. The cost is incidental to this item. This excavated material shall be paid for at the contract unit price per cubic yard for Unclassified Excavation. The excavated area shall be backfilled with suitable material obtained from the grading operations or borrow areas and compacted to specified densities. The necessary backfill will constitute a part of the embankment. Where rock cuts are made, backfill with select material. Any pockets created in the rock surface shall be drained in accordance with the details shown on the plans. Undercutting will be paid as unclassified excavation.
- **c. Over-break.** Over-break, including slides, is that portion of any material displaced or loosened beyond the finished work as planned or authorized by the RPR. All over-break shall be graded or removed by the Contractor and disposed of as directed by the RPR. The RPR shall determine if the displacement of such material was unavoidable and their own decision shall be final. Payment will not be made for the removal and disposal of over-break that the RPR determines as avoidable. Unavoidable over-break will be classified as "Unclassified Excavation."
- **d. Removal of utilities.** The removal of existing structures and utilities required to permit the orderly progress of work will be accomplished by someone other than the Contractor. All existing foundations shall be excavated at least 2 feet below the top of subgrade or as indicated on the plans, and the material disposed of as directed by the RPR. All foundations thus excavated shall be backfilled with suitable material and compacted as specified for embankment or as shown on the plans.

152-2.3 Borrow excavation.

There are borrow sources within the boundaries of the airport property. The Contractor shall notify the RPR at least 15 days prior to beginning the excavation so necessary measurements and tests can be made by the RPR. All borrow pits shall be opened to expose the various strata of acceptable material to allow obtaining a uniform product. Borrow areas shall be drained and left in a neat, presentable condition with all slopes dressed uniformly. Borrow areas shall not create a hazardous wildlife attractant.

152-2.4 Drainage excavation. Drainage excavation shall consist of excavating drainage ditches including intercepting, inlet, or outlet ditches; or other types as shown on the plans. The work shall be performed in sequence with the other construction. Ditches shall be constructed prior to starting adjacent excavation

operations. All satisfactory material shall be placed in embankment fills; unsuitable material shall be placed in designated waste areas or as directed by the RPR. All necessary work shall be performed true to final line, elevation, and cross-section. The Contractor shall maintain ditches constructed on the project to the required cross-section and shall keep them free of debris or obstructions until the project is accepted.

152-2.5 Preparation of cut areas or areas where existing pavement has been removed. Not used.

152-2.6 Preparation of embankment area. All sod and vegetative matter shall be removed from the surface upon which the embankment is to be placed. The cleared surface shall be broken up by plowing or scarifying to a minimum depth of 6 inches and shall then be compacted per paragraph 152-2.10.

Sloped surfaces steeper than one (1) vertical to four (4) horizontal shall be plowed, stepped, benched, or broken up so that the fill material will bond with the existing material. When the subgrade is part fill and part excavation or natural ground, the excavated or natural ground portion shall be scarified to a depth of 12 inches and compacted as specified for the adjacent fill.

No direct payment shall be made for the work performed under this section. The necessary clearing and grubbing and the quantity of excavation removed will be paid for under the respective items of work.

152-2.7 Control Strip. The first half-day of construction of subgrade and/or embankment shall be considered as a control strip for the Contractor to demonstrate, in the presence of the RPR, that the materials, equipment, and construction processes meet the requirements of this specification. The sequence and manner of rolling necessary to obtain specified density requirements shall be determined. The maximum compacted thickness may be increased to a maximum of 12 inches (300 mm) upon the Contractor's demonstration that approved equipment and operations will uniformly compact the lift to the specified density. The RPR must witness this demonstration and approve the lift thickness prior to full production.

Control strips that do not meet specification requirements shall be reworked, re-compacted, or removed and replaced at the Contractor's expense. Full operations shall not begin until the control strip has been accepted by the RPR. The Contractor shall use the same equipment, materials, and construction methods for the remainder of construction, unless adjustments made by the Contractor are approved in advance by the RPR.

152-2.8 Formation of embankments. The material shall be constructed in lifts as established in the control strip, but not less than 6 inches nor more than 12 inches of compacted thickness.

When more than one lift is required to establish the layer thickness shown on the plans, the construction procedure described here shall apply to each lift. No lift shall be covered by subsequent lifts until tests verify that compaction requirements have been met. The Contractor shall rework, re-compact and retest any material placed which does not meet the specifications.

The lifts shall be placed, to produce a soil structure as shown on the typical cross-section or as directed by the RPR. Materials such as brush, hedge, roots, stumps, grass and other organic matter, shall not be incorporated or buried in the embankment.

Earthwork operations shall be suspended at any time when satisfactory results cannot be obtained due to rain, freezing, or other unsatisfactory weather conditions in the field. Frozen material shall not be placed in the embankment nor shall embankment be placed upon frozen material. Material shall not be placed on surfaces that are muddy, frozen, or contain frost. The Contractor shall drag, blade, or slope the embankment to provide surface drainage at all times.

The material in each lift shall be within $\pm 2\%$ of optimum moisture content before rolling to obtain the prescribed compaction. The material shall be moistened or aerated as necessary to achieve a uniform moisture content throughout the lift. Natural drying may be accelerated by blending in dry material or manipulation alone to increase the rate of evaporation.

The Contractor shall make the necessary corrections and adjustments in methods, materials or moisture content to achieve the specified embankment density.

The RPR will take samples of excavated materials which will be used in embankment for testing and develop a Moisture-Density Relations of Soils Report (Proctor) in accordance with ASTM D698. A new Proctor shall be developed for each soil type based on visual classification.

Density tests will be taken by the RPR for every **500** square yards of compacted embankment for each lift which is required to be compacted, or other appropriate frequencies as determined by the RPR.

If the material has greater than 30% retained on the 3/4-inch sieve, follow AASHTO T-180 Annex Correction of maximum dry density and optimum moisture for oversized particles.

Rolling operations shall be continued until the embankment is compacted to not less than 95% of maximum density for non-cohesive soils, and 90% of maximum density for cohesive soils as determined by ASTM D698. Under all areas to be paved, the embankments shall be compacted to a depth of **6**° and to a density of not less than **95** percent of the maximum density as determined by ASTM D698. As used in this specification, "non-cohesive" shall mean those soils having a plasticity index (PI) of less than 3 as determined by ASTM D4318.

On all areas outside of the pavement areas, no compaction will be required on the top 4 inches which shall be prepared for a seedbed in accordance with Item T-901.

The in-place field density shall be determined in accordance with ASTM D6938 using Procedure A, the direct transmission method, and ASTM D6938 shall be used to determine the moisture content of the material. The machine shall be calibrated in accordance with ASTM D6938. The RPR shall perform all density tests. If the specified density is not attained, the area represented by the test or as designated by the RPR shall be reworked and/or re-compacted and additional random tests made. This procedure shall be followed until the specified density is reached.

Compaction areas shall be kept separate, and no lift shall be covered by another lift until the proper density is obtained.

During construction of the embankment, the Contractor shall route all construction equipment evenly over the entire width of the embankment as each lift is placed. Lift placement shall begin in the deepest portion of the embankment fill. As placement progresses, the lifts shall be constructed approximately parallel to the finished pavement grade line.

When rock, concrete pavement, asphalt pavement, and other embankment material are excavated at approximately the same time as the subgrade, the material shall be incorporated into the outer portion of the embankment and the subgrade material shall be incorporated under the future paved areas. Stones, fragmentary rock, and recycled pavement larger than 4 inches in their greatest dimensions will not be allowed in the top 12 inches of the subgrade. Rockfill shall be brought up in lifts as specified or as directed by the RPR and the finer material shall be used to fill the voids forming a dense, compact mass. Rock, cement concrete pavement, asphalt pavement, and other embankment material shall not be disposed of except at places and in the manner designated on the plans or by the RPR.

When the excavated material consists predominantly of rock fragments of such size that the material cannot be placed in lifts of the prescribed thickness without crushing, pulverizing or further breaking down the pieces, such material may be placed in the embankment as directed in lifts not exceeding 2 feet in thickness. Each lift shall be leveled and smoothed with suitable equipment by distribution of spalls and finer fragments of rock. The lift shall not be constructed above an elevation 4 feet below the finished subgrade.

There will be no separate measurement of payment for compacted embankment. All costs incidental to placing in lifts, compacting, discing, watering, mixing, sloping, and other operations necessary for construction of embankments will be included in the contract price for excavation, borrow, or other items.

152-2.9 Proof rolling. Not used.

152-2.10 Compaction requirements. The subgrade under areas to be paved shall be compacted to a depth of 12 inches and to a density of not less than 100 percent of the maximum dry density as determined by ASTM D698. The subgrade in areas outside the limits of the pavement areas shall be compacted to a depth of 12 inches and to a density of not less than 95 percent of the maximum density as determined by ASTM D 698.

The material to be compacted shall be within $\pm 2\%$ of optimum moisture content before being rolled to obtain the prescribed compaction (except for expansive soils). When the material has greater than 30 percent retained on the $\frac{3}{4}$ inch sieve, follow the methods in ASTM D698 or procedures in AASHTO T180 Annex for correction of maximum dry density and optimum moisture for oversized particles. Tests for moisture content and compaction will be taken at a minimum of 500 S.Y. of subgrade. All quality assurance testing shall be done by the RPR.

The in-place field density shall be determined in accordance with ASTM D6938 using Procedure A, the direct transmission method, and ASTM D6938 shall be used to determine the moisture content of the material. The machine shall be calibrated in accordance with ASTM D6938 within 12 months prior to its use on this contract. The gage shall be field standardized daily.

Maximum density refers to maximum dry density at optimum moisture content unless otherwise specified.

If the specified density is not attained, the entire lot shall be reworked and/or re-compacted and additional random tests made. This procedure shall be followed until the specified density is reached.

All cut-and-fill slopes shall be uniformly dressed to the slope, cross-section, and alignment shown on the plans or as directed by the RPR and the finished subgrade shall be maintained.

152-2.11 Finishing and protection of subgrade. Finishing and protection of the subgrade is incidental to this item. Grading and compacting of the subgrade shall be performed so that it will drain readily. All low areas, holes or depressions in the subgrade shall be brought to grade. Scarifying, blading, rolling and other methods shall be performed to provide a thoroughly compacted subgrade shaped to the lines and grades shown on the plans. All ruts or rough places that develop in the completed subgrade shall be graded, recompacted, and retested. The Contractor shall protect the subgrade from damage and limit hauling over the finished subgrade to only traffic essential for construction purposes.

The Contractor shall maintain the completed course in satisfactory condition throughout placement of subsequent layers. No subbase, base, or surface course shall be placed on the subgrade until the subgrade has been accepted by the RPR.

152-2.12 Haul. All hauling will be considered a necessary and incidental part of the work. The Contractor shall include the cost in the contract unit price for the pay of items of work involved. No payment will be made separately or directly for hauling on any part of the work.

The Contractor's equipment shall not cause damage to any excavated surface, compacted lift or to the subgrade as a result of hauling operations. Any damage caused as a result of the Contractor's hauling operations shall be repaired at the Contractor's expense.

The Contractor shall be responsible for providing, maintaining and removing any haul roads or routes within or outside of the work area, and shall return the affected areas to their former condition, unless otherwise authorized in writing by the Owner. No separate payment will be made for any work or materials associated with providing, maintaining and removing haul roads or routes.

152-2.13 Surface Tolerances. In those areas on which a subbase or base course is to be placed, the surface shall be tested for smoothness and accuracy of grade and crown. Any portion lacking the required smoothness or failing in accuracy of grade or crown shall be scarified to a depth of at least 3 inches (75 mm), reshaped and re-compacted to grade until the required smoothness and accuracy are obtained and approved by the RPR. The Contractor shall perform all final smoothness and grade checks in the presence

of the RPR. Any deviation in surface tolerances shall be corrected by the Contractor at the Contractor's expense.

- **a. Smoothness.** The finished surface shall not vary more than +/- ½ inch (12 mm) when tested with a 12-foot (3.7-m) straightedge applied parallel with and at right angles to the centerline. The straightedge shall be moved continuously forward at half the length of the 12-foot (3.7-m) straightedge for the full length of each line on a 50-foot (15-m) grid.
- **b. Grade.** The grade and crown shall be measured on a 50-foot (15-m) grid and shall be within +/-0.05 feet (15 mm) of the specified grade.

On safety areas, turfed areas and other designated areas within the grading limits where no subbase or base is to placed, grade shall not vary more than 0.10 feet (30 mm) from specified grade. Any deviation in excess of this amount shall be corrected by loosening, adding or removing materials, and reshaping.

152-2.14 Topsoil. When topsoil is specified or required as shown on the plans or under Item T-905, it shall be salvaged from stripping or other grading operations. The topsoil shall meet the requirements of Item T-905. If, at the time of excavation or stripping, the topsoil cannot be placed in its final section of finished construction, the material shall be stockpiled at approved locations. Stockpiles shall be located as shown on the plans and the approved CSPP, and shall not be placed on areas that subsequently will require any excavation or embankment fill. If, in the judgment of the RPR, it is practical to place the salvaged topsoil at the time of excavation or stripping, the material shall be placed in its final position without stockpiling or further re-handling.

Upon completion of grading operations, stockpiled topsoil shall be handled and placed as shown on the plans and as required in Item T-905. Topsoil shall be paid for as provided in Item T-905. No direct payment will be made for topsoil under Item P-152.

METHOD OF MEASUREMENT

152-3.1 The quantity of unclassified excavation to be paid for shall be the number of cubic yards measured in its original position. Measurement shall not include the quantity of materials excavated without authorization beyond normal slope lines, or the quantity of material used for purposes other than those directed.

BASIS OF PAYMENT

152-4.1 Unclassified excavation payment shall be made at the contract unit price per cubic yard. This price shall be full compensation for furnishing all materials, labor, equipment, tools, and incidentals necessary to complete the item.

Payment will be made under:

Item P-152-4.1 Unclassified Excavation – per cubic yard.

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

American Association of State Highway and Transportation Officials (AASHTO)

AASHTO T-180 Standard Method of Test for Moisture-Density Relations of Soils Using a

4.54-kg (10-lb) Rammer and a 457-mm (18-in.) Drop

ASTM International (ASTM)

ASTM D698 Standard Test Methods for Laboratory Compaction Characteristics of Soil

Using Standard Effort (12,400 ft-lbf/ft³ (600 kN-m/m³))

ASTM D1556 Standard Test Method for Density and Unit Weight of Soil in Place by the

Sand-Cone Method

ASTM D1557 Standard Test Methods for Laboratory Compaction Characteristics of Soil

Using Modified Effort (56,000 ft-lbf/ft³ (2700 kN-m/m³))

ASTM D6938 Standard Test Methods for In-Place Density and Water Content of Soil

and Soil-Aggregate by Nuclear Methods (Shallow Depth)

Advisory Circulars (AC)

AC 150/5370-2 Operational Safety on Airports During Construction Software

Software

FAARFIELD - FAA Rigid and Flexible Iterative Elastic Layered Design

U.S. Department of Transportation

FAA RD-76-66 Design and Construction of Airport Pavements on Expansive Soils

END OF ITEM P-152

THIS PAGE INTENTIONALLY LEFT BLANK

ITEM P-153 CONTROLLED LOW-STRENGTH MATERIAL (CLSM)

DESCRIPTION

153-1.1 This item shall consist of furnishing, transporting, and placing a controlled low-strength material (CLSM) as flowable backfill in trenches or at other locations shown on the plans or as directed by the Resident Project Representative (RPR).

MATERIALS

153-2.1 Materials.

- **a. Cement.** Cement shall conform to the requirements of ASTM C150 Type I or Type II. If for any reason, cement becomes partially set or contains lumps of caked cement, it shall be rejected. Cement salvaged from discarded or used bags shall not be used.
 - **b. Fly ash.** Fly ash shall conform to ASTM C618, Class C or F.
- **c. Fine aggregate (sand).** Fine aggregate shall conform to the requirements of ASTM C33 except for aggregate gradation. Any aggregate gradation which produces the specified performance characteristics of the CLSM and meets the following requirements, will be accepted.

Sieve Size	Percent Passing by weight
3/4 inch (19.0 mm)	100
No. 200 (75 µm)	0 - 12

d. Water. Water used in mixing or curing shall be from potable water sources. Other sources shall be tested in accordance with ASTM C1602 prior to use.

MIX DESIGN

- **153-3.1 Proportions.** The Contractor shall submit, to the RPR, a mix design including the proportions and source of aggregate, fly ash, cement, water, and approved admixtures. No CLSM mixture shall be produced for payment until the RPR has given written approval of the proportions. The proportions shall be prepared by a laboratory and shall remain in effect for the duration of the project. The proportions shall establish a single percentage or weight for aggregate, fly ash, cement, water, and any admixtures proposed. Laboratory costs are incidental to this item.
- **a.** Compressive strength. CLSM shall be designed to achieve a 28-day compressive strength of 100 to 200 psi (690 to 1379 kPa) when tested in accordance with ASTM D4832, with no significant strength gain after 28 days.
- **b.** Consistency. Design CLSM to achieve a consistency that will produce an approximate 8-inch (200 mm) diameter circular-type spread without segregation. CLSM consistency shall be determined per ASTM D6103.

CONSTRUCTION METHODS

153-4.1 Placement.

- **a. Placement.** CLSM may be placed by any reasonable means from the mixing unit into the space to be filled. Agitation is required during transportation and waiting time. Placement shall be performed so structures or pipes are not displaced from their final position and intrusion of CLSM into unwanted areas is avoided. The material shall be brought up uniformly to the fill line shown on the plans or as directed by the RPR. Each placement of CLSM shall be as continuous an operation as possible. If CLSM is placed in more than one lift, the base lift shall be free of surface water and loose foreign material prior to placement of the next lift.
- **b. Contractor Quality Control**. The Contractor shall collect all batch tickets to verify the CLSM delivered to the project conforms to the mix design. The Contractor shall verify daily that the CLSM is consistent with 153-3.1a and 153-3.1b. Adjustments shall be made as necessary to the proportions and materials as needed. The Contractor shall provide all batch tickets to the RPR.
- **c. Limitations of placement.** CLSM shall not be placed on frozen ground. Mixing and placing may begin when the air or ground temperature is at least 35°F (2°C) and rising. Mixing and placement shall stop when the air temperature is 40°F (4°C) and falling or when the anticipated air or ground temperature will be 35°F (2°C) or less in the 24-hour period following proposed placement. At the time of placement, CLSM shall have a temperature of at least 40°F (4°C).

153-4.2 Curing and protection

- **a.** Curing. The air in contact with the CLSM shall be maintained at temperatures above freezing for a minimum of 72 hours. If the CLSM is subjected to temperatures below 32°F (0°C), the material may be rejected by the RPR if damage to the material is observed.
- **b. Protection.** The CLSM shall not be subject to loads and shall remain undisturbed by construction activities for a period of 48 hours or until a compressive strength of 15 psi (105 kPa) is obtained. The Contractor shall be responsible for providing evidence to the RPR that the material has reached the desired strength. Acceptable evidence shall be based upon compressive tests made in accordance with paragraph 153-3.1a.
- **153-4.3 Quality Assurance (QA) Acceptance.** CLSM QA acceptance shall be based upon batch tickets provided by the Contractor to the RPR to confirm that the delivered material conforms to the mix design.

METHOD OF MEASUREMENT

153-5.1 Measurement. No separate measurement for payment shall be made for controlled low strength material (CLSM). CLSM shall be considered necessary and incidental to the work of this Contract.

BASIS OF PAYMENT

153-6.1 Payment. No payment will be made separately or directly for controlled low strength material (CLSM). CLSM shall be considered necessary and incidental to the work of this Contract.

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM C33	Standard Specification for Concrete Aggregates
ASTM C150	Standard Specification for Portland Cement
ASTM C618	Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use in Concrete
ASTM C595	Standard Specification for Blended Hydraulic Cements
ASTM C1602	Standard Specification for Mixing Water Used in the Production of Hydraulic Cement Concrete
ASTM D4832	Standard Test Method for Preparation and Testing of Controlled Low- Strength Material (CLSM) Test Cylinders
ASTM D6103	Flow Consistency of Controlled Low Strength Material (CLSM)

END OF ITEM P-153

THIS PAGE INTENTIONALLY LEFT BLANK

ITEM P-401 ASPHALT MIX PAVEMENT

DESCRIPTION

401-1.1 This item shall consist of pavement courses composed of mineral aggregate and asphalt binder mixed in a central mixing plant and placed on a prepared base or stabilized course in accordance with these specifications and shall conform to the lines, grades, thicknesses, and typical cross-sections shown on the plans. Each course shall be constructed to the depth, typical section, and elevation required by the plans and shall be rolled, finished, and approved before the placement of the next course.

MATERIALS

- **401-2.1 Aggregate.** Aggregates shall consist of crushed stone, crushed gravel, crushed slag, screenings, natural sand, and mineral filler, as required. The aggregates should have no known history of detrimental pavement staining due to ferrous sulfides, such as pyrite. Coarse aggregate is the material retained on the No. 4 (4.75 mm) sieve. Fine aggregate is the material passing the No. 4 (4.75 mm) sieve.
- **a. Coarse aggregate.** Coarse aggregate shall consist of sound, tough, durable particles, free from films of matter that would prevent thorough coating and bonding with the asphalt material and free from organic matter and other deleterious substances. Coarse aggregate material requirements are given in the table below.

Coarse Aggregate Material Requirements

Material Test	Requirement	Standard
Resistance to Degradation	Loss: 40% maximum	ASTM C131
Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate	Loss after 5 cycles: 12% maximum using Sodium sulfate - or - 18% maximum using magnesium sulfate	ASTM C88
Clay lumps and friable particles	0.3% maximum	ASTM C142
Percentage of Fractured Particles	Minimum 75% by weight of particles with at least two fractured faces and 85% with at least one fractured face ¹	ASTM D5821
Flat, Elongated, or Flat and Elongated Particles	8% maximum, by weight, of flat, elongated, or flat and elongated particles at 5:1 ²	ASTM D4791
Bulk density of slag ³	Weigh not less than 70 pounds per cubic foot (1.12 Mg/cubic meter)	ASTM C29.

The area of each face shall be equal to at least 75% of the smallest mid-sectional area of the piece. When two fractured faces are contiguous, the angle between the planes of fractures shall be at least 30 degrees to count as two fractured faces.

b. Fine aggregate. Fine aggregate shall consist of clean, sound, tough, durable, angular shaped particles produced by crushing stone, slag, or gravel and shall be free from coatings of clay, silt, or other objectionable matter. Natural (non-manufactured) sand may be used to obtain the gradation of the fine aggregate blend or to improve the workability of the mix. The addition of natural sand to a mix containing

² A flat particle is one having a ratio of width to thickness greater than five (5); an elongated particle is one having a ratio of length to width greater than five (5).

³ Only required if slag is specified.

all crushed coarse and fine aggregates will normally increase its workability and compactability. The addition of natural sand tends to decrease the stability of the mixture, therefore, it is recommended to not use natural sand. However, if natural sand is used, use the minimum amount necessary to achieve a workable mixture. Fine aggregate material requirements are listed in the table below.

Fine Aggregate Material Requirements

Material Test	Requirement	Standard
Liquid limit	25 maximum	ASTM D4318
Plasticity Index	4 maximum	ASTM D4318
Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate	Loss after 5 cycles: 10% maximum using Sodium sulfate - or - 15% maximum using magnesium sulfate	ASTM C88
Clay lumps and friable particles	0.3% maximum	ASTM C142
Sand equivalent	45 minimum	ASTM D2419
Natural Sand	0% to 15% maximum by weight of total aggregate	ASTM D1073

c. Sampling. ASTM D75 shall be used in sampling coarse and fine aggregate.

401-2.2 Mineral filler. Mineral filler (baghouse fines) may be added in addition to material naturally present in the aggregate. Mineral filler shall meet the requirements of ASTM D242.

Mineral Filler Requirements

Material Test	Requirement	Standard
Plasticity Index	4 maximum	ASTM D4318

401-2.3 Asphalt binder. Asphalt binder shall conform to ASTM D6373 Performance Grade (PG) 70-28.

401-2.4 Anti-stripping agent. Any anti-stripping agent or additive (anti-strip) shall be heat stable and shall not change the asphalt binder grade beyond specifications. Anti-strip shall be an approved material of the Department of Transportation of the State in which the project is located.

COMPOSITION

- **401-3.1 Composition of mixture(s).** The asphalt mix shall be composed of a mixture of aggregates, filler and anti-strip agent if required, and asphalt binder. The aggregate fractions shall be sized, handled in separate size groups, and combined in such proportions that the resulting mixture meets the grading requirements of the job mix formula (JMF).
- **401-3.2 Job mix formula (JMF) laboratory.** The laboratory used to develop the JMF shall possess a current certificate of accreditation, listing D3666 from a national accrediting authority and all test methods required for developing the JMF; and be listed on the accrediting authority's website. A copy of the laboratory's current accreditation and accredited test methods shall be submitted to the Resident Project Representative (RPR) prior to start of construction.

401-3.3 Job mix formula (JMF). No asphalt mixture shall be placed until an acceptable mix design has been submitted to the RPR for review and accepted in writing. The RPR's review shall not relieve the Contractor of the responsibility to select and proportion the materials to comply with this section.

When the project requires asphalt mixtures of differing aggregate gradations and/or binders, a separate JMF shall be submitted for each mix. Add anti-stripping agent to meet tensile strength requirements.

The JMF shall be prepared by an accredited laboratory that meets the requirements of paragraph 401-3.2. The asphalt mixture shall be designed using procedures contained in Asphalt Institute MS-2 Mix Design Manual, 7th Edition. Samples shall be prepared and compacted using a Marshall compactor in accordance with ASTM D6926.

Should a change in sources of materials be made, a new JMF must be submitted to the RPR for review and accepted in writing before the new material is used. After the initial production JMF has been approved by the RPR and a new or modified JMF is required for whatever reason, the subsequent cost of the new or modified JMF, including a new control strip when required by the RPR, will be borne by the Contractor.

The RPR may request samples at any time for testing, prior to and during production, to verify the quality of the materials and to ensure conformance with the applicable specifications.

The JMF shall be submitted in writing by the Contractor at least 30 days prior to the start of paving operations. The JMF shall be developed within the same construction season using aggregates proposed for project use.

The JMF shall be dated, and stamped or sealed by the responsible professional Engineer of the laboratory and shall include the following items as a minimum:

- Manufacturer's Certificate of Analysis (COA) for the asphalt binder used in the JMF in accordance with paragraph 401-2.3. Certificate of asphalt performance grade is with modifier already added, if used and must indicate compliance with ASTM D6373. For plant modified asphalt binder, certified test report indicating grade certification of modified asphalt binder.
- Manufacturer's Certificate of Analysis (COA) for the anti-stripping agent if used in the JMF in accordance with paragraph 401-2.4.
- Certified material test reports for the course and fine aggregate and mineral filler in accordance with paragraphs 401-2.1.
- Percent passing each sieve size for individual gradation of each aggregate cold feed and/or hot bin; percent by weight of each cold feed and/or hot bin used; and the total combined gradation in the JMF.
- Specific Gravity and absorption of each coarse and fine aggregate.
- Percent natural sand.
- Percent fractured faces.
- Percent by weight of flat particles, elongated particles, and flat and elongated particles (and criteria).
- Percent of asphalt.
- Number of blows or gyrations
- Laboratory mixing and compaction temperatures.
- Supplier-recommended field mixing and compaction temperatures.
- Plot of the combined gradation on a 0.45 power gradation curve.

- Graphical plots of air voids, voids in the mineral aggregate (VMA), and unit weight versus asphalt content. To achieve minimum VMA during production, the mix design needs to account for material breakdown during production.
- Tensile Strength Ratio (TSR).
- Type and amount of Anti-strip agent when used.
- Asphalt Pavement Analyzer (APA) results.
- Date the JMF was developed. Mix designs that are not dated or which are from a prior construction season shall not be accepted.

Table 1. Asphalt Design Criteria

Test Property	Value	Test Method
Number of blows or gyrations	75	
Air voids (%)	3.5	ASTM D3203
Percent voids in mineral aggregate (VMA), minimum	See Table 2	ASTM D6995
Tensile Strength Ratio (TSR) ¹	not less than 80 at a saturation of 70-80%	ASTM D4867
Asphalt Pavement Analyzer (APA) ²	Less than 10 mm @ 4000 passes	AASHTO T340 at 250 psi hose pressure at 64°C test temperature

Test specimens for TSR shall be compacted at 7 ± 1.0 % air voids. In areas subject to freeze-thaw, use freeze-thaw conditioning in lieu of moisture conditioning per ASTM D4867

The mineral aggregate shall be of such size that the percentage composition by weight, as determined by laboratory sieves, will conform to the gradation or gradations specified in Table 2 when tested in accordance with ASTM C136 and ASTM C117.

The gradations in Table 2 represent the limits that shall determine the suitability of aggregate for use from the sources of supply; be well graded from coarse to fine and shall not vary from the low limit on one sieve to the high limit on the adjacent sieve, or vice versa.

AASHTO T340 at 100 psi hose pressure at 64°C test temperature may be used in the interim. If this method is used the required Value shall be less than 5 mm @ 8000 passes

Table 2. Aggregate - Asphalt Pavements

Sieve Size	Percentage by Weight Passing Sieve
1 inch (25.0 mm)	
3/4 inch (19.0 mm)	100
1/2 inch (12.5 mm)	90-100
3/8 inch (9.5 mm)	72-88
No. 4 (4.75 mm)	53-73
No. 8 (2.36 mm)	38-60
No. 16 (1.18 mm)	26-48
No. 30 (600 μm)	18-38
No. 50 (300 μm)	11-27
No. 100 (150 μm)	6-18
No. 200 (75 μm)	3-6
Minimum Voids in Mineral Aggregate (VMA) ¹	15.0
Asphalt Percent:	
Stone or gravel	5.0-7.5
Slag	6.5-9.5
Recommended Minimum Construction Lift Thickness	2 inch

¹To achieve minimum VMA during production, the mix design needs to account for material breakdown during production.

The aggregate gradations shown are based on aggregates of uniform specific gravity. The percentages passing the various sieves shall be corrected when aggregates of varying specific gravities are used, as indicated in the Asphalt Institute MS-2 Mix Design Manual, 7th Edition.

401-3.4 Reclaimed asphalt pavement (RAP). RAP shall not be used

401-3.5 Control Strip. Full production shall not begin until an acceptable control strip has been constructed and accepted in writing by the RPR. The Contractor shall prepare and place a quantity of asphalt according to the JMF. The underlying grade or pavement structure upon which the control strip is to be constructed shall be the same as the remainder of the course represented by the control strip.

The Contractor will not be allowed to place the control strip until the Contractor quality control program (CQCP), showing conformance with the requirements of paragraph 401-5.1, has been accepted, in writing, by the RPR.

The control strip will consist of at least 250 tons (227 metric tons) or 1/2 sublot, whichever is greater. The control strip shall be placed in two lanes of the same width and depth to be used in production with a longitudinal cold joint. The cold joint must be cut back in accordance with paragraph 401-4.14 using the same procedure that will be used during production. The cold joint for the control strip will be an exposed construction joint at least four (4) hours old or when the mat has cooled to less than 160°F (71°C). The equipment used in construction of the control strip shall be the same type, configuration and weight to be used on the project.

The control strip will be considered acceptable by the RPR if the gradation, asphalt content, and VMA are within the action limits specified in paragraph 401-5.5a; and Mat density, air voids, and joint density meet the requirements specified in paragraphs 401-6.2.

If the control strip is unacceptable, necessary adjustments to the JMF, plant operation, placing procedures, and/or rolling procedures shall be made and another control strip shall be placed. Unacceptable control strips shall be removed at the Contractor's expense.

Payment will only be made for an acceptable control strip in accordance with paragraph 401-8.1 using a lot pay factor equal to 100.

CONSTRUCTION METHODS

401-4.1 Weather limitations. The asphalt shall not be placed upon a wet surface or when the surface temperature of the underlying course is less than specified in Table 4. The temperature requirements may be waived by the RPR, if requested; however, all other requirements including compaction shall be met.

Mr. 4 /Fil. 2 - L	Base Temperature (Minimum)		
Mat Thickness	°F	°C	
3 inches (7.5 cm) or greater	40 1	4	
Greater than 2 inches (50 mm) but less than 3 inches (7.5 cm)	45	7	

Table 4. Surface Temperature Limitations of Underlying Course

- **401-4.2 Asphalt plant.** Plants used for the preparation of asphalt shall conform to the requirements of American Association of State Highway and Transportation Officials (AASHTO) M156 including the following items.
- **a. Inspection of plant.** The RPR, or RPR's authorized representative, shall have access, at all times, to all areas of the plant for checking adequacy of equipment; inspecting operation of the plant: verifying weights, proportions, and material properties; and checking the temperatures maintained in the preparation of the mixtures.
- **b. Storage bins and surge bins.** The asphalt mixture stored in storage and/or surge bins shall meet the same requirements as asphalt mixture loaded directly into trucks. Asphalt mixture shall not be stored in storage and/or surge bins for a period greater than twelve (12) hours. If the RPR determines there is an excessive heat loss, segregation, or oxidation of the asphalt mixture due to temporary storage, temporary storage shall not be allowed.
- **401-4.3 Aggregate stockpile management.** Aggregate stockpiles shall be constructed in a manner that prevents segregation and intermixing of deleterious materials. Aggregates from different sources shall be stockpiled, weighed and batched separately at the asphalt batch plant. Aggregates that have become segregated or mixed with earth or foreign material shall not be used.

A continuous supply of materials shall be provided to the work to ensure continuous placement.

401-4.4 Hauling equipment. Trucks used for hauling asphalt shall have tight, clean, and smooth metal beds. To prevent the asphalt from sticking to the truck beds, the truck beds shall be lightly coated with a minimum amount of paraffin oil, lime solution, or other material approved by the RPR. Petroleum products shall not be used for coating truck beds. Each truck shall have a suitable cover to protect the mixture from adverse weather. When necessary, to ensure that the mixture will be delivered to the site at the specified temperature, truck beds shall be insulated or heated and covers shall be securely fastened.

- **401-4.4.1 Material transfer vehicle (MTV).** Material transfer vehicles used to transfer the material from the hauling equipment to the paver, shall use a self-propelled, material transfer vehicle with a swing conveyor that can deliver material to the paver without making contact with the paver. The MTV shall be able to move back and forth between the hauling equipment and the paver providing material transfer to the paver, while allowing the paver to operate at a constant speed. The Material Transfer Vehicle will have remixing and storage capability to prevent physical and thermal segregation.
- **401-4.5 Asphalt pavers.** Asphalt pavers shall be self-propelled with an activated heated screed, capable of spreading and finishing courses of asphalt that will meet the specified thickness, smoothness, and grade. The paver shall have sufficient power to propel itself and the hauling equipment without adversely affecting the finished surface. The asphalt paver shall be equipped with a control system capable of automatically maintaining the specified screed grade and elevation.

If the spreading and finishing equipment in use leaves tracks or indented areas, or produces other blemishes in the pavement that are not satisfactorily corrected by the scheduled operations, the use of such equipment shall be discontinued.

The paver shall be capable of paving to a minimum width specified in paragraph 401-4.12.

- **401-4.6 Rollers.** The number, type, and weight of rollers shall be sufficient to compact the asphalt to the required density while it is still in a workable condition without crushing of the aggregate, depressions or other damage to the pavement surface. Rollers shall be in good condition, clean, and capable of operating at slow speeds to avoid displacement of the asphalt. All rollers shall be specifically designed and suitable for compacting asphalt concrete and shall be properly used. Rollers that impair the stability of any layer of a pavement structure or underlying soils shall not be used.
- **401-4.7 Density device.** The Contractor shall have on site a density gauge during all paving operations in order to assist in the determination of the optimum rolling pattern, type of roller and frequencies, as well as to monitor the effect of the rolling operations during production paving. The Contractor shall supply a qualified technician during all paving operations to calibrate the gauge and obtain accurate density readings for all new asphalt. These densities shall be supplied to the RPR upon request at any time during construction. No separate payment will be made for supplying the density gauge and technician.
- **401-4.8 Preparation of asphalt binder.** The asphalt binder shall be heated in a manner that will avoid local overheating and provide a continuous supply of the asphalt binder to the mixer at a uniform temperature. The temperature of unmodified asphalt binder delivered to the mixer shall be sufficient to provide a suitable viscosity for adequate coating of the aggregate particles, but shall not exceed 325°F (160°C) when added to the aggregate. The temperature of modified asphalt binder shall be no more than 350°F (175°C) when added to the aggregate.
- **401-4.9 Preparation of mineral aggregate.** The aggregate for the asphalt shall be heated and dried. The maximum temperature and rate of heating shall be such that no damage occurs to the aggregates. The temperature of the aggregate and mineral filler shall not exceed 350°F (175°C) when the asphalt binder is added. Particular care shall be taken that aggregates high in calcium or magnesium content are not damaged by overheating. The temperature shall not be lower than is required to obtain complete coating and uniform distribution on the aggregate particles and to provide a mixture of satisfactory workability.
- **401-4.10 Preparation of Asphalt mixture.** The aggregates and the asphalt binder shall be weighed or metered and mixed in the amount specified by the JMF. The combined materials shall be mixed until the aggregate obtains a uniform coating of asphalt binder and is thoroughly distributed throughout the mixture. Wet mixing time shall be the shortest time that will produce a satisfactory mixture, but not less than 25 seconds for batch plants. The wet mixing time for all plants shall be established by the Contractor, based on the procedure for determining the percentage of coated particles described in ASTM D2489, for each individual plant and for each type of aggregate used. The wet mixing time will be set to achieve 95% of coated particles. For continuous mix plants, the minimum mixing time shall be determined by dividing the

weight of its contents at operating level by the weight of the mixture delivered per second by the mixer. The moisture content of all asphalt upon discharge shall not exceed 0.5%.

401-4.11 Application of Prime and Tack Coat. Immediately before placing the asphalt mixture, the underlying course shall be cleaned of all dust and debris.

A prime coat in accordance with Item P-602 shall be applied to aggregate base prior to placing the asphalt mixture.

A tack coat shall be applied in accordance with Item P-603 to all vertical and horizontal asphalt and concrete surfaces prior to placement of the first and each subsequent lift of asphalt mixture.

401-4.12 Laydown plan, transporting, placing, and finishing. Prior to the placement of the asphalt, the Contractor shall prepare a laydown plan with the sequence of paving lanes and width to minimize the number of cold joints; the location of any temporary ramps; laydown temperature; and estimated time of completion for each portion of the work (milling, paving, rolling, cooling, etc.). The laydown plan and any modifications shall be approved by the RPR.

Deliveries shall be scheduled so that placing and compacting of asphalt is uniform with minimum stopping and starting of the paver. Hauling over freshly placed material shall not be permitted until the material has been compacted, as specified, and allowed to cool to approximately ambient temperature. The Contractor, at their expense, shall be responsible for repair of any damage to the pavement caused by hauling operations.

Contractor shall survey each lift of asphalt surface course and certify to RPR that every lot of each lift meets the grade tolerances of paragraph 401-6.2d before the next lift can be placed.

Edges of existing asphalt pavement abutting the new work shall be saw cut and the cut off material and laitance removed. Apply a tack coat in accordance with P-603 before new asphalt material is placed against it.

The speed of the paver shall be regulated to eliminate pulling and tearing of the asphalt mat. Placement of the asphalt mix shall begin along the centerline of a crowned section or on the high side of areas with a one way slope unless shown otherwise on the laydown plan as accepted by the RPR. The asphalt mix shall be placed in consecutive adjacent lanes having a minimum width of 12 feet except where edge lanes require less width to complete the area. Additional screed sections attached to widen the paver to meet the minimum lane width requirements must include additional auger sections to move the asphalt mixture uniformly along the screed extension.

The longitudinal joint in one course shall offset the longitudinal joint in the course immediately below by at least one foot (30 cm); however, the joint in the surface top course shall be at the centerline of crowned pavements. Transverse joints in one course shall be offset by at least 10 feet (3 m) from transverse joints in the previous course. Transverse joints in adjacent lanes shall be offset a minimum of 10 feet (3 m). On areas where irregularities or unavoidable obstacles make the use of mechanical spreading and finishing equipment impractical, the asphalt may be spread and luted by hand tools.

The RPR may at any time, reject any batch of asphalt, on the truck or placed in the mat, which is rendered unfit for use due to contamination, segregation, incomplete coating of aggregate, or overheated asphalt mixture. Such rejection may be based on only visual inspection or temperature measurements. In the event of such rejection, the Contractor may take a representative sample of the rejected material in the presence of the RPR, and if it can be demonstrated in the laboratory, in the presence of the RPR, that such material was erroneously rejected, payment will be made for the material at the contract unit price.

Areas of segregation in the surface course, as determined by the RPR, shall be removed and replaced at the Contractor's expense. The area shall be removed by saw cutting and milling a minimum of the construction lift thickness as specified in paragraph 401-3.3, Table 2 for the approved mix design. The area to be removed and replaced shall be a minimum width of the paver and a minimum of 10 feet (3 m) long.

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

401-4.13 Compaction of asphalt mixture. After placing, the asphalt mixture shall be thoroughly and uniformly compacted by self-propelled rollers. The surface shall be compacted as soon as possible when the asphalt has attained sufficient stability so that the rolling does not cause undue displacement, cracking or shoving. The sequence of rolling operations and the type of rollers used shall be at the discretion of the Contractor. The speed of the roller shall, at all times, be sufficiently slow to avoid displacement of the hot mixture and be effective in compaction. Any surface defects and/or displacement occurring as a result of the roller, or from any other cause, shall be corrected at the Contractor's expense.

Sufficient rollers shall be furnished to handle the output of the plant. Rolling shall continue until the surface is of uniform texture, true to grade and cross-section, and the required field density is obtained. To prevent adhesion of the asphalt to the roller, the wheels shall be equipped with a scraper and kept moistened with water as necessary.

In areas not accessible to the roller, the mixture shall be thoroughly compacted with approved power tampers.

Any asphalt that becomes loose and broken, mixed with dirt, contains check-cracking, or in any way defective shall be removed and replaced with fresh hot mixture and immediately compacted to conform to the surrounding area. This work shall be done at the Contractor's expense. Skin patching shall not be allowed.

401-4.14 Joints. The formation of all joints shall be made to ensure a continuous bond between the courses and obtain the required density. All joints shall have the same texture as other sections of the course and meet the requirements for smoothness and grade.

The roller shall not pass over the unprotected end of the freshly laid asphalt except when necessary to form a transverse joint. When necessary to form a transverse joint, it shall be made by means of placing a bulkhead or by tapering the course. The tapered edge shall be cut back to its full depth and width on a straight line to expose a vertical face prior to placing the adjacent lane. In both methods, all contact surfaces shall be coated with an asphalt tack coat before placing any fresh asphalt against the joint.

Longitudinal joints which have been left exposed for more than four (4) hours; the surface temperature has cooled to less than 175°F (80°C); or are irregular, damaged, uncompacted or otherwise defective shall be cut back with a cutting wheel or pavement saw a maximum of 3 inches (75 mm) to expose a clean, sound, uniform vertical surface for the full depth of the course. All cutback material and any laitance produced from cutting joints shall be removed from the project. Asphalt tack coat in accordance with P-603 shall be applied to the clean, dry joint prior to placing any additional fresh asphalt against the joint. The cost of this work shall be considered incidental to the cost of the asphalt.

The Contractor may provide additional joint density QC by use of joint heaters at the Contractor's expense. Electrically powered infrared heating equipment should consist of one or more low-level radiant energy heaters to uniformly heat and soften the pavement joints. The heaters should be configured to uniformly heat an area up to 18 inches (0.5 m) in width and 3 inches (75 mm) in depth. Infrared equipment shall be thermostatically controlled to provide a uniform, consistent temperature increase throughout the layer being heated up to a maximum temperature range of 200 to 300°F (93 to 150°C).

Propane powered infrared heating equipment shall be attached to the paving machine and the output of infrared energy shall be in the one to six-micron range. Converters shall be arranged end to end directly over the joint to be heated in sufficient numbers to continuously produce, when in operation, a minimum of 240,000 BTU per hour. The joint heater shall be positioned not more than one inch (25 mm) above the pavement to be heated and in front of the paver screed and shall be fully adjustable. Heaters will be required to be in operation at all times.

The heaters shall be operated so they do not produce excessive heat when the units pass over new or previously paved material.

- **401-4.15 Saw-cut grooving.** Saw-cut grooving is not required.
- **401-4.16 Diamond grinding.** Diamond grinding shall be accomplished by sawing with saw blades impregnated with industrial diamond abrasive. Diamond grinding shall be performed with a machine designed specifically for diamond grinding capable of cutting a path at least 3 feet (0.9 m) wide. The saw blades shall be 1/8-inch (3-mm) wide with a sufficient number of blades to create grooves between 0.090 and 0.130 inches (2 and 3.5 mm) wide; and peaks and ridges approximately 1/32 inch (1 mm) higher than the bottom of the grinding cut. The actual number of blades will be determined by the Contractor and depend on the hardness of the aggregate. Equipment or grinding procedures that cause ravels, aggregate fractures, spalls or disturbance to the pavement will not be permitted. Contractor shall demonstrate to the RPR that the grinding equipment will produce satisfactory results prior to making corrections to surfaces. Grinding will be tapered in all directions to provide smooth transitions to areas not requiring grinding. The slurry resulting from the grinding operation shall be continuously removed and the pavement left in a clean condition. The Contractor shall apply a surface treatment per P-608 to all areas that have been subject to grinding.
- **401-4.17 Nighttime paving requirements.** The Contractor shall provide adequate lighting during any nighttime construction. A lighting plan shall be submitted by the Contractor and approved by the RPR prior to the start of any nighttime work. All work shall be in accordance with the approved CSPP and lighting plan.

CONTRACTOR QUALITY CONTROL (CQC)

- **401-5.1 General.** The Contractor shall develop a Contractor Quality Control Program (CQCP) in accordance with Item C-100. No partial payment will be made for materials without an approved CQCP.
- **401-5.2 Contractor quality control (QC) facilities.** The Contractor shall provide or contract for testing facilities in accordance with Item C-100. The RPR shall be permitted unrestricted access to inspect the Contractor's QC facilities and witness QC activities. The RPR will advise the Contractor in writing of any noted deficiencies concerning the QC facility, equipment, supplies, or testing personnel and procedures. When the deficiencies are serious enough to be adversely affecting the test results, the incorporation of the materials into the work shall be suspended immediately and will not be permitted to resume until the deficiencies are satisfactorily corrected.
- **401-5.3 Contractor QC testing.** The Contractor shall perform all QC tests necessary to control the production and construction processes applicable to these specifications and as set forth in the approved CQCP. The testing program shall include, but not necessarily be limited to, tests for the control of asphalt content, aggregate gradation, temperatures, aggregate moisture, field compaction, and surface smoothness. A QC Testing Plan shall be developed as part of the CQCP.
- **a. Asphalt content.** A minimum of two tests shall be performed per day in accordance with ASTM D6307 or ASTM D2172 for determination of asphalt content. When using ASTM D6307, the correction factor shall be determined as part of the first test performed at the beginning of plant production; and as part of every tenth test performed thereafter. The asphalt content for the day will be determined by averaging the test results.
- **b. Gradation.** Aggregate gradations shall be determined a minimum of twice per day from mechanical analysis of extracted aggregate in accordance with ASTM D5444, ASTM C136, and ASTM C117.
- **c. Moisture content of aggregate.** The moisture content of aggregate used for production shall be determined a minimum of once per day in accordance with ASTM C566.

- **d. Moisture content of asphalt.** The moisture content shall be determined once per day in accordance with AASHTO T329 or ASTM D1461.
- **e. Temperatures.** Temperatures shall be checked, at least four times per day, at necessary locations to determine the temperatures of the dryer, the asphalt binder in the storage tank, the asphalt at the plant, and the asphalt at the job site.
- **f. In-place density monitoring.** The Contractor shall conduct any necessary testing to ensure that the specified density is being achieved. A nuclear gauge may be used to monitor the pavement density in accordance with ASTM D2950.

g. Smoothness for Contractor Quality Control.

The Contractor shall perform smoothness testing in transverse and longitudinal directions daily to verify that the construction processes are producing pavement with variances less than ¼ inch in 12 feet, identifying areas that may pond water which could lead to hydroplaning of aircraft. If the smoothness criteria is not met, appropriate changes and corrections to the construction process shall be made by the Contractor before construction continues.

The Contractor may use a 12-foot (3.7 m) "straightedge, a rolling inclinometer meeting the requirements of ASTM E2133 or rolling external reference device that can simulate a 12-foot (3.7m) straightedge approved by the RPR. Straight-edge testing shall start with one-half the length of the straightedge at the edge of pavement section being tested and then moved ahead one-half the length of the straightedge for each successive measurement. Testing shall be continuous across all joints. The surface irregularity shall be determined by placing the freestanding (unleveled) straightedge on the pavement surface and allowing it to rest upon the two highest spots covered by its length, and measuring the maximum gap between the straightedge and the pavement surface in the area between the two high points. If the rolling inclinometer or external reference device is used, the data may be evaluated using the FAA profile program, ProFAA, using the 12-foot straightedge simulation function.

Smoothness readings shall not be made across grade changes or cross slope transitions. The transition between new and existing pavement shall be evaluated separately for conformance with the plans.

- (1) **Transverse measurements.** Transverse measurements shall be taken for each day's production placed. Transverse measurements shall be taken perpendicular to the pavement centerline each 50 feet (15 m) or more often as determined by the RPR. The joint between lanes shall be tested separately to facilitate smoothness between lanes.
- (2) Longitudinal measurements. Longitudinal measurements shall be taken for each day's production placed. Longitudinal tests shall be parallel to the centerline of paving; at the center of paving lanes when widths of paving lanes are less than 20 feet (6 m); and at the third points of paving lanes when widths of paving lanes are 20 ft (6 m) or greater.

Deviations on the final surface course in either the transverse or longitudinal direction that will trap water greater than 1/4 inch (6 mm) shall be corrected with diamond grinding per paragraph 401-4.16 or by removing and replacing the surface course to full depth. Grinding shall be tapered in all directions to provide smooth transitions to areas not requiring grinding. All areas in which diamond grinding has been performed shall be subject to the final pavement thickness tolerances specified in paragraph 401-6.1d(3). Areas that have been ground shall be sealed with a surface treatment in accordance with Item P-608. To avoid the surface treatment creating any conflict with runway or taxiway markings, it may be necessary to seal a larger area.

Control charts shall be kept to show area of each day's placement and the percentage of corrective grinding required. Corrections to production and placement shall be initiated when corrective grinding is required. If the Contractor's machines and/or methods produce significant areas that need corrective actions in excess of 10 percent of a day's production, production shall be stopped until corrective measures are implemented by the Contractor.

h. Grade. Grade shall be evaluated daily to allow adjustments to paving operations when grade measurements do not meet specifications. As a minimum, grade shall be evaluated prior to and after the placement of the first lift and after placement of the surface lift.

Measurements will be taken at appropriate gradelines (as a minimum at center and edges of paving lane) and longitudinal spacing as shown on cross-sections and plans. The final surface of the pavement will not vary from the gradeline elevations and cross-sections shown on the plans by more than 1/2 inch (12 mm) vertically and 0.1 feet (30 mm) laterally. The documentation will be provided by the Contractor to the RPR by the end of the following working day.

Areas with humps or depressions that exceed grade or smoothness criteria and that retain water on the surface must be ground off provided the course thickness after grinding is not more than 1/2 inch (12 mm) less than the thickness specified on the plans. Grinding shall be in accordance with paragraph 401-4.16.

The Contractor shall repair low areas or areas that cannot be corrected by grinding by removal of deficient areas to the depth of the final course plus ½ inch and replacing with new material. Skin patching is not allowed.

- **401-5.4 Sampling.** When directed by the RPR, the Contractor shall sample and test any material that appears inconsistent with similar material being sampled, unless such material is voluntarily removed and replaced or deficiencies corrected by the Contractor. All sampling shall be in accordance with standard procedures specified.
- **401-5.5 Control charts.** The Contractor shall maintain linear control charts for both individual measurements and range (i.e. difference between highest and lowest measurements) for aggregate gradation, asphalt content, and VMA. The VMA for each day will be calculated and monitored by the QC laboratory.

Control charts shall be posted in a location satisfactory to the RPR and kept current. As a minimum, the control charts shall identify the project number, the contract item number, the test number, each test parameter, the Action and Suspension Limits applicable to each test parameter, and the Contractor's test results. The Contractor shall use the control charts as part of a process control system for identifying potential problems and assignable causes before they occur. If the Contractor's projected data during production indicates a problem and the Contractor is not taking satisfactory corrective action, the RPR may suspend production or acceptance of the material.

a. Individual measurements. Control charts for individual measurements shall be established to maintain process control within tolerance for aggregate gradation, asphalt content, and VMA. The control charts shall use the job mix formula target values as indicators of central tendency for the following test parameters with associated Action and Suspension Limits:

Control Chart Limits for Individual Measurements

Sieve	Action Limit	Suspension Limit
3/4 inch (19.0 mm)	±6%	±9%
1/2 inch (12.5 mm)	±6%	±9%
3/8 inch (9.5 mm)	±6%	±9%
No. 4 (4.75 mm)	±6%	±9%
No. 16 (1.18 mm)	±5%	±7.5%
No. 50 (300 μm)	±3%	±4.5%
No. 200 (75 μm)	±2%	±3%
Asphalt Content	±0.45%	±0.70%
Minimum VMA	-0.5%	-1.0%

b. Range. Control charts shall be established to control gradation process variability. The range shall be plotted as the difference between the two test results for each control parameter. The Suspension Limits specified below are based on a sample size of n=2. Should the Contractor elect to perform more than two tests per lot, the Suspension Limits shall be adjusted by multiplying the Suspension Limit by 1.18 for n=3 and by 1.27 for n=4.

Control Chart Limits Based on Range

Sieve	Suspension Limit
1/2 inch (12.5 mm)	11%
3/8 inch (9.5 mm)	11%
No. 4 (4.75 mm)	11%
No. 16 (1.18 mm)	9%
No. 50 (300 μm)	6%
No. 200 (75 μm)	3.5%
Asphalt Content	0.8%

- **c. Corrective Action.** The CQCP shall indicate that appropriate action shall be taken when the process is believed to be out of tolerance. The Plan shall contain rules to gauge when a process is out of control and detail what action will be taken to bring the process into control. As a minimum, a process shall be deemed out of control and production stopped and corrective action taken, if:
 - (1) One point falls outside the Suspension Limit line for individual measurements or range; or
 - (2) Two points in a row fall outside the Action Limit line for individual measurements.
- **401-5.6 QC reports.** The Contractor shall maintain records and shall submit reports of QC activities daily, in accordance with Item C-100.

MATERIAL ACCEPTANCE

401-6.1 Acceptance sampling and testing. Unless otherwise specified, all acceptance sampling and testing necessary to determine conformance with the requirements specified in this section will be performed by

the RPR at no cost to the Contractor except that coring as required in this section shall be completed and paid for by the Contractor.

- **a. Quality assurance (QA) testing laboratory**. The QA testing laboratory performing these acceptance tests will be accredited in accordance with ASTM D3666. The QA laboratory accreditation will be current and listed on the accrediting authority's website. All test methods required for acceptance sampling and testing will be listed on the lab accreditation.
- **b.** Lot size. A standard lot will be equal to one day's production divided into approximately equal sublots of between 400 to 600 tons. When only one or two sublots are produced in a day's production, the sublots will be combined with the production lot from the previous or next day.

Where more than one plant is simultaneously producing asphalt for the job, the lot sizes will apply separately for each plant.

- **c. Asphalt air voids.** Plant-produced asphalt will be tested for air voids on a sublot basis.
- (1) **Sampling.** Material from each sublot shall be sampled in accordance with ASTM D3665. Samples shall be taken from material deposited into trucks at the plant or at the job site in accordance with ASTM D979. The sample of asphalt may be put in a covered metal tin and placed in an oven for not less than 30 minutes nor more than 60 minutes to maintain the material at or above the compaction temperature as specified in the JMF.
- (2) **Testing.** Air voids will be determined for each sublot in accordance with ASTM D3203 for a set of compacted specimens prepared in accordance with ASTM D6926.
- **d. In-place asphalt mat and joint density.** Each sublot will be tested for in-place mat and joint density as a percentage of the theoretical maximum density (TMD).
- (1) Sampling. The RPR will cut minimum 5 inch (125 mm) diameter samples in accordance with ASTM D5361. The Contractor shall furnish all tools, labor, and materials for cleaning, and filling the cored pavement. Laitance produced by the coring operation shall be removed immediately after coring, and core holes shall be filled within one day after sampling in a manner acceptable to the RPR.
- (2) **Bond.** Each lift of asphalt shall be bonded to the underlying layer. If cores reveal that the surface is not bonded, additional cores shall be taken as directed by the RPR to determine the extent of unbonded areas. Unbonded areas shall be removed by milling and replaced at no additional cost as directed by the RPR.
- (3) Thickness. Thickness of each lift of surface course will be evaluated by the RPR for compliance to the requirements shown on the plans after any necessary corrections for grade. Measurements of thickness will be made using the cores extracted for each sublot for density measurement. The maximum allowable deficiency at any point will not be more than 1/4 inch (6 mm) less than the thickness indicated for the lift. Average thickness of lift, or combined lifts, will not be less than the indicated thickness. Where the thickness tolerances are not met, the lot or sublot shall be corrected by the Contractor at his expense by removing the deficient area and replacing with new pavement. The Contractor, at his expense, may take additional cores as approved by the RPR to circumscribe the deficient area.
- (4) Mat density. One core shall be taken from each sublot. Core locations will be determined by the RPR in accordance with ASTM D3665. Cores for mat density shall not be taken closer than one foot (30 cm) from a transverse or longitudinal joint. The bulk specific gravity of each cored sample will be determined in accordance with ASTM D2726. The percent compaction (density) of each sample will be determined by dividing the bulk specific gravity of each sublot sample by the TMD for that sublot.
- (5) **Joint density**. One core centered over the longitudinal joint shall be taken for each sublot that has a longitudinal joint. Core locations will be determined by the RPR in accordance with ASTM D3665. The bulk specific gravity of each core sample will be determined in accordance with ASTM D2726. The percent compaction (density) of each sample will be determined by dividing the bulk specific gravity of

each joint density sample by the average TMD for the lot. The TMD used to determine the joint density at joints formed between lots will be the lower of the average TMD values from the adjacent lots.

401-6.2 Acceptance criteria.

- **a. General.** Acceptance will be based on the implementation of the Contractor Quality Control Program (CQCP) and the following characteristics of the asphalt and completed pavements: air voids, mat density, joint density, grade and Profilograph roughness.
- **b.** Air Voids and Mat density. Acceptance of each lot of plant produced material for mat density and air voids will be based on the percentage of material within specification limits (PWL). If the PWL of the lot equals or exceeds 90%, the lot will be acceptable. Acceptance and payment will be determined in accordance with paragraph 401-8.1.
- **c. Joint density.** Acceptance of each lot of plant produced asphalt for joint density will be based on the PWL. If the PWL of the lot is equal to or exceeds 90%, the lot will be considered acceptable. If the PWL is less than 90%, the Contractor shall evaluate the reason and act accordingly. If the PWL is less than 80%, the Contractor shall cease operations and until the reason for poor compaction has been determined. If the PWL is less than 71%, the pay factor for the lot used to complete the joint will be reduced by five (5) percentage points. This lot pay factor reduction will be incorporated and evaluated in accordance with paragraph 401-8.1.
- **d. Grade.** The final finished surface of the pavement shall be surveyed to verify that the grade elevations and cross-sections shown on the plans do not deviate more than 1/2 inch (12 mm) vertically or 0.1 feet laterally.

Cross-sections of the pavement shall be taken at a minimum 50-foot longitudinal spacing and at all longitudinal grade breaks. Minimum cross-section grade points shall include grade at centerline, and edge of taxiway pavement.

The survey and documentation shall be stamped and signed by a licensed surveyor. Payment for sublots that do not meet grade for over 25% of the sublot shall not be more than 95%.

e. Profilograph roughness for QA Acceptance. The final profilograph shall be the full length of the project to facilitate testing of roughness between lots. The Contractor, in the presence of the RPR shall perform a profilograph roughness test on the completed project with a profilograph meeting the requirements of ASTM E1274 or a Class I inertial profiler meeting ASTM E950. Data and results shall be provided within 48 hrs of profilograph roughness tests.

The pavement shall have an average profile index less than 15 inches per mile per 1/10 mile. The equipment shall utilize electronic recording and automatic computerized reduction of data to indicate "must grind" bumps and the Profile Index for the pavement using a 0.2-inch (5 mm) blanking band. The bump template must span one inch (25 mm) with an offset of 0.4 inches (10 mm). The profilograph must be calibrated prior to use and operated by a factory or State DOT approved, trained operator. Profilograms shall be recorded on a longitudinal scale of one inch (25 mm) equals 25 feet (7.5 m) and a vertical scale of one inch (25 mm) equals one inch (25 mm). Profilograph shall be performed one foot right and left of project centerline and 15 feet (4.5 m) right and left of project centerline. Any areas that indicate "must grind" shall be corrected with diamond grinding per paragraph 401-4.16 or by removing and replacing full depth of surface course, as directed by the RPR. Where corrections are necessary, a second profilograph run shall be performed to verify that the corrections produced an average profile index of 15 inches per mile per 1/10 mile or less.

401-6.3 Percentage of material within specification limits (PWL). The PWL will be determined in accordance with procedures specified in Item C-110. The specification tolerance limits (L) for lower and (U) for upper are contained in Table 5.

Test Property		Specification nce Limits
	L	U
Air Voids Total Mix (%)	2.0	5.0
Surface Course Mat Density (%)	92.8	-
Base Course Mat Density (%)	92.0	-
Joint density (%)	90.5	

Table 5. Acceptance Limits for Air Voids and Density

a. Outliers. All individual tests for mat density and air voids will be checked for outliers (test criterion) in accordance with ASTM E178, at a significance level of 5%. Outliers will be discarded, and the PWL will be determined using the remaining test values. The criteria in Table 5 is based on production processes which have a variability with the following standard deviations: Surface Course Mat Density (%), 1.30; Base Course Mat Density (%), 1.55; Joint Density (%), 1.55.

The Contractor should note that (1) 90 PWL is achieved when consistently producing a surface course with an average mat density of at least 94.5% with 1.30% or less variability, (2) 90 PWL is achieved when consistently producing a base course with an average mat density of at least 94.0% with 1.55% or less variability, and (3) 90 PWL is achieved when consistently producing joints with an average joint density of at least 92.5% with 1.55% or less variability.

401-6.4 Resampling pavement for mat density.

- **a. General.** Resampling of a lot of pavement will only be allowed for mat density, and then, only if the Contractor requests same, in writing, within 48 hours after receiving the written test results from the RPR. A retest will consist of all the sampling and testing procedures contained in paragraphs 401-6.1d and 401-6.2b. Only one resampling per lot will be permitted.
- (1) A redefined PWL will be calculated for the resampled lot. The number of tests used to calculate the redefined PWL will include the initial tests made for that lot plus the retests.
 - (2) The cost for resampling and retesting shall be borne by the Contractor.
- **b. Payment for resampled lots.** The redefined PWL for a resampled lot will be used to calculate the payment for that lot in accordance with Table 6.
 - **c. Outliers.** Check for outliers in accordance with ASTM E178, at a significance level of 5%.

METHOD OF MEASUREMENT

401-7.1 Measurement. Asphalt shall be measured by the number of tons of asphalt used in the accepted work. Batch weights or truck scale weights will be used to determine the basis for the tonnage.

BASIS OF PAYMENT

401-8.1 Payment. Payment for a lot of asphalt meeting all acceptance criteria as specified in paragraph 401-6.2 shall be made based on results of tests for mat density and air voids. Payment for acceptable lots shall be adjusted according to paragraph 401-8.1c for mat density and air voids; and paragraph 401-6.2c for joint density, subject to the limitation that:

- **a.** The total project payment for plant mix asphalt pavement shall not exceed 100 percent of the product of the contract unit price and the total number of tons (kg) of asphalt used in the accepted work.
- **b.** The price shall be compensation for furnishing all materials, for all preparation, mixing, and placing of these materials, and for all labor, equipment, tools, and incidentals necessary to complete the item.
- **c. Basis of adjusted payment.** The pay factor for each individual lot shall be calculated in accordance with Table 6. A pay factor shall be calculated for both mat density and air voids. The lot pay factor shall be the higher of the two values when calculations for both mat density and air voids are 100% or higher. The lot pay factor shall be the product of the two values when only one of the calculations for either mat density or air voids is 100% or higher. The lot pay factor shall be the lower of the two values when calculations for both mat density and air voids are less than 100%. If PWL for joint density is less than 71% then the lot pay factor shall be reduced by 5% but be no higher than 95%.

For each lot accepted, the adjusted contract unit price shall be the product of the lot pay factor for the lot and the contract unit price. Payment shall be subject to the total project payment limitation specified in paragraph 401-8.1a. Payment in excess of 100% for accepted lots of asphalt shall be used to offset payment for accepted lots of asphalt payment that achieve a lot pay factor less than 100%.

Payment for sublots which do not meet grade in accordance with paragraph 401-6.2d after correction for over 25% of the sublot shall be reduced by 5%.

Percentage of material within specification limits (PWL)	Lot pay factor (percent of contract unit price)
96 – 100	106
90 – 95	PWL + 10
75 – 89	0.5 PWL + 55
55 – 74	1.4 PWL – 12
Below 55	Reject ²

Table 6. Price adjustment schedule¹

d. Profilograph Roughness. The Contractor will receive full payment when the profilograph average profile index is in accordance with paragraph 401-6.2e. When the final average profile index for the entire length of payment does not exceed 15 inches per mile per 1/10 mile, payment will be made at the contract unit price for the completed payment.

401-8.1 Payment.

Payment will be made under:

Item P-401-8.1 Asphalt Mix Pavement - Overlay - per ton

Although it is theoretically possible to achieve a pay factor of 106% for each lot, actual payment above 100% shall be subject to the total project payment limitation specified in paragraph 401-8.1a.

² The lot shall be removed and replaced. However, the RPR may decide to allow the rejected lot to remain. In that case, if the RPR and Contractor agree in writing that the lot shall not be removed, it shall be paid for at 50% of the contract unit price and the total project payment shall be reduced by the amount withheld for the rejected lot.

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM C29	Standard Test Method for Bulk Density ("Unit Weight") and Voids in Aggregate
ASTM C88	Standard Test Method for Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM C117	Standard Test Method for Materials Finer than 75-µm (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C127	Standard Test Method for Density, Relative Density (Specific Gravity) and Absorption of Coarse Aggregate
ASTM C131	Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C136	Standard Test Method for Sieve or Screen Analysis of Fine and Coarse Aggregates
ASTM C142	Standard Test Method for Clay Lumps and Friable Particles in Aggregates
ASTM C566	Standard Test Method for Total Evaporable Moisture Content of Aggregate by Drying
ASTM D75	Standard Practice for Sampling Aggregates
ASTM D242	Standard Specification for Mineral Filler for Bituminous Paving Mixtures
ASTM D946	Standard Specification for Penetration-Graded Asphalt Cement for Use in Pavement Construction
ASTM D979	Standard Practice for Sampling Asphalt Paving Mixtures
ASTM D1073	Standard Specification for Fine Aggregate for Asphalt Paving Mixtures
ASTM D1188	Standard Test Method for Bulk Specific Gravity and Density of Compacted Bituminous Mixtures Using Coated Samples
ASTM D2172	Standard Test Method for Quantitative Extraction of Bitumen from Asphalt Paving Mixtures
ASTM D1461	Standard Test Method for Moisture or Volatile Distillates in Asphalt Paving Mixtures
ASTM D2041	Standard Test Method for Theoretical Maximum Specific Gravity and Density of Bituminous Paving Mixtures
ASTM D2419	Standard Test Method for Sand Equivalent Value of Soils and Fine Aggregate
ASTM D2489	Standard Practice for Estimating Degree of Particle Coating of Bituminous-Aggregate Mixtures
ASTM D2726	Standard Test Method for Bulk Specific Gravity and Density of Non-Absorptive Compacted Bituminous Mixtures

ASTM D2950	Standard Test Method for Density of Bituminous Concrete in Place by Nuclear Methods
ASTM D3203	Standard Test Method for Percent Air Voids in Compacted Dense and Open Bituminous Paving Mixtures
ASTM D3381	Standard Specification for Viscosity-Graded Asphalt Cement for Use in Pavement Construction
ASTM D3665	Standard Practice for Random Sampling of Construction Materials
ASTM D3666	Standard Specification for Minimum Requirements for Agencies Testing and Inspecting Road and Paving Materials
ASTM D4318	Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM D4552	Standard Practice for Classifying Hot-Mix Recycling Agents
ASTM D4791	Standard Test Method for Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate
ASTM D4867	Standard Test Method for Effect of Moisture on Asphalt Concrete Paving Mixtures
ASTM D5361	Standard Practice for Sampling Compacted Asphalt Mixtures for Laboratory Testing
ASTM D5444	Standard Test Method for Mechanical Size Analysis of Extracted Aggregate
ASTM D5821	Standard Test Method for Determining the Percentage of Fractured Particles in Coarse Aggregate
ASTM D6084	Standard Test Method for Elastic Recovery of Bituminous Materials by Ductilometer
ASTM D6307	Standard Test Method for Asphalt Content of Hot Mix Asphalt by Ignition Method
ASTM D6373	Standard Specification for Performance Graded Asphalt Binder
ASTM D6752	Standard Test Method for Bulk Specific Gravity and Density of Compacted Bituminous Mixtures Using Automatic Vacuum Sealing Method
ASTM D6925	Standard Test Method for Preparation and Determination of the Relative Density of Hot Mix Asphalt (HMA) Specimens by Means of the SuperPave Gyratory Compactor.
ASTM D6926	Standard Practice for Preparation of Bituminous Specimens Using Marshall Apparatus
ASTM D6927	Standard Test Method for Marshall Stability and Flow of Bituminous Mixtures
ASTM D6995	Standard Test Method for Determining Field VMA based on the Maximum Specific Gravity of the Mix (Gmm)
ASTM E11	Standard Specification for Woven Wire Test Sieve Cloth and Test Sieves
ASTM E178	Standard Practice for Dealing with Outlying Observations

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

ASTM E1274 Standard Test Method for Measuring Pavement Roughness Using a

Profilograph

ASTM E950 Standard Test Method for Measuring the Longitudinal Profile of Traveled

Surfaces with an Accelerometer Established Inertial Profiling Reference

ASTM E2133 Standard Test Method for Using a Rolling Inclinometer to Measure

Longitudinal and Transverse Profiles of a Traveled Surface

American Association of State Highway and Transportation Officials (AASHTO)

AASHTO M156 Standard Specification for Requirements for Mixing Plants for Hot-

Mixed, Hot-Laid Bituminous Paving Mixtures.

AASHTO T329 Standard Method of Test for Moisture Content of Hot Mix Asphalt (HMA)

by Oven Method

AASHTO T324 Standard Method of Test for Hamburg Wheel-Track Testing of

Compacted Asphalt Mixtures

AASHTO T 340 Standard Method of Test for Determining the Rutting Susceptibility of Hot

Mix Asphalt (APA) Using the Asphalt Pavement Analyzer (APA)

Asphalt Institute (AI)

Asphalt Institute Handbook MS-26, Asphalt Binder

Asphalt Institute MS-2 Mix Design Manual, 7th Edition

AI State Binder Specification Database

Federal Highway Administration (FHWA)

Long Term Pavement Performance Binder Program

Advisory Circulars (AC)

AC 150/5320-6 Airport Pavement Design and Evaluation

FAA Orders

5300.1 Modifications to Agency Airport Design, Construction, and Equipment

Standards

Software

FAARFIELD

END OF ITEM P-401

ITEM P-603 EMULSIFIED ASPHALT TACK COAT

DESCRIPTION

603-1.1 This item shall consist of preparing and treating an asphalt or concrete surface with asphalt material in accordance with these specifications and in reasonably close conformity to the lines shown on the plans.

MATERIALS

603-2.1 ASPHALT MATERIALS. The asphalt material shall be an emulsified asphalt as specified in ASTM D3628 as an asphalt application for tack coat appropriate to local conditions. The emulsified asphalt shall not be diluted. The Contractor shall provide a copy of the manufacturer's Certificate of Analysis (COA) for the asphalt material to the Resident Project Representative (RPR) before the asphalt material is applied for review and acceptance. The furnishing of COA for the asphalt material shall not be interpreted as a basis for final acceptance. The manufacturer's COA may be subject to verification by testing the material delivered for use on the project.

CONSTRUCTION METHODS

603-3.1 WEATHER LIMITATIONS. The tack coat shall be applied only when the existing surface is dry and the atmospheric temperature is 50°F or above; the temperature has not been below 35°F for the 12 hours prior to application; and when the weather is not foggy or rainy. The temperature requirements may be waived when directed by the RPR.

603-3.2 EQUIPMENT. The Contractor shall provide equipment for heating and applying the emulsified asphalt material. The emulsion shall be applied with a manufacturer-approved computer rate-controlled asphalt distributor. The equipment shall be in good working order and contain no contaminants or diluents in the tank. Spray bar tips must be clean, free of burrs, and of a size to maintain an even distribution of the emulsion. Any type of tip or pressure source is suitable that will maintain predetermined flow rates and constant pressure during the application process with application speeds under eight (8) miles per hour (13 km per hour) or seven (700) feet per minute (213 m per minute).

The equipment will be tested under pressure for leaks and to ensure proper set-up before use to verify truck set-up (via a test-shot area), including but not limited to, nozzle tip size appropriate for application, spray-bar height and pressure and pump speed, evidence of triple-overlap spray pattern, lack of leaks, and any other factors relevant to ensure the truck is in good working order before use.

The distributor truck shall be equipped with a minimum 12-foot (3.7-m) spreader spray bar with individual nozzle control with computer-controlled application rates. The distributor truck shall have an easily accessible thermometer that constantly monitors the temperature of the emulsion, and have an operable mechanical tank gauge that can be used to cross-check the computer accuracy. If the distributor is not equipped with an operable quick shutoff valve, the prime operations shall be started and stopped on building paper.

The distributor truck shall be equipped to effectively heat and mix the material to the required temperature prior to application as required. Heating and mixing shall be done in accordance with the manufacturer's recommendations. Do not overheat or over mix the material.

The distributor shall be equipped with a hand sprayer.

Asphalt distributors must be calibrated annually in accordance with ASTM D2995. The Contractor must furnish a current calibration certification for the asphalt distributor truck from any State or other agency as approved by the RPR.

A power broom and/or power blower suitable for cleaning the surfaces to which the asphalt tack coat is to be applied shall be provided.

603-3.3 APPLICATION OF EMULSIFIED ASPHALT MATERIAL. The emulsified asphalt shall not be diluted. Immediately before applying the emulsified asphalt tack coat, the full width of surface to be treated shall be swept with a power broom and/or power blower to remove all loose dirt and other objectionable material.

The emulsified asphalt material shall be uniformly applied with an asphalt distributor at the rates appropriate for the conditions and surface specified in the table below. The type of asphalt material and application rate shall be approved by the RPR prior to application.

Emulsified Asphalt

Surface Type	Residual Rate, gal/SY	Emulsion Application Bar Rate, gal/SY
New asphalt	0.02-0.05	0.03-0.07
Existing asphalt	0.04-0.07	0.06-0.11
Milled Surface	0.04-0.08	.0.06-0.12
Concrete	0.03-0.05	0.05-0.08

After application of the tack coat, the surface shall be allowed to cure without being disturbed for the period of time necessary to permit drying and setting of the tack coat. This period shall be determined by the RPR. The Contractor shall protect the tack coat and maintain the surface until the next course has been placed. When the tack coat has been disturbed by the Contractor, tack coat shall be reapplied at the Contractor's expense.

603-3.4 Freight and waybills The Contractor shall submit waybills and delivery tickets, during progress of the work. Before the final statement is allowed, file with the RPR certified waybills and certified delivery tickets for all emulsified asphalt materials used in the construction of the pavement covered by the contract. Do not remove emulsified asphalt material from storage until the initial outage and temperature measurements have been taken. The delivery or storage units will not be released until the final outage has been taken.

METHOD OF MEASUREMENT

603-4.1 The emulsified asphalt material for tack coat shall be measured by the gallon. Volume shall be corrected to the volume at 60°F in accordance with ASTM D1250. The emulsified asphalt material paid for will be the measured quantities used in the accepted work, provided that the measured quantities are not 10% over the specified application rate. Any amount of emulsified asphalt material more than 10% over the specified application rate for each application will be deducted from the measured quantities, except for irregular areas where hand spraying of the emulsified asphalt material is necessary. Water added to emulsified asphalt will not be measured for payment.

BASIS OF PAYMENT

603.5-1 Payment shall be made at the contract unit price per gallon of emulsified asphalt material. This price shall be full compensation for furnishing all materials, for all preparation, delivery, and application of these materials, and for all labor, equipment, tools, and incidentals necessary to complete the item.

Payment will be made under:

Item P-603-5.1 Emulsified Asphalt Tack Coat - per gallon

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM D1250	Standard Guide for Use of the Petroleum Measurement Tables
ASTM D2995	Standard Practice for Estimating Application Rate and Residual Application Rate of Bituminous Distributors
ASTM D3628	Standard Practice for Selection and Use of Emulsified Asphalts

END ITEM P-603

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

THIS PAGE INTENTIONALLY LEFT BLANK

ITEM P-610 CONCRETE FOR MISCELLANEOUS STRUCTURES

DESCRIPTION

610-1.1 This item shall consist of concrete and reinforcement, as shown on the plans, prepared and constructed in accordance with these specifications. This specification shall be used for all concrete other than airfield pavement which are cast-in-place.

MATERIALS

610-2.1 General. Only approved materials, conforming to the requirements of these specifications, shall be used in the work. Materials may be subject to inspection and tests at any time during their preparation or use. The source of all materials shall be approved by the Resident Project Representative (RPR) before delivery or use in the work. Representative preliminary samples of the materials shall be submitted by the Contractor, when required, for examination and test. Materials shall be stored and handled to ensure preservation of their quality and fitness for use and shall be located to facilitate prompt inspection. All equipment for handling and transporting materials and concrete must be clean before any material or concrete is placed in them.

The use of pit-run aggregates shall not be permitted unless the pit-run aggregate has been screened and washed, and all fine and coarse aggregates stored separately and kept clean. The mixing of different aggregates from different sources in one storage stockpile or alternating batches of different aggregates shall not be permitted.

a. Reactivity. Fine aggregate and coarse aggregates to be used in all concrete shall have been tested separately within six months of the project in accordance with ASTM C1260. Test results shall be submitted to the RPR. The aggregate shall be considered innocuous if the expansion of test specimens, tested in accordance with ASTM C1260, does not exceed 0.08% at 14 days (16 days from casting). If the expansion either or both test specimen is greater than 0.08% at 14 days, but less than 0.20%, a minimum of 25% of Type F fly ash, or between 40% and 55% of slag cement shall be used in the concrete mix.

If the expansion is greater than 0.20%, the aggregates shall not be used, and test results for other aggregates must be submitted for evaluation; or aggregates that meet P-501 reactivity test requirements may be utilized.

610-2.2 Coarse aggregate. The coarse aggregate for concrete shall meet the requirements of ASTM C33 and the requirements of Table 4, Class Designation 5S; and the grading requirements shown below, as required for the project.

Coarse Aggregate Grading Requirements

Maximum Aggregate Size	ASTM C33, Table 3 Grading Requirements (Size No.)
1 1/2 inch (37.5 mm)	467 or 4 and 67
1 inch (25 mm)	57
³ / ₄ inch (19 mm)	67
½ inch (12.5 mm)	7

610-2.2.1 Coarse Aggregate susceptibility to durability (D) cracking.

Coarse aggregate may only be accepted from sources that have a 20-year service history for the same gradation to be supplied with no history of D-Cracking. Aggregates that do not have a 20-year record of service free from major repairs (less than 5% of slabs replaced) in similar conditions without D-cracking shall not be used unless the material currently being produced has a durability factor greater than or equal to 95 per ASTM C666. The Contractor shall submit a current certification and test results to verify the aggregate acceptability. Test results will only be accepted from a State Department of Transportation (DOT) materials laboratory or an accredited laboratory. Certification and test results which are not dated, or which are over one (1) year old or which are for different gradations will not be accepted.

Crushed granite, calcite cemented sandstone, quartzite, basalt, diabase, rhyolite or trap rock are considered to meet the D-cracking test requirements but must meet all other quality tests specified in Item P-501.

610-2.3 Fine aggregate. The fine aggregate for concrete shall meet all fine aggregate requirements of ASTM C33.

610-2.4 Cement. Cement shall conform to the requirements of ASTM C 150 Type I or II.

610-2.5 Cementitious materials.

- **a. Fly ash.** Fly ash shall meet the requirements of ASTM C618, with the exception of loss of ignition, where the maximum shall be less than 6%. Fly ash shall have a Calcium Oxide (CaO) content of less than 15% and a total available alkali content less than 3% per ASTM C311. Fly ash produced in furnace operations using liming materials or soda ash (sodium carbonate) as an additive shall not be acceptable. The Contractor shall furnish the previous three most recent, consecutive ASTM C618 reports for each source of fly ash proposed in the concrete mix, and shall furnish each additional report as they become available during the project. The reports can be used for acceptance or the material may be tested independently by the RPR.
- **b. Slag cement (ground granulated blast furnace (GGBF)).** Slag cement shall conform to ASTM C989, Grade 100 or Grade 120. Slag cement shall be used only at a rate between 25% and 55% of the total cementitious material by mass.
- **610-2.6 Water.** Water used in mixing or curing shall be from potable water sources. Other sources shall be tested in accordance with ASTM C1602 prior to use.
- **610-2.7 Admixtures.** The Contractor shall submit certificates indicating that the material to be furnished meets all of the requirements indicated below. In addition, the RPR may require the Contractor to submit complete test data from an approved laboratory showing that the material to be furnished meets all of the requirements of the cited specifications. Subsequent tests may be made of samples taken by the RPR from

the supply of the material being furnished or proposed for use on the work to determine whether the admixture is uniform in quality with that approved.

- **a. Air-entraining admixtures.** Air-entraining admixtures shall meet the requirements of ASTM C260 and shall consistently entrain the air content in the specified ranges under field conditions. The air-entrainment agent and any water reducer admixture shall be compatible.
- **b. Water-reducing admixtures**. Water-reducing admixture shall meet the requirements of ASTM C494, Type A, B, or D. ASTM C494, Type F and G high range water reducing admixtures and ASTM C1017 flowable admixtures shall not be used.
- **c. Other chemical admixtures**. The use of set retarding, and set-accelerating admixtures shall be approved by the RPR. Retarding shall meet the requirements of ASTM C494, Type A, B, or D and set-accelerating shall meet the requirements of ASTM C494, Type C. Calcium chloride and admixtures containing calcium chloride shall not be used.
- **610-2.8 Premolded joint material.** Premolded joint material for expansion joints shall meet the requirements of ASTM D1751.
- **610-2.9 Joint filler.** The filler for joints shall meet the requirements of Item P-605, unless otherwise specified.
- **610-2.10 Steel reinforcement.** Reinforcing shall consist of Reinforcing Steel Bars conforming to the requirements of ASTM A615 or Welded Steel Wire Fabric conforming to the requirements of ASTM A1064.
- **610-2.11 Materials for curing concrete.** Curing materials shall conform to one of the following specifications:

Materials for Curing

Waterproof paper	ASTM C171
Clear or white Polyethylene Sheeting	ASTM C171
White-pigmented Liquid Membrane-Forming Compound, Type 2, Class B	ASTM C309

CONSTRUCTION METHODS

- **610-3.1 General.** The Contractor shall furnish all labor, materials, and services necessary for, and incidental to, the completion of all work as shown on the drawings and specified here. All machinery and equipment used by the Contractor on the work, shall be of sufficient size to meet the requirements of the work. All work shall be subject to the inspection and approval of the RPR.
- **610-3.2 Concrete Mixture.** The concrete shall develop a compressive strength of 4000 psi in 28 days as determined by test cylinders made in accordance with ASTM C31 and tested in accordance with ASTM C39. The concrete shall contain not less than 470 pounds of cementitious material per cubic yard. The water cementitious ratio shall not exceed 0.45 by weight. The air content of the concrete shall be 5% +/- 1.2% as determined by ASTM C231 and shall have a slump of not more than 4 inches as determined by ASTM C143.
- **610-3.3 Mixing.** Concrete may be mixed at the construction site, at a central point, or wholly or in part in truck mixers. The concrete shall be mixed and delivered in accordance with the requirements of ASTM C94 or ASTM C685.

The concrete shall be mixed only in quantities required for immediate use. Concrete shall not be mixed while the air temperature is below 40°F without the RPRs approval. If approval is granted for mixing under such conditions, aggregates or water, or both, shall be heated and the concrete shall be placed at a temperature not less than 50°F nor more than 100°F. The Contractor shall be held responsible for any defective work, resulting from freezing or injury in any manner during placing and curing, and shall replace such work at his expense.

Retempering of concrete by adding water or any other material is not permitted.

The rate of delivery of concrete to the job shall be sufficient to allow uninterrupted placement of the concrete.

610-3.4 Forms. Concrete shall not be placed until all the forms and reinforcements have been inspected and approved by the RPR. Forms shall be of suitable material and shall be of the type, size, shape, quality, and strength to build the structure as shown on the plans. The forms shall be true to line and grade and shall be mortar-tight and sufficiently rigid to prevent displacement and sagging between supports. The surfaces of forms shall be smooth and free from irregularities, dents, sags, and holes. The Contractor shall be responsible for their adequacy.

The internal form ties shall be arranged so no metal will show in the concrete surface or discolor the surface when exposed to weathering when the forms are removed. All forms shall be wetted with water or with a non-staining mineral oil, which shall be applied immediately before the concrete is placed. Forms shall be constructed so they can be removed without injuring the concrete or concrete surface.

- **610-3.5 Placing reinforcement.** All reinforcement shall be accurately placed, as shown on the plans, and shall be firmly held in position during concrete placement. Bars shall be fastened together at intersections. The reinforcement shall be supported by approved metal chairs. Shop drawings, lists, and bending details shall be supplied by the Contractor when required.
- **610-3.6 Embedded items.** Before placing concrete, all embedded items shall be firmly and securely fastened in place as indicated. All embedded items shall be clean and free from coating, rust, scale, oil, or any foreign matter. The concrete shall be spaded and consolidated around and against embedded items. The embedding of wood shall not be allowed.
- **610-3.7 Concrete Consistency**. The Contractor shall monitor the consistency of the concrete delivered to the project site; collect each batch ticket; check temperature; and perform slump tests on each truck at the project site in accordance with ASTM C143.
- **610-3.8 Placing concrete.** All concrete shall be placed during daylight hours, unless otherwise approved. The concrete shall not be placed until the depth and condition of foundations, the adequacy of forms and falsework, and the placing of the steel reinforcing have been approved by the RPR. Concrete shall be placed as soon as practical after mixing, but in no case later than one (1) hour after water has been added to the mix. The method and manner of placing shall avoid segregation and displacement of the reinforcement. Troughs, pipes, and chutes shall be used as an aid in placing concrete when necessary. The concrete shall not be dropped from a height of more than 5 feet. Concrete shall be deposited as nearly as practical in its final position to avoid segregation due to rehandling or flowing. Do not subject concrete to procedures which cause segregation. Concrete shall be placed on clean, damp surfaces, free from running water, or on a properly consolidated soil foundation.
- **610-3.9 Vibration.** Vibration shall follow the guidelines in American Concrete Institute (ACI) Committee 309R, Guide for Consolidation of Concrete.
- **610-3.10 Joints.** Joints shall be constructed as indicated on the plans.
- **610-3.11 Finishing.** All exposed concrete surfaces shall be true, smooth, and free from open or rough areas, depressions, or projections. All concrete horizontal plane surfaces shall be brought flush to the proper elevation with the finished top surface struck-off with a straightedge and floated.

- **610-3.12** Curing and protection. All concrete shall be properly cured in accordance with the recommendations in American Concrete Institute (ACI) 308R, Guide to External Curing of Concrete. The concrete shall be protected from damage until project acceptance.
- **610-3.13** Cold weather placing. When concrete is placed at temperatures below 40°F (4°C), follow the cold weather concreting recommendations found in ACI 306R, Cold Weather Concreting.
- **610-3.14 Hot weather placing.** When concrete is placed in hot weather greater than 85°F (30 °C), follow the hot weather concreting recommendations found in ACI 305R, Hot Weather Concreting.

QUALITY ASSURANCE (QA)

610-4.1 Quality Assurance sampling and testing. Concrete for each day's placement will be accepted on the basis of the compressive strength specified in paragraph 610-3.2. The RPR will sample the concrete in accordance with ASTM C172; test the slump in accordance with ASTM C143; test air content in accordance with ASTM C231; make and cure compressive strength specimens in accordance with ASTM C31; and test in accordance with ASTM C39. The QA testing agency will meet the requirements of ASTM C1077.

The Contractor shall provide adequate facilities for the initial curing of cylinders.

610-4.2 Defective work. Any defective work that cannot be satisfactorily repaired as determined by the RPR, shall be removed and replaced at the Contractor's expense. Defective work includes, but is not limited to, uneven dimensions, honeycombing and other voids on the surface or edges of the concrete.

METHOD OF MEASUREMENT

610-5.1 Concrete shall be considered incidental, and no separate measurement shall be made.

BASIS OF PAYMENT

610-6.1 Payment shall be made at the contract price concrete shall be considered incidental and no separate payment shall be made. This price shall be full compensation for furnishing all materials including reinforcement and embedded items and for all preparation, delivery, installation, and curing of these materials, and for all labor, equipment, tools, and incidentals necessary to complete the item.

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM A184	Standard Specification for Welded Deformed Steel Bar Mats for Concrete Reinforcement
ASTM A615	Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement
ASTM A704	Standard Specification for Welded Steel Plain Bar or Rod Mats for Concrete Reinforcement
ASTM A706	Standard Specification for Low-Alloy Steel Deformed and Plain Bars for Concrete Reinforcement

ASTM A775	Standard Specification for Epoxy-Coated Steel Reinforcing Bars
ASTM A773	Standard Specification for Epoxy-Coated Steel Wire and Welded Wire
	Reinforcement
ASTM A934	Standard Specification for Epoxy-Coated Prefabricated Steel Reinforcing Bars
ASTM A1064	Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete
ASTM C31	Standard Practice for Making and Curing Concrete Test Specimens in the Field
ASTM C33	Standard Specification for Concrete Aggregates
ASTM C39	Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens
ASTM C94	Standard Specification for Ready-Mixed Concrete
ASTM C136	Standard Test Method for Sieve or Screen Analysis of Fine and Coarse Aggregates
ASTM C114	Standard Test Methods for Chemical Analysis of Hydraulic Cement
ASTM C136	Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM C143	Standard Test Method for Slump of Hydraulic-Cement Concrete
ASTM C150	Standard Specification for Portland Cement
ASTM C171	Standard Specification for Sheet Materials for Curing Concrete
ASTM C172	Standard Practice for Sampling Freshly Mixed Concrete
ASTM C231	Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method
ASTM C260	Standard Specification for Air-Entraining Admixtures for Concrete
ASTM C309	Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete
ASTM C311	Standard Test Methods for Sampling and Testing Fly Ash or Natural Pozzolans for Use in Portland-Cement Concrete
ASTM C494	Standard Specification for Chemical Admixtures for Concrete
ASTM C618	Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use in Concrete
ASTM C666	Standard Test Method for Resistance of Concrete to Rapid Freezing and Thawing
ASTM C685	Standard Specification for Concrete Made by Volumetric Batching and Continuous Mixing
ASTM C989	Standard Specification for Slag Cement for Use in Concrete and Mortars
ASTM C1017	Standard Specification for Chemical Admixtures for Use in Producing Flowing Concrete

ASTM C1077	Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation
ASTM C1157	Standard Performance Specification for Hydraulic Cement
ASTM C1260	Standard Test Method for Potential Alkali Reactivity of Aggregates (Mortar-Bar Method)
ASTM C1365	Standard Test Method for Determination of the Proportion of Phases in Portland Cement and Portland-Cement Clinker Using X-Ray Powder Diffraction Analysis
ASTM C1602	Standard Specification for Mixing Water Used in the Production of Hydraulic Cement Concrete
ASTM D1751	Standard Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Asphalt Types)
ASTM D1752	Standard Specification for Preformed Sponge Rubber Cork and Recycled PVC Expansion Joint Fillers for Concrete Paving and Structural Construction

American Concrete Institute (ACI)

ACI 305R	Hot Weather Concreting
ACI 306R	Cold Weather Concreting
ACI 308R	Guide to External Curing of Concrete
ACI 309R	Guide for Consolidation of Concrete

END OF ITEM P-610

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

THIS PAGE INTENTIONALLY LEFT BLANK

ITEM P-615 AIRCRAFT TIE DOWNS

DESCRIPTION

615-1.1 This item shall consist of furnishing, fabricating, and transporting all equipment and materials to construct aircraft tie downs in accordance with these specifications, and details and locations shown on the plans.

MATERIALS

- **615-2.1 Tie down anchors.** Anchor rods for tie downs shall be 105 ksi, 3/4" diameter galvanized steel conforming to the requirements of ASTM F1554 and as detailed on the drawings.
- **615-2.2 Concrete.** Concrete for the tie down anchors shall conform to the requirement of Item P-610, "Structural Portland Cement Concrete" of these Specifications.

CONSTRUCTION METHODS

- **615-3.1 General.** Anchors shall be installed in apron areas after final bituminous paving is completed and no sooner than 36-hours after the pavement has been placed.
- **615-3.2 Tie down anchors.** The Contractor shall core drill a hole to the dimensions specified on the drawing. The anchor shall be installed in concrete in the cored hole. Caution shall be exercised to assure that neither the concrete nor the anchor is higher that the surrounding pavement. The anchor shall be placed 1/4" below surrounding pavement surface.

METHOD OF MEASUREMENT

615-4.1 The quantity of aircraft tie downs shall be the number of anchor rods, measured in place, completed and accepted by the Engineer and defined as per each. There will be no separate measurement and payment for coring, concrete or other miscellaneous items needed to complete the tie down anchor installation as shown on the drawings. These items shall be considered incidental to the tie down anchor item and included in the bid price for the anchor installation.

BASIS OF PAYMENT

615-5.1 Payment will be made at the contract unit price for each aircraft tie down anchor installation completed and accepted by the Engineer.

Payment will be made under:

Item P-615-5.1 Aircraft Tie Down - per each

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM F1554 Standard Specification for Anchor Bolts, Steel, 36, 55, and 105-ksi Yield

Strength

END OF ITEM P-615

ITEM P-620 RUNWAY AND TAXIWAY MARKING

DESCRIPTION

620-1.1 This item shall consist of the preparation and painting of numbers, markings, and stripes on the surface of runways, taxiways, and aprons, in accordance with these specifications and at the locations shown on the plans, or as directed by the Resident Project Representative (RPR). The terms "paint" and "marking material" as well as "painting" and "application of markings" are interchangeable throughout this specification.

MATERIALS

620-2.1 Materials acceptance. The Contractor shall furnish manufacturer's certified test reports, for materials shipped to the project. The certified test reports shall include a statement that the materials meet the specification requirements. This certification along with a copy of the paint manufacturer's surface preparation; marking materials, including adhesion, flow promoting and/or floatation additive; and application requirements must be submitted and approved by the Resident Project Representative (RPR) prior to the initial application of markings. The reports can be used for material acceptance or the RPR may perform verification testing. The reports shall not be interpreted as a basis for payment. The Contractor shall notify the RPR upon arrival of a shipment of materials to the site. All material shall arrive in sealed containers that are easily quantifiable for inspection by the RPR.

620-2.2 Marking materials.

Paint1 Glass Beads² Fed Std. 595 **Application Rate Application Rate Type** Color **Type** Number Maximum Minimum Temporary Markings Waterborne Yellow 33538 or 33655 230 ft²/gal None Permanent Markings Waterborne 115 ft²/gal Yellow 33538 or 33655 I 7 lb/gal 115 ft²/gal Black Waterborne 37038 None

Table 1. Marking Materials

- **a. Paint**. Paint shall be waterborne in accordance with the requirements of this paragraph. Paint colors shall comply with Federal Standard No. 595. Paint shall meet the requirements of Federal Specification TT-P-1952F, Type II. The non-volatile portion of the vehicle for all paint types shall be composed of a 100% acrylic polymer as determined by infrared spectral analysis.
- **b. Reflective media.** Glass beads shall meet the requirements for Federal Specification TT-B-1325D Type I, Gradation A.

Glass beads shall be treated with all compatible coupling agents recommended by the manufacturers of the paint and reflective media to ensure adhesion and embedment.

Glass beads shall not be used in black or green paint.

¹See paragraph 620-2.2a

² See paragraph 620-2.2b

CONSTRUCTION METHODS

- **620-3.1 Weather limitations.** Painting shall only be performed when the surface is dry, and the ambient temperature and the pavement surface temperature meet the manufacturer's recommendations in accordance with paragraph 620-2.1. Painting operations shall be discontinued when the ambient or surface temperatures does not meet the manufacturer's recommendations. Markings shall not be applied when the wind speed exceeds 10 mph unless windscreens are used to shroud the material guns. Markings shall not be applied when weather conditions are forecasts to not be within the manufacturers' recommendations for application and dry time.
- **620-3.2 Equipment.** Equipment shall include the apparatus necessary to properly clean the existing surface, a mechanical marking machine, a bead dispensing machine, and such auxiliary hand-painting equipment as may be necessary to satisfactorily complete the job.

The mechanical marker shall be an atomizing spray-type or airless type marking machine with automatic glass bead dispensers suitable for application of traffic paint. It shall produce an even and uniform film thickness and appearance of both paint and glass beads at the required coverage and shall apply markings of uniform cross-sections and clear-cut edges without running or spattering and without over spray. The marking equipment for both paint and beads shall be calibrated daily.

- **620-3.3 Preparation of surfaces.** Immediately before application of the paint, the surface shall be dry and free from dirt, grease, oil, laitance, or other contaminates that would reduce the bond between the paint and the pavement. Use of any chemicals or impact abrasives during surface preparation shall be approved in advance by the RPR. After the cleaning operations, sweeping, blowing, or rinsing with pressurized water shall be performed to ensure the surface is clean and free of grit or other debris left from the cleaning process.
- **a. Preparation of new pavement surfaces.** The area to be painted shall be cleaned by broom, blower, water blasting, or by other methods approved by the RPR to remove all contaminants, including PCC curing compounds, minimizing damage to the pavement surface.
- **b. Preparation of pavement to remove existing markings.** Existing pavement markings shall be removed by rotary grinding, water blasting, or by other methods approved by the RPR minimizing damage to the pavement surface. The removal area may need to be larger than the area of the markings to eliminate ghost markings. After removal of markings on asphalt pavements, apply a fog seal or seal coat to 'block out' the removal area to eliminate 'ghost' markings.
- **c. Preparation of pavement markings prior to remarking.** Prior to remarking existing markings, loose existing markings must be removed minimizing damage to the pavement surface, with a method approved by the RPR. After removal, the surface shall be cleaned of all residue or debris.

Prior to the application of markings, the Contractor shall certify in writing that the surface is dry and free from dirt, grease, oil, laitance, or other foreign material that would prevent the bond of the paint to the pavement or existing markings. This certification along with a copy of the paint manufactures application and surface preparation requirements must be submitted to the RPR prior to the initial application of markings.

- **620-3.4 Layout of markings.** The proposed markings shall be laid out in advance of the paint application. The locations of markings to receive glass beads shall be shown on the plans.
- **620-3.5 Application.** A period of 30 days shall elapse between placement of surface course or seal coat and application of the permanent paint markings. Paint shall be applied at the locations and to the dimensions and spacing shown on the plans. Paint shall not be applied until the layout and condition of the surface has been approved by the RPR.

The edges of the markings shall not vary from a straight line more than 1/2 inch (12 mm) in 50 feet (15 m), and marking dimensions and spacing shall be within the following tolerances:

Marking Dimensions and Spacing Tolerance

Dimension and Spacing	Tolerance
36 inch or less	±1/2 inch
greater than 36 inch to 6 feet	±1 inch
greater than 6 feet to 60 feet	±2 inch
greater than 60 feet	±3 inch

The paint shall be mixed in accordance with the manufacturer's instructions and applied to the pavement with a marking machine at the rate shown in Table 1. The addition of thinner will not be permitted.

Glass beads shall be distributed upon the marked areas at the locations shown on the plans to receive glass beads immediately after application of the paint. A dispenser shall be furnished that is properly designed for attachment to the marking machine and suitable for dispensing glass beads. Glass beads shall be applied at the rate shown in Table 1. Glass beads shall not be applied to black paint or green paint. Glass beads shall adhere to the cured paint or all marking operations shall cease until corrections are made. Different bead types shall not be mixed. Regular monitoring of glass bead embedment and distribution should be performed.

620-3.6 Application--preformed thermoplastic airport pavement markings. Preformed thermoplastic pavement markings not used.

620-3.7 Control strip. Prior to the full application of airfield markings, the Contractor shall prepare a control strip in the presence of the RPR. The Contractor shall demonstrate the surface preparation method and all striping equipment to be used on the project. The marking equipment must achieve the prescribed application rate of paint and population of glass beads (per Table 1) that are properly embedded and evenly distributed across the full width of the marking. Prior to acceptance of the control strip, markings must be evaluated during darkness to ensure a uniform appearance.

620-3.8 Retro-reflectance. Reflectance shall be measured with a portable retro-reflectometer meeting ASTM E1710 (or equivalent). A total of 6 reading shall be taken over a 6 square foot area with 3 readings taken from each direction. The average shall be equal to or above the minimum levels of all readings which are within 30% of each other.

Minimum Retro-Reflectance Values

Material	Retro-reflectance mcd/m²/lux		
	White	Yellow	Red
Initial Type I	300	175	35
All materials, remark when less than ¹	100	75	10

¹ 'Prior to remarking determine if removal of contaminants on markings will restore retro-reflectance

620-3.9 Protection and cleanup. After application of the markings, all markings shall be protected from damage until dry. All surfaces shall be protected from excess moisture and/or rain and from disfiguration by spatter, splashes, spillage, or drippings. The Contractor shall remove from the work area all debris, waste, loose reflective media, and by-products generated by the surface preparation and application operations to the satisfaction of the RPR. The Contractor shall dispose of these wastes in strict compliance with all applicable state, local, and federal environmental statutes and regulations.

METHOD OF MEASUREMENT

- **620-4.1** The quantity of pavement marking removal shall be measured by the number of square feet for surface preparation as specified in paragraph **620-3.3b**.
- **620-4.2** The quantity of runway and taxiway markings to be paid for shall be the number of square feet of painting performed in accordance with the specifications and accepted by the Engineer. No separate measurement will be made for the glass beads which will be considered as incidental to the runway and taxiway markings. No separate measurement will be made for surface preparation as specified in paragraph **620-3.3a** which will be considered as incidental to the runway and taxiway markings.
- **620-4.3** The quantity of temporary runway and taxiway markings to be paid for shall be the number of square feet of painting performed in accordance with the specifications and accepted by the Engineer. No separate measurement will be made for surface preparation as specified in paragraph **620-3.3a** which will be considered as incidental to the runway and taxiway markings.

BASIS OF PAYMENT

- **620-5.1** Payment for pavement marking removal shall be made at the contract price for the number of square feet removed. This price shall be full compensation for furnishing all materials and for all labor, equipment, tools, and incidentals necessary to complete the item complete in place and accepted by the RPR in accordance with these specifications.
- **620-5.2** Payment for runway and taxiway pavement marking shall be made at the contract price for respective type of markings. This price shall be full compensation for furnishing all materials and for all labor, equipment, tools, and incidentals necessary to complete the item complete in place and accepted by the RPR in accordance with these specifications.

Payment will be made under:

P-620-5.1	Pavement Marking Removal – per square foot
P-620-5.2	Temporary Pavement Marking (Yellow) - per square foot
P-620-5.3	Reflectorized Pavement Marking (Yellow) - per square foot
P-620-5.4	Non-Reflectorized Pavement Marking (Black) - per square foot

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM DA76

ASTM D476	Standard Classification for Dry Pigmentary Titanium Dioxide Products
ASTM D968	Standard Test Methods for Abrasion Resistance of Organic Coatings by Falling Abrasive
ASTM D1652	Standard Test Method for Epoxy Content of Epoxy Resins
ASTM D2074	Standard Test Method for Total, Primary, Secondary, and Tertiary Amine Values of Fatty Amines by Alternative Indicator Method
ASTM D2240	Standard Test Method for Rubber Property - Durometer Hardness

ASTM D7585	Standard Practice for Evaluating Retroreflective Pavement Markings

Using Portable Hand-Operated Instruments

ASTM E303 Standard Test Method for Measuring Surface Frictional Properties Using

the British Pendulum Tester

ASTM E1710 Standard Test Method for Measurement of Retroreflective Pavement

Marking Materials with CEN-Prescribed Geometry Using a Portable

Retroreflectometer

ASTM E2302 Standard Test Method for Measurement of the Luminance Coefficient

Under Diffuse Illumination of Pavement Marking Materials Using a

Portable Reflectometer

ASTM G154 Standard Practice for Operating Fluorescent Ultraviolet (UV) Lamp

Apparatus for Exposure of Nonmetallic Materials

Code of Federal Regulations (CFR)

40 CFR Part 60, Appendix A-7, Method 24

Determination of volatile matter content, water content, density, volume

solids, and weight solids of surface coatings

29 CFR Part 1910.1200 Hazard Communication

Federal Specifications (FED SPEC)

FED SPEC TT-B-1325D Beads (Glass Spheres) Retro-Reflective

FED SPEC TT-P-1952F Paint, Traffic and Airfield Marking, Waterborne

FED STD 595 Colors used in Government Procurement

Commercial Item Description

A-A-2886B Paint, Traffic, Solvent Based

Advisory Circulars (AC)

AC 150/5340-1 Standards for Airport Markings

AC 150/5320-12 Measurement, Construction, and Maintenance of Skid Resistant Airport

Pavement Surfaces

END OF ITEM P-620

Terminal Apron Rehabilitation AIP 3-20-0082-027 BIL-AIG 3-20-0082-028

THIS PAGE INTENTIONALLY LEFT BLANK

ITEM P-629 THERMOPLASTIC COAL TAR EMULSION SURFACE TREATMENTS

DESCRIPTION

629-1.1 This item shall consist of an application of a thermoplastic coal tar emulsion Sand Slurry Seal applied to an existing, previously prepared asphalt surface, including airport pavements serving small airplanes, roads, and other general applications. Thermoplastic resin coal tar emulsion products provide a fuel-resistant surface where pavements are subjected to fuel spills. Thermoplastic resin coal tar emulsion products assist in pavement preservation through reducing the rate of pavement oxidation. The application of the surface treatment shall be in accordance with these specifications and shall conform to the dimensions shown on the plans or as directed by the Resident Project Representative (RPR).

MATERIALS

- **629-2.1 Thermoplastic coal tar emulsion.** The emulsion material shall be a thermoplastic coal tar emulsion made up of plastic resin and emulsified coal tar pitch. The thermoplastic coal tar emulsion shall be manufactured as a complete product and tested at the manufacturing plant for material certification. The cured thermoplastic coal tar emulsion sample must pass the fuel-resistance test in accordance with ASTM D5727.
- **629-2.2 Manufacturer's certifications.** The Contractor shall furnish the manufacturer's certification of Analysis (COA) that all thermoplastic coal tar emulsion shipped to the project meets the following testing requirements:

Thermoplastic Coal Tar Emulsion Properties

Property	Standard	Requirement
Water content	ASTM D5727, Section 6.1.6	≤58%
Ash of Residue	ASTM D5727, Section 6.1.9	≤ 15%
Flexibility	ASTM D5727, Section 6.1.14	1 rating
Resistance to Kerosene	ASTM D5727, Section 6.1.12	Pass with no loss of adhesion and no softening of film
Softening Point	ASTM D36	>212°F (100°C)

- **629-2.3 Manufacturer sampling.** A sample of undiluted thermoplastic coal tar emulsion shall be obtained at the production facility from each consignment shipped to the job. Manufacturer shall store the samples in containers that are sealed against contamination and retained for a period of six months. Samples shall be stored at room temperature and not be subjected to freezing temperatures.
- **629-2.4 Water.** Water used in mixing or curing shall be from potable water sources. Other sources shall be tested in accordance with ASTM C1602 prior to use. The temperature of the water added during mixing shall be at least 50°F (10°C).
- **629-2.5 Handling and storage.** All emulsion stored on-site shall be agitated at least once per day for a minimum of 15 minutes. The distributor or applicator, pumps and all tools shall be maintained in satisfactory working condition. Spray bar nozzles, pumps, or other equipment can be cleaned mechanically or with clean water.
- **629-2.6 Health, safety, and environment.** The Contractor must provide a complete Safety Data Sheet (SDS) in accordance with U.S. Department of Labor, Occupational Safety and Health Administration

(OSHA), Regulations (Standards – 29 CFR), 1910.1200 which establishes the requirement and minimum information for the SDS for hazardous materials. The SDS, Section II, shall include the Chemical Abstracts Service (CAS) registry numbers for all applicable hazardous ingredients in the coal tar emulsion product. The Contractor must provide the manufacturer's certification that the product complies with the Code of Federal Regulation (CFR) Title 40 – Protection of Environment. The manufacturer's certification shall address compliance for Air Programs, Part 59, National Volatile Organic Compound Emission Standards for Consumer and Commercial Products (for the airport location) and Water Programs, Part 116, Designation of Hazardous Substances.

COMPOSITION AND APPLICATION

629-3.0 Thermoplastic coal tar emulsion sand slurry seal.

629-3.1 Quantities of materials per square yard. Based on the data in this specification, the Contractor shall submit the proportions of thermoplastic coal tar emulsion and aggregate proposed for use to the RPR for approval prior to the start of operations. A copy of the mix design and test data required by this specification shall be submitted to the RPR for approval along with the above information. No thermoplastic coal tar emulsion sand slurry seal shall be produced for payment until a job mix formula has been approved in writing by the RPR.

Application Rate

Composition ⁱ lbs/gal (kg/l)	Application Rate ⁱⁱ lb/yd ² (kg/m ²)
17-19	4
(2.04-2.28)	(2.17)

- 1. Aggregate (lbs) shall be mixed homogeneously with the thermoplastic coal tar emulsion (gals).
- 2. Minimum application rate of uncured thermoplastic coal tar emulsion sand slurry seal.

629-3.2 Aggregate. The aggregate shall consist of sound, durable crushed igneous type stone (crushed basalt, granite, trap rock, etc.), clean washed masonry sand, or clean washed manufactured silica sand, be free from films of matter that would prevent thorough coating and bonding with the asphalt material and free from coatings of clay, organic matter, and other deleterious materials. Aggregate shall have a minimum Mohs hardness of 6. The aggregate shall meet the gradation in the table below when tested in accordance with ASTM C136.

The Contractor shall provide a certification showing particle size analysis and properties of the material delivered for use on the project.

Aggregate Material Gradation Requirements

Sieve Designation (square openings)	Percentage by Weight Passing Sieves
No. 4 (4.75 mm)	100
No. 8 (2.36 mm)	99.5-100
No. 16 (1.18 mm)	85-100
No. 30 (600 µm)	50-90
No. 50 (300 μm)	15-55
No. 100 (150 μm)	0-20
No. 200 (75 μm)	0-20

629-3.3 Application.

- **a. Application of prime coat.** After preparation of the pavement and acceptance by the RPR, the prime coat shall be applied to the pavement surface only where thermoplastic coal tar emulsion sand slurry seal will be applied. Apply a prime coat of thermoplastic coal tar emulsion diluted with 50% water at the rate of 0.10 gallons of mix per square yard (0.45 l/m^2) .
- **b. Application of sand slurry seal.** The surface shall be pre-wet by fogging ahead of the spreader box. Water used in pre-wetting the surface shall be applied at such a rate that the entire surface is damp with no apparent flowing water in front of the spreader box. The mixture shall be of the desired consistency when deposited on the surface, and no additional elements shall be added. A sufficient amount of mixture shall be carried in the spreader box at all times so that even distribution is obtained. No clumped or unmixed aggregate shall be permitted. No segregation of the thermoplastic coal tar emulsion and aggregate fines from the coarse aggregate will be permitted.

Upon completion of the work, the thermoplastic coal tar emulsion sand slurry seal shall have no bare spots or cracks through which liquids or foreign matter could penetrate to the underlying pavement. The finished surface shall present a uniform texture.

In areas where the spreader box cannot be used, the thermoplastic coal tar emulsion sand slurry seal shall be applied by a means of a hand squeegee.

629-3.4 Equipment and tools.

a. Mobile mixing machine. The mobile mixing machine shall be a truck-mounted mobile mixing plant with a towed-type spreader box. It shall have a water tank and water pump capable of delivering a constant volume of water.

The mobile mixing machine shall have an agitated storage tank for the thermoplastic coal tar emulsion and a non-shearing peristaltic pump with variable rate of flow for the delivery of this material. The mobile mixing machine shall have a hopper for holding aggregate, supplying this material to the mixing chamber by a conveyor belt. The rate of aggregate delivery shall be mechanically dependent upon the speed of the peristaltic pump.

The mobile mixing machine shall be a continuous-flow mixing unit capable of delivering predetermined quantities of thermoplastic coal tar emulsion, aggregate, and if necessary water, to the mixing chamber and discharging the thoroughly mixed material on a continuous basis. The mobile mixing machine shall deliver the materials to the mixing chamber in a constant proportion in a manner not dependent on power plant or vehicle speed. The machine shall be equipped with a water spray bar capable of fogging the pavement surface to aid in the application process.

Attached to the mixing machine shall be a mechanical-type squeegee distributor, equipped with flexible material in contact with the surface to prevent loss of material from the distributor. It shall be maintained to prevent loss of micro-surfacing on varying grades and adjusted to assure uniform spread. The spreader box may have an adjustable width.

- **b. Prime coat distributor.** The prime coat distributor shall be either a truck-mounted 300 to 3,000-gallon (1136 to 11356 liter) tank or a trailer-mounted unit with a 300 to 1000-gallon tank (1136 to 3785 liters) containing suitably driven mixing blades to combine predetermined quantities of thermoplastic emulsion and water into a homogeneous mixture. It shall be equipped with a diaphragm style pump capable of delivering a constant volume of material to a spray wand or spray bar. The device shall have a bottom ball valve capable of delivering material to a squeegee spreader or a drag box.
- **c. Auxiliary equipment.** Other tools or equipment such as power brooms, power blowers, air compressors, hand brooms, hand squeegees, etc., shall be provided as required.

- **d. Calibration.** The Contractor shall furnish all equipment, materials and labor necessary to calibrate the equipment. It shall be calibrated to assure that it will produce and apply a mix that conforms to the job mix formula. Commercial equipment should be provided with a method of calibration by the manufacturer. All calibrations shall be made with the approved job materials prior to applying the slurry seal to the pavement. A copy of the calibration test results shall be furnished to the RPR.
- **629-3.5 Control strip.** A qualified manufacturer's representative shall be present in the field to assist the Contractor in applying control areas and/or control strips. The area to be tested will be designated by the RPR and will be located on the existing pavement.

The control strip shall determine the quality of the mixture in place as well as the performance of the equipment. The same equipment and method of operations shall be used on the control strip as will be used on the remainder of the work. If the control strip should prove to be unsatisfactory, the necessary adjustments to the mix composition, application rate, placement operations and equipment shall be made. Additional control strips shall be placed and evaluated if required.

629-3.6 Friction characteristics. Friction testing is not required for sand slurry installations.

CONSTRUCTION METHODS

- **629-4.1** Worker safety. The Contractor shall obtain a SDS for both the thermoplastic coal tar emulsion product and aggregate and require workmen to follow the manufacturer's recommended safety precautions.
- **629-4.2 Weather limitations.** The material shall not be applied when the humidity or impending weather conditions will not allow proper drying or when the atmospheric or pavement temperature is below 50°F (10°C), unless otherwise directed by the RPR.

During application of thermoplastic coal tar emulsion surface treatment, account for wind drift. Cover existing buildings, structures, runway edge lights, taxiway edge lights, informational signs, retro-reflective marking and in-pavement duct markers as necessary to protect against overspray before applying the emulsion. Should thermoplastic coal tar emulsion surface treatment get on any light or marker fixture, promptly clean the fixture. If cleaning is not satisfactory to the RPR, the Contractor shall replace any light, sign or marker with equivalent equipment at no cost to the Owner.

- **629-4.3 Preparation of asphalt pavement surfaces.** Clean pavement surface immediately prior to placing the surface treatment so that it is free of dust, dirt, grease, vegetation, oil or any type of objectionable surface film. Remove oil or grease by scrubbing with a detergent, then wash thoroughly with clean water. Any additional surface preparation, such as crack repair, shall be in accordance with P101-3.6.
- **629-4.4 Application.** Application shall be in accordance with paragraph 629-3.3.
- **629-4.5 Curing.** The mixture shall be permitted to dry for a minimum of 24 hours after the application, before opening to traffic or painting, and shall be sufficiently cured to drive over without damage to the installation. Any damage to the uncured mixture caused by the Contractor will be the responsibility of the Contractor to repair.

QUALITY CONTROL (QC)

- **629-5.1 Field emulsion sampling.** All emulsion sampling methods shall be in accordance with ASTM D140. Samples must be taken from the center of an agitated bulk storage tank after a minimum of 15 minutes of continual agitation.
- **629-5.2 Field composite mix sampling.** Composite mix of thermoplastic coal emulsion and aggregate shall be taken directly from the pug mill of the mobile mixing machine for micro-surface and sand slurry

installations into a sealed 1-gallon container to be weighed. The minimum weight of composite mix shall be the following:

- **a.** Type A Micro-Surface Composite Mix Minimum 14 pounds per gallon
- **b.** Type B Micro-Surface Composite Mix Minimum 13.5 pounds per gallon
- c. Sand Slurry Composite Mix Minimum 13 pounds per gallon
- **629-5.3 Manufacturer's representation**. The manufacturer's representative shall have knowledge of the material, procedures, and equipment described in the specification and shall be responsible for verifying the job mix formula submitted to the RPR and shall oversee the preparation and application of the thermoplastic coal tar emulsion surface treatment. Documentation of the manufacturer representative's experience and knowledge for applying the thermoplastic coal tar emulsion surface treatment shall be furnished to the RPR a minimum of 10 work days prior to placement of the control strips. The cost of the manufacturer's representative shall be included in the bid price.
- **629-5.4 Contractor qualifications.** The Contractor shall provide the RPR Contractor qualifications for applicators, personnel and equipment. The Contractor shall also provide, from the thermoplastic coal tar emulsion Manufacturer, documentation that the Contractor is certified to apply the thermoplastic coal tar emulsion surface treatment. Contractor shall provide documentation for at least three (3) applications similar to this project completed in the past two (2) years.

MATERIAL ACCEPTANCE

629-6.1 Friction tests. Sand slurry versions do not require friction testing.

METHOD OF MEASUREMENT

629-7.1 Measurement. The Thermoplastic Coal Tar Emulsion Sand Slurry Seal shall be measured by the square yard (sq m) of the area indicated on the contract drawings or designated by the RPR.

BASIS OF PAYMENT

629-8.1 Payment. Payment shall be made at the contract unit price per square yard (square meter) for the Thermoplastic Coal Tar Emulsion Sand Slurry Seal. This price shall fully compensate the Contractor for furnishing all materials and for all labor, equipment tools and incidentals necessary to complete the thermoplastic coal tar emulsion product installation, including mix design and data sheets stipulated in these specifications.

Payments will be made under:

Item P-629-8.1 Thermoplastic Coal Tar Emulsion Sand Slurry Seal – per square yard

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM D36 Standard Test Method for Softening Point of Bitumen (Ring-and-Ball Apparatus)

Timp Binard Wallerpar 2	BIL-AIG 3-20-0082-028			
ASTM C131	Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine			
ASTM C136	Standard Test Method for Sieve or Screen Analysis of Fine and Coarse Aggregates			
ASTM C1602	Standard Specification for Mixing Water Used in the Production of Hydraulic Cement Concrete			
ASTM D140	Standard Practice for Sampling Bituminous Materials			
ASTM D5340	Standard Test Method for Airport Pavement Condition Index Surveys			
ASTM D5727	Standard Specification for Emulsified Refined Coal Tar (Mineral Colloid Type)			
Advisory Circulars (AC)				
AC 150/5320-12	Measurement, Construction, and Maintenance of Skid-Resistant Airport Pavement Surfaces			
AC 150/5320-17	Airfield Pavement Surface Evaluation and Rating (PASER) Manuals			
Code of Federal Regulations (CFR)				
29 CFR Part 1910.1200	29 CFR Part 1910.1200 Hazard Communication			

Metropolitan Topeka Airport Authority Philip Billard Municipal Airport

40 CFR

END OF ITEM P-629

Protection of the Environment

Terminal Apron Rehabilitation

AIP 3-20-0082-027

ITEM T-901 SEEDING

DESCRIPTION

901-1.1 This item shall consist of soil preparation, seeding and fertilizing the areas shown on the plans or as directed by the RPR in accordance with these specifications.

MATERIALS

901-2.1 Seed. The species and application rates of grass, legume, and cover-crop seed furnished shall be those stipulated herein. Seed shall conform to the requirements of Federal Specification JJJ-S-181, Federal Specification, Seeds, Agricultural.

Seed shall be furnished separately or in mixtures in standard containers labeled in conformance with the Agricultural Marketing Service (AMS) Seed Act and applicable state seed laws with the seed name, lot number, net weight, percentages of purity and of germination and hard seed, and percentage of maximum weed seed content clearly marked for each kind of seed. The Contractor shall furnish the RPR duplicate signed copies of a statement by the vendor certifying that each lot of seed has been tested by a recognized laboratory for seed testing within six (6) months of date of delivery. This statement shall include name and address of laboratory, date of test, lot number for each kind of seed, and the results of tests as to name, percentages of purity and of germination, and percentage of weed content for each kind of seed furnished, and, in case of a mixture, the proportions of each kind of seed. Wet, moldy, or otherwise damaged seed will be rejected.

Seeds shall be applied as follows:

Seed Properties and Rate of Application

Seed	Minimum Seed Purity (Percent)	Minimum Germination (Percent)	Rate of Application lb/acre
Bluestem, Big (Kaw)	65	95	3
Buffalograss (Sharp's Improved)	95	80	25
Fescue, Tall, (K-31), (Rebel II)	98	85	8
Grama, Blue (Lovington)	80	98	2
Grama, Sideoats (El Reno)	95	95	8
Wild-rye, Canada	95	95	9
Wheatgrass, Western (Barton)	88	25	4

Seeding shall be performed during the period between March 15 to May 15 and September 1 to October 1 inclusive, unless otherwise approved by the RPR.

901-2.2 Lime. Not required.

901-2.3 Fertilizer. Fertilizer shall be standard commercial fertilizers supplied separately or in mixtures containing the percentages of total nitrogen, available phosphoric acid, and water-soluble potash. They shall be applied at the rate and to the depth specified and shall meet the requirements of applicable state laws. They shall be furnished in standard containers with name, weight, and guaranteed analysis of contents clearly marked thereon. No cyanamide compounds or hydrated lime shall be permitted in mixed fertilizers.

T-901 Seeding T-901-1 of 4

The fertilizers may be supplied in one of the following forms:

- a. A dry, free-flowing fertilizer suitable for application by a common fertilizer spreader;
- b. A finely-ground fertilizer soluble in water, suitable for application by power sprayers; or
- c. A granular or pellet form suitable for application by blower equipment.

Fertilizers shall be standard 12-12-12 commercial fertilizer and shall be spread at the rate of 500 lbs/acre

901-2.4 Soil for repairs. The soil for fill and topsoiling of areas to be repaired shall be at least of equal quality to that which exists in areas adjacent to the area to be repaired. The soil shall be relatively free from large stones, roots, stumps, or other materials that will interfere with subsequent sowing of seed, compacting, and establishing turf, and shall be approved by the RPR before being placed.

CONSTRUCTION METHODS

901-3.1 Advance preparation and cleanup. After grading of areas has been completed and before applying fertilizer and ground limestone, areas to be seeded shall be raked or otherwise cleared of stones larger than 2 inches in any diameter, sticks, stumps, and other debris that might interfere with sowing of seed, growth of grasses, or subsequent maintenance of grass-covered areas. If any damage by erosion or other causes has occurred after the completion of grading and before beginning the application of fertilizer and ground limestone, the Contractor shall repair such damage include filling gullies, smoothing irregularities, and repairing other incidental damage.

An area to be seeded shall be considered a satisfactory seedbed without additional treatment if it has recently been thoroughly loosened and worked to a depth of not less than 5 inches as a result of grading operations and, if immediately prior to seeding, the top 3 inches of soil is loose, friable, reasonably free from large clods, rocks, large roots, or other undesirable matter, and if shaped to the required grade.

When the area to be seeded is sparsely sodded, weedy, barren and unworked, or packed and hard, any grass and weeds shall first be cut or otherwise satisfactorily disposed of, and the soil then scarified or otherwise loosened to a depth not less than 5 inches. Clods shall be broken, and the top 3 inches of soil shall be worked into a satisfactory seedbed by discing, or by use of cultipackers, rollers, drags, harrows, or other appropriate means.

901-3.2 Dry application method.

- a. Liming. Not required.
- **b. Fertilizing.** Following advance preparations and cleanup fertilizer shall be uniformly spread at the rate that will provide not less than the minimum quantity stated in paragraph 901-2.3.
- **c. Seeding.** Grass seed shall be sown at the rate specified in paragraph 901-2.1 immediately after fertilizing. The fertilizer and seed shall be raked within the depth range stated in the special provisions. Seeds of legumes, either alone or in mixtures, shall be inoculated before mixing or sowing, in accordance with the instructions of the manufacturer of the inoculant. When seeding is required at other than the seasons shown on the plans or in the special provisions, a cover crop shall be sown by the same methods required for grass and legume seeding.
- **d. Rolling.** After the seed has been properly covered, the seedbed shall be immediately compacted by means of an approved lawn roller, weighing 40 to 65 pounds per foot (60 to 97 kg per meter) of width for clay soil (or any soil having a tendency to pack), and weighing 150 to 200 pounds per foot (223 to 298 kg per meter) of width for sandy or light soils.

901-3.3 Wet application method. Not used.

T-901 Seeding T-901-2 of 4

901-3.4 Maintenance of seeded areas. The Contractor shall protect seeded areas against traffic or other use by warning signs or barricades, as approved by the RPR. Surfaces gullied or otherwise damaged following seeding shall be repaired by regrading and reseeding as directed. The Contractor shall mow, water as directed, and otherwise maintain seeded areas in a satisfactory condition until final inspection and acceptance of the work.

When either the dry or wet application method outlined above is used for work done out of season, it will be required that the Contractor establish a good stand of grass of uniform color and density to the satisfaction of the RPR. A grass stand shall be considered adequate when bare spots are one square foot (0.01 sq m) or less, randomly dispersed, and do not exceed 3% of the area seeded.

METHOD OF MEASUREMENT

901-4.1 The quantity of seeding, including lime, fertilizer and mulch, to be paid for shall be the number of square yards measured on the ground surface, completed and accepted.

BASIS OF PAYMENT

901-5.1 Payment shall be made at the contract unit price per square yards or fraction thereof, which price and payment shall be full compensation for furnishing and placing all material, including fertilizer and mulch, and for all labor, equipment, tools, and incidentals necessary to complete the work prescribed in this item.

Payment will be made under:

Item T-901-5.1 Permanent Seeding & Mulching – per square yards

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM C602 Standard Specification for Agricultural Liming Materials

Federal Specifications (FED SPEC)

FED SPEC JJJ-S-181, Federal Specification, Seeds, Agricultural

Advisory Circulars (AC)

AC 150/5200-33 Hazardous Wildlife Attractants on or Near Airports

FAA/United States Department of Agriculture

Wildlife Hazard Management at Airports, A Manual for Airport Personnel

END OF ITEM T-901

T-901 Seeding T-901-3 of 4

THIS PAGE INTENTIONALLY LEFT BLANK

T-901 Seeding T-901-4 of 4

ITEM T-905 TOPSOIL

DESCRIPTION

905-1.1 This item shall consist of preparing the ground surface for topsoil application, removing topsoil from designated stockpiles or areas to be stripped on the site or from approved sources off the site, and placing and spreading the topsoil on prepared areas in accordance with this specification at the locations shown on the plans or as directed by the RPR.

MATERIALS

905-2.1 Topsoil. Topsoil shall be the surface layer of soil with no admixture of refuse or any material toxic to plant growth, and it shall be reasonably free from subsoil and stumps, roots, brush, stones (2 inches or more in diameter), and clay lumps or similar objects. Brush and other vegetation that will not be incorporated with the soil during handling operations shall be cut and removed. Ordinary sod and herbaceous growth such as grass and weeds are not to be removed, but shall be thoroughly broken up and intermixed with the soil during handling operations. Heavy sod or other cover, which cannot be incorporated into the topsoil by discing or other means, shall be removed. The topsoil or soil mixture, unless otherwise specified or approved, shall have a pH range of approximately 5.5 pH to 7.6 pH, when tested in accordance with the methods of testing of the Association of Official Agricultural Chemists in effect on the date of invitation of bids. The organic content shall be not less than 3% nor more than 20% as determined by the wet-combustion method (chromic acid reduction). There shall be not less than 20% nor more than 80% of the material passing the 200 mesh sieve as determined by the wash test in accordance with ASTM C117.

Natural topsoil may be amended by the Contractor with approved materials and methods to meet the above specifications.

905-2.2 Inspection and tests. Within 10 days following acceptance of the bid, the RPR shall be notified of the source of topsoil to be furnished by the Contractor. The topsoil shall be inspected to determine if the selected soil meets the requirements specified and to determine the depth to which stripping will be permitted. At this time, the Contractor may be required to take representative soil samples from several locations within the area under consideration and to the proposed stripping depths, for testing purposes as specified in paragraph 905-2.1.

CONSTRUCTION METHODS

905-3.1 General. Areas to be topsoiled shall be shown on the plans. If topsoil is available on the site, the location of the stockpiles or areas to be stripped of topsoil and the stripping depths shall be shown on the plans.

Suitable equipment necessary for proper preparation and treatment of the ground surface, stripping of topsoil, and for the handling and placing of all required materials shall be on hand, in good condition, and approved by the RPR before the various operations are started.

905-3.2 Preparing the ground surface. Immediately prior to dumping and spreading the topsoil on any area, the surface shall be loosened by discs or spike-tooth harrows, or by other means approved by the RPR, to a minimum depth of 2 inches to facilitate bonding of the topsoil to the covered subgrade soil. The surface of the area to be topsoiled shall be cleared of all stones larger than 2 inches in any diameter and all litter or other material which may be detrimental to proper bonding, the rise of capillary moisture, or the proper

T-905 Topsoil T-905-1 of 4

growth of the desired planting. Limited areas, as shown on the plans, which are too compact to respond to these operations shall receive special scarification.

Grades on the area to be topsoiled, which have been established by others as shown on the plans, shall be maintained in a true and even condition. Where grades have not been established, the areas shall be smooth-graded and the surface left at the prescribed grades in an even and compacted condition to prevent the formation of low places or pockets where water will stand.

905-3.3 Obtaining topsoil. Prior to the stripping of topsoil from designated areas, any vegetation, briars, stumps and large roots, rubbish or stones found on such areas, which may interfere with subsequent operations, shall be removed using methods approved by the RPR. Heavy sod or other cover, which cannot be incorporated into the topsoil by discing or other means shall be removed.

When suitable topsoil is available on the site, the Contractor shall remove this material from the designated areas and to the depth as directed by the RPR. The topsoil shall be spread on areas already tilled and smooth-graded, or stockpiled in areas approved by the RPR. Any topsoil stockpiled by the Contractor shall be rehandled and placed without additional compensation. Any topsoil that has been stockpiled on the site by others, and is required for topsoil purposes, shall be removed and placed by the Contractor. The sites of all stockpiles and areas adjacent thereto which have been disturbed by the Contractor shall be graded if required and put into a condition acceptable for seeding.

When suitable topsoil is secured off the airport site, the Contractor shall locate and obtain the supply, subject to the approval of the RPR. The Contractor shall notify the RPR sufficiently in advance of operations in order that necessary measurements and tests can be made. The Contractor shall remove the topsoil from approved areas and to the depth as directed. The topsoil shall be hauled to the site of the work and placed for spreading, or spread as required. Any topsoil hauled to the site of the work and stockpiled shall be rehandled and placed without additional compensation.

905-3.4 Placing topsoil. The topsoil shall be evenly spread on the prepared areas to a uniform depth of 2 inches after compaction, unless otherwise shown on the plans or stated in the special provisions. Spreading shall not be done when the ground or topsoil is frozen, excessively wet, or otherwise in a condition detrimental to the work. Spreading shall be carried on so that turfing operations can proceed with a minimum of soil preparation or tilling.

After spreading, any large, stiff clods and hard lumps shall be broken with a pulverizer or by other effective means, and all stones or rocks (2 inches or more in diameter), roots, litter, or any foreign matter shall be raked up and disposed of by the Contractor. after spreading is completed, the topsoil shall be satisfactorily compacted by rolling with a cultipacker or by other means approved by the RPR. The compacted topsoil surface shall conform to the required lines, grades, and cross-sections. Any topsoil or other dirt falling upon pavements as a result of hauling or handling of topsoil shall be promptly removed.

METHOD OF MEASUREMENT

905-4.1 Topsoil, whether obtained on the site or off Airport property, shall be included in the measurement for embankment in place per Specification P-152. No separate measurement for topsoil will be made.

BASIS OF PAYMENT

905-5.1 No separate payment will be made for this item. Payment will be made at the contract unit price per cubic yard for embankment in place per Specification P-152. This price shall be full compensation for furnishing all materials and for all preparation, placing, and spreading of the materials, and for all labor, equipment, tools, and incidentals necessary to complete the item.

T-905 Topsoil T-905-2 of 4

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM C117 Materials Finer than 75 µm (No. 200) Sieve in Mineral Aggregates by

Washing

Advisory Circulars (AC)

AC 150/5200-33 Hazardous Wildlife Attractants on or Near Airports

FAA/United States Department of Agriculture

Wildlife Hazard Management at Airports, A Manual for Airport Personnel

END OF ITEM T-905

T-905 Topsoil T-905-3 of 4

THIS PAGE INTENTIONALLY LEFT BLANK

T-905 Topsoil T-905-4 of 4

ITEM T-908 MULCHING

DESCRIPTION

908-1.1 This item shall consist of furnishing, hauling, placing, and securing mulch on surfaces indicated on the plans or designated by the RPR.

MATERIALS

- **908-2.1 Mulch material.** Acceptable mulch shall be the materials listed below or any approved locally available material that is similar to those specified. Mulch shall be free from noxious weeds, mold, and other deleterious materials. Mulch materials, which contain matured seed of species that would volunteer and be detrimental to the proposed overseeding, or to surrounding farm land, will not be acceptable. Straw or other mulch material which is fresh and/or excessively brittle, or which is in such an advanced stage of decomposition as to smother or retard the planted grass, will not be acceptable.
- **a. Hay**. Hay shall be native hay in an air-dry condition and of proper consistency for placing with commercial mulch blowing equipment. Hay shall be sterile, containing no fertile seed.
- **b. Straw.** Straw shall be the stalks from threshed plant residue of oats, wheat, barley, rye, or rice from which grain has been removed. Furnish in air-dry condition and of proper consistency for placing with commercial mulch blowing equipment. Straw shall contain no fertile seed.
- **c. Manufactured mulch**. Cellulose-fiber or wood-pulp mulch shall be products commercially available for use in spray applications.
- **908-2.2 Inspection.** The RPR shall be notified of sources and quantities of mulch materials available, and the Contractor shall furnish him with representative samples of the materials to be used 30 days before delivery to the project. These samples may be used as standards with the approval of the RPR and any materials brought on the site that do not meet these standards shall be rejected.

CONSTRUCTION METHODS

908-3.1 Mulching. Before spreading mulch, all large clods, stumps, stones, brush, roots, and other foreign Mulch shall be applied immediately after seeding. The spreading of the mulch may be by hand methods, blower, or other mechanical methods, provided a uniform covering is obtained.

Mulch material shall be furnished, hauled, and evenly applied on the area shown on the plans or designated by the RPR. Straw or hay shall be spread over the surface to a uniform thickness at the rate of 2 to 3 tons per acre (1800 - 2700 kg per acre) to provide a loose depth of not less than 1-1/2 inches (38 cm) nor more than 3 inches (75 mm). Other organic material shall be spread at the rate directed by the RPR. Mulch may be blown on the slopes and the use of cutters in the equipment for this purpose will be permitted to the extent that at least 95% of the mulch in place on the slope shall be 6 inches (150 mm) or more in length. When mulches applied by the blowing method are cut, the loose depth in place shall be not less than one inch (25 mm) nor more than 2 inches (50 mm).

908-3.2 Securing mulch. The mulch shall be held in place by light discing, a very thin covering of topsoil, pins, stakes, wire mesh, or other adhesive material approved by the RPR.

If the "peg and string" method is used, the mulch shall be secured by the use of stakes or wire pins driven into the ground on 5-foot (1.5-m) centers or less. Binder twine shall be strung between adjacent stakes in

T-908 Mulching T-908-1 of 2

straight lines and crisscrossed diagonally over the mulch, after which the stakes shall be firmly driven nearly flush to the ground to draw the twine down tight onto the mulch.

908-3.3 Care and repair.

- **a.** The Contractor shall care for the mulched areas until final acceptance of the project. Care shall consist of providing protection against traffic or other use by placing warning signs, as approved by the RPR, and erecting any barricades that may be shown on the plans before or immediately after mulching has been completed on the designated areas.
- **b.** The Contractor shall be required to repair or replace any mulch that is defective or becomes damaged until the project is finally accepted. When, in the judgment of the RPR, such defects or damages are the result of poor workmanship or failure to meet the requirements of the specifications, the cost of the necessary repairs or replacement shall be borne by the Contractor.

METHOD OF MEASUREMENT

908-4.1 No separate measurement for mulching will be made.

BASIS OF PAYMENT

908-5.1 No separate payment for mulching shall be made. Mulching shall be considered incidental to Item T-901 Seeding.

REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM International (ASTM)

ASTM D977 Standard Specification for Emulsified Asphalt

Advisory Circulars (AC)

AC 150/5200-33 Hazardous Wildlife Attractants on or Near Airports

FAA/United States Department of Agriculture

Wildlife Hazard Management at Airports, A Manual for Airport Personnel

END OF ITEM T-908

T-908 Mulching T-908-2 of 2

ADVISORY CIRCULAR

150/5210-5D - PAINTING, MARKING, AND LIGHTING OF VEHICLES USED ON AN AIRPORT



Federal Aviation Administration

Advisory Circular

Subject: Painting, Marking, and Lighting of **Date:** April 1, 2010 **AC No:** AC 150/5210-5D

Vehicles Used on an Airport Initiated by: AAS-100 Change:

- 1. **PURPOSE.** This advisory circular (AC) provides guidance, specifications, and standards for painting, marking, and lighting of vehicles operating in the airport air operations area (AOA). The approved lights, colors, and markings herein assure the conspicuity of vehicles operating in the AOA from both the ground and the air.
- **2. CANCELLATION.** This AC cancels AC 150/5210-5C, Painting, Marking, and Lighting of Vehicles Used on an Airport, dated August 31, 2007.
- **3. APPLICATION.** The Federal Aviation Administration (FAA) recommends the guidelines and standards in this Advisory Circular for vehicles operating in the airport AOA. In general, use of this AC is not mandatory. *However*, use of this AC is mandatory for vehicles funded with federal grant monies through the Airport Improvement Program (AIP) and/or with revenue from the Passenger Facility Charges (PFC) Program. See Grant Assurance No. 34, "Policies, Standards, and Specifications," and PFC Assurance No. 9, "Standard and Specifications."

Vehicles covered by this AC that do not meet this standard may be used until the vehicle is repainted or replaced, but no later than **December 31, 2010.**

- **4. PRINCIPAL CHANGES.** This AC contains new specifications and recommendations for the painting, marking, and lighting of Towbarless Tow Vehicles (TLTVs).
- **5. METRIC UNITS.** To promote an orderly transition to metric units, this AC includes both English and metric dimensions. The metric conversions may not be exact equivalents, and until there is an official changeover to the metric system, the English dimensions will govern.
- **6. COMMENTS OR SUGGESTIONS** for improvements to this AC should be sent to:

Manager, Airport Engineering Division Federal Aviation Administration

ATTN: AAS-100

800 Independence Avenue, S.W.

Washington, DC 20591

Michael J. O'Donnell

Director of Airport Safety and Standards

4/1/2010 AC 150/5210-5D

Intentionally left blank.

4/1/2010 AC 150/5210-5D

PAINTING, MARKING, AND LIGHTING OF VEHICLES USED ON AN AIRPORT

1. SOURCES OF APPLICABLE DOCUMENTS.

- **a.** American National Standards Institute, Inc. (ANSI), 25 West 43rd St. 4th Floor, New York, NY 10036. Website: **www.ansi.org**
- **b.** American Society for Testing & Materials (ASTM), ASTM International, 100 Barr Harbor Drive, P.O. Box C700, West Conshohocken, PA 19428-2959. Website: **www.astm.org**
- **c.** The National Fire Protection Association (NFPA), 1 Batterymarch Park, Quincy, Massachusetts 02169-7471. Website: **www.nfpa.org**
- **d.** The U. S. General Services Administration (GSA), Centralized Mailing List Services, 501 West Felix Street, Whse 9, South End P.O. Box 6477, Fort Worth, Texas 76115-6477. Website: **www.gsa.gov**
- **e.** The Superintendent of Documents, U.S. Government Printing Office, 732 North Capitol St. NW, Washington, DC 20401.
- **f.** Society of Automotive Engineers, Inc. (SAE), 400 Commonwealth Drive, Warrendale, PA 15096-0001. Website: **www.sae.org**
- **g.** FAA Advisory Circulars: U.S. Department of Transportation, Subsequent Distribution Office, Ardmore East Business Center, 3341 Q 75th Ave., Landover, MD 20785. Website: **www.faa.gov**
- h. FAA Engineering Briefs: www.faa.gov/airports/engineering/engineering briefs/
- **2. DEFINITIONS.** The following definitions apply in this AC:
 - **a. Vehicle** All conveyances, except aircraft, used on the ground to transport persons, cargo, equipment or those required to perform maintenance, construction, service, and security duties.
 - **b.** Air Operations Area (AOA) The portion of airport that encompasses the landing, take off, taxiing, and parking areas for aircraft.
 - **c. Airport Emergency Vehicles** Vehicles that are authorized in the AOA for emergency purposes (e.g., ambulances, aircraft rescue and fire fighting (ARFF) vehicles and emergency response vehicles) as authorized by the airport traffic control tower (ATCT) or an authorized onsite accident/incident commander.
 - **d. Airport Operations Vehicles** Vehicles routinely used by airport operations personnel for airport inspection and duties associated with airfield operations (such as airfield condition reporting and Incident Command) on the AOA and Movement Area.
 - **e. Airport Security Vehicles** Vehicles that are authorized in the AOA for security purposes, as needed (e.g. police cars).

AC 150/5210-5D 4/1/2010

f. Airfield Service Vehicles – Vehicles that are routinely used in the AOA for airfield service, maintenance, or construction (e.g. snow blowers, snowplows, maintenance trucks, and tractors).

- **g.** Aircraft Support Vehicles Vehicles that are routinely used in the AOA to support aircraft operations (e.g. aircraft pushback tractors, baggage/cargo tractors or trucks, air conditioning and aviation fuel trucks). These vehicles are typically owned by airlines, vendors, or contractors and are not eligible for Federal funding.
- **h. Reduced Visibility** Prevailing visibility is less than one statute mile (1609 meters) and/or the runway visual range (RVR) is less than 6,000 feet (1830 meters).
- **i. Movement Area** The runways, taxiways, and other areas of an airport/heliport that are used for taxiing/hover taxiing, air taxiing, takeoff, and landing of aircraft, exclusive of loading ramps and parking areas. At those airports/heliports with an operating airport traffic control tower (ATCT), specific approval for entry onto the movement area must be obtained from air traffic control (ATC).
- **j.** Other Vehicles Vehicles that are not routinely authorized in the AOA (e.g. construction vehicles). These vehicles are typically owned by airlines, vendors, or contractors and are not eligible for Federal funding.
- **k. Peak Intensity** Peak intensity, for purposes of this document, means the maximum magnitude of luminescence as measured in candela.
- **I.** Towbarless Tow Vehicle (TLTV) a type of aircraft support vehicle whose main purpose is to tow aircraft in the AOA by way of nose gear capture.

3. VEHICLE PAINTING.

NOTE: Airport vehicle paint and markings are a safety of flight requirement. The approved colors/markings herein assure conspicuity of vehicles operating in the AOA from both the ground and air.

- a. Airport Emergency Vehicles.
 - (1) Ambulances. Ambulance vehicles are painted per the most current version of Federal Specification KKK-A-1822, *Federal Specification for the Star-of-Life Ambulance*. Ambulances are not considered vehicles routinely operating on the AOA.
 - (2) Aircraft Rescue and Fire Fighting (ARFF) Vehicles. Yellowish-green is the vehicle color standard. Color specifications are per Appendix A.

NOTE: A yellowish-green color provides optimum visibility during all light levels encountered during a 24-hour day and under variations of light that result from weather and seasonal changes.

- **b. Airport Operations Vehicles.** Airport operations vehicles may be painted in colors designated by the airport operator. The characteristics must be coordinated with the respective ATCT and identified in the tower letter of agreement.
- **c. Airport Security Vehicles.** Comply with specific state or local requirements.

4/1/2010 AC 150/5210-5D

d. Airfield Service Vehicles. Chrome yellow is the vehicle color standard. Color specifications are per Appendix A. When vehicles are equipped with bumper bars 8 inches (200 mm) or more in depth, the bars must be painted in alternate stripes 4 inches (100 mm) in width of chrome yellow and black inclined 45° to the vertical.

e. Aircraft Support Vehicles.

- (1) Any color or combination of colors other than yellowish-green or chrome yellow. The bumper bar paint scheme in paragraph 3.d (of alternating chrome yellow and black stripe) is recommended.
- (2) TLTVs. International orange is the vehicle color standard. Retroreflective tape covering more than 25 percent of the vehicle's vertical surfaces may be used as a temporary measure to meet this standard prior to scheduled vehicle painting.
- **f. Other Vehicles.** Any color or combination of colors other than solid black or white.

4. VEHICLE MARKING.

- a. Airport Emergency Vehicles.
 - (1) **Ambulances.** Ambulances are marked per the most current version of Federal Specification KKK-A-1822.
 - (2) ARFF Vehicles. Emergency rescue and fire fighting vehicles are marked with the letters "ARFF, "Fire," or "Rescue" and in accordance with 4.c.(1)-(5) of this AC.
- **b.** Airport Operations Vehicles. Airport operations vehicles may be marked as designated by the airport operator. Marking must be coordinated with the respective ATCT and identified in the tower letter of agreement.

c. Airfield Service Vehicles and Aircraft Support Vehicles.

- (1) Airport operator owned vehicles must display an identification number on each side and on the roof (the hood should be used if the vehicle has no roof).
- (2) Side numbers will be a minimum of 16 inches (410 mm) in height and conspicuously located.
- (3) Roof numbers will be a minimum of 24 inches (610 mm) in height and affixed with their bases toward the front of the vehicle. The identification numbers should provide sharp color contrast to the vehicle color.
- (4) In addition to the identification numbers, airport operator-owned vehicles must display either the name of the airport and/or the airport insignia.
- (5) To further improve night-time recognition of vehicles, a minimum 8 inch (200 mm) wide horizontal band of high gloss white paint or white reflective tape (Retroreflective, ASTM-D 4956-09, *Standard Specification for Retroreflective Sheeting for Traffic Control*, Type III & above) must be used around the vehicle's surface. Figures 1, 2, and 3 show suggested locations for the horizontal reflective band.

AC 150/5210-5D 4/1/2010




Figure 1: Suggested location for the horizontal reflective band, Option 1




Figure 2: Suggested location for the horizontal reflective band, Option 2




Figure 3: Suggested location for the horizontal reflective band, Option 3

(6) TLTVs. Retroreflective tape is used to outline the shape of a TLTV. If the vertical edge of the vehicle is rounded, the tape should be placed on the rounded portion to reflect light in both the horizontal and vertical planes. Where the placement of the tape may interfere with, or may be worn down by, maintenance or operational activities, tape is not required. Suggested locations for the retroreflective bands are shown in Figure 4.




Figure 4: Suggested placement of retroreflective tape on a TLTV

4/1/2010 AC 150/5210-5D

d. Airport Security and Other Vehicles.

(1) Vehicles other than those that routinely traverse any portion of the AOA under the control of ATC, which are not escorted by a vehicle in constant two-way radio communication with ATC and properly equipped and authorized to operate in the AOA, must be provided with a flag on a staff attached to the vehicle so that the flag will be readily visible.

- (2) At airports without air traffic control facilities, flags must be provided on all vehicles.
- (3) The flag must be at least a 3-foot by 3-foot (0.9 meter by 0.9 meter) square having a checkered pattern of international orange and white squares at least 1 foot (300 mm) on each side (see Appendix A for the fabric color specification).

5. VEHICLE LIGHTING.

a. Airfield Service, Aircraft Support, and Airport Operations Vehicles.

- (1) The standard for identification lighting is a yellow flashing light that is mounted on the uppermost part of the vehicle structure. A steady yellow light designates vehicles limited to non-movement areas.
- (2) The light must be visible from any direction, day and night, including from the air.
- (3) Color specifications for vehicle identification lights are per Appendix B.
- (4) TLTVs. An LED light bar placed above the operator's cab may be used in place of the rotating yellow flashing light. In addition, a yellow flashing light (of any type) must be installed on the upper left-rear and right-rear corners of the TLTV, and must be activated when an aircraft is in tow. The size of the rear flashing lights must be large enough to meet the requirements of Section 5.c, but not so large as to interfere with the normal or towing operations of the TLTV.
- **b.** Airport Emergency, Security, and Other Vehicles, which are not escorted by a properly lighted vehicle, must be identified during periods of low visibility by a light.

c. Characteristics of Flashing Lights:

- (1) Ambulance lights must meet the specifications in the most current version of Federal Specification KKK-A-1822, and ARFF vehicles must meet NFPA, state, and local requirements.
- Lights must have peak intensity within the range of 40 to 400 candelas (effective) from 0° (horizontal) up to 10° above the horizontal and for 360° horizontally. The upper limit of 400 candelas (effective) is necessary to avoid damage to night vision.
- (3) From 10° to 15° above the horizontal plane, the light output must be 1/10th of peak intensity or between 4 and 40 candelas (effective).

AC 150/5210-5D 4/1/2010

(4) Lights must flash at 75 ± 15 flashes per minute.

NOTES:

- 1. The effective intensity of a flashing light is equal to the intensity of a steady-burning (fixed) light of the same color that produces the same visual range under identical conditions of observation.
- 2. If xenon flashtubes are used, refer to AC 150/5345-43, Specification for Obstruction Lighting Equipment, for guidance concerning methods of calculating effective intensity.

d. Light Colors.

- (1) Airport Emergency Vehicles.
 - (a) **Ambulances.** Per the most current version of Federal Specification KKK-A-1822.
 - (b) **ARFF Vehicles.** Red or a combination of red-and-white flashing lights per the chromaticity requirements in Appendix B.
- (2) Airport Security Vehicles. Signal blue or a combination of red and signal blue flashing light per the chromaticity requirements in Appendix B.
- (3) Airfield Service, Aircraft Support, Airport Operations, and Other Vehicles. Yellow flashing light per the chromaticity requirements in Appendix B.

4/1/2010 AC 150/5210-5D Appendix A

APPENDIX A. COLOR SPECIFICATIONS

A-1. SPECIFICATIONS. Colors specified in Table A-1 are per the Commission Internationale de l'Eclairage (CIE) L*a*b* system of color specification. For a description of this system, refer to American Society for Testing & Materials (ASTM) D 2244, Standard Practice for Calculation of Color Tolerances and Color Differences from Instrumentally Measured Color Coordinates.

Standard	Chrome Yellow		Yellowish-Green			International Orange			
Illuminant D65 Usage	Vehicle Paint			Vehicle Paint			Vehicle Paint / Flag Fabric		
CIELAB DATA	L*	a*	b*	L*	a*	b*	L*	a*	b*
Centroid Color	72.8	24.4	77.6	78.3	-10.2	80.4	45.0	53.5	52.0
Point 1	72.8	31.8	82.9	78.3	-9.0	92.0	45.0	61.4	47.8
Point 2	72.8	25.5	66.7	78.3	-7.6	73.2	45.0	53.9	41.4
Point 3	72.8	18.0	69.3	78.3	-11.0	69.3	45.0	53.5	53.4
Point 4	72.8	22.4	86.0	78.3	-13.4	86.2	45.0	49.7	60.4
Light Limit	77.8			83.3			49.9		
Dark Limit	67.8			73.3			41.6		
Max AE		11.1			11.7			10.7	

Table A-1. Specification for vehicle and flag colors

A-2. COLOR TESTS. Acceptable colors are those that meet the gloss rating test and either a visual or an instrumental color test as follows:

NOTE: Flag fabric colors must meet either the instrumental tests in Table A-1 or the visual method described in paragraph A-2b(1).

a. Gloss Rating Test. This test is performed per ASTM D 523, Standard Test Method for Specular Gloss, on a paint sample of the color to be applied on the vehicle. An acceptable color sample is high gloss with a minimum gloss rating of 70 units, for 60° geometry.

b. Color Test Methods:

(1) Visual. Prepare a master specimen of the color (per Table A-1) and gloss (per paragraph A-2a). This specimen will be the master color and be used as the basis of comparison per ASTM D 5531-05, Standard Guide for the Preparation, Maintenance, and Distribution of Physical Product Standards for Color and Geometric Appearance of Coatings. To verify the paint color of a vehicle visually, vehicle paint samples must be

prepared and viewed per ASTM D 1729-96 (Reapproved 2009), Standard Practice for Visual Appraisal of Colors and Color Differences of Diffusely-Illuminated Opaque Materials.

- (2) Instrumental. This test requires a test specimen sample and reference to Table A-1. All test specimen measurements should be conducted per ASTM E 1164-09a Standard Practice for Obtaining Spectrometric Data for Object-Color Evaluation. Test specimen tolerances must be per Table A-1 per the following:
 - (a) Plot the centroid color using the a* and b* CIELAB coordinate data from Table A-1 on graph paper or by entry of the coordinate data into a computer program. Plot and connect points 1 through 4 from the same table to form a quadrilateral; noting that the centroid color is within this figure. See Figure A-1 for plots of all three color specifications in Table A-1.
 - (b) Perform color sample measurements per ASTM E 1164-09a. If necessary, convert measurements to CIELAB L*, a*, and b* color space. See ASTM E 308-08, *Standard Practice for Computing the Colors of Objects by Using the CIE System*, for color space conversion formulae.
 - (c) An acceptable color is one that meets:
 - (i) the chromaticity requirements of the color samples a* and b* CIELAB coordinate data by falling within the quadrilateral;
 - (ii) the L* data lightness requirement by falling within the range defined by the light and dark data of Table A-1;
 - (iii) the total color difference (ΔE) by not exceeding the limits in Table A-1 when the CIELAB data are computed in the following formula:

$$\Delta E = (\Delta L^{*2} + \Delta a^{*2} + \Delta b^{*2})^{\frac{1}{2}}$$

where ΔL^* , Δa^* , and Δb^* values are the differences between those values for the centroid color in Table A-1 and those of the color sample measurements.




Figure A-1. Plot of selected color paint specifications

Intentionally left blank.

4/1/2010 AC 150/5210-5D Appendix B

APPENDIX B. COLOR SPECIFICATIONS FOR VEHICLE IDENTIFICATION LIGHTS

B-1. SPECIFICATIONS. The Society of Automotive Engineers (SAE) Standard J578 Revised December 2006, *Color Specification*, defines the acceptable color boundary limits and measurement of emitted red, white, signal blue, and yellow light for vehicle lights. This standard applies to the overall emitted color of light from the device in lieu of emitted light from any small area of the lens. The color of emitted light must fall within the color boundaries per SAE J578 Revised December 2006 (color boundary equations are in the standard) using color measurement methods detailed in the standard. See FAA Engineering Brief #67, Light Sources Other Than Incandescent and Xenon for Airport and Obstruction Lighting Fixtures, for additional information and Alternative Lighting Devices.

Intentionally left blank.

ADVISORY CIRCULAR

150/5370-2G - OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION



Advisory Circular

Subject: Operational Safety on Date: 12/13/2017 AC No: 150/5370-2G

Airports During Construction Initiated By: AAS-100 Change:

1 **Purpose.**

This AC sets forth guidelines for operational safety on airports during construction.

2 Cancellation.

This AC cancels AC 150/5370-2F, Operational Safety on Airports during Construction, dated September 29, 2011.

3 **Application.**

This AC assists airport operators in complying with Title 14 Code of Federal Regulations (CFR) Part 139, *Certification of Airports*. For those certificated airports, this AC provides one way, but not the only way, of meeting those requirements. The use of this AC is mandatory for those airport construction projects receiving funds under the Airport Improvement Program (AIP). See Grant Assurance No. 34, *Policies, Standards, and Specifications*. While we do not require non-certificated airports without grant agreements or airports using Passenger Facility Charge (PFC) Program funds for construction projects to adhere to these guidelines, we recommend that they do so to help these airports maintain operational safety during construction.

4 Related Documents.

ACs and Orders referenced in the text of this AC do not include a revision letter, as they refer to the latest version. <u>Appendix A</u> contains a list of reading material on airport construction, design, and potential safety hazards during construction, as well as instructions for obtaining these documents.

5 **Principal Changes.**

The AC incorporates the following principal changes:

1. Notification about impacts to both airport owned and FAA-owned NAVAIDs was added. See paragraph 2.13.5.3, NAVAIDs.

- 2. Guidance for the use of orange construction signs was added. See paragraph 2.18.4.2, Temporary Signs.
- 3. Open trenches or excavations may be permitted in the taxiway safety area while the taxiway is open to aircraft operations, subject to restrictions. See paragraph 2.22.3.4, Excavations.
- 4. Guidance for temporary shortened runways and displaced thresholds has been enhanced. See <u>Figure 2-1</u> and <u>Figure 2-2</u>.
- 5. Figures have been improved and a new <u>Appendix F</u> on the placement of orange construction signs has been added.

Hyperlinks (allowing the reader to access documents located on the internet and to maneuver within this document) are provided throughout this document and are identified with underlined text. When navigating within this document, return to the previously viewed page by pressing the "ALT" and " \leftarrow " keys simultaneously.

Figures in this document are schematic representations and are not to scale.

6 Use of Metrics.

Throughout this AC, U.S. customary units are used followed with "soft" (rounded) conversion to metric units. The U.S. customary units govern.

7 Where to Find this AC.

You can view a list of all ACs at http://www.faa.gov/regulations_policies/advisory_circulars/. You can view the Federal Aviation Regulations at http://www.faa.gov/regulations_policies/faa_regulations/.

8 Feedback on this AC.

If you have suggestions for improving this AC, you may use the <u>Advisory Circular</u> Feedback form at the end of this AC.

John R. Dermody

Director of Airport Safety and Standards

CONTENTS

Paragraph		Page
Chapte	er 1. Planning an Airfield Construction Project	1-1
1.1	Overview	1-1
1.2	Plan for Safety	1-1
1.3	Develop a Construction Safety and Phasing Plan (CSPP)	1-3
1.4	Who Is Responsible for Safety During Construction?	1-4
Chapte	er 2. Construction Safety and Phasing Plans	2-1
2.1	Overview	2-1
2.2	Assume Responsibility	2-1
2.3	Submit the CSPP	2-1
2.4	Meet CSPP Requirements.	2-2
2.5	Coordination.	2-6
2.6	Phasing.	2-7
2.7	Areas and Operations Affected by Construction Activity	2-7
2.8	Navigation Aid (NAVAID) Protection.	2-11
2.9	Contractor Access.	2-11
2.10) Wildlife Management	2-15
2.11	Foreign Object Debris (FOD) Management.	2-16
2.12	2 Hazardous Materials (HAZMAT) Management	2-16
2.13	Notification of Construction Activities	2-16
2.14	Inspection Requirements	2-18
2.15	5 Underground Utilities.	2-19
2.16	5 Penalties.	2-19
2.17	7 Special Conditions.	2-19
2.18	Runway and Taxiway Visual Aids	2-19
2.19	Marking and Signs for Access Routes.	2-29
2.20	Hazard Marking, Lighting and Signing.	2-30
2.21	Work Zone Lighting for Nighttime Construction.	2-32
2.22	2 Protection of Runway and Taxiway Safety Areas.	2-33
2.23	Other Limitations on Construction.	2-37

Chapte	r 3. Guidelines for Writing a CSPP	3-1
3.1	General Requirements.	3-1
3.2	Applicability of Subjects	3-1
3.3	Graphical Representations.	3-1
3.4	Reference Documents.	3-2
3.5	Restrictions.	3-2
3.6	Coordination.	3-2
3.7	Phasing.	3-2
3.8	Areas and Operations Affected by Construction.	3-2
3.9	NAVAID Protection.	3-2
3.10	Contractor Access.	3-3
3.11	Wildlife Management.	3-4
3.12	FOD Management.	3-4
3.13	HAZMAT Management	3-4
3.14	Notification of Construction Activities.	3-4
3.15	Inspection Requirements.	3-5
3.16	Underground Utilities.	3-5
3.17	Penalties.	3-5
3.18	Special Conditions.	3-5
3.19	Runway and Taxiway Visual Aids.	3-6
3.20	Marking and Signs for Access Routes.	3-6
3.21	Hazard Marking and Lighting.	3-6
3.22	Work Zone Lighting for Nighttime Construction.	3-6
3.23	Protection of Runway and Taxiway Safety Areas.	3-7
3.24	Other Limitations on Construction.	3-7
Append	lix A. Related Reading Material	. A-1
Append	lix B. Terms and Acronyms	B-1
Append	lix C. Safety and Phasing Plan Checklist	. C-1
Append	dix D. Construction Project Daily Safety Inspection Checklist	. D-1
Append	lix E. Sample Operational Effects Table	E-1
Append	lix F. Orange Construction Signs	F-1

FIGURES

Number	Page
Figure 2-1. Temporary Partially Closed Runway	2-9
Figure 2-2. Temporary Displaced Threshold	2-10
Figure 2-3. Markings for a Temporarily Closed Runway	2-21
Figure 2-4. Temporary Taxiway Closure	2-22
Figure 2-5. Temporary Outboard White Threshold Bars and Yellow Arrowheads	2-24
Figure 2-6. Lighted X in Daytime	2-26
Figure 2-7. Lighted X at Night	2-26
Figure 2-8. Interlocking Barricades	2-31
Figure 2-9. Low Profile Barricades	2-32
Figure E-1. Phase I Example	E-1
Figure E-2. Phase II Example	E-2
Figure E-3. Phase III Example	E-3
Figure F-1. Approved Sign Legends	F-1
Figure F-2. Orange Construction Sign Example 1	F-2
Figure F-3. Orange Construction Sign Example 2	F-3
TABLES	
Number	Page
Table A-1. FAA Publications	A-1
Table A-2. Code of Federal Regulation	A-3
Table B-1. Terms and Acronyms	B-1
Table C-1. CSPP Checklist	C-1
Table D-1. Potentially Hazardous Conditions	D-1
Table E-1. Operational Effects Table	E-4
Table E-2. Runway and Taxiway Edge Protection	E-6
Table E-3. Protection Prior to Runway Threshold	E-7

Page Intentionally Blank

CHAPTER 1. PLANNING AN AIRFIELD CONSTRUCTION PROJECT

1.1 **Overview.**

Airports are complex environments, and procedures and conditions associated with construction activities often affect aircraft operations and can jeopardize operational safety. Safety considerations are paramount and may make operational impacts unavoidable. However, careful planning, scheduling, and coordination of construction activities can minimize disruption of normal aircraft operations and avoid situations that compromise the airport's operational safety. The airport operator must understand how construction activities and aircraft operations affect one another to be able to develop an effective plan to complete the project. While the guidance in this AC is primarily used for construction operations, the concepts, methods and procedures described may also enhance the day-to-day airport maintenance operations, such as lighting maintenance and snow removal operations.

1.2 Plan for Safety.

Safety, maintaining aircraft operations, and construction costs are all interrelated. Since safety must not be compromised, the airport operator must strike a balance between maintaining aircraft operations and construction costs. This balance will vary widely depending on the operational needs and resources of the airport and will require early coordination with airport users and the FAA. As the project design progresses, the necessary construction locations, activities, and associated costs will be identified and their impact to airport operations must be assessed. Adjustments are made to the proposed construction activities, often by phasing the project, and/or to airport operations to maintain operational safety. This planning effort will ultimately result in a project Construction Safety and Phasing Plan (CSPP). The development of the CSPP takes place through the following five steps:

1.2.1 <u>Identify Affected Areas.</u>

The airport operator must determine the geographic areas on the airport affected by the construction project. Some, such as a runway extension, will be defined by the project. Others may be variable, such as the location of haul routes and material stockpiles.

1.2.2 Describe Current Operations.

Identify the normal airport operations in each affected area for each phase of the project. This becomes the baseline from which the impact on operations by construction activities can be measured. This should include a narrative of the typical users and aircraft operating within the affected areas. It should also include information related to airport operations: the Aircraft Approach Category (AAC) and Airplane Design Group (ADG) of the airplanes that operate on each runway; the ADG and Taxiway Design Group (TDG)¹ for each affected taxiway; designated approach visibility minimums;

-

¹ Find Taxiway Design Group information in AC 150/5300-13, Airport Design.

available approach and departure procedures; most demanding aircraft; declared distances; available air traffic control services; airport Surface Movement Guidance and Control System (SMGCS) plan; and others. The applicable seasons, days and times for certain operations should also be identified as applicable.

1.2.3 Allow for Temporary Changes to Operations.

To the extent practical, current airport operations should be maintained during the construction. In consultation with airport users, Aircraft Rescue and Fire Fighting (ARFF) personnel, and FAA Air Traffic Organization (ATO) personnel, the airport operator should identify and prioritize the airport's most important operations. The construction activities should be planned, through project phasing if necessary, to safely accommodate these operations. When the construction activities cannot be adjusted to safely maintain current operations, regardless of their importance, then the operations must be revised accordingly. Allowable changes include temporary revisions to approach procedures, restricting certain aircraft to specific runways and taxiways, suspension of certain operations, decreased weights for some aircraft due to shortened runways, and other changes. An example of a table showing temporary operations versus current operations is shown in Appendix E.

1.2.4 <u>Take Required Measures to Revise Operations.</u>

Once the level and type of aircraft operations to be maintained are identified, the airport operator must determine the measures required to safely conduct the planned operations during the construction. These measures will result in associated costs, which can be broadly interpreted to include not only direct construction costs, but also loss of revenue from impacted operations. Analysis of costs may indicate a need to reevaluate allowable changes to operations. As aircraft operations and allowable changes will vary widely among airports, this AC presents general guidance on those subjects.

1.2.5 <u>Manage Safety Risk.</u>

The FAA is committed to incorporating proactive safety risk management (SRM) tools into its decision-making processes. FAA Order 5200.11, FAA Airports (ARP) Safety Management System (SMS), requires the FAA to conduct a Safety Assessment for certain triggering actions. Certain airport projects may require the airport operator to provide a Project Proposal Summary to help the FAA determine whether a Safety Assessment is required prior to FAA approval of the CSPP. The airport operator must coordinate with the appropriate FAA Airports Regional or District Office early in the development of the CSPP to determine the need for a Safety Risk Assessment. If the FAA requires an assessment, the airport operator must at a minimum:

- 1. Notify the appropriate FAA Airports Regional or District Office during the project "scope development" phase of any project requiring a CSPP.
- 2. Provide documents identified by the FAA as necessary to conduct SRM.
- 3. Participate in the SRM process for airport projects.
- 4. Provide a representative to participate on the SRM panel.

5. Ensure that all applicable SRM identified risks elements are recorded and mitigated within the CSPP.

1.3 Develop a Construction Safety and Phasing Plan (CSPP).

Development of an effective CSPP will require familiarity with many other documents referenced throughout this AC. See <u>Appendix A</u> for a list of related reading material.

1.3.1 <u>List Requirements.</u>

A CSPP must be developed for each on-airfield construction project funded by the Airport Improvement Program (AIP) or located on an airport certificated under Part 139. For on-airfield construction projects at Part 139 airports funded without AIP funds, the preparation of a CSPP represents an acceptable method the certificate holder may use to meet Part 139 requirements during airfield construction activity. As per FAA Order 5200.11, projects that require Safety Assessments do not include construction, rehabilitation, or change of any facility that is entirely outside the air operations area, does not involve any expansion of the facility envelope and does not involve construction equipment, haul routes or placement of material in locations that require access to the air operations area, increase the facility envelope, or impact line-of-sight. Such facilities may include passenger terminals and parking or other structures. However, extraordinary circumstances may trigger the need for a Safety Assessment and a CSPP. The CSPP is subject to subsequent review and approval under the FAA's Safety Risk Management procedures (see paragraph 1.2.5).

1.3.2 Prepare a Safety Plan Compliance Document (SPCD).

The Safety Plan Compliance Document (SPCD) details how the contractor will comply with the CSPP. Also, it will not be possible to determine all safety plan details (for example specific hazard equipment and lighting, contractor's points of contact, construction equipment heights) during the development of the CSPP. The successful contractor must define such details by preparing an SPCD that the airport operator reviews for approval prior to issuance of a notice-to-proceed. The SPCD is a subset of the CSPP, similar to how a shop drawing review is a subset to the technical specifications.

1.3.3 Assume Responsibility for the CSPP.

The airport operator is responsible for establishing and enforcing the CSPP. The airport operator may use the services of an engineering consultant to help develop the CSPP. However, writing the CSPP cannot be delegated to the construction contractor. Only those details the airport operator determines cannot be addressed before contract award are developed by the contractor and submitted for approval as the SPCD. The SPCD does not restate nor propose differences to provisions already addressed in the CSPP.

1.4 Who Is Responsible for Safety During Construction?

1.4.1 Establish a Safety Culture.

Everyone has a role in operational safety on airports during construction: the airport operator, the airport's consultants, the construction contractor and subcontractors, airport users, airport tenants, ARFF personnel, Air Traffic personnel, including Technical Operations personnel, FAA Airports Division personnel, and others, such as military personnel at any airport supporting military operations (e.g. national guard or a joint use facility). Close communication and coordination between all affected parties is the key to maintaining safe operations. Such communication and coordination should start at the project scoping meeting and continue through the completion of the project. The airport operator and contractor should conduct onsite safety inspections throughout the project and immediately remedy any deficiencies, whether caused by negligence, oversight, or project scope change.

1.4.2 Assess Airport Operator's Responsibilities.

An airport operator has overall responsibility for all activities on an airport, including construction. This includes the predesign, design, preconstruction, construction, and inspection phases. Additional information on the responsibilities listed below can be found throughout this AC. The airport operator must:

1.4.2.1 Develop a CSPP that complies with the safety guidelines of <u>Chapter 2</u>, <u>Construction Safety and Phasing Plans</u>, and <u>Chapter 3</u>, <u>Guidelines for Writing a CSPP</u>. The airport operator may develop the CSPP internally or have a consultant develop the CSPP for approval by the airport operator. For tenant sponsored projects, approve a CSPP developed by the tenant or its consultant.

- 1.4.2.2 Require, review and approve the SPCD by the contractor that indicates how it will comply with the CSPP and provides details that cannot be determined before contract award.
- 1.4.2.3 Convene a preconstruction meeting with the construction contractor, consultant, airport employees and, if appropriate, tenant sponsor and other tenants to review and discuss project safety before beginning construction activity. The appropriate FAA representatives should be invited to attend the meeting. See <u>AC 150/5370-12</u>, *Quality Management for Federally Funded Airport Construction Projects*. (Note "FAA" refers to the Airports Regional or District Office, the Air Traffic Organization, Flight Standards Service, and other offices that support airport operations, flight regulations, and construction/environmental policies.)
- 1.4.2.4 Ensure contact information is accurate for each representative/point of contact identified in the CSPP and SPCD.
- 1.4.2.5 Hold weekly or, if necessary, daily safety meetings with all affected parties to coordinate activities.
- 1.4.2.6 Notify users, ARFF personnel, and FAA ATO personnel of construction and conditions that may adversely affect the operational safety of the airport via Notices to Airmen (NOTAM) and other methods, as appropriate. Convene a meeting for review and discussion if necessary.
- 1.4.2.7 Ensure construction personnel know applicable airport procedures and changes to those procedures that may affect their work.
- 1.4.2.8 Ensure that all temporary construction signs are located per the scheduled list for each phase of the project.
- 1.4.2.9 Ensure construction contractors and subcontractors undergo training required by the CSPP and SPCD.
- 1.4.2.10 Ensure vehicle and pedestrian operations addressed in the CSPP and SPCD are coordinated with airport tenants, the airport traffic control tower (ATCT), and construction contractors.
- 1.4.2.11 At certificated airports, ensure each CSPP and SPCD is consistent with Part 139.

1.4.2.12 Conduct inspections sufficiently frequently to ensure construction contractors and tenants comply with the CSPP and SPCD and that there are no altered construction activities that could create potential safety hazards.

- 1.4.2.13 Take immediate action to resolve safety deficiencies.
- 1.4.2.14 At airports subject to 49 CFR Part 1542, *Airport Security*, ensure construction access complies with the security requirements of that regulation.
- 1.4.2.15 Notify appropriate parties when conditions exist that invoke provisions of the CSPP and SPCD (for example, implementation of low-visibility operations).
- 1.4.2.16 Ensure prompt submittal of a Notice of Proposed Construction or Alteration (Form 7460-1) for conducting an aeronautical study of potential obstructions such as tall equipment (cranes, concrete pumps, other), stock piles, and haul routes. A separate form may be filed for each potential obstruction, or one form may be filed describing the entire construction area and maximum equipment height. In the latter case, a separate form must be filed for any object beyond or higher than the originally evaluated area/height. The FAA encourages online submittal of forms for expediency at https://oeaaa.faa.gov/oeaaa/external/portal.jsp. The appropriate FAA Airports Regional or District Office can provide assistance in determining which objects require an aeronautical study.
- 1.4.2.17 Ensure prompt transmission of the Airport Sponsor Strategic Event Submission, FAA Form 6000-26, located at https://oeaaa.faa.gov/oeaaa/external/content/AIRPORT_SPONSOR_STRATEGIC_EVENT_SUBMISSION_FORM.pdf, to assure proper coordination for NAS Strategic Interruption per Service Level Agreement with ATO.
- 1.4.2.18 Promptly notify the FAA Airports Regional or District Office of any proposed changes to the CSPP prior to implementation of the change. Changes to the CSPP require review and approval by the airport operator and the FAA. The FAA Airports Regional or District office will determine if further coordination within the FAA is needed. Coordinate with appropriate local and other federal government agencies, such as Environmental Protection Agency (EPA), Occupational Safety and Health Administration (OSHA), Transportation Security Administration (TSA), and the state environmental agency.
- 1.4.3 Define Construction Contractor's Responsibilities.

The contractor is responsible for complying with the CSPP and SPCD. The contractor must:

1.4.3.1 Submit a Safety Plan Compliance Document (SPCD) to the airport operator describing how it will comply with the requirements of the CSPP and supply any details that could not be determined before contract award. The SPCD must include a certification statement by the contractor, indicating an understanding of the operational safety requirements of the CSPP and the assertion of compliance with the approved CSPP and SPCD unless written approval is granted by the airport operator. Any construction practice proposed by the contractor that does not conform to the CSPP and SPCD may impact the airport's operational safety and will require a revision to the CSPP and SPCD and re-coordination with the airport operator and the FAA in advance.

- 1.4.3.2 Have available at all times copies of the CSPP and SPCD for reference by the airport operator and its representatives, and by subcontractors and contractor employees.
- 1.4.3.3 Ensure that construction personnel are familiar with safety procedures and regulations on the airport. Provide a point of contact who will coordinate an immediate response to correct any construction-related activity that may adversely affect the operational safety of the airport. Many projects will require 24-hour coverage.
- 1.4.3.4 Identify in the SPCD the contractor's on-site employees responsible for monitoring compliance with the CSPP and SPCD during construction. At least one of these employees must be on-site when active construction is taking place.
- 1.4.3.5 Conduct sufficient inspections to ensure construction personnel comply with the CSPP and SPCD and that there are no altered construction activities that could create potential safety hazards.
- 1.4.3.6 Restrict movement of construction vehicles and personnel to permitted construction areas by flagging, barricading, erecting temporary fencing, or providing escorts, as appropriate, and as specified in the CSPP and SPCD.
- 1.4.3.7 Ensure that no contractor employees, employees of subcontractors or suppliers, or other persons enter any part of the air operations area (AOA) from the construction site unless authorized.
- 1.4.3.8 Ensure prompt submittal through the airport operator of Form 7460-1 for the purpose of conducting an aeronautical study of contractor equipment such as tall equipment (cranes, concrete pumps, and other equipment), stock piles, and haul routes when different from cases previously filed by the airport operator. The FAA encourages online submittal of forms for expediency at https://oeaaa.faa.gov/oeaaa/external/portal.jsp.

1.4.3.9 Ensure that all necessary safety mitigations are understood by all parties involved, and any special requirements of each construction phase will be fulfilled per the approved timeframe.

1.4.3.10 Participate in pre-construction meetings to review construction limits, safety mitigations, NOTAMs, and understand all special airport operational needs during each phase of the project.

1.4.4 Define Tenant's Responsibilities.

If planning construction activities on leased property, Airport tenants, such as airline operators, fixed base operators, and FAA ATO/Technical Operations sponsoring construction are strongly encouraged to:

- 1. Develop, or have a consultant develop, a project specific CSPP and submit it to the airport operator. The airport operator may forgo a complete CSPP submittal and instead incorporate appropriate operational safety principles and measures addressed in the advisory circular within their tenant lease agreements.
- 2. In coordination with its contractor, develop an SPCD and submit it to the airport operator for approval issued prior to issuance of a Notice to Proceed.
- 3. Ensure that construction personnel are familiar with safety procedures and regulations on the airport during all phases of the construction.
- 4. Provide a point of contact of who will coordinate an immediate response to correct any construction-related activity that may adversely affect the operational safety of the airport.
- 5. Identify in the SPCD the contractor's on-site employees responsible for monitoring compliance with the CSPP and SPCD during construction. At least one of these employees must be on-site when active construction is taking place.
- 6. Ensure that no tenant or contractor employees, employees of subcontractors or suppliers, or any other persons enter any part of the AOA from the construction site unless authorized.
- 7. Restrict movement of construction vehicles to construction areas by flagging and barricading, erecting temporary fencing, or providing escorts, as appropriate, as specified in the CSPP and SPCD.
- 8. Ensure prompt submittal through the airport operator of Form 7460-1 for conducting an aeronautical study of contractor equipment such as tall equipment (cranes, concrete pumps, other), stock piles, and haul routes. The FAA encourages online submittal of forms for expediency at https://oeaaa.faa.gov/oeaaa/external/portal.jsp.
- 9. Participate in pre-construction meetings to review construction limits, safety mitigations, NOTAMs, and understand all special airport operational needs during each phase of the project.

CHAPTER 2. CONSTRUCTION SAFETY AND PHASING PLANS

2.1 **Overview.**

Aviation safety is the primary consideration at airports, especially during construction. The airport operator's CSPP and the contractor's Safety Plan Compliance Document (SPCD) are the primary tools to ensure safety compliance when coordinating construction activities with airport operations. These documents identify all aspects of the construction project that pose a potential safety hazard to airport operations and outline respective mitigation procedures for each hazard. They must provide information necessary for the Airport Operations department to conduct airfield inspections and expeditiously identify and correct unsafe conditions during construction. All aviation safety provisions included within the project drawings, contract specifications, and other related documents must also be reflected in the CSPP and SPCD.

2.2 **Assume Responsibility.**

Operational safety on the airport remains the airport operator's responsibility at all times. The airport operator must develop, certify, and submit for FAA approval each CSPP. It is the airport operator's responsibility to apply the requirements of the FAA approved CSPP. The airport operator must revise the CSPP when conditions warrant changes and must submit the revised CSPP to the FAA for approval. The airport operator must also require and approve a SPCD from the project contractor.

2.3 **Submit the CSPP.**

Construction Safety and Phasing Plans should be developed concurrently with the project design. Milestone versions of the CSPP should be submitted for review and approval as follows. While these milestones are not mandatory, early submission will help to avoid delays. Submittals are preferred in 8.5×11 inch or 11×17 inch format for compatibility with the FAA's Obstruction Evaluation / Airport Airspace Analysis (OE / AAA) process.

2.3.1 Submit an Outline/Draft.

By the time approximately 25% to 30% of the project design is completed, the principal elements of the CSPP should be established. Airport operators are encouraged to submit an outline or draft, detailing all CSPP provisions developed to date, to the FAA for review at this stage of the project design.

2.3.2 Submit a CSPP.

The CSPP should be formally submitted for FAA approval when the project design is 80 percent to 90 percent complete. Since provisions in the CSPP will influence contract costs, it is important to obtain FAA approval in time to include all such provisions in the procurement contract.

2.3.3 Submit an SPCD.

The contractor should submit the SPCD to the airport operator for approval to be issued prior to the Notice to Proceed.

2.3.4 Submit CSPP Revisions.

All revisions to a previously approved CSPP must be re-submitted to the FAA for review and approval/disapproval action.

2.4 Meet CSPP Requirements.

- 2.4.1 To the extent possible, the CSPP should address the following as outlined in <u>Chapter 3</u>, <u>Guidelines for Writing a CSPP</u>. Details that cannot be determined at this stage are to be included in the SPCD.
 - 1. Coordination.
 - a. Contractor progress meetings.
 - b. Scope or schedule changes.
 - c. FAA ATO coordination.
 - 2. Phasing.
 - a. Phase elements.
 - b. Construction safety drawings.
 - 3. Areas and operations affected by the construction activity.
 - a. Identification of affected areas.
 - b. Mitigation of effects.
 - 4. Protection of navigation aids (NAVAIDs).
 - 5. Contractor access.
 - a. Location of stockpiled construction materials.
 - b. Vehicle and pedestrian operations.
 - 6. Wildlife management.
 - a. Trash.
 - b. Standing water.
 - c. Tall grass and seeds.
 - d. Poorly maintained fencing and gates.
 - e. Disruption of existing wildlife habitat.
 - 7. Foreign Object Debris (FOD) management.
 - 8. Hazardous materials (HAZMAT) management.
 - 9. Notification of construction activities.

- a. Maintenance of a list of responsible representatives/ points of contact.
- b. NOTAM.
- c. Emergency notification procedures.
- d. Coordination with ARFF Personnel.
- e. Notification to the FAA.
- 10. Inspection requirements.
 - a. Daily (or more frequent) inspections.
 - b. Final inspections.
- 11. Underground utilities.
- 12. Penalties.
- 13. Special conditions.
- 14. Runway and taxiway visual aids. Marking, lighting, signs, and visual NAVAIDs.
 - a. General.
 - b. Markings.
 - c. Lighting and visual NAVAIDs.
 - d. Signs, temporary, including orange construction signs, and permanent signs.
- 15. Marking and signs for access routes.
- 16. Hazard marking and lighting.
 - a. Purpose.
 - b. Equipment.
- 17. Work zone lighting for nighttime construction (if applicable).
- 18. Protection of runway and taxiway safety areas, object free areas, obstacle free zones, and approach/departure surfaces.
 - a. Runway Safety Area (RSA).
 - b. Runway Object Free Area (ROFA).
 - c. Taxiway Safety Area (TSA). Provide details for any adjustments to Taxiway Safety Area width to allow continued operation of smaller aircraft. See paragraph 2.22.3.
 - d. Taxiway Object Free Area (TOFA). Provide details for any continued aircraft operations while construction occurs within the TOFA. See paragraph 2.22.4.
 - e. Obstacle Free Zone (OFZ).
 - f. Runway approach/departure surfaces.
- 19. Other limitations on construction.
 - a. Prohibitions.

- b. Restrictions.
- 2.4.2 The Safety Plan Compliance Document (SPCD) should include a general statement by the construction contractor that he/she has read and will abide by the CSPP. In addition, the SPCD must include all supplemental information that could not be included in the CSPP prior to the contract award. The contractor statement should include the name of the contractor, the title of the project CSPP, the approval date of the CSPP, and a reference to any supplemental information (that is, "I, (Name of Contractor), have read the (Title of Project) CSPP, approved on (Date), and will abide by it as written and with the following additions as noted:"). The supplemental information in the SPCD should be written to match the format of the CSPP indicating each subject by corresponding CSPP subject number and title. If no supplemental information is necessary for any specific subject, the statement, "No supplemental information," should be written after the corresponding subject title. The SPCD should not duplicate information in the CSPP:
 - 1. Coordination. Discuss details of proposed safety meetings with the airport operator and with contractor employees and subcontractors.
 - 2. Phasing. Discuss proposed construction schedule elements, including:
 - a. Duration of each phase.
 - b. Daily start and finish of construction, including "night only" construction.
 - c. Duration of construction activities during:
 - i. Normal runway operations.
 - ii. Closed runway operations.
 - iii. Modified runway "Aircraft Reference Code" usage.
 - 3. Areas and operations affected by the construction activity. These areas and operations should be identified in the CSPP and should not require an entry in the SPCD.
 - 4. Protection of NAVAIDs. Discuss specific methods proposed to protect operating NAVAIDs.
 - 5. Contractor access. Provide the following:
 - a. Details on how the contractor will maintain the integrity of the airport security fence (gate guards, daily log of construction personnel, and other).
 - b. Listing of individuals requiring driver training (for certificated airports and as requested).
 - c. Radio communications.
 - i. Types of radios and backup capabilities.
 - ii. Who will be monitoring radios.
 - iii. Who to contact if the ATCT cannot reach the contractor's designated person by radio.

- d. Details on how the contractor will escort material delivery vehicles.
- 6. Wildlife management. Discuss the following:
 - a. Methods and procedures to prevent wildlife attraction.
 - b. Wildlife reporting procedures.
- 7. Foreign Object Debris (FOD) management. Discuss equipment and methods for control of FOD, including construction debris and dust.
- 8. Hazardous Materials (HAZMAT) management. Discuss equipment and methods for responding to hazardous spills.
- 9. Notification of construction activities. Provide the following:
 - a. Contractor points of contact.
 - b. Contractor emergency contact.
 - c. Listing of tall or other requested equipment proposed for use on the airport and the timeframe for submitting 7460-1 forms not previously submitted by the airport operator.
 - d. Batch plant details, including 7460-1 submittal.
- 10. Inspection requirements. Discuss daily (or more frequent) inspections and special inspection procedures.
- 11. Underground utilities. Discuss proposed methods of identifying and protecting underground utilities.
- 12. Penalties. Penalties should be identified in the CSPP and should not require an entry in the SPCD.
- 13. Special conditions. Discuss proposed actions for each special condition identified in the CSPP.
- 14. Runway and taxiway visual aids. Including marking, lighting, signs, and visual NAVAIDs. Discuss proposed visual aids including the following:
 - a. Equipment and methods for covering signage and airfield lights.
 - b. Equipment and methods for temporary closure markings (paint, fabric, other).
 - c. Temporary orange construction signs.
 - d. Types of temporary Visual Guidance Slope Indicators (VGSI).
- 15. Marking and signs for access routes. Discuss proposed methods of demarcating access routes for vehicle drivers.
- 16. Hazard marking and lighting. Discuss proposed equipment and methods for identifying excavation areas.
- 17. Work zone lighting for nighttime construction (if applicable). Discuss proposed equipment, locations, aiming, and shielding to prevent interference with air traffic control and aircraft operations.

18. Protection of runway and taxiway safety areas, object free areas, obstacle free zones, and approach/departure surfaces. Discuss proposed methods of identifying, demarcating, and protecting airport surfaces including:

- a. Equipment and methods for maintaining Taxiway Safety Area standards.
- b. Equipment and methods to ensure the safe passage of aircraft where Taxiway Safety Area or Taxiway Object Free Area standards cannot be maintained.
- c. Equipment and methods for separation of construction operations from aircraft operations, including details of barricades.
- 19. Other limitations on construction should be identified in the CSPP and should not require an entry in the SPCD.

2.5 Coordination.

Airport operators, or tenants responsible for design, bidding and conducting construction on their leased properties, should ensure at all project developmental stages, such as predesign, prebid, and preconstruction conferences, they capture the subject of airport operational safety during construction (see <u>AC 150/5370-12</u>, *Quality Management for Federally Funded Airport Construction Projects*). In addition, the following should be coordinated as required:

2.5.1 <u>Progress Meetings.</u>

Operational safety should be a standing agenda item for discussion during progress meetings throughout the project developmental stages.

2.5.2 Scope or Schedule Changes.

Changes in the scope or duration at any of the project stages may require revisions to the CSPP and review and approval by the airport operator and the FAA (see paragraph 1.4.2.17).

2.5.3 FAA ATO Coordination.

Early coordination with FAA ATO is highly recommended during the design phase and is required for scheduling Technical Operations shutdowns prior to construction. Coordination is critical to restarts of NAVAID services and to the establishment of any special procedures for the movement of aircraft. Formal agreements between the airport operator and appropriate FAA offices are recommended. All relocation or adjustments to NAVAIDs, or changes to final grades in critical areas, should be coordinated with FAA ATO and may require an FAA flight inspection prior to restarting the facility. Flight inspections must be coordinated and scheduled well in advance of the intended facility restart. Flight inspections may require a reimbursable agreement between the airport operator and FAA ATO. Reimbursable agreements should be coordinated a minimum of 12 months prior to the start of construction. (See paragraph 2.13.5.3.2 for required FAA notification regarding FAA-owned NAVAIDs.)

2.6 **Phasing.**

Once it has been determined what types and levels of airport operations will be maintained, the most efficient sequence of construction may not be feasible. In this case, the sequence of construction may be phased to gain maximum efficiency while allowing for the required operations. The development of the resulting construction phases should be coordinated with local Air Traffic personnel and airport users. The sequenced construction phases established in the CSPP must be incorporated into the project design and must be reflected in the contract drawings and specifications.

2.6.1 Phase Elements.

For each phase the CSPP should detail:

- Areas closed to aircraft operations.
- Duration of closures.
- Taxi routes and/or areas of reduced TSA and TOFA to reflect reduced ADG use.
- ARFF access routes.
- Construction staging, disposal, and cleanout areas.
- Construction access and haul routes.
- Impacts to NAVAIDs.
- Lighting, marking, and signing changes.
- Available runway length and/or reduced RSA and ROFA to reflect reduced ADG use.
- Declared distances (if applicable).
- Required hazard marking, lighting, and signing.
- Work zone lighting for nighttime construction (if applicable).
- Lead times for required notifications.

2.6.2 Construction Safety Drawings.

Drawings specifically indicating operational safety procedures and methods in affected areas (i.e., construction safety drawings) should be developed for each construction phase. Such drawings should be included in the CSPP as referenced attachments and should also be included in the contract drawing package.

2.7 Areas and Operations Affected by Construction Activity.

Runways and taxiways should remain in use by aircraft to the maximum extent possible without compromising safety. Pre-meetings with the FAA ATO will support operational simulations. See <u>Appendix E</u> for an example of a table showing temporary operations versus current operations. The tables in <u>Appendix E</u> can be useful for coordination among all interested parties, including FAA Lines of Business.

2.7.1 Identification of Affected Areas.

Identifying areas and operations affected by the construction helps to determine possible safety problems. The affected areas should be identified in the construction safety drawings for each construction phase. (See paragraph <u>2.6.2</u>.) Of particular concern are:

2.7.1.1 Closing, or Partial Closing, of Runways, Taxiways and Aprons, and Displaced Thresholds.

When a runway is partially closed, a portion of the pavement is unavailable for any aircraft operation, meaning taxiing, landing, or takeoff in either direction on that pavement is prohibited. A displaced threshold, by contrast, is established to ensure obstacle clearance and adequate safety area for landing aircraft. The pavement prior to the displaced threshold is normally available for take-off in the direction of the displacement and for landing and takeoff in the opposite direction. Misunderstanding this difference, may result in issuance of an inaccurate NOTAM, and can lead to a hazardous condition.

2.7.1.1.1 Partially Closed Runways.

The temporarily closed portion of a partially closed runway will generally extend from the threshold to a taxiway that may be used for entering and exiting the runway. If the closed portion extends to a point between taxiways, pilots will have to back-taxi on the runway, which is an undesirable operation. See <u>Figure 2-1</u> for a desirable configuration.

2.7.1.1.2 Displaced Thresholds.

Since the portion of the runway pavement between the permanent threshold and a standard displaced threshold is available for takeoff and for landing in the opposite direction, the temporary displaced threshold need not be located at an entrance/exit taxiway. See <u>Figure 2-2</u>.

- 2.7.1.2 Closing of aircraft rescue and fire fighting access routes.
- 2.7.1.3 Closing of access routes used by airport and airline support vehicles.
- 2.7.1.4 Interruption of utilities, including water supplies for fire fighting.
- 2.7.1.5 Approach/departure surfaces affected by heights of objects.
- 2.7.1.6 Construction areas, storage areas, and access routes near runways, taxiways, aprons, or helipads.




Figure 2-1. Temporary Partially Closed Runway

OBLITERATE AIMING POINT MARKING INSTALL TEMPORARY RUNWAY DESIGNATION, ARROWHEADS AND DISPLACED THRESHOLD BAR USE DECLARED DISTANCES TO PROVIDE RSA AND CLEAR INSTALL TEMPORARY RUNWAY THRESHOLD LIGHTING (INBOARD LIGHT IS YELLOW/GREEN, APPROACH/DEPARTURE INSTALL TEMPORARY ALL OTHERS ARE BLANK/GREEN) SURFACE REIL (OPTIONAL) INSTALL TEMPORARY ARROWS TO EXISTING CENTERLINE MARKING, SEE NOTE OBLITERATE TOUCHDOWN ZONE AND CENTERLINE TURN CENTERLINE LIGHTS OFF IF DISPLACEMENT OF THRESHOLD IS MORE THAN 700' OBLITERATE RUNWAY DESIGNATION MARKING CHANGE EXISTING LIGHTS TO YELLOW/RED RUNWAY SAFETY AREA EXTENDS REQUIRED DISTANCE PRIOR TO THRESHOLD **∀\∀→ ←**l∀ OBLITERATE THRESHOLD MARKINGS INSTALL RED/RED LIGHTS NOTES: 1. THIS FIGURE IS A SCHEMATIC REPRESENTATION BLAST FENCE OUTSIDE CONSTRUCTION AREA AND NOT INTENDED FOR INSPECTION PURPOSES. REFER TO THE APPLICABLE ACS FOR GUIDANCE. TOFA TO PROTECT CONSTRUCTION ZONE (MAY BE REQUIRED) 2. THIS FIGURE DIPICTS A TYPICAL TEMPORARY DISPLACED THRESHOLD. THE ACTUAL TEMPORARY MEASURES WILL VARY PER EACH SPECIFIC NOT TO SCALE 3. DURING CONSTRUCTION VASI AND PAPI SYSTEMS SHOULD BE TAKEN OUT OF SERVICE.

Figure 2-2. Temporary Displaced Threshold

Note: See paragraph 2.18.2.5.

2.7.2 <u>Mitigation of Effects.</u>

Establishment of specific procedures is necessary to maintain the safety and efficiency of airport operations. The CSPP must address:

- 2.7.2.1 Temporary changes to runway and/or taxi operations.
- 2.7.2.2 Detours for ARFF and other airport vehicles.
- 2.7.2.3 Maintenance of essential utilities.
- 2.7.2.4 Temporary changes to air traffic control procedures. Such changes must be coordinated with the ATO.

2.8 Navigation Aid (NAVAID) Protection.

Before commencing construction activity, parking vehicles, or storing construction equipment and materials near a NAVAID, coordinate with the appropriate FAA ATO/Technical Operations office to evaluate the effect of construction activity and the required distance and direction from the NAVAID. (See paragraph 2.13.5.3.) Construction activities, materials/equipment storage, and vehicle parking near electronic NAVAIDs require special consideration since they may interfere with signals essential to air navigation. If any NAVAID may be affected, the CSPP and SPCD must show an understanding of the "critical area" associated with each NAVAID and describe how it will be protected. Where applicable, the operational critical areas of NAVAIDs should be graphically delineated on the project drawings. Pay particular attention to stockpiling material, as well as to movement and parking of equipment that may interfere with line of sight from the ATCT or with electronic emissions. Interference from construction equipment and activities may require NAVAID shutdown or adjustment of instrument approach minimums for low visibility operations. This condition requires that a NOTAM be filed (see paragraph 2.13.2). Construction activities and materials/equipment storage near a NAVAID must not obstruct access to the equipment and instruments for maintenance. Submittal of a 7460-1 form is required for construction vehicles operating near FAA NAVAIDs. (See paragraph 2.13.5.3.)

2.9 Contractor Access.

The CSPP must detail the areas to which the contractor must have access, and explain how contractor personnel will access those areas. Specifically address:

2.9.1 Location of Stockpiled Construction Materials.

Stockpiled materials and equipment storage are not permitted within the RSA and OFZ, and if possible should not be permitted within the Object Free Area (OFA) of an operational runway. Stockpiling material in the OFA requires submittal of a 7460-1 form and justification provided to the appropriate FAA Airports Regional or District Office for approval. The airport operator must ensure that stockpiled materials and equipment adjacent to these areas are prominently marked and lighted during hours of restricted visibility or darkness. (See paragraph 2.18.2.) This includes determining and

verifying that materials are stabilized and stored at an approved location so as not to be a hazard to aircraft operations and to prevent attraction of wildlife and foreign object damage from blowing or tracked material. See paragraphs <u>2.10</u> and <u>2.11</u>.

2.9.2 Vehicle and Pedestrian Operations.

The CSPP should include specific vehicle and pedestrian requirements. Vehicle and pedestrian access routes for airport construction projects must be controlled to prevent inadvertent or unauthorized entry of persons, vehicles, or animals onto the AOA. The airport operator should coordinate requirements for vehicle operations with airport tenants, contractors, and the FAA air traffic manager. In regard to vehicle and pedestrian operations, the CSPP should include the following, with associated training requirements:

2.9.2.1 **Construction Site Parking.**

Designate in advance vehicle parking areas for contractor employees to prevent any unauthorized entry of persons or vehicles onto the AOA. These areas should provide reasonable contractor employee access to the job site.

2.9.2.2 Construction Equipment Parking.

Contractor employees must park and service all construction vehicles in an area designated by the airport operator outside the OFZ and never in the safety area of an active runway or taxiway. Unless a complex setup procedure makes movement of specialized equipment infeasible, inactive equipment must not be parked on a closed taxiway or runway. If it is necessary to leave specialized equipment on a closed taxiway or runway at night, the equipment must be well lighted. Employees should also park construction vehicles outside the OFA when not in use by construction personnel (for example, overnight, on weekends, or during other periods when construction is not active). Parking areas must not obstruct the clear line of sight by the ATCT to any taxiways or runways under air traffic control nor obstruct any runway visual aids, signs, or navigation aids. The FAA must also study those areas to determine effects on airport design criteria, surfaces established by 14 CFR Part 77, Safe, Efficient Use, and Preservation of the Navigable Airspace (Part 77), and on NAVAIDs and Instrument Approach Procedures (IAP). See paragraph 2.13.1 for further information.

2.9.2.3 Access and Haul Roads.

Determine the construction contractor's access to the construction sites and haul roads. Do not permit the construction contractor to use any access or haul roads other than those approved. Access routes used by contractor vehicles must be clearly marked to prevent inadvertent entry to areas open to airport operations. Pay special attention to ensure that if construction traffic is to share or cross any ARFF routes that ARFF right of way is not impeded at any time, and that construction traffic on haul

roads does not interfere with NAVAIDs or approach surfaces of operational runways. Address whether access gates will be blocked or inoperative or if a rally point will be blocked or inaccessible.

- 2.9.2.4 Marking and lighting of vehicles in accordance with <u>AC 150/5210-5</u>, *Painting, Marking, and Lighting of Vehicles Used on an Airport.*
- 2.9.2.5 Description of proper vehicle operations on various areas under normal, lost communications, and emergency conditions.
- 2.9.2.6 Required escorts.
- 2.9.2.7 Training Requirements for Vehicle Drivers to Ensure Compliance with the Airport Operator's Vehicle Rules and Regulations.

Specific training should be provided to vehicle operators, including those providing escorts. See <u>AC 150/5210-20</u>, *Ground Vehicle Operations on Airports*, for information on training and records maintenance requirements.

2.9.2.8 **Situational Awareness.**

Vehicle drivers must confirm by personal observation that no aircraft is approaching their position (either in the air or on the ground) when given clearance to cross a runway, taxiway, or any other area open to airport operations. In addition, it is the responsibility of the escort vehicle driver to verify the movement/position of all escorted vehicles at any given time. At non-towered airports, all aircraft movements and flight operations rely on aircraft operators to self-report their positions and intentions. However, there is no requirement for an aircraft to have radio communications. Because aircraft do not always broadcast their positions or intentions, visual checking, radio monitoring, and situational awareness of the surroundings is critical to safety.

2.9.2.9 **Two-Way Radio Communication Procedures.**

2.9.2.9.1 General.

The airport operator must ensure that tenant and construction contractor personnel engaged in activities involving unescorted operation on aircraft movement areas observe the proper procedures for communications, including using appropriate radio frequencies at airports with and without ATCT. When operating vehicles on or near open runways or taxiways, construction personnel must understand the critical importance of maintaining radio contact, as directed by the airport operator, with:

- 1. Airport operations
- 2. ATCT

3. Common Traffic Advisory Frequency (CTAF), which may include UNICOM, MULTICOM.

4. Automatic Terminal Information Service (ATIS). This frequency is useful for monitoring conditions on the airport. Local air traffic will broadcast information regarding construction related runway closures and "shortened" runways on the ATIS frequency.

2.9.2.9.2 Areas Requiring Two-Way Radio Communication with the ATCT.

Vehicular traffic crossing active movement areas must be controlled either by two-way radio with the ATCT, escort, flagman, signal light, or other means appropriate for the particular airport.

2.9.2.9.3 <u>Frequencies to be Used.</u>

The airport operator will specify the frequencies to be used by the contractor, which may include the CTAF for monitoring of aircraft operations. Frequencies may also be assigned by the airport operator for other communications, including any radio frequency in compliance with Federal Communications Commission requirements. At airports with an ATCT, the airport operator will specify the frequency assigned by the ATCT to be used between contractor vehicles and the ATCT.

- 2.9.2.9.4 Proper radio usage, including read back requirements.
- 2.9.2.9.5 Proper phraseology, including the International Phonetic Alphabet.

2.9.2.9.6 Light Gun Signals.

Even though radio communication is maintained, escort vehicle drivers must also familiarize themselves with ATCT light gun signals in the event of radio failure. See the FAA safety placard "Ground Vehicle Guide to Airport Signs and Markings." This safety placard may be downloaded through the Runway Safety Program Web site at http://www.faa.gov/airports/runway_safety/publications/ (see "Signs & Markings Vehicle Dashboard Sticker") or obtained from the FAA Airports Regional Office.

2.9.2.10 Maintenance of the secured area of the airport, including:

2.9.2.10.1 Fencing and Gates.

Airport operators and contractors must take care to maintain security during construction when access points are created in the security fencing to permit the passage of construction vehicles or personnel. Temporary gates should be equipped so they can be securely closed and locked to prevent access by animals and unauthorized people. Procedures should be in place to ensure that only authorized persons and vehicles have access to the AOA and to prohibit "piggybacking" behind another person or vehicle. The Department of Transportation (DOT) document DOT/FAA/AR-

00/52, Recommended Security Guidelines for Airport Planning and Construction, provides more specific information on fencing. A copy of this document can be obtained from the Airport Consultants Council, Airports Council International, or American Association of Airport Executives.

2.9.2.10.2 <u>Badging Requirements.</u>

Airports subject to 49 CFR Part 1542, *Airport Security*, must meet standards for access control, movement of ground vehicles, and identification of construction contractor and tenant personnel.

2.10 Wildlife Management.

The CSPP and SPCD must be in accordance with the airport operator's wildlife hazard management plan, if applicable. See <u>AC 150/5200-33</u>, *Hazardous Wildlife Attractants On or Near Airports*, and CertAlert 98-05, *Grasses Attractive to Hazardous Wildlife*. Construction contractors must carefully control and continuously remove waste or loose materials that might attract wildlife. Contractor personnel must be aware of and avoid construction activities that can create wildlife hazards on airports, such as:

2.10.1 Trash.

Food scraps must be collected from construction personnel activity.

2.10.2 Standing Water.

2.10.3 Tall Grass and Seeds.

Requirements for turf establishment can be at odds with requirements for wildlife control. Grass seed is attractive to birds. Lower quality seed mixtures can contain seeds of plants (such as clover) that attract larger wildlife. Seeding should comply with the guidance in <u>AC 150/5370-10</u>, *Standards for Specifying Construction of Airports*, Item T-901, Seeding. Contact the local office of the United Sates Department of Agriculture Soil Conservation Service or the State University Agricultural Extension Service (County Agent or equivalent) for assistance and recommendations. These agencies can also provide liming and fertilizer recommendations.

2.10.4 Poorly Maintained Fencing and Gates.

See paragraph 2.9.2.10.1.

2.10.5 Disruption of Existing Wildlife Habitat.

While this will frequently be unavoidable due to the nature of the project, the CSPP should specify under what circumstances (location, wildlife type) contractor personnel should immediately notify the airport operator of wildlife sightings.

2.11 Foreign Object Debris (FOD) Management.

Waste and loose materials, commonly referred to as FOD, are capable of causing damage to aircraft landing gears, propellers, and jet engines. Construction contractors must not leave or place FOD on or near active aircraft movement areas. Materials capable of creating FOD must be continuously removed during the construction project. Fencing (other than security fencing) or covers may be necessary to contain material that can be carried by wind into areas where aircraft operate. See <u>AC 150/5210-24</u>, *Foreign Object Debris (FOD) Management*.

2.12 Hazardous Materials (HAZMAT) Management.

Contractors operating construction vehicles and equipment on the airport must be prepared to expeditiously contain and clean-up spills resulting from fuel or hydraulic fluid leaks. Transport and handling of other hazardous materials on an airport also requires special procedures. See <u>AC 150/5320-15</u>, *Management of Airport Industrial Waste*.

2.13 **Notification of Construction Activities.**

The CSPP and SPCD must detail procedures for the immediate notification of airport users and the FAA of any conditions adversely affecting the operational safety of the airport. It must address the notification actions described below, as applicable.

2.13.1 List of Responsible Representatives/points of contact for all involved parties, and procedures for contacting each of them, including after hours.

2.13.2 NOTAMs.

Only the airport operator may initiate or cancel NOTAMs on airport conditions, and is the only entity that can close or open a runway. The airport operator must coordinate the issuance, maintenance, and cancellation of NOTAMs about airport conditions resulting from construction activities with tenants and the local air traffic facility (control tower, approach control, or air traffic control center), and must either enter the NOTAM into NOTAM Manager, or provide information on closed or hazardous conditions on airport movement areas to the FAA Flight Service Station (FSS) so it can issue a NOTAM. The airport operator must file and maintain a list of authorized representatives with the FSS. Refer to <u>AC 150/5200-28</u>, *Notices to Airmen (NOTAMs) for Airport Operators*, for a sample NOTAM form. Only the FAA may issue or cancel NOTAMs on shutdown or irregular operation of FAA owned facilities. Any person having reason to believe that a NOTAM is missing, incomplete, or inaccurate must notify the airport operator. See paragraph <u>2.7.1.1</u> about issuing NOTAMs for partially closed runways versus runways with displaced thresholds.

2.13.3 Emergency notification procedures for medical, fire fighting, and police response.

2.13.4 Coordination with ARFF.

The CSPP must detail procedures for coordinating through the airport sponsor with ARFF personnel, mutual aid providers, and other emergency services if construction requires:

- 1. The deactivation and subsequent reactivation of water lines or fire hydrants, or
- 2. The rerouting, blocking and restoration of emergency access routes, or
- 3. The use of hazardous materials on the airfield.

2.13.5 Notification to the FAA.

2.13.5.1 **Part 77.**

Any person proposing construction or alteration of objects that affect navigable airspace, as defined in Part 77, must notify the FAA. This includes construction equipment and proposed parking areas for this equipment (i.e., cranes, graders, other equipment) on airports. FAA Form 7460-1, *Notice of Proposed Construction or Alteration*, can be used for this purpose and submitted to the appropriate FAA Airports Regional or District Office. See <u>Appendix A</u> to download the form. Further guidance is available on the FAA web site at <u>oeaaa.faa.gov</u>.

2.13.5.2 **Part 157.**

With some exceptions, Title 14 CFR Part 157, *Notice of Construction*, *Alteration, Activation, and Deactivation of Airports*, requires that the airport operator notify the FAA in writing whenever a non-Federally funded project involves the construction of a new airport; the construction, realigning, altering, activating, or abandoning of a runway, landing strip, or associated taxiway; or the deactivation or abandoning of an entire airport. Notification involves submitting FAA Form 7480-1, *Notice of Landing Area Proposal*, to the nearest FAA Airports Regional or District Office. See <u>Appendix A</u> to download the form.

2.13.5.3 **NAVAIDs.**

For emergency (short-notice) notification about impacts to both airport owned and FAA owned NAVAIDs, contact: 866-432-2622.

2.13.5.3.1 Airport Owned/FAA Maintained.

If construction operations require a shutdown of 24 hours or greater in duration, or more than 4 hours daily on consecutive days, of a NAVAID owned by the airport but maintained by the FAA, provide a 45-day minimum notice to FAA ATO/Technical Operations prior to facility shutdown, using Strategic Event Coordination (SEC) Form 6000.26 contained within FAA Order 6000.15, *General Maintenance Handbook for National Airspace System (NAS) Facilities*.

2.13.5.3.2 FAA Owned.

1. The airport operator must notify the appropriate FAA ATO Service Area Planning and Requirements (P&R) Group a minimum of 45 days prior to implementing an event that causes impacts to NAVAIDs, using SEC Form 6000.26.

2. Coordinate work for an FAA owned NAVAID shutdown with the local FAA ATO/Technical Operations office, including any necessary reimbursable agreements and flight checks. Detail procedures that address unanticipated utility outages and cable cuts that could impact FAA NAVAIDs. Refer to active Service Level Agreement with ATO for specifics.

2.14 **Inspection Requirements.**

2.14.1 <u>Daily Inspections.</u>

Inspections should be conducted at least daily, but more frequently if necessary to ensure conformance with the CSPP. A sample checklist is provided in <u>Appendix D</u>, <u>Construction Project Daily Safety Inspection Checklist</u>. See also <u>AC 150/5200-18</u>, *Airport Safety Self-Inspection*. Airport operators holding a Part 139 certificate are required to conduct self-inspections during unusual conditions, such as construction activities, that may affect safe air carrier operations.

2.14.2 <u>Interim Inspections.</u>

Inspections should be conducted of all areas to be (re)opened to aircraft traffic to ensure the proper operation of lights and signs, for correct markings, and absence of FOD. The contractor should conduct an inspection of the work area with airport operations personnel. The contractor should ensure that all construction materials have been secured, all pavement surfaces have been swept clean, all transition ramps have been properly constructed, and that surfaces have been appropriately marked for aircraft to operate safely. Only if all items on the list meet with the airport operator's approval should the air traffic control tower be notified to open the area to aircraft operations. The contractor should be required to retain a suitable workforce and the necessary equipment at the work area for any last minute cleanup that may be requested by the airport operator prior to opening the area.

2.14.3 <u>Final Inspections.</u>

New runways and extended runway closures may require safety inspections at certificated airports prior to allowing air carrier service. Coordinate with the FAA Airport Certification Safety Inspector (ACSI) to determine if a final inspection will be necessary.

2.15 Underground Utilities.

The CSPP and/or SPCD must include procedures for locating and protecting existing underground utilities, cables, wires, pipelines, and other underground facilities in excavation areas. This may involve coordinating with public utilities and FAA ATO/Technical Operations. Note that "One Call" or "Miss Utility" services do not include FAA ATO/Technical Operations.

2.16 **Penalties.**

The CSPP should detail penalty provisions for noncompliance with airport rules and regulations and the safety plans (for example, if a vehicle is involved in a runway incursion). Such penalties typically include rescission of driving privileges or access to the AOA.

2.17 **Special Conditions.**

The CSPP must detail any special conditions that affect the operation of the airport and will require the activation of any special procedures (for example, low-visibility operations, snow removal, aircraft in distress, aircraft accident, security breach, Vehicle / Pedestrian Deviation (VPD) and other activities requiring construction suspension/resumption).

2.18 Runway and Taxiway Visual Aids.

This includes marking, lighting, signs, and visual NAVAIDs. The CSPP must ensure that areas where aircraft will be operating are clearly and visibly separated from construction areas, including closed runways. Throughout the duration of the construction project, verify that these areas remain clearly marked and visible at all times and that marking, lighting, signs, and visual NAVAIDs that are to continue to perform their functions during construction remain in place and operational. Visual NAVAIDs that are not serving their intended function during construction must be temporarily disabled, covered, or modified as necessary. The CSPP must address the following, as appropriate:

2.18.1 General.

Airport markings, lighting, signs, and visual NAVAIDs must be clearly visible to pilots, not misleading, confusing, or deceptive. All must be secured in place to prevent movement by prop wash, jet blast, wing vortices, and other wind currents and constructed of materials that will minimize damage to an aircraft in the event of inadvertent contact. Items used to secure such markings must be of a color similar to the marking.

2.18.2 Markings.

During the course of construction projects, temporary pavement markings are often required to allow for aircraft operations during or between work periods. During the design phase of the project, the designer should coordinate with the project manager,

airport operations, airport users, the FAA Airports project manager, and Airport Certification Safety Inspector for Part 139 airports to determine minimum temporary markings. The FAA Airports project manager will, wherever a runway is closed, coordinate with the appropriate FAA Flight Standards Office and disseminate findings to all parties. Where possible, the temporary markings on finish grade pavements should be placed to mirror the dimensions of the final markings. Markings must be in compliance with the standards of <u>AC 150/5340-1</u>, *Standards for Airport Markings*, except as noted herein. Runways and runway exit taxiways closed to aircraft operations are marked with a yellow X. The preferred visual aid to depict temporary runway closure is the lighted X signal placed on or near the runway designation numbers. (See paragraph <u>2.18.2.1.2</u>.)

2.18.2.1 Closed Runways and Taxiways.

2.18.2.1.1 Permanently Closed Runways.

For runways, obliterate the threshold marking, runway designation marking, and touchdown zone markings, and place an X at each end and at 1,000-foot (300 m) intervals. For a multiple runway environment, if the lighted X on a designated number will be located in the RSA of an adjacent active runway, locate the lighted X farther down the closed runway to clear the RSA of the active runway. In addition, the closed runway numbers located in the RSA of an active runway must be marked with a flat yellow X.

2.18.2.1.2 Temporarily Closed Runways.

For runways that have been temporarily closed, place an X at each end of the runway directly on or as near as practicable to the runway designation numbers. For a multiple runway environment, if the lighted X on a designated number will be located in the RSA of an adjacent active runway, locate the lighted X farther down the closed runway to clear the RSA of the active runway. In addition, the closed runway numbers located in the RSA of an active runway must be marked with a flat yellow X. See Figure 2-3. See also paragraph 2.18.3.3.

2.18.2.1.3 Partially Closed Runways and Displaced Thresholds.

When threshold markings are needed to identify the temporary beginning of the runway that is available for landing, the markings must comply with AC 150/5340-1. An X is not used on a partially closed runway or a runway with a displaced threshold. See paragraph 2.7.1.1 for the difference between partially closed runways and runways with displaced thresholds. Because of the temporary nature of threshold displacement due to construction, it is not necessary to re-adjust the existing runway centerline markings to meet standard spacing for a runway with a visual approach. Some of the requirements below may be waived in the cases of low-activity airports and/or short duration changes that are measured in days rather than weeks. Consider whether the presence of an airport traffic

control tower allows for the development of special procedures. Contact the appropriate FAA Airports Regional or District Office for assistance.




Figure 2-3. Markings for a Temporarily Closed Runway

- 1. **Partially Closed Runways.** Pavement markings for temporary closed portions of the runway consist of a runway threshold bar, runway designation, and yellow chevrons to identify pavement areas that are unsuitable for takeoff or landing (see <u>AC 150/5340-1</u>). Obliterate or cover markings prior to the moved threshold. Existing touchdown zone markings beyond the moved threshold may remain in place. Obliterate aiming point markings. Issue appropriate NOTAMs regarding any nonstandard markings. See <u>Figure 2-4</u>.
- 2. **Displaced Thresholds.** Pavement markings for a displaced threshold consist of a runway threshold bar, runway designation, and white arrowheads with and without arrow shafts. These markings are required to identify the portion of the runway before the displaced threshold to provide centerline guidance for pilots during approaches, takeoffs, and landing rollouts from the opposite direction. See <u>AC 150/5340-1</u>. Obliterate markings prior to the displaced threshold. Existing touchdown zone markings beyond the displaced threshold may remain in place. Obliterate aiming point markings. Issue appropriate NOTAMs regarding any nonstandard markings. See <u>Figure 2-2</u>.

2.18.2.1.4 <u>Taxiways.</u>

1. **Permanently Closed Taxiways.** AC 150/5300-13 Airport Design, notes that it is preferable to remove the pavement, but for pavement that is to remain, place an X at the entrance to both ends of the closed section. Obliterate taxiway centerline markings, including runway leadoff lines, leading to the closed taxiway. See Figure 2-4.

Figure 2-4. Temporary Taxiway Closure



2. **Temporarily Closed Taxiways.** Place barricades outside the safety area of intersecting taxiways. For runway/taxiway intersections, place an X at the entrance to the closed taxiway from the runway. If the taxiway will be closed for an extended period, obliterate taxiway centerline markings, including runway leadoff lines and taxiway to taxiway turns, leading to the closed section. Always obliterate runway lead-off lines for high speed exits, regardless of the duration of the closure. If the centerline markings will be reused upon reopening the taxiway, it is preferable to paint over the marking. This will result in less damage to the pavement when the upper layer of paint is ultimately removed. See Figure 2-4.


2.18.2.1.5 Temporarily Closed Airport.

When the airport is closed temporarily, mark all the runways as closed.

- 2.18.2.2 If unable to paint temporary markings on the pavement, construct them from any of the following materials: fabric, colored plastic, painted sheets of plywood, or similar materials. They must be properly configured and appropriately secured to prevent movement by prop wash, jet blast, or other wind currents. Items used to secure such markings must be of a color similar to the marking.
- 2.18.2.3 It may be necessary to remove or cover runway markings, including but not limited to, runway designation markings, threshold markings, centerline markings, edge stripes, touchdown zone markings and aiming point markings, depending on the length of construction and type of activity at the airport. When removing runway markings, apply the same treatment to areas between stripes or numbers, as the cleaned area will appear to pilots as a marking in the shape of the treated area.
- 2.18.2.4 If it is not possible to install threshold bars, chevrons, and arrows on the pavement, "temporary outboard white threshold bars and yellow arrowheads", see <u>Figure 2-5</u>, may be used. Locate them outside of the runway pavement surface on both sides of the runway. The dimensions must be as shown in <u>Figure 2-5</u>. If the markings are not discernible on grass or snow, apply a black background with appropriate material over the ground to ensure they are clearly visible.
- 2.18.2.5 The application rate of paint to mark a short-term temporary runway and taxiway markings may deviate from the standard (see Item P-620, "Runway and Taxiway Painting," in <u>AC 150/5370-10</u>), but the dimensions must meet the existing standards. When applying temporary markings at night, it is recommended that the fast curing, Type II paint be used to help offset the higher humidity and cooler temperatures often experienced at night. Diluting the paint will substantially increase cure time and is not recommended. Glass beads are not recommended for temporary markings. Striated markings may also be used for certain temporary markings. <u>AC</u>

 $\underline{150/5340-1}$, Standards for Airport Markings, has additional guidance on temporary markings.

Figure 2-5. Temporary Outboard White Threshold Bars and Yellow Arrowheads



2.18.3 <u>Lighting and Visual NAVAIDs.</u>

This paragraph refers to standard runway and taxiway lighting systems. See below for hazard lighting. Lighting installation must be in conformance with AC 150/5340-30, Design and Installation Details for Airport Visual Aids, and fixture design in conformance with AC 150/5345-50, Specification for Portable Runway and Taxiway Lights. When disconnecting runway and taxiway lighting fixtures, disconnect the associated isolation transformers. See AC 150/5340-26, Maintenance of Airport Visual Aid Facilities, for disconnect procedures and safety precautions. Alternately, cover the light fixture in such a way as to prevent light leakage. Avoid removing the lamp from energized fixtures because an excessive number of isolation transformers with open secondaries may damage the regulators and/or increase the current above its normal value. Secure, identify, and place any above ground temporary wiring in conduit to prevent electrocution and fire ignition sources. Maintain mandatory hold signs to operate normally in any situation where pilots or vehicle drivers could mistakenly be in that location. At towered airports certificated under Part 139, holding position signs are required to be illuminated on open taxiways crossing to closed or inactive runways. If the holding position sign is installed on the runway circuit for the closed runway, install a jumper to the taxiway circuit to provide power to the holding position sign for nighttime operations. Where it is not possible to maintain power to signs that would normally be operational, install barricades to exclude aircraft. Figure 2-1, Figure 2-2, Figure 2-3, and Figure 2-4 illustrate temporary changes to lighting and visual NAVAIDs.

2.18.3.1 **Permanently Closed Runways and Taxiways.**

For runways and taxiways that have been permanently closed, disconnect the lighting circuits.

2.18.3.2 Temporarily Closed Runways and New Runways Not Yet Open to Air Traffic.

If available, use a lighted X, both at night and during the day, placed at each end of the runway on or near the runway designation numbers facing the approach. (Note that the lighted X must be illuminated at all times that it is on a runway.) The use of a lighted X is required if night work requires runway lighting to be on. See AC 150/5345-55, Specification for L-893, Lighted Visual Aid to Indicate Temporary Runway Closure. For runways that have been temporarily closed, but for an extended period, and for those with pilot controlled lighting, disconnect the lighting circuits or secure switches to prevent inadvertent activation. For runways that will be opened periodically, coordinate procedures with the FAA air traffic manager or, at airports without an ATCT, the airport operator. Activate stop bars if available. Figure 2-6 shows a lighted X by day. Figure 2-7 shows a lighted X at night.



Figure 2-6. Lighted X in Daytime

Figure 2-7. Lighted X at Night



2.18.3.3 Partially Closed Runways and Displaced Thresholds.

When a runway is partially closed, a portion of the pavement is unavailable for any aircraft operation, meaning taxiing and landing or taking off in either direction. A displaced threshold, by contrast, is put in place to ensure obstacle clearance by landing aircraft. The pavement prior to the displaced threshold is available for takeoff in the direction of the displacement, and for landing and takeoff in the opposite direction. Misunderstanding this difference and issuance of a subsequently inaccurate NOTAM can result in a hazardous situation. For both partially

closed runways and displaced thresholds, approach lighting systems at the affected end must be placed out of service.

2.18.3.3.1 Partially Closed Runways.

Disconnect edge and threshold lights on that part of the runway at and behind the threshold (that is, the portion of the runway that is closed). Alternately, cover the light fixtures in such a way as to prevent light leakage. See <u>Figure 2-1</u>.

2.18.3.3.2 Temporary Displaced Thresholds.

Edge lighting in the area of the displacement emits red light in the direction of approach and yellow light (white for visual runways) in the opposite direction. If the displacement is 700 feet or less, blank out centerline lights in the direction of approach or place the centerline lights out of service. If the displacement is over 700 feet, place the centerline lights out of service. See <u>AC 150/5340-30</u> for details on lighting displaced thresholds. See <u>Figure 2-2</u>.

- 2.18.3.3.3 Temporary runway thresholds and runway ends must be lighted if the runway is lighted and it is the intended threshold for night landings or instrument meteorological conditions.
- 2.18.3.3.4 A temporary threshold on an unlighted runway may be marked by retroreflective, elevated markers in addition to markings noted in paragraph 2.18.2.1.3. Markers seen by aircraft on approach are green. Markers at the rollout end of the runway are red. At certificated airports, temporary elevated threshold markers must be mounted with a frangible fitting (see 14 CFR Part 139.309). At non-certificated airports, the temporary elevated threshold markings may either be mounted with a frangible fitting or be flexible. See <u>AC 150/5345-39</u>, *Specification for L-853*, *Runway and Taxiway Retroreflective Markers*.
- 2.18.3.3.5 Temporary threshold lights and runway end lights and related visual NAVAIDs are installed outboard of the edges of the full-strength pavement only when they cannot be installed on the pavement. They are installed with bases at grade level or as low as possible, but not more than 3 inch (7.6 cm) above ground. (The standard above ground height for airport lighting fixtures is 14 inches (35 cm)). When any portion of a base is above grade, place properly compacted fill around the base to minimize the rate of gradient change so aircraft can, in an emergency, cross at normal landing or takeoff speeds without incurring significant damage. See <u>AC 150/5370-10</u>.
- 2.18.3.3.6 Maintain threshold and edge lighting color and spacing standards as described in <u>AC 150/5340-30</u>. Battery powered, solar, or portable lights that meet the criteria in <u>AC 150/5345-50</u> may be used. These systems are intended primarily for visual flight rules (VFR) aircraft operations but may

be used for instrument flight rules (IFR) aircraft operations, upon individual approval from the Flight Standards Division of the applicable FAA Regional Office.

- 2.18.3.3.7 When runway thresholds are temporarily displaced, reconfigure yellow lenses (caution zone), as necessary, and place the centerline lights out of service.
- 2.18.3.3.8 Relocate the Visual Glide Slope Indicator (VGSI), such as Visual Approach Slope Indicator (VASI) and Precision Approach Path Indicator (PAPI); other airport lights, such as Runway End Identifier Lights (REIL); and approach lights to identify the temporary threshold. Another option is to disable the VGSI or any equipment that would give misleading indications to pilots as to the new threshold location. Installation of temporary visual aids may be necessary to provide adequate guidance to pilots on approach to the affected runway. If the FAA owns and operates the VGSI, coordinate its installation or disabling with the local ATO/Technical Operations Office. Relocation of such visual aids will depend on the duration of the project and the benefits gained from the relocation, as this can result in great expense. See FAA JO 6850.2, Visual Guidance Lighting Systems, for installation criteria for FAA owned and operated NAVAIDs.
- 2.18.3.3.9 Issue a NOTAM to inform pilots of temporary lighting conditions.

2.18.3.4 **Temporarily Closed Taxiways.**

If possible, deactivate the taxiway lighting circuits. When deactivation is not possible (for example other taxiways on the same circuit are to remain open), cover the light fixture in a way as to prevent light leakage.

2.18.4 Signs.

To the extent possible, signs must be in conformance with <u>AC 150/5345-44</u>, *Specification for Runway and Taxiway Signs*, and <u>AC 150/5340-18</u>, *Standard for Airport Sign Systems*.

2.18.4.1 **Existing Signs.**

Runway exit signs are to be covered for closed runway exits. Outbound destination signs are to be covered for closed runways. Any time a sign does not serve its normal function or would provide conflicting information, it must be covered or removed to prevent misdirecting pilots. Note that information signs identifying a crossing taxiway continue to perform their normal function even if the crossing taxiway is closed. For long term construction projects, consider relocating signs, especially runway distance remaining signs.

2.18.4.2 **Temporary Signs.**

Orange construction signs comprise a message in black on an orange background. Orange construction signs may help pilots be aware of changed conditions. The airport operator may choose to introduce these signs as part of a movement area construction project to increase situational awareness when needed. Locate signs outside the taxiway safety limits and ahead of construction areas so pilots can take timely action. Use temporary signs judiciously, striking a balance between the need for information and the increase in pilot workload. When there is a concern of pilot "information overload," the applicability of mandatory hold signs must take precedence over orange construction signs recommended during construction. Temporary signs must meet the standards for such signs in Engineering Brief 93, Guidance for the Assembly and Installation of Temporary Orange Construction Signs. Many criteria in AC 150/5345-44, Specification for Runway and Taxiway Signs, are referenced in the Engineering Brief. Permissible sign legends are:

- 1. CONSTRUCTION AHEAD,
- 2. CONSTRUCTION ON RAMP, and
- 3. RWY XX TAKEOFF RUN AVAILABLE XXX FT.

Phasing, supported by drawings and sign schedule, for the installation of orange construction signs must be included in the CSPP or SPCD.

2.18.4.2.1 Takeoff Run Available (TORA) signs.

Recommended: Where a runway has been shortened for takeoff, install orange TORA signs well before the hold lines, such as on a parallel taxiway prior to a turn to a runway hold position. See EB 93 for sign size and location.

2.18.4.2.2 Sign legends are shown in <u>Figure F-1</u>.

Note: See Figure E-1, Figure E-2, Figure E-3, Figure F-2, and Figure F-3 for examples of orange construction sign locations.

2.19 Marking and Signs for Access Routes.

The CSPP should indicate that pavement markings and signs for construction personnel will conform to <u>AC 150/5340-18</u> and, to the extent practicable, with the Federal Highway Administration Manual on Uniform Traffic Control Devices (MUTCD) and/or State highway specifications. Signs adjacent to areas used by aircraft must comply with the frangibility requirements of <u>AC 150/5220-23</u>, *Frangible Connections*, which may require modification to size and height guidance in the MUTCD.

2.20 Hazard Marking, Lighting and Signing.

2.20.1 Hazard marking, lighting, and signing prevent pilots from entering areas closed to aircraft, and prevent construction personnel from entering areas open to aircraft. The CSPP must specify prominent, comprehensible warning indicators for any area affected by construction that is normally accessible to aircraft, personnel, or vehicles. Hazard marking and lighting must also be specified to identify open manholes, small areas under repair, stockpiled material, waste areas, and areas subject to jet blast. Also consider less obvious construction-related hazards and include markings to identify FAA, airport, and National Weather Service facilities cables and power lines; instrument landing system (ILS) critical areas; airport surfaces, such as RSA, OFA, and OFZ; and other sensitive areas to make it easier for contractor personnel to avoid these areas.

2.20.2 Equipment.

2.20.2.1 **Barricades.**

Low profile barricades, including traffic cones, (weighted or sturdily attached to the surface) are acceptable methods used to identify and define the limits of construction and hazardous areas on airports. Careful consideration must be given to selecting equipment that poses the least danger to aircraft but is sturdy enough to remain in place when subjected to typical winds, prop wash and jet blast. The spacing of barricades must be such that a breach is physically prevented barring a deliberate act. For example, if barricades are intended to exclude aircraft, gaps between barricades must be smaller than the wingspan of the smallest aircraft to be excluded; if barricades are intended to exclude vehicles, gaps between barricades must be smaller than the width of the excluded vehicles, generally 4 feet (1.2 meters). Provision must be made for ARFF access if necessary. If barricades are intended to exclude pedestrians, they must be continuously linked. Continuous linking may be accomplished through the use of ropes, securely attached to prevent FOD.

2.20.2.2 **Lights.**

Lights must be red, either steady burning or flashing, and must meet the luminance requirements of the State Highway Department. Batteries powering lights will last longer if lights flash. Lights must be mounted on barricades and spaced at no more than 10 feet (3 meters). Lights must be operated between sunset and sunrise and during periods of low visibility whenever the airport is open for operations. They may be operated by photocell, but this may require that the contractor turn them on manually during periods of low visibility during daytime hours.

2.20.2.3 Supplement Barricades with Signs (for example) As Necessary.

Examples are "No Entry" and "No Vehicles." Be aware of the increased effects of wind and jet blast on barricades with attached signs.

2.20.2.4 Air Operations Area – General.

Barricades are not permitted in any active safety area or on the runway side of a runway hold line. Within a runway or taxiway object free area, and on aprons, use orange traffic cones, flashing or steady burning red lights as noted above, highly reflective collapsible barricades marked with diagonal, alternating orange and white stripes; and/or signs to separate all construction/maintenance areas from the movement area. Barricades may be supplemented with alternating orange and white flags at least 20 by 20 inch (50 by 50 cm) square and securely fastened to eliminate FOD. All barricades adjacent to any open runway or taxiway / taxilane safety area, or apron must be as low as possible to the ground, and no more than 18 inches high, exclusive of supplementary lights and flags. Barricades must be of low mass; easily collapsible upon contact with an aircraft or any of its components; and weighted or sturdily attached to the surface to prevent displacement from prop wash, jet blast, wing vortex, and other surface wind currents. If affixed to the surface, they must be frangible at grade level or as low as possible, but not to exceed 3 inch (7.6 cm) above the ground. Figure 2-8 and Figure 2-9 show sample barricades with proper coloring and flags.

Figure 2-8. Interlocking Barricades





Figure 2-9. Low Profile Barricades

2.20.2.5 Air Operations Area – Runway/Taxiway Intersections.

Use highly reflective barricades with lights to close taxiways leading to closed runways. Evaluate all operating factors when determining how to mark temporary closures that can last from 10 to 15 minutes to a much longer period of time. However, even for closures of relatively short duration, close all taxiway/runway intersections with barricades. The use of traffic cones is appropriate for short duration closures.

2.20.2.6 Air Operations Area – Other.

Beyond runway and taxiway object free areas and aprons, barricades intended for construction vehicles and personnel may be many different shapes and made from various materials, including railroad ties, sawhorses, jersey barriers, or barrels.

2.20.2.7 **Maintenance.**

The construction specifications must include a provision requiring the contractor to have a person on call 24 hours a day for emergency maintenance of airport hazard lighting and barricades. The contractor must file the contact person's information with the airport operator. Lighting should be checked for proper operation at least once per day, preferably at dusk.

2.21 Work Zone Lighting for Nighttime Construction.

Lighting equipment must adequately illuminate the work area if the construction is to be performed during nighttime hours. Refer to <u>AC 150/5370-10</u> for minimum illumination levels for nighttime paving projects. Additionally, it is recommended that all support equipment, except haul trucks, be equipped with artificial illumination to safely

illuminate the area immediately surrounding their work areas. The lights should be positioned to provide the most natural color illumination and contrast with a minimum of shadows. The spacing must be determined by trial. Light towers should be positioned and adjusted to aim away from ATCT cabs and active runways to prevent blinding effects. Shielding may be necessary. Light towers should be removed from the construction site when the area is reopened to aircraft operations. Construction lighting units should be identified and generally located on the construction phasing plans in relationship to the ATCT and active runways and taxiways.

2.22 Protection of Runway and Taxiway Safety Areas.

Runway and taxiway safety areas, OFZs, OFAs, and approach surfaces are described in <u>AC 150/5300-13</u>. Protection of these areas includes limitations on the location and height of equipment and stockpiled material. An FAA airspace study may be required. Coordinate with the appropriate FAA Airports Regional or District Office if there is any doubt as to requirements or dimensions (see paragraph <u>2.13.5</u>) as soon as the location and height of materials or equipment are known. The CSPP should include drawings showing all safety areas, object free areas, obstacle free zones and approach departure surfaces affected by construction.

2.22.1 Runway Safety Area (RSA).

A runway safety area is the defined surface surrounding the runway prepared or suitable for reducing the risk of damage to airplanes in the event of an undershoot, overshoot, or excursion from the runway (see <u>AC 150/5300-13</u>). Construction activities within the existing RSA are subject to the following conditions:

- 2.22.1.1 No construction may occur within the existing RSA while the runway is open for aircraft operations. The RSA dimensions may be temporarily adjusted if the runway is restricted to aircraft operations requiring an RSA that is equal to the RSA width and length beyond the runway ends available during construction. (See <u>AC 150/5300-13</u>). The temporary use of declared distances and/or partial runway closures may provide the necessary RSA under certain circumstances. Coordinate with the appropriate FAA Airports Regional or District Office to have declared distances information published, and appropriate NOTAMs issued. See <u>AC 150/5300-13</u> for guidance on the use of declared distances.
- 2.22.1.2 The airport operator must coordinate the adjustment of RSA dimensions as permitted above with the appropriate FAA Airports Regional or District Office and the local FAA air traffic manager and issue a NOTAM.
- 2.22.1.3 The CSPP and SPCD must provide procedures for ensuring adequate distance for protection from blasting operations, if required by operational considerations.

2.22.1.4 Excavations.

2.22.1.4.1 Open trenches or excavations are not permitted within the RSA while the runway is open. Backfill trenches before the runway is opened. If backfilling excavations before the runway must be opened is impracticable, cover the excavations appropriately. Covering for open trenches must be designed to allow the safe operation of the heaviest aircraft operating on the runway across the trench without damage to the aircraft.

2.22.1.4.2 Construction contractors must prominently mark open trenches and excavations at the construction site with red or orange flags, as approved by the airport operator, and light them with red lights during hours of restricted visibility or darkness.

2.22.1.5 Erosion Control.

Soil erosion must be controlled to maintain RSA standards, that is, the RSA must be cleared and graded and have no potentially hazardous ruts, humps, depressions, or other surface variations, and capable, under dry conditions, of supporting snow removal equipment, aircraft rescue and fire fighting equipment, and the occasional passage of aircraft without causing structural damage to the aircraft.

2.22.2 Runway Object Free Area (ROFA).

Construction, including excavations, may be permitted in the ROFA. However, equipment must be removed from the ROFA when not in use, and material should not be stockpiled in the ROFA if not necessary. Stockpiling material in the OFA requires submittal of a 7460-1 form and justification provided to the appropriate FAA Airports Regional or District Office for approval.

2.22.3 <u>Taxiway Safety Area (TSA).</u>

- 2.22.3.1 A taxiway safety area is a defined surface alongside the taxiway prepared or suitable for reducing the risk of damage to an airplane unintentionally departing the taxiway. (See <u>AC 150/5300-13</u>.) Since the width of the TSA is equal to the wingspan of the design aircraft, no construction may occur within the TSA while the taxiway is open for aircraft operations. The TSA dimensions may be temporarily adjusted if the taxiway is restricted to aircraft operations requiring a TSA that is equal to the TSA width available during construction. Give special consideration to TSA dimensions at taxiway turns and intersections. (see <u>AC 150/5300-13</u>).
- 2.22.3.2 The airport operator must coordinate the adjustment of the TSA width as permitted above with the appropriate FAA Airports Regional or District Office and the FAA air traffic manager and issue a NOTAM.

2.22.3.3 The CSPP and SPCD must provide procedures for ensuring adequate distance for protection from blasting operations.

2.22.3.4 Excavations.

- 1. Curves. Open trenches or excavations are not permitted within the TSA while the taxiway is open. Trenches should be backfilled before the taxiway is opened. If backfilling excavations before the taxiway must be opened is impracticable, cover the excavations appropriately. Covering for open trenches must be designed to allow the safe operation of the heaviest aircraft operating on the taxiway across the trench without damage to the aircraft.
- 2. Straight Sections. Open trenches or excavations are not permitted within the TSA while the taxiway is open for unrestricted aircraft operations. Trenches should be backfilled before the taxiway is opened. If backfilling excavations before the taxiway must be opened is impracticable, cover the excavations to allow the safe passage of ARFF equipment and of the heaviest aircraft operating on the taxiway across the trench without causing damage to the equipment or aircraft. In rare circumstances where the section of taxiway is indispensable for aircraft movement, open trenches or excavations may be permitted in the TSA while the taxiway is open to aircraft operations, subject to the following restrictions:
 - a. Taxiing speed is limited to 10 mph.
 - b. Appropriate NOTAMs are issued.
 - c. Marking and lighting meeting the provisions of paragraphs <u>2.18</u> and 2.20 are implemented.
 - d. Low mass, low-profile lighted barricades are installed.
 - e. Appropriate temporary orange construction signs are installed.
- 3. Construction contractors must prominently mark open trenches and excavations at the construction site with red or orange flags, as approved by the airport operator, and light them with red lights during hours of restricted visibility or darkness.

2.22.3.5 Erosion control.

Soil erosion must be controlled to maintain TSA standards, that is, the TSA must be cleared and graded and have no potentially hazardous ruts, humps, depressions, or other surface variations, and capable, under dry conditions, of supporting snow removal equipment, aircraft rescue and firefighting equipment, and the occasional passage of aircraft without causing structural damage to the aircraft.

2.22.4 <u>Taxiway Object Free Area (TOFA).</u>

Unlike the Runway Object Free Area, aircraft wings regularly penetrate the taxiway object free area during normal operations. Thus, the restrictions are more stringent. Except as provided below, no construction may occur within the taxiway object free area while the taxiway is open for aircraft operations.

- 2.22.4.1 The taxiway object free area dimensions may be temporarily adjusted if the taxiway is restricted to aircraft operations requiring a taxiway object free area that is equal to the taxiway object free area width available. Give special consideration to TOFA dimensions at taxiway turns and intersections.
- 2.22.4.2 Offset taxiway centerline and edge pavement markings (do not use glass beads) may be used as a temporary measure to provide the required taxiway object free area. Where offset taxiway pavement markings are provided, centerline lighting, centerline reflectors, or taxiway edge reflectors are required. Existing lighting that does not coincide with the temporary markings must be taken out of service.
- 2.22.4.3 Construction activity, including open excavations, may be accomplished without adjusting the width of the taxiway object free area, subject to the following restrictions:
- 2.22.4.3.1 Taxiing speed is limited to 10 mph.
- 2.22.4.3.2 NOTAMs issued advising taxiing pilots of hazard and recommending reduced taxiing speeds on the taxiway.
- 2.22.4.3.3 Marking and lighting meeting the provisions of paragraphs <u>2.18</u> and <u>2.20</u> are implemented.
- 2.22.4.3.4 If desired, appropriate orange construction signs are installed. See paragraph 2.18.4.2 and Appendix F.
- 2.22.4.3.5 Five-foot clearance is maintained between equipment and materials and any part of an aircraft (includes wingtip overhang). If such clearance can only be maintained if an aircraft does not have full use of the entire taxiway width (with its main landing gear at the edge of the usable pavement), then it will be necessary to move personnel and equipment for the passage of that aircraft.
- 2.22.4.3.6 Flaggers furnished by the contractor must be used to direct and control construction equipment and personnel to a pre-established setback distance for safe passage of aircraft, and airline and/or airport personnel. Flaggers must also be used to direct taxiing aircraft. Due to liability issues, the airport operator should require airlines to provide flaggers for directing taxiing aircraft.

2.22.5 Obstacle Free Zone (OFZ).

In general, personnel, material, and/or equipment may not penetrate the OFZ while the runway is open for aircraft operations. If a penetration to the OFZ is necessary, it may be possible to continue aircraft operations through operational restrictions. Coordinate with the FAA through the appropriate FAA Airports Regional or District Office.

2.22.6 Runway Approach/Departure Areas and Clearways.

All personnel, materials, and/or equipment must remain clear of the applicable threshold siting surfaces, as defined in <u>AC 150/5300-13</u>. Objects that do not penetrate these surfaces may still be obstructions to air navigation and may affect standard instrument approach procedures. Coordinate with the FAA through the appropriate FAA Airports Regional or District Office.

2.22.6.1 Construction activity in a runway approach/departure area may result in the need to partially close a runway or displace the existing runway threshold. Partial runway closure, displacement of the runway threshold, as well as closure of the complete runway and other portions of the movement area also require coordination through the airport operator with the appropriate FAA air traffic manager (FSS if non-towered) and ATO/Technical Operations (for affected NAVAIDS) and airport users.

2.22.6.2 Caution About Partial Runway Closures.

When filing a NOTAM for a partial runway closure, clearly state that the portion of pavement located prior to the threshold is not available for landing and departing traffic. In this case, the threshold has been moved for both landing and takeoff purposes (this is different than a displaced threshold). There may be situations where the portion of closed runway is available for taxiing only. If so, the NOTAM must reflect this condition).

2.22.6.3 Caution About Displaced Thresholds.

Implementation of a displaced threshold affects runway length available for aircraft landing over the displacement. Depending on the reason for the displacement (to provide obstruction clearance or RSA), such a displacement may also require an adjustment in the landing distance available and accelerate-stop distance available in the opposite direction. If project scope includes personnel, equipment, excavation, or other work within the existing RSA of any usable runway end, do not implement a displaced threshold unless arrivals and departures toward the construction activity are prohibited. Instead, implement a partial closure.

2.23 Other Limitations on Construction.

The CSPP must specify any other limitations on construction, including but not limited to:

2.23.1	<u>Prohibitions</u>	<u>.</u>
	2.23.1.1	No use of tall equipment (cranes, concrete pumps, and so on) unless a 7460-1 determination letter is issued for such equipment.
	2.23.1.2	No use of open flame welding or torches unless fire safety precautions are provided and the airport operator has approved their use.
	2.23.1.3	No use of electrical blasting caps on or within 1,000 feet (300 meters) of the airport property. See <u>AC 150/5370-10</u> .
2.23.2	Restrictions	<u>.</u>
	2.23.2.1	Construction suspension required during specific airport operations.
	2.23.2.2	Areas that cannot be worked on simultaneously.
	2.23.2.3	Day or night construction restrictions.
	2.23.2.4	Seasonal construction restrictions.

Temporary signs not approved by the airport operator.

Grades changes that could result in unplanned effects on NAVAIDs.

2.23.2.5

2.23.2.6

CHAPTER 3. GUIDELINES FOR WRITING A CSPP

3.1 General Requirements.

The CSPP is a standalone document written to correspond with the subjects outlined in paragraph 2.4. The CSPP is organized by numbered sections corresponding to each subject listed in paragraph 2.4, and described in detail in paragraphs 2.5 - 2.23. Each section number and title in the CSPP matches the corresponding subject outlined in paragraph 2.4 (for example, 1. Coordination, 2. Phasing, 3. Areas and Operations Affected by the Construction Activity, and so on). With the exception of the project scope of work outlined in Section 2. Phasing, only subjects specific to operational safety during construction should be addressed.

3.2 **Applicability of Subjects.**

Each section should, to the extent practical, focus on the specific subject. Where an overlapping requirement spans several sections, the requirement should be explained in detail in the most applicable section. A reference to that section should be included in all other sections where the requirement may apply. For example, the requirement to protect existing underground FAA ILS cables during trenching operations could be considered FAA ATO coordination (Coordination, paragraph 2.5.3), an area and operation affected by the construction activity (Areas and Operations Affected by the Construction Activity, paragraph 2.7.1.4), a protection of a NAVAID (Protection of Navigational Aids (NAVAIDs), paragraph 2.8), or a notification to the FAA of construction activities (Notification of Construction Activities, paragraph 2.13.5.3.2). However, it is more specifically an underground utility requirement (Underground Utilities, paragraph 2.15). The procedure for protecting underground ILS cables during trenching operations should therefore be described in 2.4.2.11: "The contractor must coordinate with the local FAA System Support Center (SSC) to mark existing ILS cable routes along Runway 17-35. The ILS cables will be located by hand digging whenever the trenching operation moves within 10 feet of the cable markings." All other applicable sections should include a reference to 2.4.2.11: "ILS cables shall be identified and protected as described in 2.4.2.11" or "See 2.4.2.11 for ILS cable identification and protection requirements." Thus, the CSPP should be considered as a whole, with no need to duplicate responses to related issues.

3.3 **Graphical Representations.**

Construction safety drawings should be included in the CSPP as attachments. When other graphical representations will aid in supporting written statements, the drawings, diagrams, and/or photographs should also be attached to the CSPP. References should be made in the CSPP to each graphical attachment and may be made in multiple sections.

3.4 **Reference Documents.**

The CSPP must not incorporate a document by reference unless reproduction of the material in that document is prohibited. In that case, either copies of or a source for the referenced document must be provided to the contractor. Where this AC recommends references (e.g. as in paragraph 3.9) the intent is to include a reference to the corresponding section in the CSPP, not to this Advisory Circular.

3.5 **Restrictions.**

The CSPP should not be considered as a project design review document. The CSPP should also avoid mention of permanent ("as-built") features such as pavements, markings, signs, and lighting, except when such features are intended to aid in maintaining operational safety during the construction.

3.6 **Coordination.**

Include in this section a detailed description of conferences and meetings to be held both before and during the project. Include appropriate information from <u>AC 150/5370-12</u>. Discuss coordination procedures and schedules for each required FAA ATO Technical Operations shutdown and restart and all required flight inspections.

3.7 **Phasing.**

Include in this section a detailed scope of work description for the project as a whole and each phase of work covered by the CSPP. This includes all locations and durations of the work proposed. Attach drawings to graphically support the written scope of work. Detail in this section the sequenced phases of the proposed construction. Include a reference to paragraph 3.8, as appropriate.

3.8 Areas and Operations Affected by Construction.

Focus in this section on identifying the areas and operations affected by the construction. Describe corresponding mitigation that is not covered in detail elsewhere in the CSPP. Include references to paragraphs below as appropriate. Attach drawings as necessary to graphically describe affected areas and mechanisms proposed. See Appendix F for sample operational effects tables and figures.

3.9 **NAVAID Protection.**

List in this section all NAVAID facilities that will be affected by the construction. Identify NAVAID facilities that will be placed out of service at any time prior to or during construction activities. Identify individuals responsible for coordinating each shutdown and when each facility will be out of service. Include a reference to paragraph 3.6 for FAA ATO NAVAID shutdown, restart, and flight inspection coordination. Outline in detail procedures to protect each NAVAID facility remaining in service from interference by construction activities. Include a reference to paragraph 3.14 for the

issuance of NOTAMs as required. Include a reference to paragraph <u>3.16</u> for the protection of underground cables and piping serving NAVAIDs. If temporary visual aids are proposed to replace or supplement existing facilities, include a reference to paragraph <u>3.19</u>. Attach drawings to graphically indicate the affected NAVAIDS and the corresponding critical areas.

3.10 **Contractor Access.**

This will necessarily be the most extensive section of the CSPP. Provide sufficient detail so that a contractor not experienced in working on airports will understand the unique restrictions such work will require. Due to this extent, it should be broken down into subsections as described below:

3.10.1 Location of Stockpiled Construction Materials.

Describe in this section specific locations for stockpiling material. Note any height restrictions on stockpiles. Include a reference to paragraph 3.21 for hazard marking and lighting devices used to identify stockpiles. Include a reference to paragraph 3.11 for provisions to prevent stockpile material from becoming wildlife attractants. Include a reference to paragraph 3.12 for provisions to prevent stockpile material from becoming FOD. Attach drawings to graphically indicate the stockpile locations.

3.10.2 <u>Vehicle and Pedestrian Operations.</u>

While there are many items to be addressed in this major subsection of the CSPP, all are concerned with one main issue: keeping people and vehicles from areas of the airport where they don't belong. This includes preventing unauthorized entry to the AOA and preventing the improper movement of pedestrians or vehicles on the airport. In this section, focus on mechanisms to prevent construction vehicles and workers traveling to and from the worksite from unauthorized entry into movement areas. Specify locations of parking for both employee vehicles and construction equipment, and routes for access and haul roads. In most cases, this will best be accomplished by attaching a drawing. Quote from <u>AC 150/5210-5</u> specific requirements for contractor vehicles rather than referring to the AC as a whole, and include special requirements for identifying HAZMAT vehicles. Quote from, rather than incorporate by reference, <u>AC 150/5210-20</u> as appropriate to address the airport's rules for ground vehicle operations, including its training program. Discuss the airport's recordkeeping system listing authorized vehicle operators.

3.10.3 <u>Two-Way Radio Communications.</u>

Include a special section to identify all individuals who are required to maintain communications with Air Traffic (AT) at airports with active towers, or monitor CTAF at airports without or with closed ATCT. Include training requirements for all individuals required to communicate with AT. Individuals required to monitor AT frequencies should also be identified. If construction employees are also required to communicate by radio with Airport Operations, this procedure should be described in detail. Usage of vehicle mounted radios and/or portable radios should be addressed. Communication procedures for the event of disabled radio communication (that is, light

signals, telephone numbers, others) must be included. All radio frequencies should by identified (Tower, Ground Control, CTAF, UNICOM, ATIS, and so on).

3.10.4 Airport Security.

Address security as it applies to vehicle and pedestrian operations. Discuss TSA requirements, security badging requirements, perimeter fence integrity, gate security, and other needs. Attach drawings to graphically indicate secured and/or Security Identification Display Areas (SIDA), perimeter fencing, and available access points.

3.11 Wildlife Management.

Discuss in this section wildlife management procedures. Describe the maintenance of existing wildlife mitigation devices, such as perimeter fences, and procedures to limit wildlife attractants. Include procedures to notify Airport Operations of wildlife encounters. Include a reference to paragraph 3.10 for security (wildlife) fence integrity maintenance as required.

3.12 **FOD Management.**

In this section, discuss methods to control and monitor FOD: worksite housekeeping, ground vehicle tire inspections, runway sweeps, and so on. Include a reference to paragraph 3.15 for inspection requirements as required.

3.13 **HAZMAT Management.**

Describe in this section HAZMAT management procedures: fuel deliveries, spill recovery procedures, Safety Data Sheet (SDS), Material Safety Data Sheet (MSDS) or Product Safety Data Sheet (PSDS) availability, and other considerations. Any specific airport HAZMAT restrictions should also be identified. Include a reference to paragraph 3.10 for HAZMAT vehicle identification requirements. Quote from, rather than incorporate by reference, AC 150/5320-15.

3.14 Notification of Construction Activities.

List in this section the names and telephone numbers of points of contact for all parties affected by the construction project. We recommend a single list that includes all telephone numbers required under this section. Include emergency notification procedures for all representatives of all parties potentially impacted by the construction. Identify individual representatives – and at least one alternate – for each party. List both on-duty and off-duty contact information for each individual, including individuals responsible for emergency maintenance of airport construction hazard lighting and barricades. Describe procedures to coordinate immediate response to events that might adversely affect the operational safety of the airport (such as interrupted NAVAID service). Explain requirements for and the procedures for the issuance of Notices to Airmen (NOTAMs), notification to FAA required by 14 CFR Part 77 and Part 157 and in the event of affected NAVAIDs. For NOTAMs, identify an individual, and at least one alternate, responsible for issuing and cancelling each specific type of Notice to

Airmen (NOTAM) required. Detail notification methods for police, fire fighting, and medical emergencies. This may include 911, but should also include direct phone numbers of local police departments and nearby hospitals. Identify the E911 address of the airport and the emergency access route via haul roads to the construction site. Require the contractor to have this information available to all workers. The local Poison Control number should be listed. Procedures regarding notification of Airport Operations and/or the ARFF Department of such emergencies should be identified, as applicable. If airport radio communications are identified as a means of emergency notification, include a reference to paragraph 3.10. Differentiate between emergency and nonemergency notification of ARFF personnel, the latter including activities that affect ARFF water supplies and access roads. Identify the primary ARFF contact person and at least one alternate. If notification is to be made through Airport Operations, then detail this procedure. Include a method of confirmation from the ARFF department.

3.15 **Inspection Requirements.**

Describe in this section inspection requirements to ensure airfield safety compliance. Include a requirement for routine inspections by the resident engineer (RE) or other airport operator's representative and the construction contractors. If the engineering consultants and/or contractors have a Safety Officer who will conduct such inspections, identify this individual. Describe procedures for special inspections, such as those required to reopen areas for aircraft operations. Part 139 requires daily airfield inspections at certificated airports, but these may need to be more frequent when construction is in progress. Discuss the role of such inspections on areas under construction. Include a requirement to immediately remedy any deficiencies, whether caused by negligence, oversight, or project scope change.

3.16 Underground Utilities.

Explain how existing underground utilities will be located and protected. Identify each utility owner and include contact information for each company/agency in the master list. Address emergency response procedures for damaged or disrupted utilities. Include a reference to paragraph 3.14 for notification of utility owners of accidental utility disruption as required.

3.17 **Penalties.**

Describe in this section specific penalties imposed for noncompliance with airport rules and regulations, including the CSPP: SIDA violations, VPD, and others.

3.18 **Special Conditions.**

Identify any special conditions that may trigger specific safety mitigation actions outlined in this CSPP: low visibility operations, snow removal, aircraft in distress, aircraft accident, security breach, VPD, and other activities requiring construction suspension/resumption. Include a reference to paragraph 3.10 for compliance with airport safety and security measures and for radio communications as required. Include

a reference to paragraph <u>3.14</u> for emergency notification of all involved parties, including police/security, ARFF, and medical services.

3.19 Runway and Taxiway Visual Aids.

Include marking, lighting, signs, and visual NAVAIDs. Detail temporary runway and taxiway marking, lighting, signs, and visual NAVAIDs required for the construction. Discuss existing marking, lighting, signs, and visual NAVAIDs that are temporarily, altered, obliterated, or shut down. Consider non-federal facilities and address requirements for reimbursable agreements necessary for alteration of FAA facilities and for necessary flight checks. Identify temporary TORA signs or runway distance remaining signs if appropriate. Identify required temporary visual NAVAIDs such as REIL or PAPI. Quote from, rather than incorporate by reference, <u>AC 150/5340-1</u>, *Standards for Airport Markings*; <u>AC 150/5340-18</u>, *Standards for Airport Sign Systems*; and <u>AC 150/5340-30</u>, as required. Attach drawings to graphically indicate proposed marking, lighting, signs, and visual NAVAIDs.

3.20 Marking and Signs for Access Routes.

Detail plans for marking and signs for vehicle access routes. To the extent possible, signs should be in conformance with the Federal Highway Administration MUTCD and/or State highway specifications, not hand lettered. Detail any modifications to the guidance in the MUTCD necessary to meet frangibility/height requirements.

3.21 **Hazard Marking and Lighting.**

Specify all marking and lighting equipment, including when and where each type of device is to be used. Specify maximum gaps between barricades and the maximum spacing of hazard lighting. Identify one individual and at least one alternate responsible for maintenance of hazard marking and lighting equipment in the master telephone list. Include a reference to paragraph 3.14. Attach drawings to graphically indicate the placement of hazard marking and lighting equipment.

3.22 Work Zone Lighting for Nighttime Construction.

If work is to be conducted at night, specify all lighting equipment, including when and where each type of device is to be used. Indicate the direction lights are to be aimed and any directions that aiming of lights is prohibited. Specify any shielding necessary in instances where aiming is not sufficient to prevent interference with air traffic control and aircraft operations. Attach drawings to graphically indicate the placement and aiming of lighting equipment. Where the plan only indicates directions that aiming of lights is prohibited, the placement and positioning of portable lights must be proposed by the Contractor and approved by the airport operator's representative each time lights are relocated or repositioned.

3.23 Protection of Runway and Taxiway Safety Areas.

This section should focus exclusively on procedures for protecting all safety areas, including those altered by the construction: methods of demarcation, limit of access, movement within safety areas, stockpiling and trenching restrictions, and so on. Reference AC 150/5300-13, as required. Include a reference to paragraph 3.10 for procedures regarding vehicle and personnel movement within safety areas. Include a reference to paragraph 3.10 for material stockpile restrictions as required. Detail requirements for trenching, excavations, and backfill. Include a reference to paragraph 3.21 for hazard marking and lighting devices used to identify open excavations as required. If runway and taxiway closures are proposed to protect safety areas, or if temporary displaced thresholds and/or revised declared distances are used to provide the required Runway Safety Area, include a reference to paragraphs 3.14 and 3.19. Detail procedures for protecting the runway OFZ, runway OFA, taxiway OFA and runway approach surfaces including those altered by the construction: methods of demarcation, limit of cranes, storage of equipment, and so on. Quote from, rather than incorporate by reference, AC 150/5300-13, as required. Include a reference to paragraph 3.24 for height (i.e., crane) restrictions as required. One way to address the height of equipment that will move during the project is to establish a three-dimensional "box" within which equipment will be confined that can be studied as a single object. Attach drawings to graphically indicate the safety area, OFZ, and OFA boundaries.

3.24 Other Limitations on Construction.

This section should describe what limitations must be applied to each area of work and when each limitation will be applied: limitations due to airport operations, height (i.e., crane) restrictions, areas which cannot be worked at simultaneously, day/night work restrictions, winter construction, and other limitations. Include a reference to paragraph 3.7 for project phasing requirements based on construction limitations as required.

Page Intentionally Blank

APPENDIX A. RELATED READING MATERIAL

Obtain the latest version of the following free publications from the FAA on its Web site at http://www.faa.gov/airports/.

Table A-1. FAA Publications

Number	Title and Description
AC 150/5200-28	Notices to Airmen (NOTAMs) for Airport Operators Guidance for using the NOTAM System in airport reporting.
AC 150/5200-30	Airport Field Condition Assessments and Winter Operations Safety Guidance for airport owners/operators on the development of an acceptable airport snow and ice control program and on appropriate field condition reporting procedures.
AC 150/5200-33	Hazardous Wildlife Attractants On or Near Airports Guidance on locating certain land uses that might attract hazardous wildlife to public-use airports.
AC 150/5210-5	Painting, Marking, and Lighting of Vehicles Used on an Airport Guidance, specifications, and standards for painting, marking, and lighting vehicles operating in the airport air operations areas.
AC 150/5210-20	Ground Vehicle Operations to include Taxiing or Towing an Aircraft on Airports Guidance to airport operators on developing ground vehicle operation training programs.
AC 150/5300-13	Airport Design FAA standards and recommendations for airport design. Establishes approach visibility minimums as an airport design parameter, and contains the Object Free area and the obstacle free-zone criteria.
AC 150/5210-24	Airport Foreign Object Debris (FOD) Management Guidance for developing and managing an airport foreign object debris (FOD) program

Number	Title and Description
AC 150/5320-15	Management of Airport Industrial Waste
	Basic information on the characteristics, management, and regulations of industrial wastes generated at airports. Guidance for developing a Storm Water Pollution Prevention Plan (SWPPP) that applies best management practices to eliminate, prevent, or reduce pollutants in storm water runoff with particular airport industrial activities.
AC 150/5340-1	Standards for Airport Markings
	FAA standards for the siting and installation of signs on airport runways and taxiways.
AC 150/5340-18	Standards for Airport Sign Systems
	FAA standards for the siting and installation of signs on airport runways and taxiways.
AC 150/5345-28	Precision Approach Path Indicator (PAPI) Systems
	FAA standards for PAPI systems, which provide pilots with visual glide slope guidance during approach for landing.
AC 150/5340-30	Design and Installation Details for Airport Visual Aids
	Guidance and recommendations on the installation of airport visual aids.
AC 150/5345-39	Specification for L-853, Runway and Taxiway Retroreflective Markers
AC 150/5345-44	Specification for Runway and Taxiway Signs
	FAA specifications for unlighted and lighted signs for taxiways and runways.
AC 150/5345-53	Airport Lighting Equipment Certification Program
	Details on the Airport Lighting Equipment Certification Program (ALECP).
AC 150/5345-50	Specification for Portable Runway and Taxiway Lights
	FAA standards for portable runway and taxiway lights and runway end identifier lights for temporary use to permit continued aircraft operations while all or part of a runway lighting system is inoperative.
AC 150/5345-55	Specification for L-893, Lighted Visual Aid to Indicate Temporary Runway Closure

Number	Title and Description		
AC 150/5370-10	Standards for Specifying Construction of Airports		
	Standards for construction of airports, including earthwork, drainage, paving, turfing, lighting, and incidental construction.		
AC 150/5370-12	Quality Management for Federally Funded Airport Construction Projects		
EB 93	Guidance for the Assembly and Installation of Temporary Orange Construction Signs		
FAA Order 5200.11	FAA Airports (ARP) Safety Management System (SMS)		
	Basics for implementing SMS within ARP. Includes roles and responsibilities of ARP management and staff as well as other FAA lines of business that contribute to the ARP SMS.		
FAA Certalert 98-05	Grasses Attractive to Hazardous Wildlife		
	Guidance on grass management and seed selection.		
FAA Form 7460-1	Notice of Proposed Construction or Alteration		
FAA Form 7480-1	Notice of Landing Area Proposal		
FAA Form 6000.26	National NAS Strategic Interruption Service Level Agreement, Strategic Events Coordination, Airport Sponsor Form		

Obtain the latest version of the following free publications from the Electronic Code of Federal Regulations at http://www.ecfr.gov/.

Table A-2. Code of Federal Regulation

Number	Title			
Title 14 CFR Part 77	Safe, Efficient Use and Preservation of the Navigable Airspace			
Title 14 CFR Part 139	Certification of Airports			
Title 49 CFR Part 1542	Airport Security			

Obtain the latest version of the Manual on Uniform Traffic Control Devices from the Federal Highway Administration at http://mutcd.fhwa.dot.gov/.

Page Intentionally Blank

APPENDIX B. TERMS AND ACRONYMS

Table B-1. Terms and Acronyms

Term	Definition
Form 7460-1	Notice of Proposed Construction or Alteration. For on-airport projects, the form submitted to the FAA regional or airports division office as formal written notification of any kind of construction or alteration of objects that affect navigable airspace, as defined in 14 CFR Part 77, <i>Safe, Efficient Use, and Preservation of the Navigable Airspace</i> . (See guidance available on the FAA web site at https://oeaaa.faa.gov .) The form may be downloaded at http://www.faa.gov/airports/resources/forms/ , or filed electronically at: https://oeaaa.faa.gov .
Form 7480-1	Notice of Landing Area Proposal. Form submitted to the FAA Airports Regional Division Office or Airports District Office as formal written notification whenever a project without an airport layout plan on file with the FAA involves the construction of a new airport; the construction, realigning, altering, activating, or abandoning of a runway, landing strip, or associated taxiway; or the deactivation or abandoning of an entire airport The form may be downloaded at http://www.faa.gov/airports/resources/forms/ .
Form 6000-26	Airport Sponsor Strategic Event Submission Form
AC	Advisory Circular
ACSI	Airport Certification Safety Inspector
ADG	Airplane Design Group
AIP	Airport Improvement Program
ALECP	Airport Lighting Equipment Certification Program
ANG	Air National Guard
AOA	Air Operations Area, as defined in 14 CFR Part 107. Means a portion of an airport, specified in the airport security program, in which security measures are carried out. This area includes aircraft movement areas, aircraft parking areas, loading ramps, and safety areas, and any adjacent areas (such as general aviation areas) that are not separated by adequate security systems, measures, or procedures. This area does not include the secured area of the airport terminal building.
ARFF	Aircraft Rescue and Fire Fighting
ARP	FAA Office of Airports
ASDA	Accelerate-Stop Distance Available
AT	Air Traffic
ATCT	Airport Traffic Control Tower
ATIS	Automatic Terminal Information Service
ATO	Air Traffic Organization
Certificated Airport	An airport that has been issued an Airport Operating Certificate by the FAA under

Term	Definition		
	the authority of 14 CFR Part 139, Certification of Airports.		
CFR	Code of Federal Regulations		
Construction	The presence of construction-related personnel, equipment, and materials in any location that could infringe upon the movement of aircraft.		
CSPP	Construction Safety and Phasing Plan. The overall plan for safety and phasing of a construction project developed by the airport operator, or developed by the airport operator's consultant and approved by the airport operator. It is included in the invitation for bids and becomes part of the project specifications.		
CTAF	Common Traffic Advisory Frequency		
Displaced Threshold	A threshold that is located at a point on the runway other than the designated beginning of the runway. The portion of pavement behind a displaced threshold is available for takeoffs in either direction or landing from the opposite direction.		
DOT	Department of Transportation		
EPA	Environmental Protection Agency		
FAA	Federal Aviation Administration		
FOD	Foreign Object Debris/Damage		
FSS	Flight Service Station		
GA	General Aviation		
HAZMAT	Hazardous Materials		
НМА	Hot Mix Asphalt		
IAP	Instrument Approach Procedures		
IFR	Instrument Flight Rules		
ILS	Instrument Landing System		
LDA	Landing Distance Available		
LOC	Localizer antenna array		
Movement Area	The runways, taxiways, and other areas of an airport that are used for taxiing or hover taxiing, air taxiing, takeoff, and landing of aircraft, exclusive of loading aprons and aircraft parking areas (reference 14 CFR Part 139).		
MSDS	Material Safety Data Sheet		
MUTCD	Manual on Uniform Traffic Control Devices		
NAVAID	Navigation Aid		
NAVAID Critical Area	An area of defined shape and size associated with a NAVAID that must remain clear and graded to avoid interference with the electronic signal.		
Non-Movement Area	The area inside the airport security fence exclusive of the Movement Area. It is important to note that the non-movement area includes pavement traversed by aircraft.		

Term	Definition
NOTAM	Notices to Airmen
Obstruction	Any object/obstacle exceeding the obstruction standards specified by 14 CFR Part 77, subpart C.
OCC	Operations Control Center
OE / AAA	Obstruction Evaluation / Airport Airspace Analysis
OFA	Object Free Area. An area on the ground centered on the runway, taxiway, or taxi lane centerline provided to enhance safety of aircraft operations by having the area free of objects except for those objects that need to be located in the OFA for air navigation or aircraft ground maneuvering purposes. (See <u>AC 150/5300-13</u> for additional guidance on OFA standards and wingtip clearance criteria.)
OFZ	Obstacle Free Zone. The airspace below 150 ft (45 m) above the established airport elevation and along the runway and extended runway centerline that is required to be clear of all objects, except for frangible visual NAVAIDs that need to be located in the OFZ because of their function, in order to provide clearance protection for aircraft landing or taking off from the runway and for missed approaches. The OFZ is subdivided as follows: Runway OFZ, Inner Approach OFZ, Inner Transitional OFZ, and Precision OFZ. Refer to AC 150/5300-13 for guidance on OFZ.
OSHA	Occupational Safety and Health Administration
OTS	Out of Service
P&R	Planning and Requirements Group
NPI	NAS Planning & Integration
PAPI	Precision Approach Path Indicator
PFC	Passenger Facility Charge
PLASI	Pulse Light Approach Slope Indicator
Project Proposal Summary	A clear and concise description of the proposed project or change that is the object of Safety Risk Management.
RA	Reimbursable Agreement
RE	Resident Engineer
REIL	Runway End Identifier Lights
RNAV	Area Navigation
ROFA	Runway Object Free Area
RSA	Runway Safety Area. A defined surface surrounding the runway prepared or suitable for reducing the risk of damage to airplanes in the event of an undershoot, overshoot, or excursion from the runway, in accordance with <u>AC 150/5300-13</u> .
SDS	Safety Data Sheet
SIDA	Security Identification Display Area
SMS	Safety Management System

Term	Definition
SPCD	Safety Plan Compliance Document. Details developed and submitted by a contractor to the airport operator for approval providing details on how the performance of a construction project will comply with the CSPP.
SRM	Safety Risk Management
SSC	System Support Center
Taxiway Safety Area	A defined surface alongside the taxiway prepared or suitable for reducing the risk of damage to an airplane unintentionally departing the taxiway, in accordance with <u>AC 150/5300-13</u> .
TDG	Taxiway Design Group
Temporary	Any condition that is not intended to be permanent.
Temporary Runway End	The beginning of that portion of the runway available for landing and taking off in one direction, and for landing in the other direction. Note the difference from a displaced threshold.
Threshold	The beginning of that portion of the runway available for landing. In some instances, the landing threshold may be displaced.
TODA	Takeoff Distance Available
TOFA	Taxiway Object Free Area
TORA	Takeoff Run Available. The length of the runway less any length of runway unavailable and/or unsuitable for takeoff run computations. See <u>AC 150/5300-13</u> for guidance on declared distances.
TSA	Taxiway Safety Area, or Transportation Security Administration
UNICOM	A radio communications system of a type used at small airports.
VASI	Visual Approach Slope Indicator
VGSI	Visual Glide Slope Indicator. A device that provides a visual glide slope indicator to landing pilots. These systems include precision approach path indicator (PAPI), visual approach slope indicator (VASI), and pulse light approach slope indicator (PLASI).
VFR	Visual Flight Rules
VOR	Very High Frequency Omnidirectional Radio Range
VPD	Vehicle / Pedestrian Deviation

APPENDIX C. SAFETY AND PHASING PLAN CHECKLIST

This appendix is keyed to <u>Chapter 2</u>. In the electronic version of this AC, clicking on the paragraph designation in the Reference column will access the applicable paragraph. There may be instances where the CSPP requires provisions that are not covered by the list in this appendix.

This checklist is intended as an aid, not a required submittal.

Table C-1. CSPP Checklist

Coordination	Reference	Addressed?			Remarks
		Yes	No	NA	
Ge	neral Considerat	tions			
Requirements for predesign, prebid, and preconstruction conferences to introduce the subject of airport operational safety during construction are specified.	<u>2.5</u>				
Operational safety is a standing agenda item for construction progress meetings.	<u>2.5</u>				
Scheduling of the construction phases is properly addressed.	<u>2.6</u>				
Any formal agreements are established.	2.5.3				
Areas and Operation	ons Affected by C	Construction	Activity		
Drawings showing affected areas are included.	<u>2.7.1</u>				
Closed or partially closed runways, taxiways, and aprons are depicted on drawings.	2.7.1.1				
Access routes used by ARFF vehicles affected by the project are addressed.	2.7.1.2				
Access routes used by airport and airline support vehicles affected by the project are addressed.	2.7.1.3				
Underground utilities, including water supplies for firefighting and drainage.	2.7.1.4				

Coordination	Reference	Addressed?			Remarks
		Yes	No	NA	
Approach/departure surfaces affected by heights of temporary objects are addressed.	2.7.1.5				
Construction areas, storage areas, and access routes near runways, taxiways, aprons, or helipads are properly depicted on drawings.	<u>2.7.1</u>				
Temporary changes to taxi operations are addressed.	<u>2.7.2.1</u>				
Detours for ARFF and other airport vehicles are identified.	2.7.2.2				
Maintenance of essential utilities and underground infrastructure is addressed.	2.7.2.3				
Temporary changes to air traffic control procedures are addressed.	2.7.2.4				
	NAVAIDs				
Critical areas for NAVAIDs are depicted on drawings.	<u>2.8</u>				
Effects of construction activity on the performance of NAVAIDS, including unanticipated power outages, are addressed.	2.8				
Protection of NAVAID facilities is addressed.	2.8				
The required distance and direction from each NAVAID to any construction activity is depicted on drawings.	2.8				
Procedures for coordination with FAA ATO/Technical Operations, including identification of points of contact, are included.	2.8, 2.13.1, 2.13.5.3.1, 2.18.1				
	Contractor Acces	ss	_	1	
The CSPP addresses areas to which contractor will have access and how	<u>2.9</u>				

Coordination	Reference	Addressed?			Remarks
		Yes	No	NA	
the areas will be accessed.					
The application of 49 CFR Part 1542 Airport Security, where appropriate, is addressed.	2.9				
The location of stockpiled construction materials is depicted on drawings.	2.9.1				
The requirement for stockpiles in the ROFA to be approved by FAA is included.	<u>2.9.1</u>				
Requirements for proper stockpiling of materials are included.	<u>2.9.1</u>				
Construction site parking is addressed.	2.9.2.1				
Construction equipment parking is addressed.	2.9.2.2				
Access and haul roads are addressed.	2.9.2.3				
A requirement for marking and lighting of vehicles to comply with AC 150/5210-5, Painting, Marking and Lighting of Vehicles Used on an Airport, is included.	2.9.2.4				
Proper vehicle operations, including requirements for escorts, are described.	2.9.2.5, 2.9.2.6				
Training requirements for vehicle drivers are addressed.	2.9.2.7				
Two-way radio communications procedures are described.	2.9.2.9				
Maintenance of the secured area of the airport is addressed.	2.9.2.10				
V	Vildlife Managemo	ent			
The airport operator's wildlife management procedures are addressed.	2.10				

Coordination	Reference	Addressed?		Addressed?	Remarks
		Yes	No	NA	-
Foreign (Object Debris Ma	nagement		I	
The airport operator's FOD management procedures are addressed.	2.11				
Hazardo	ous Materials Ma	nagement	•		
The airport operator's hazardous materials management procedures are addressed.	2.12				
Notification	on of Construction	n Activities			
Procedures for the immediate notification of airport user and local FAA of any conditions adversely affecting the operational safety of the airport are detailed.	2.13				
Maintenance of a list by the airport operator of the responsible representatives/points of contact for all involved parties and procedures for contacting them 24 hours a day, seven days a week is specified.	2.13.1				
A list of local ATO/Technical Operations personnel is included.	2.13.1				
A list of ATCT managers on duty is included.	2.13.1				
A list of authorized representatives to the OCC is included.	2.13.2				
Procedures for coordinating, issuing, maintaining and cancelling by the airport operator of NOTAMS about airport conditions resulting from construction are included.	2.8, 2.13.2, 2.18.3.3.9				
Provision of information on closed or hazardous conditions on airport movement areas by the airport operator to the OCC is specified.	2.13.2				
Emergency notification procedures for medical, fire fighting, and police	2.13.3				

Coordination	Reference	Addressed?		Remarks	
		Yes	No	NA	
response are addressed.					
Coordination with ARFF personnel for non-emergency issues is addressed.	2.13.4				
Notification to the FAA under 14 CFR parts 77 and 157 is addressed.	<u>2.13.5</u>				
Reimbursable agreements for flight checks and/or design and construction for FAA owned NAVAIDs are addressed.	2.13.5.3.2				
Ins	pection Requirem	ents	•	•	1
Daily and interim inspections by both the airport operator and contractor are specified.	2.14.1, 2.14.2				
Final inspections at certificated airports are specified when required.	2.14.3				
Uı	nderground Utilit	ties	·		•
Procedures for protecting existing underground facilities in excavation areas are described.	<u>2.15</u>				
	Penalties	•	•	•	1
Penalty provisions for noncompliance with airport rules and regulations and the safety plans are detailed.	<u>2.16</u>				
,	Special Condition	ns			
Any special conditions that affect the operation of the airport or require the activation of any special procedures are addressed.	<u>2.17</u>				
Runway and Taxiway Visual Aids - Marking, Lighting, Signs, and Visual NAVAIDs					
The proper securing of temporary airport markings, lighting, signs, and visual NAVAIDs is addressed.	<u>2.18.1</u>				
Frangibility of airport markings, lighting, signs, and visual NAVAIDs is specified.	2.18.1, 2.18.3, 2.18.4.2, 2.20.2.4				

Coordination	Reference	Addressed?		Reference Addressed?	Remarks
		Yes	No	NA	
The requirement for markings to be in compliance with AC 150/5340-1, Standards for Airport Markings, is specified.	2.18.2				
Detailed specifications for materials and methods for temporary markings are provided.	2.18.2				
The requirement for lighting to conform to AC 150/5340-30, Design and Installation Details for Airport Visual Aids; AC 150/5345-50, Specification for Portable Runway and Taxiway Lights; and AC 150/5345-53, Airport Lighting Certification Program, is specified.	2.18.3				
The use of a lighted X is specified where appropriate.	2.18.2.1.2, 2.18.3.2				
The requirement for signs to conform to AC 150/5345-44, Specification for Runway and Taxiway Signs; AC 50/5340-18, Standards for Airport Sign Systems; and AC 150/5345-53, Airport Lighting Certification Program, is specified.	2.18.4				
Marking a	and Signs For Acc	cess Routes	•		•
The CSPP specifies that pavement markings and signs intended for construction personnel should conform to AC 150/5340-18 and, to the extent practicable, with the MUTCD and/or State highway specifications.	2.18.4.2				
Hazar	d Marking and L	ighting			
Prominent, comprehensible warning indicators for any area affected by construction that is normally accessible to aircraft, personnel, or vehicles are specified.	2.20.1				

Coordination	Reference	Addressed?		Remarks	
		Yes	No	NA	
Hazard marking and lighting are specified to identify open manholes, small areas under repair, stockpiled material, and waste areas.	<u>2.20.1</u>				
The CSPP considers less obvious construction-related hazards.	<u>2.20.1</u>				
Equipment that poses the least danger to aircraft but is sturdy enough to remain in place when subjected to typical winds, prop wash and jet blast is specified.	<u>2.20.2.1</u>				
The spacing of barricades is specified such that a breach is physically prevented barring a deliberate act.	<u>2.20.2.1</u>				
Red lights meeting the luminance requirements of the State Highway Department are specified.	<u>2.20.2.2</u>				
Barricades, temporary markers, and other objects placed and left in areas adjacent to any open runway, taxiway, taxi lane, or apron are specified to be as low as possible to the ground, and no more than 18 inch high.	2.20.2.3				
Barricades are specified to indicate construction locations in which no part of an aircraft may enter.	2.20.2.3				
Highly reflective barriers with lights are specified to barricade taxiways leading to closed runways.	<u>2.20.2.5</u>				
Markings for temporary closures are specified.	2.20.2.5				
The provision of a contractor's representative on call 24 hours a day for emergency maintenance of airport hazard lighting and barricades is specified.	<u>2.20.2.7</u>				

Coordination	Reference	Addressed?			Remarks
		Yes	No	NA	
Work Zone Lig	hting for Nightt	ime Construc	tion	I.	
If work is to be conducted at night, the CSPP identifies construction lighting units and their general locations and aiming in relationship to the ATCT and active runways and taxiways.	2.21				
Protection of R	unway and Taxi	way Safety A	reas		
The CSPP clearly states that no construction may occur within a safety area while the associated runway or taxiway is open for aircraft operations.	2.22.1.1, 2.22.3.1				
The CSPP specifies that the airport operator coordinates the adjustment of RSA or TSA dimensions with the ATCT and the appropriate FAA Airports Regional or District Office and issues a local NOTAM.	2.22.1.2, 2.22.3.2				
Procedures for ensuring adequate distance for protection from blasting operations, if required by operational considerations, are detailed.	2.22.3.3				
The CSPP specifies that open trenches or excavations are not permitted within a safety area while the associated runway or taxiway is open, subject to approved exceptions.	2.22.1.4				
Appropriate covering of excavations in the RSA or TSA that cannot be backfilled before the associated runway or taxiway is open is detailed.	2.22.1.4				
The CSPP includes provisions for prominent marking of open trenches and excavations at the construction site.	2.22.1.4				
Grading and soil erosion control to maintain RSA/TSA standards are	2.22.3.5				

Coordination	Reference	Addressed?		Remarks	
		Yes	No	NA	
addressed.					
The CSPP specifies that equipment is to be removed from the ROFA when not in use.	2.22.2				
The CSPP clearly states that no construction may occur within a taxiway safety area while the taxiway is open for aircraft operations.	2.22.3				
Appropriate details are specified for any construction work to be accomplished in a taxiway object free area.	2.22.4				
Measures to ensure that personnel, material, and/or equipment do not penetrate the OFZ or threshold siting surfaces while the runway is open for aircraft operations are included.	2.22.4.3.6				
Provisions for protection of runway approach/departure areas and clearways are included.	2.22.6				
Other Li	imitations on Co	nstruction			
The CSPP prohibits the use of open flame welding or torches unless adequate fire safety precautions are provided and the airport operator has approved their use.	2.23.1.2				
The CSPP prohibits the use of electrical blasting caps on or within 1,000 ft (300 m) of the airport property.	2.23.1.3				

APPENDIX D. CONSTRUCTION PROJECT DAILY SAFETY INSPECTION CHECKLIST

The situations identified below are potentially hazardous conditions that may occur during airport construction projects. Safety area encroachments, unauthorized and improper ground vehicle operations, and unmarked or uncovered holes and trenches near aircraft operating surfaces pose the most prevalent threats to airport operational safety during airport construction projects. The list below is one tool that the airport operator or contractor may use to aid in identifying and correcting potentially hazardous conditions. It should be customized as appropriate for each project including information such as the date, time and name of the person conducting the inspection.

Table D-1. Potentially Hazardous Conditions

Item	Action Required (Describe)	No Action Required (Check)
Excavation adjacent to runways, taxiways, and aprons improperly backfilled.		
Mounds of earth, construction materials, temporary structures, and other obstacles near any open runway, taxiway, or taxi lane; in the related Object Free area and aircraft approach or departure areas/zones; or obstructing any sign or marking.		
Runway resurfacing projects resulting in lips exceeding 3 inch (7.6 cm) from pavement edges and ends.		
Heavy equipment (stationary or mobile) operating or idle near AOA, in runway approaches and departures areas, or in OFZ.		
Equipment or material near NAVAIDs that may degrade or impair radiated signals and/or the monitoring of navigation and visual aids. Unauthorized or improper vehicle operations in localizer or glide slope critical areas, resulting in electronic interference and/or facility shutdown.		
Tall and especially relatively low visibility units (that is, equipment with slim profiles) — cranes, drills, and similar objects — located in critical areas, such as OFZ and		

Item	Action Required (Describe)	No Action Required (Check)
approach zones.		
Improperly positioned or malfunctioning lights or unlighted airport hazards, such as holes or excavations, on any apron, open taxiway, or open taxi lane or in a related safety, approach, or departure area.		
Obstacles, loose pavement, trash, and other debris on or near AOA. Construction debris (gravel, sand, mud, paving materials) on airport pavements may result in aircraft propeller, turbine engine, or tire damage. Also, loose materials may blow about, potentially causing personal injury or equipment damage.		
Inappropriate or poorly maintained fencing during construction intended to deter human and animal intrusions into the AOA. Fencing and other markings that are inadequate to separate construction areas from open AOA create aviation hazards.		
Improper or inadequate marking or lighting of runways (especially thresholds that have been displaced or runways that have been closed) and taxiways that could cause pilot confusion and provide a potential for a runway incursion. Inadequate or improper methods of marking, barricading, and lighting of temporarily closed portions of AOA create aviation hazards.		
Wildlife attractants — such as trash (food scraps not collected from construction personnel activity), grass seeds, tall grass, or standing water — on or near airports.		
Obliterated or faded temporary markings on active operational areas.		
Misleading or malfunctioning obstruction lights. Unlighted or unmarked obstructions in the approach to any open runway pose aviation hazards.		

Item	Action Required (Describe)	No Action Required (Check)
Failure to issue, update, or cancel NOTAMs about airport or runway closures or other construction related airport conditions.		
Failure to mark and identify utilities or power cables. Damage to utilities and power cables during construction activity can result in the loss of runway / taxiway lighting; loss of navigation, visual, or approach aids; disruption of weather reporting services; and/or loss of communications.		
Restrictions on ARFF access from fire stations to the runway / taxiway system or airport buildings.		
Lack of radio communications with construction vehicles in airport movement areas.		
Objects, regardless of whether they are marked or flagged, or activities anywhere on or near an airport that could be distracting, confusing, or alarming to pilots during aircraft operations.		
Water, snow, dirt, debris, or other contaminants that temporarily obscure or derogate the visibility of runway/taxiway marking, lighting, and pavement edges. Any condition or factor that obscures or diminishes the visibility of areas under construction.		
Spillage from vehicles (gasoline, diesel fuel, oil) on active pavement areas, such as runways, taxiways, aprons, and airport roadways.		
Failure to maintain drainage system integrity during construction (for example, no temporary drainage provided when working on a drainage system).		

Item	Action Required (Describe)	No Action Required (Check)
Failure to provide for proper electrical lockout and tagging procedures. At larger airports with multiple maintenance shifts/workers, construction contractors should make provisions for coordinating work on circuits.		
Failure to control dust. Consider limiting the amount of area from which the contractor is allowed to strip turf.		
Exposed wiring that creates an electrocution or fire ignition hazard. Identify and secure wiring, and place it in conduit or bury it.		
Site burning, which can cause possible obscuration.		
Construction work taking place outside of designated work areas and out of phase.		

APPENDIX E. SAMPLE OPERATIONAL EFFECTS TABLE

E.1 Project Description.

Runway 15-33 is currently 7820 feet long, with a 500 foot stopway on the north end. This project will remove the stopway and extend the runway 1000 feet to the north and 500 feet to the south. Finally, the existing portion of the runway will be repaved. The runway 33 glide slope will be relocated. The new runway 33 localizer has already been installed by FAA Technical Operations and only needs to be switched on. Runway 15 is currently served only by a localizer, which will remain in operation as it will be beyond the future RSA. Appropriate NOTAMS will be issued throughout the project.

E.1.1 During Phase I, the runway 15 threshold will be displaced 1000 feet to keep construction equipment below the approach surface. The start of runway 15 takeoff and the departure end of runway 33 will also be moved 500 feet to protect workers from jet blast. Declared distances for runway 33 will be adjusted to provide the required RSA and applicable departure surface. Excavation near Taxiway G will require its ADG to be reduced from IV to III. See Figure E-1.




Figure E-1. Phase I Example

- **Note 1:** Where hold signs are installed on both sides of a taxiway, install the TORA sign on the left side of the taxiway before the final turn to the runway intersection.
- **Note 2:** Based on the declared distances for Runway 33 departures, the maximum equipment height in the construction area is 12.5 feet (500/40 = 12.5).

E.2 During Phase II, the runway 33 threshold will be displaced 1000 feet to keep construction equipment below the approach surface. The start of runway 33 takeoff and the departure end of runway 15 will also be moved 500 feet to protect workers from jet blast. Declared distances for runway 15 will be adjusted to provide the required RSA and applicable departure surface. See <u>Figure E-2</u>.

NEW CONSTRUCTION

7,820 FEET (ASDA, LDA)

8,320 (TORA, TODA, ASDA)

7,820 (LDA)

8,320 (TORA, TODA)

1,820 (LDA)

8,320 (TORA, TODA)

1,820 (LDA)

Figure E-2. Phase II Example

- **Note 1:** Where hold signs are installed on both sides of a taxiway, install the TORA sign on the left side of the taxiway before the final turn to the runway intersection.
- **Note 2:** Based on the declared distances for Runway 15 departures, the maximum equipment height in the construction area is 12.5 feet (500/40 = 12.5).

E.3 During Phase III, the existing portion of the runway will be repaved with Hot Mix Asphalt (HMA) and the runway 33 glide slope will be relocated. Construction will be accomplished between the hours of 8:00 pm and 5:00 am, during which the runway will be closed to operations.




Figure E-3. Phase III Example

Table E-1. Operational Effects Table

Project	Runway 15-33 Extension and Repaving			
Phase	Normal (Existing)	Phase I: Extend Runway 15 End	Phase II: Extend Runway 33 End	Phase III: Repave Runway
Scope of Work	N/A	Extend Runway 15-33 1,000 ft on north end with Hot Mix Asphaltic Concrete (HMA).	Extend Runway 15-33 500 ft on south end with Hot Mix Asphaltic Concrete (HMA).	Repave existing runway with HMA Relocate Runway 33 Glide Slope
Effects of Construction Operations	N/A	Existing North 500 ft closed	Existing South 500 ft closed	Runway closed between 8:00 pm and 5:00 am Edge lighting out of service
Construction Phase	N/A	Phase I (Anticipated)	Phase II (Anticipated)	Phase III (Anticipated)
Runway 15 Average Aircraft Operations	Carrier: 52 /day GA: 26 /day Military: 11 /day	Carrier: 40 /day GA: 26 /day Military: 0 /day	Carrier: 45 /day GA: 26 /day Military: 5 /day	Carrier: 45 / day GA: 20 / day Military: 0 /day
Runway 33 Average Aircraft Operations	Carrier: 40 /day GA: 18 /day Military: 10 /day	Carrier: 30 /day GA: 18 /day Military: 0 /day	Carrier: 25 /day GA: 18 /day Military: 5 /day	Carrier: 20 /day GA: 5 /day Military: 0 /day
Runway 15-33 Aircraft Category	C-IV	C-IV	C-IV	C-IV
Runway 15 Approach Visibility Minimums	1 mile	1 mile	1 mile	1 mile
Runway 33 Approach Visibility Minimums	¾ mile	¾ mile	¾ mile	1 mile

Note: Proper coordination with Flight Procedures group is necessary to maintain instrument approach procedures during construction.

Project		Runway 15-33 Extension and Repaving			
Phase		Normal (Existing)	Phase I: Extend Runway 15 End	Phase II: Extend Runway 33 End	Phase III: Repave Runway
Runway 15 Declared Distances TODA		7,820	7,320	8,320	9,320
		7,820	7,320	8,320	9,320
	ASDA	7,820	7,320	7,820	9,320
	LDA	7,820	6,820	7,820	9,320
Runway 33	TORA	7,820	7,320	8,320	9,320
Declared Distances	TODA	7,820	7,320	8,320	9,320
	ASDA	8,320	6,820	8,320	9,320
	LDA	7,820	6,820	7,820	9,320
Runwa	v 15	LOC only	LOC only	LOC only	LOC only
Approach Procedures		RNAV	RNAV	RNAV	RNAV
		VOR	VOR	VOR	VOR
Runway 33 Approach Procedures Runway 15 NAVAIDs		ILS	ILS	ILS	LOC only
		RNAV	RNAV	RNAV	RNAV
		VOR	VOR	VOR	VOR
		LOC	LOC	LOC	LOC
Runwa NAVA	•	ILS, MALSR	ILS, MALSR	ILS, MALSR	LOC, MALSR
Taxiway G ADG		IV	III	IV	IV
Taxiway (G TDG	4	4	4	4
ATCT (hou	rs open)	24 hours	24 hours	24 hours	0500 - 2000
ARFF I	ndex	D	D	D	D

Project	Runway 15-33 Extension and Repaving			
Phase	Normal (Existing)	Phase I: Extend Runway 15 End	Phase II: Extend Runway 33 End	Phase III: Repave Runway
Special Conditions	Air National Guard (ANG) military operations	All military aircraft relocated to alternate ANG Base	Some large military aircraft relocated to alternate ANG Base	All military aircraft relocated to alternate ANG Base
Information for NOTAMs		Refer above for applicable declared distances. Taxiway G limited to 118 ft wingspan	Refer above for applicable declared distances.	Refer above for applicable declared distances. Airport closed 2000 – 0500. Runway 15 glide slope OTS.

Note: This table is one example. It may be advantageous to develop a separate table for each project phase and/or to address the operational status of the associated NAVAIDs per construction phase.

Complete the following chart for each phase to determine the area that must be protected along the runway and taxiway edges:

Table E-2. Runway and Taxiway Edge Protection

Runway/Taxiway	Aircraft Approach Category* A, B, C, or D	Airplane Design Group* I, II, III, or IV	Safety Area Width in Feet Divided by 2*

^{*}See AC 150/5300-13 to complete the chart for a specific runway/taxiway.

Complete the following chart for each phase to determine the area that must be protected before the runway threshold:

Table E-3. Protection Prior to Runway Threshold

Runway End Number	Airplane Design Group* I, II, III, or IV	Aircraft Approach Category* A, B, C, or D	Minimum Safety Area Prior to the Threshold*		Distance to I Based on proach Slope*
			ft	ft	: 1
			ft	ft	: 1
			ft	ft	: 1
			ft	ft	: 1

^{*}See AC 150/5300-13 to complete the chart for a specific runway.

Page Intentionally Blank

APPENDIX F. ORANGE CONSTRUCTION SIGNS

Figure F-1. Approved Sign Legends

CONSTRUCTION AHEAD

CONSTRUCTION ON RAMP

RWY 4L TAKEOFF RUN AVAILABLE 9,780 FT




Figure F-2. Orange Construction Sign Example 1

Note: For proper placement of signs, refer to EB 93.




Figure F-3. Orange Construction Sign Example 2

Note: For proper placement of signs, refer to EB 93.

Page Intentionally Blank

Advisory Circular Feedback

If you find an error in this AC, have recommendations for improving it, or have suggestions for new items/subjects to be added, you may let us know by (1) mailing this form to Manager, Airport Engineering Division, Federal Aviation Administration ATTN: AAS-100, 800 Independence Avenue SW, Washington DC 20591 or (2) faxing it to the attention of the Office of Airport Safety and Standards at (202) 267-5383.

Subj	ect: AC 150/53/0-2G	Date:	
Plea	se check all appropriate line	items:	
	An error (procedural or typo	ographical) has been noted in paragrap	on page
		on page	
	In a future change to this AC (Briefly describe what you war	·	
	Other comments:		
	I would like to discuss the al	bove. Please contact me at (phone nu	mber, email address).
Subr	nitted by:	Date	



APPENDIX A GEOTECHNICAL ENGINEERING REPORT

REPORT OF SUBSURFACE EXPLORATION AND GEOTECHNICAL ENGINEERING EVALUATION

MTAA TOP REHAB DESIGN PHILIP BILLARD AIRPORT TOPEKA, KANSAS TSI PROJECT NO. 20242056.00

WSP USA, INC.

300 Wyandotte Street Kansas City, Missouri 64105



8248 NW 101st Terrace, #5 Kansas City, Missouri 64153

February 10, 2025



February 10, 2025

Mr. Sam Stallbaumer, PE WSP USA, INC.
300 Wyandotte Street
Kansas City, Missouri 64105

Re: Report of Subsurface Exploration and Geotechnical Engineering Evaluation MTAA TOP Rehab Design – Philip Billard Airport Topeka, Kansas TSi Project No. 20242056.00

Dear Mr. Stallbaumer:

TSi Geotechnical, Inc. (TSi) has completed the authorized Subsurface Exploration and Geotechnical Engineering Evaluation for the referenced project and is pleased to submit this report of our findings to WSP USA, Inc. (WSP). The purpose of our work was to assess subsurface conditions at specific test boring locations in order to prepare geotechnical recommendations for use in the design and reconstruction of the existing apron located at the Philip Billard Airport in Topeka, Kansas. This report presents the field and laboratory data and includes our evaluations and recommendations relative to the geotechnical engineering aspects of the project.

We appreciate the opportunity to assist you with this project. If you have any questions, or if we may be of further service to you, please call us.

Respectfully submitted, TSI GEOTECHNICAL, INC.

DRAFT

Anderson L. Borges Project Manager

DRAFT

Andrew Declue, PE Director of Operations **DRAFT**

Denise B. Hervey, PE Principal

CONTENTS

1.0 Scope of Work	1
2.0 Project and Site Descriptions	2
3.0 FIELD EXPLORATION AND LABORATORY TESTING	3
4.0 SUBSURFACE CONDITIONS	
4.0 SUBSURFACE CONDITIONS 4.1 General Geology 4.2 Generalized Subsurface Profile 4.3 Groundwater	5 5
5.0 DESIGN RECOMMENDATIONS	7
6.0 SITE PREPARATION AND EXCAVATION CONSIDERATIONS 6.1 Subgrade Preparation 6.2 Excavations 6.3 Subgrade Protection 6.4 Fill and Backfill Materials 6.5 Fill and Backfill Placement	9 10 10
7.0 CONSTRUCTION OBSERVATION AND TESTING	11
8.0 REPORT LIMITATIONS	12
Appendix A – Vicinity Map, Figure 1.0 Site and Boring Location Plans, Figure 2.0 Appendix B - Logs of Boring Boring Log Notes General Notes Unified Soil Classification System Appendix C – Laboratory Test Results	
Appendix D – Pavement Core Photographs	

SUBSURFACE EXPLORATION AND GEOTECHNICAL ENGINEERING EVALUATION MTAA TOP REHAB DESIGN – PHILIP BILLARD AIRPORT TOPEKA, KANSAS

1.0 SCOPE OF WORK

This report summarizes the results of a subsurface exploration and geotechnical evaluation completed for use in the design and reconstruction of the existing apron at the Philip Billard Airport in Topeka, Kansas. The study was performed in general accordance with TSi's proposal to WSP dated on November 15, 2024 and authorized on November 19, 2024. Based on TSi's understanding of the project, the following items have been identified for inclusion in this geotechnical study report:

- Subsurface conditions including material types at the boring locations;
- Laboratory test results for soil samples;
- Influence of groundwater on design and construction;
- Soil strength parameters;
- Soil remediation recommendations;
- Locations and descriptions of any existing fill or potentially deleterious materials encountered at the site that may interfere with construction progress or structure performance, if encountered;
- Type and depth of any rock encountered;
- Pavement design considerations;
- Recommendations for fill materials, placement, and compaction;
- General construction considerations; and
- Recommendations for engineering observation and testing during construction.

2.0 Project and Site Descriptions

The following understanding of the project is based on information provided by **WSP**. The project will consist of the design and reconstruction of the existing apron at the Philip Billard Airport in Topeka, Kansas.

Based on a provided plan, the project area consists of existing apron pavements area located southeast of the existing terminal and extends northeast to paved area west of Runway 18-36. The project site is relatively level and generally paved with asphaltic concrete (AC). Structural details of the new pavement have not been provided at the time of writing this report. However, we anticipate pavements with asphaltic concrete and Portland cement concrete will be used for design of this project.

The general location of the project site is shown on the Vicinity Map, Figure 1 in Appendix A. General site features and the location of the test borings performed for this study are provided on the Site and Boring Location Plan, Figure 2 in Appendix A.

3.0 FIELD EXPLORATION AND LABORATORY TESTING

3.1 FIELD EXPLORATION

TSi conducted an exploration program at the proposed project site on January 3, 2025. The exploration consisted of four (4) borings with pavement core, designated as Borings B-1 to B-4, one (1) companion boring designated as CB-1 located at the grass area south of the existing apron near B-1 and one (1) pavement core designated as P-1 located on the southeast corner of the apron near existing taxiway. Borings were advanced to depths of about 20.0 feet. The boring locations were selected and marked on the field by WSP. Ground surface elevations were estimated from Google Earth. The approximate location of the borings are indicated on the Site and Boring Location Plan, Figures 2.0 in Appendix A.

A geotechnical specialist from TSi observed drilling and sampling procedures for the borings that were drilled. A split-spoon sample was recovered from one location using a 2-inch outside-diameter, split-barrel sampler, driven by an automatic hammer, in accordance with ASTM D 1586. The split-spoon sample was placed in a plastic bag for later testing in the laboratory. Shelby tube samples were recovered from most of the sampling locations and were preserved by sealing the entire sample in the tube in accordance with ASTM D 1587. Bulk soil sample from depths of about 2 to 5 feet was collected in 5-gallon buckets for the CBR and modified Proctor tests. Borings were backfilled with cuttings, and asphalt patches and concrete in pavements. The sampling sequence for each boring is summarized on the Logs of Boring in Appendix B.

The results of the field tests and measurements were recorded on field logs and appropriate data sheets. Those data sheets and logs contain information concerning the boring methods, samples attempted and recovered, indications of the presence of various subsurface materials, and the observation of groundwater. The field logs and data sheets contain the geotechnical specialist's interpretations of the conditions between samples, based on the performance of the drilling equipment and the cuttings brought to the surface by the drilling tools.

3.2 Laboratory Testing

A laboratory testing program was conducted by TSi to determine selected engineering properties of the obtained soil samples. The results of the individual tests are presented on the Logs of Boring and in Appendix C of this report. The following laboratory tests were performed on the samples recovered from the borings in general accordance with the applicable ASTM standards:

- Visual descriptions by color and texture of each sample;
- Moisture content of soil samples;
- Atterberg limits on selected cohesive samples;
- Unit weight on selected cohesive samples
- Unconfined compression strength of soil on selected soil samples;
- Hydrometer analysis;
- Sieve tests;
- Modified Proctor compaction test from selected samples.
- California bearing ratio tests (CBR); and
- Pavement core photographs;

Data and observations from laboratory tests were recorded on laboratory data sheets during the course of the testing program. The logs represent considered interpretation of the field and laboratory data. The analyses and conclusions contained in this report are based on field and laboratory test results and on the interpretations of the subsurface conditions as reported on the logs. Only data pertinent to the objectives of this report have been included on the logs; therefore, these logs should not be used for other purposes.

4.0 SUBSURFACE CONDITIONS

Details of the subsurface conditions encountered at the test borings are presented on each Log of Boring in Appendix B. The general subsurface conditions encountered and their pertinent engineering characteristics are described in the following paragraphs. Conditions represented by the borings should be considered applicable only at that exploration location on the date shown; the reported conditions may be different at other locations or at other times.

4.1 GENERAL GEOLOGY

Based on the United States Geological Survey (USGS) and the Kansas Geological Survey (KGS) databases, the site lies in the Quaternary System geologic formation that is located about 1 to 1.5 miles from the Kansas River on the east, west, and north sides.

The Quaternary System in this location typically consists of alluvium of the late Pleistocene and Holocene Series that have been formed by clay, silt, sand, gravel, or similar unconsolidated material deposited during recent geologic time by a stream or other running water, such as the Kansas River Flood Plain. Additional data from FEMA's National Flood Hazard Layer (NFHC) viewer indicates that the site is situated in an area with flooding risks associated with levees. Well logs in the project area indicate the depth to bedrock could be 60 to 80 feet or more.

4.2 GENERALIZED SUBSURFACE PROFILE

Surface materials at the site generally consists of pavements with various thicknesses of AC and Portland cement concrete (PCC) as depicted in the pavement core photographs in Appendix D. Note that some core losses may have occurred due to deteriorated pavement sections.

Native soils underlying the surface materials, consist of lean and fat clays, sands, clayey sands, and silts (CL, CH, SP, SC and ML, respectively, in accordance with the Unified Soil Classification System) with various amounts of sand, gravel, silt and clay extending to termination depths of about 20 feet below ground surface. In general, cohesive soils were encountered to depths of about 12 to 20 feet, underlain by sands. Most of the soil sampling was in Shelby tubes. However, a standard penetration test (N) value in the native soils is 11 blows per foot (bpf) in the clayey sand at a depth of 20 feet in Boring B-2. Moisture contents within these soils range from 5% to 46%. Atterberg limit tests within the soils resulted in LL ranging from 23 to 77, and PI ranging from 5 to 39, respectively. Dry unit weights and undrained shear strength values range from 76 to 108 pounds per cubic foot (pcf) and 0.15 to 1.27 tons per square foot (tsf), respectively. Atterberg limit tests of the bulk sample resulted in LL's of 29, and PI's of 9, respectively.

4.3 GROUNDWATER

Groundwater was generally not encountered in the borings during drilling to depths of 20 feet. The Kansas River may be approximately 30 feet below the project site elevation. The presence or absence of groundwater at a particular location does not necessarily mean that groundwater will be present or absent at that location at other times. Seasonal variations, the Kansas River stages and other unknown considerations could cause fluctuations in water levels. Excessive groundwater seepage is not expected at the shallow, temporary excavation for the proposed reconstruction of the existing apron. If minor groundwater seepage occur in shallow excavations, it should be able to be handled by shallow sump and pump systems.



5.0 DESIGN RECOMMENDATIONS

5.1 SWELLING CLAY CONSIDERATIONS

Based on the laboratory tests and our visual classifications, fat clay soils were encountered within the soil materials at this site at depths of about 6 to 13 feet. The liquid limit and plasticity index of tested fat clay were ranging from 58 to 77, and 30 to 39, respectively. Fat clays are considered to be highly plastic and prone to moisture-induced potential vertical movements. Although not encountered at the surface of the borings, if fat clay is encountered within 2 feet of the pavement subgrade elevation, the fat clay materials should be overexcavated to a depth of at least 24 inches and be replaced with properly placed and compacted Low Volume Change (LVC) fill material, which is considered select or engineered fill. LVC fill should consist of approved, well-graded granular materials or low plasticity cohesive soil. Low plasticity cohesive materials used as LVC fill should consist of inorganic clay with a liquid limit less than 45 and a plasticity index between 10 and 25. Granular fill, such as crushed limestone (KDOT AB-1 aggregate), should be well-graded, have a maximum particle size of 1.5 inch, and a maximum of 8% passing a #200 sieve.

Alternatively, if fat clays are encountered at the pavement subgrade elevation, the upper subgrade soils can be lime or cement stabilized to a depth of at least 12 inches. For lime stabilization about 1 to 2% more lime is added than needed to increase the soil PH above 12 and the unconfined compressive strength should be at least 50 psi. For cement stabilization about 1 to 2% more than required using the PCA method should be used. These stabilization methods require complete mixing of the soil and additives using equipment such as a gator.

In addition to the removal and replacement or stabilization, some relatively simple design and construction considerations are recommended that will help to maintain the natural moisture content of the fat clay. Avoiding conditions that could result in excessive wetting or drying of the fat clay will reduce its potential for volume change. The following design and construction precautions are recommended:

- 1. Positive surface drainage should be provided during construction to prevent ponding of water in and around any excavations or the exposed subgrade;
- 2. Storm water runoff should be collected and carried away from the pavement to avoid saturating the subgrade under the pavement;
- 3. Excessive watering of grass adjacent to the pavement should be avoided.
- 4. Install joint sealant and seal cracks immediately;

5.2 PAVEMENT DESIGN CONSIDERATIONS

Based on the cohesive soils encountered in the borings, a California Bearing Ratio (CBR) value of 3 could be used for design of a new flexible pavement. A modulus-of-subgrade reaction (k) of 68 pounds per cubic inch can be used for the design of a rigid pavement. These values are based on the assumption that the subgrade is prepared in accordance with the recommendations provided in Section 6 of this report.

FAA recommends to improve the subgrade through stabilization or replacement with suitable soil when CBR values are less than 5. We recommend to remove and replace at least 2 feet of unsuitable soils or cement stabilize the silty subgrade soils to a depth of at least 12 inches as described in Section 5.2 of this report.

A Modified Proctor test was conducted on the bulk sample obtained in the area across the site from depths of approximately 2 to 5 feet. The Modified Proctor test yielded maximum dry densities of 115.8 pounds per cubic foot (pcf) and optimum moisture content of 11.4%, respectively. These modified Proctor test result is included in Appendix C of this report.

Related civil design factors such as subgrade drainage, shoulder support, cross-sectional configurations, surface elevations and environmental factors which will significantly affect the service life must be included in the preparation of the construction drawings and specifications. Normal periodic maintenance will be required.

Long-term pavement performance will be dependent upon several factors, including maintaining subgrade moisture levels and providing for preventative maintenance. Preventative maintenance activities are intended to slow the rate of pavement deterioration, and consist of both localized maintenance (e.g. crack and joint sealing and patching) and global maintenance (e.g. surface sealing). Prior to implementing any maintenance, additional engineering observations are recommended to determine the type and extent of preventative maintenance.

Stabilization of the subgrade will provide a stiffer, more durable subgrade, which will improve the durability of the pavements. It will also provide a subgrade that is less prone to disturbance under construction traffic, especially during rainy weather. If the design team desires to increase the CBR value of the subgrade, subgrade stabilization with cement could be used. Our experience indicates that CBR values of up to 15 or more can be achieved with cement treated subgrades. The CBR value for cement treated soils will be greater than the CBR values measured in the surface soils. Laboratory tests should be conducted to determine the percentage of cement that is required to stabilize the pavement subgrade silty soils and the resulting increased CBR values for pavement design. The stabilized soils should be compacted as recommended in Section 6.4 of this report. The CBR value used in design for treated soils should be verified during construction using dynamic cone penetrometer (DCP) tests or other methods.

6.0 SITE PREPARATION AND EXCAVATION CONSIDERATIONS

6.1 SUBGRADE PREPARATION

Construction areas for new pavements should be stripped of existing pavement, organic soil, and any deleterious materials, including construction debris from demolition of the existing pavement, prior to site excavation and grading. If fat clays are encountered at the subgrade level, they should be removed to a depth of at least 24 inches and replaced with LVC as described in Section 5.1 of this report. Alternatively, fat clay subgrade soils can be lime or cement stabilized to a depth of at least 12 inches as described in Section 5.2 of this report. The existing silts and silty lean clays would likely require cement treatment. Care should be taken during stripping to prevent excessive disturbance of the underlying material. After the removal of these materials, and where further excavation is not required, the exposed subgrade should be proofrolled. Proofrolling is accomplished by passing over the subgrade with a fully loaded tandem-axle dump truck or fully loaded scraper and observing the subgrade for areas of excessive pumping or rolling which indicate the presence of soft, wet, disturbed, or otherwise unsuitable soils. Any unacceptable materials encountered should be excavated and either recompacted or replaced with new structural fill.

Prior to placing fill in any area, the subgrade should be scarified to a depth of about 6 inches, the moisture contents adjusted as outlined in Section 6.4 of this report, and the subgrade recompacted in accordance with recommendations made in subsequent sections of this report. Following the satisfactory preparation of the subgrade, controlled fill material may be placed.

6.2 EXCAVATIONS

It appears that the existing native soils can likely be excavated using conventional earth moving equipment and methods. Trenching, excavating, and bracing should be performed in accordance with OSHA (Occupational Safety and Health Administration) regulations and other applicable regulatory agencies. In accordance with the OSHA excavation standards, the existing natural clay soils at the site are considered Type B, which requires a side slope inclinations for temporary excavations open less than 24 hours of not steeper than 1.0 horizontal to 1.0 vertical (1H:1V) based on the soil borings. If granular soils or soft soils are encountered, flatter side slopes could be required. However, worker safety and classification of the excavation soil is the responsibility of the contractor. Also, according to OSHA requirements, any excavation extending to a depth of more than 20 feet must be designed by a registered professional engineer.

6.3 SUBGRADE PROTECTION

Construction areas should be properly drained in order to reduce or prevent surface runoff from collecting on the subgrade. Any ponded water on the exposed subgrade should be removed immediately. To prevent unnecessary disturbance of the subgrade soils, heavy construction vehicles should be restricted from traveling through the finished subgrade. If areas of disturbed subgrade develop, they should be properly repaired in accordance with the recommendations in this report.

6.4 FILL AND BACKFILL MATERIALS

Any fat clays exposed during excavations are not recommended for use as fill due to their shrink and swell potential. The suitability of any existing fill material should be determined by TSi as it is excavated. Off-site fill should consist of lean clay having a liquid limit of 45 or less and a plasticity index between 10 and 25. Off-site fill should be approved by TSi prior to being imported to the job site. In general, acceptable fill materials would include predominantly soil with no significant content of inert material such as brick, concrete, or stone pieces. Soil with decayable material such as wood, metal, or vegetation is not acceptable. Well-graded granular soils with the maximum particle size of 1.5 inches and less than 8% passing a #200 sieve are acceptable, such as KDOT AB-1 aggregate with those requirements.

At this time, the moisture content of the on-site soil is variable, and at the time of construction may not be within a range necessary for proper placement and compaction. Prior to compaction, some of the soil may require moisture reduction. During warm weather, moisture reduction can generally be accomplished by disking, or otherwise aerating the soil. Some of the soil may require the addition of moisture prior to compaction. This should be performed in a controlled manner using a tank truck with a spray bar, and the moistened soil should be thoroughly blended with a disk or pulverizer to produce a uniform moisture content. Repeated passages of the equipment may be required to achieve uniform moisture content.

If the project is constructed during the winter season, fill materials should be carefully observed to see that no ice or frozen soils are placed as fill or remain in the base materials upon which fill is placed.

6.5 FILL AND BACKFILL PLACEMENT

Lean clay fill placed for structure support should be compacted to a dry density of at least 90% of the modified Proctor maximum dry density (ASTM D 1557) of the soil. Fat clay should not be used as structural fill or backfill. Granular material, such as crushed limestone that is placed for structure support, should be compacted to at least 95% of the modified Proctor maximum dry density. The moisture content of fill at the time of compaction should generally be within plus or minus 3% of the optimum moisture content of the material as determined by the standard Proctor compaction test. Fill should be placed in loose lifts not in excess of 8 inches thick, and compacted to the aforementioned criterion. However, it may be necessary to place fill in thinner lifts to achieve the recommended compaction when using small hand-operated equipment.

7.0 CONSTRUCTION OBSERVATION AND TESTING

It is recommended that TSi be retained during construction to perform testing and observation, and documentation services for the following items:

- Site stripping, and existing structure removal, proofrolling, recompaction, and preparation of the soil subgrade that will support new fill or structural elements;
- Evaluation of the suitability of fill and backfill materials;
- Placement and compaction of fill and backfill; and
- Quality assurance testing for asphalt and concrete materials.

These quality assurance services should help to verify the design assumptions and maintain construction procedures in accordance with the project plans, specifications, and good engineering practice.

8.0 REPORT LIMITATIONS

This report has been prepared for the exclusive use of WSP USA, Inc. for the specific application to the subject project. The recommendations contained in this report have been made in accordance with generally accepted soil and foundation engineering practices; no other warranties are implied or expressed.

The analysis and recommendations submitted in this report are based in part upon the data obtained from the test borings. The nature and extent of variations away from the borings may not become evident until construction. If variations then appear evident, it may be necessary to re-evaluate the recommendations of this report.


We emphasize that this report was prepared for design purposes only and may not be sufficient to prepare an accurate construction bid. Contractors reviewing this report should acknowledge that the information and recommendations contained herein are for design purposes.

If conditions at the site have changed due to natural causes or construction operations, this report should be reviewed by TSi to determine the applicability of the analysis and recommendations considering the changed conditions. The report should also be reviewed by TSi if changes occur in the structure locations, sizes, and types, or in the planned loads, elevations, or project concepts.

TSi requests the opportunity to review the final plans and specifications for the project prior to construction to verify that the recommendations in this report are properly interpreted and incorporated in the design and construction documents. If TSi is not accorded the opportunity to make this recommended review, we can assume no responsibility for the misinterpretation of our recommendations.

APPENDIX A


Figure 1, Vicinity Map
Figure 2, Site and Boring Location Plans



Note: This plan was prepared from an image obtained from Google Earth on December 18, 2024.



Figure 1.0, Vicinity Map	Project No. 20242056.00	
MTAA TOP Rehab Design – Philip Billard Airport Topeka, Kansas		Tsi
Not to Scale Approved by: AB		geofechnical, inc.



Legend

O Approximate Boring Locations

Note: This plan was prepared from an image obtained from Google Earth on January 14, 2025.



Figure 2.0, Site and Bori	Project No. 20242056.00	
MTAA TOP Rehab Design – Philip Billard Airport Topeka, Kansas		Tsi
Not to Scale Approved by: AB		geofechnical, inc.

APPENDIX B

Boring Logs General Notes Unified Soil Classification System

LOG OF BORING NO. B-1 TSi Geotechnical Inc. 8248 NW 101st Terrace, #5 Project Description: MTAA TOP Rehab Design Kansas City, Missouri 64153 Philip Billard Airport - Topeka, Kansas (816) 599-7965 (816) 599-7967 FAX Surface El.: Approx. 880.0 Penetration Blows Per 6 inches % Hand Penetrometer, TSF Plasticity Index Location: See Site and Boring Unit Dry Weight Ib/cu ft. Graphic Log Undrained Shear Strength, Water Content, Recovery % Plastic Limit Liquid Limit Depth, feet Sample # **Location Plan** RQD MATERIAL DESCRIPTION Asphaltic concrete (3.5") Portland cement concrete (9.25") Aggregate base (4.0") Brown and tan, lean CLAY (CL), ST-1 100 1.00 18 ST-2 <0.25 0.15 98 26 100 5 ST-3 2.00 0.93 100 90 30 46 22 24 ST-4 100 2.00 0.88 26 98 -10 - tan, trace sand below 13.0 ft. ST-5 83 1.00 0.73 108 17 27 19 8 (85% passing No. 200 sieve) 15 ST-6 100 1.00 20 20 Boring terminated at 20.0 ft. 20.0 Boring drilled with B-57 using FA. Groundwater not Completion Depth: Remarks: 1/3/25 Date Boring Started: encountered while drilling. 1/3/25 Date Boring Completed: Engineer/Geologist: ΕV 20242056.00 Project No.:

DESIGN.GPJ

LOG OF BORING NO. B-2 TSi Geotechnical Inc. 8248 NW 101st Terrace, #5 Project Description: MTAA TOP Rehab Design Kansas City, Missouri 64153 Philip Billard Airport - Topeka, Kansas (816) 599-7965 (816) 599-7967 FAX Surface El.: Approx. 880.0 Penetration Blows Per 6 inches % Hand Penetrometer, TSF Plasticity Index Location: See Site and Boring Undrained Shear Strength, Unit Dry Weight Ib/cu ft. Water Content, Graphic Log Recovery % Plastic Limit Liquid Limit Depth, feet Sample # **Location Plan** RQD MATERIAL DESCRIPTION Asphaltic concrete (1.5") Portland cement concrete (9.0") Aggregate base (3.0") Brown, lean CLAY (CL), silty, trace ST-1 100 0.75 0.30 98 23 29 20 9 ST-2 0.26 98 0.75 95 26 5 Brown and gray, fat CLAY (CH), trace sand ST-3 100 2.50 0.92 89 33 58 28 30 Brown, lean CLAY (CL), with sand ST-4 3.00 | 1.21 30 88 94 -10 Tan, fine SAND (SP) ST-5 100 96 16 15 Brown, clayey SAND (SC) 100 6 9 (46% passing No. 200 sieve) 5 20 Boring terminated at 20.0 ft. 20.0 Boring drilled with B-57 using FA and auto SPT. Completion Depth: Remarks: 1/3/25 Date Boring Started: Groundwater not encountered while drilling. 1/3/25 Date Boring Completed: Engineer/Geologist: ΕV 20242056.00 Project No.:

DESIGN.GPJ

LOG OF BORING NO. B-3 TSi Geotechnical Inc. 8248 NW 101st Terrace, #5 Project Description: MTAA TOP Rehab Design Kansas City, Missouri 64153 Philip Billard Airport - Topeka, Kansas (816) 599-7965 (816) 599-7967 FAX Surface El.: Approx. 879.0 Blows Per 6 inches % Hand Penetrometer, TSF Plasticity Index Location: See Site and Boring Unit Dry Weight Ib/cu ft. Undrained Shear Strength, Water Content, Graphic Log Recovery % Plastic Limit Penetration Liquid Limit Depth, feet Sample # **Location Plan** Samples RQD MATERIAL DESCRIPTION Portland cement concrete (7.5") Aggregate base (4.0") Brown, lean CLAY (CL) - silty from 0.9 to 10.0 ft. 88 0.50 0.28 96 26 - tan from 3.0 to 13.0 ft. ST-2 <0.25 0.24 22 9 96 97 28 31 5 ST-3 1.00 0.90 100 88 33 ST-4 27 90 1.00 1.27 97 -10 Brown and gray, fat CLAY (CH), with sand, trace gravel 100 1.50 0.19 76 46 77 38 39 15 Tan, lean CLAY (CL), silty ST-6 100 0.75 0.89 101 25 20 Boring terminated at 20.0 ft. 20.0 Boring drilled with B-57 using FA. Groundwater not Completion Depth: Remarks: 1/3/25 Date Boring Started: encountered while drilling. 1/3/25 Date Boring Completed: Engineer/Geologist: ΕV 20242056.00 Project No.:

DESIGN.GPJ

LOG OF BORING NO. B-4 TSi Geotechnical Inc. 8248 NW 101st Terrace, #5 Project Description: MTAA TOP Rehab Design Kansas City, Missouri 64153 Philip Billard Airport - Topeka, Kansas (816) 599-7965 (816) 599-7967 FAX Surface El.: Approx. 881.0 Penetration Blows Per 6 inches % Hand Penetrometer, TSF Plasticity Index Location: See Site and Boring Undrained Shear Strength, Unit Dry Weight Ib/cu ft. Water Content, Graphic Log Recovery % Plastic Limit Liquid Limit Depth, feet Sample # **Location Plan** Samples RQD MATERIAL DESCRIPTION Portland cement concrete (6.0") Brown and tan, SILT (ML), clayey, with sand ST-1 100 1.50 0.23 98 22 (85% passing No. 200 sieve) ST-2 100 0.50 0.17 94 26 29 24 5 5 0.50 0.25 ST-3 100 27 94 Brown, lean CLAY (CL), silty - with sand from 8.0 to 10.0 ft. ST-4 100 2.00 0.24 27 94 -10 ST-5 98 1.50 0.99 103 23 15 Tan, fine SAND (SP) ST-6 96 5 20 Boring terminated at 20.0 ft. DESIGN.GPJ 20.0 Boring drilled with B-57 using FA. Groundwater not Completion Depth: Remarks: 1/3/25 Date Boring Started: encountered while drilling. 1/3/25 Date Boring Completed: Engineer/Geologist: ΕV 20242056.00 Project No.:



GENERAL NOTES

The number of borings is based on: topographic and geologic factors; the magnitude of structure loading; the size, shape, and value of the structure; consequences of failure; and other factors. The type and sequence of sampling are selected to reduce the possibility of undiscovered anomalies and maintain drilling efficiency. Attempts are made to detect and/or identify occurrences during drilling and sampling such as the presence of water, boulders, gas, zones of lost circulation, relative ease or resistance to drilling progress, unusual sample recovery, variation in resistance to driving split-spoon samplers, unusual odors, etc. However, lack of notation regarding these occurrences does not preclude their presence.

Although attempts are made to obtain stabilized groundwater levels, the levels shown on the Logs of Boring may not have stabilized, particularly in more impermeable cohesive soils. Consequently, the indicated groundwater levels may not represent present or future levels. Groundwater levels may vary significantly over time due to the effects of precipitation, infiltration, or other factors not evident at the time indicated.

Unless otherwise noted, soil classifications indicated on the Logs of Boring are based on visual observations and are not the result of classification tests. Although visual classifications are performed by experienced technicians or engineers, classifications so made may not be conclusive.

Generally, variations in texture less than one foot in thickness are described as layers within a stratum, while thicker zones are logged as individual strata. However, minor anomalies and changes of questionable lateral extent may appear only in the verbal description. The lines indicating changes in strata on the Logs of Borings are approximate boundaries only, as the actual material change may be between samples or may be a gradual transition.

Samples chosen for laboratory testing are selected in such a manner as to measure selected physical characteristics of each material encountered. However, as samples are recovered only intermittently and not all samples undergo a complete series of tests, the results of such tests may not conclusively represent the characteristics of all subsurface materials present.

NOTATION USED ON BORING LOGS

APPROXIMATE PROPORTIONS

PARTICLE SIZE

< 0.002 mm

TRACE	<15%	BOULDERS	>12 Inches
WITH	15-30%	COBBLES	12 Inches – 3 Inches
MODIFIER	>30%	GRAVEL	
		Coarse	3 Inches – ¾ Inch
		Fine	³ / ₄ Inch – No. 4 Sieve (4.750 mm)
		SAND	
Clay or clayey n	nay be used as major	Coarse	No. 4 – No. 10 Sieve (2.000 mm)
material or mod	ifier, regardless of	Mediu	m No. 10 – No. 40 Sieve (0.420 mm)
relative proporti	ons, if the clay content is	Fine	No. 40 – No. 200 Sieve (0.074 mm)
sufficient to don	ninate the soil properties.	SILT	No. 200 Sieve - 0.002 mm

CLAY

PENETRATION – BLOWS

Number of impacts of a 140-pound hammer falling a distance of 30 inches to cause a standard split-barrel sampler, 1 3/8 inches I.D., to penetrate a distance of 6 inches. The number of impacts for the first 6 inches of penetration is known as the seating drive. The sum of the impacts for the last 12 inches of penetration is the Standard Penetration Test Resistance or "N" value, blows per foot. For example, if blows = 6-8-9, "N" = 8+9 or 17.

OTHER NOTATIONS

Recovery % – length of recovered soil divided by length of sample attempted.

50/2" Impacts of hammer to cause sampler to penetrate the indicated number of inches

WR Sampler penetrated under the static loading of the weight of the drill rods

WH Sampler penetrated under the static loading the weight of the hammer and drill rods

HSA Hollow stem auger drilling method

FA Flight auger drilling method

RW Rotary wash drilling methods with drilling mud

AH Automatic hammer used for Standard Penetration Test sample

SH Safety hammer with rope and cathead used for Standard Penetration Test sample

GRAPHIC SYMBOLS

 ∇ Depth at which groundwater was encountered during drilling

▼ Depth at which groundwater was measured after drilling

Standard Penetration Test Sample, ASTM D1586

3-inch diameter Shelby Tube Sample, ASTM D1587

G Sample grabbed from auger

NX Size rock core sample



UNIFIED SOIL CLASSIFICATION SYSTEM, (ASTM D-2487)

Мај	or Divi	sions	Gro Sym	_	Typical Names	La	boratory Classification (Criteria
	on is	Clean gravels (Little or no fines)	G'		Well-graded gravels, gravel- sand mixtures, little or no fines		$C_u = D_{60}$ greater than 4; $C_c = (D_{10})$	
ize)	rse fractic ieve size)	Clean (Little or	G	P	Poorly graded gravels, gravel- sand mixtures, little or no fines	e size), c	Not meeting all gradation re	quirements for GW
Coarse-grained soils (More than half of materials is larger than No. 200 sieve size)	Gravels (More than half of coarse fraction is larger than No. 4 sieve size)	Gravels with fines (Appreciable amount of fines)	GMª	d	Silty gravels, gravel-sand-silt mixtures	el from grain-size curve. ion smaller than No. 200 sieve size), coar GW, GP, SW, SP GM, GC, SM, SC Borderline cases requiring dual symbols ^b	Atterberg limits below "A" line or P.1. less than 4	Above "A" line with P.1. between 4 and 7 are borderline
ined soils arger than	(More	Gravel (Apprec of	G	C	Clayey gravels, gravel-sand- clay mixtures	ion smaller than N GW, GP, SW, SP GM, GC, SM, SC Borderline cases r	Atterberg limits below "A" line with P.1. greater than 7	cases requiring use of dual symbols
Coarse-grained soils aterials is larger thar	ion is ze)	Clean sands (Little or no fines)	SV	W	Well-graded sands, gravelly sands, little or no fines	nd gravel i s (fraction lows: GN GN	$C_u = D_{60}$ greater than 6; $C_c = (D_{c0})^2$	$\frac{D_{30})^2}{\sqrt{x}D_{60}}$ between 1 and 3
C half of ma	s oarse fract 4 sieve siz	Clean (Little or	S	P	Poorly graded sands, gravelly sands, little or no fines	of sand arige of fines fied as fol	Not meeting all gradation requi	rements for SW
(More than	Sands (More than half of coarse fraction is smaller than No. 4 sieve size)	Sands with fines (Appreciable amount of fines)	SM ^a	d u	Silty sands, sand-mix mixtures	Determine percentages of sand and gravel from grain-size curve. Depending on percentage of fines (fraction smaller than No. 200 sieve size), coarse-Grained soils are classified as follows: GW, GP, SW, SP More than 12 per cent GM, GC, SM, SC More than 12 per cent Borderline cases requiring dual symbols ^b	Atterberg limits about "A" line or P.I. less than 4	Limits plotting in hatched zone with P.I. between 4 and 7 are borderline
	(Mc	Sands (Apprecia	S	С	Clayey sands, sand-clay mixtures	Detern Depen Graine Less th More t	Atterberg limits about "A" line with P.I. greater than 7	cases requiring use of dual symbols
	lays)	М	L	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands, or clayey silts with slight plasticity			
Fine-grained soils (More than half of materials is smaller than No. 200 sieve size)	Silts and clays	(Ergund minit ress than 50)	C	L	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays	60 For clas	ssification of fine-grained soils	
1 No. 20			0	L	Organic silts and organic silty clays of low plasticity			· · · · · · · · · · · · · · · · · · ·
Fine-grained soils erials is smaller that	ıys	reater	М	Н	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts	ST 10 130	in of A - line tol of PI=4 to LL=25.5, PI=0.73 (LL-20) in of "U"-line il of t LL=16 to PI=7 iI=0.9 (LL-8)	
Fine-gra materials is	Silts and clays	(Liquid inini greater than 50)	C.	H	Inorganic clays of medium to high plasticity, organic silts	10-	MH or OL	OH
half of		(T)	O	Н	Organic clays of medium to high plasticity, organic silts	00 10	16 20 30 40 50 60 70 LIQUID LIMIT (LL)	80 90 100 110
(More than	Highly	soils	P	't	Peat and other highly organic soils			
aDivici	on of GM	and SM a	rounc in	to subdi	visions of d and u are for roads and	Lairfields only Si	ubdivision is based on Atterberg	limite: cuffix d usad

^aDivision of GM and SM groups into subdivisions of d and u are for roads and airfields only. Subdivision is based on Atterberg limits; suffix d used when L.L. is 26 or less and the P.1. is 6 or less; the suffix u used when L.L. is greater than 28.

^bBorderline classifications, used for soils possessing characteristics of two groups, are designated by combinations of group symbols. For example: GW-GC, well-graded gravel-sand mixture with clay binder.

T:\Geotechnical Group\Notes for Geotech Reports\Unified Soil Classifications System2.doc

APPENDIX C

Laboratory Test Data



PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by: ML
PROJECT LOCATION: Topeka, Kansas	Calculated by: MN
PROJECT NUMBER: 20242056.00	Checked by: AB


BORING NO.	B-1
Sample No.	ST-2
Sample Depth (ft)	3.0
Visual Classification (USCS)	Lean CLAY (CL)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	
Plastic Limit	
Plasticity Index	
Classification (USCS)	

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	123.0
Moisture Content (%)	25.6
Dry Unit Weight (pcf)	97.9

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.15
% Strain at q _∪	7.9





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport		Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas		Calculated by:	MN	
PROJECT NUMBER: 20242056.00		Checked by:	AB	


BORING NO.	B-1
Sample No.	ST-3
Sample Depth (ft)	6.0
Visual Classification (USCS)	Lean CLAY (CL)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	46
Plastic Limit	22
Plasticity Index	24
Classification (USCS)	CL

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	117.0
Moisture Content (%)	30.1
Dry Unit Weight (pcf)	90.0

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.93
% Strain at q _∪	4.6





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas	Calculated by:	MN	
PROJECT NUMBER: 20242056.00	Checked by:	AB	


BORING NO.	B-1
Sample No.	ST-4
Sample Depth (ft)	8.0
Visual Classification (USCS)	Lean CLAY (CL)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	
Plastic Limit	
Plasticity Index	
Classification (USCS)	

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	123.0
Moisture Content (%)	26.1
Dry Unit Weight (pcf)	97.5

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.88
% Strain at q _∪	3.2





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by:	ML
PROJECT LOCATION: Topeka, Kansas	Calculated by:	MN
PROJECT NUMBER: 20242056.00	Checked by:	AB


BORING NO.	B-1
Sample No.	ST-5
Sample Depth (ft)	13.0
Visual Classification (USCS)	Lean CLAY (CL)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	27
Plastic Limit	19
Plasticity Index	8
Classification (USCS)	CL

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	126.1
Moisture Content (%)	17.2
Dry Unit Weight (pcf)	107.6

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.73
% Strain at q _∪	3.1





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas	Calculated by:	MN	
PROJECT NUMBER: 20242056.00	Checked by:	AB	


BORING NO.	B-2
Sample No.	ST-1
Sample Depth (ft)	1.4
Visual Classification (USCS)	Lean CLAY (CL)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	29
Plastic Limit	20
Plasticity Index	9
Classification (USCS)	CL

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	121.2
Moisture Content (%)	23.2
Dry Unit Weight (pcf)	98.4

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.30
% Strain at q _∪	5.9





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas	Calculated by:	MN	
PROJECT NUMBER: 20242056.00	Checked by:	AB	


BORING NO.	B-2
Sample No.	ST-2
Sample Depth (ft)	3.4
Visual Classification (USCS)	Lean CLAY (CL)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	
Plastic Limit	
Plasticity Index	
Classification (USCS)	

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	120.7
Moisture Content (%)	26.5
Dry Unit Weight (pcf)	95.5

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.26
% Strain at q _∪	9.1





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas	Calculated by:	MN	
PROJECT NUMBER: 20242056.00	Checked by:	AB	


BORING NO.	B-2
Sample No.	ST-3
Sample Depth (ft)	6.0
Visual Classification (USCS)	Fat CLAY (CH)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	58
Plastic Limit	28
Plasticity Index	30
Classification (USCS)	СН

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	117.9
Moisture Content (%)	32.8
Dry Unit Weight (pcf)	88.8

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.92
% Strain at q _∪	3.9





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas	Calculated by:	MN	
PROJECT NUMBER: 20242056.00	Checked by:	AB	


BORING NO.	B-2
Sample No.	ST-4
Sample Depth (ft)	8.0
Visual Classification (USCS)	Lean CLAY (CL)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	
Plastic Limit	
Plasticity Index	
Classification (USCS)	

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	121.7
Moisture Content (%)	29.5
Dry Unit Weight (pcf)	93.9

STRENGTH	
Undrained Shear Strength, S _i (tsf)	1.21
% Strain at q _∪	4.5





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by:	ML
PROJECT LOCATION: Topeka, Kansas	Calculated by:	MN
PROJECT NUMBER: 20242056.00	Checked by:	AB


BORING NO.	B-3
Sample No.	ST-1
Sample Depth (ft)	··\$" <u>-</u>
Visual Classification (USCS)	Lean CLAY (CL)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	
Plastic Limit	
Plasticity Index	
Classification (USCS)	

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	120.0
Moisture Content (%)	25.5
Dry Unit Weight (pcf)	95.7

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.28
% Strain at q _∪	5.8





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by: ML
PROJECT LOCATION: Topeka, Kansas	Calculated by: MN
PROJECT NUMBER: 20242056.00	Checked by: AB


BORING NO.	B-3
Sample No.	ST-2
Sample Depth (ft)	3.0
Visual Classification (USCS)	Lean CLAY (CL)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	31
Plastic Limit	22
Plasticity Index	9
Classification (USCS)	CL

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	123.3
Moisture Content (%)	27.6
Dry Unit Weight (pcf)	96.6

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.24
% Strain at q _∪	11.4





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas	Calculated by:	MN	
PROJECT NUMBER: 20242056.00	Checked by:	AB	


BORING NO.	B-3
Sample No.	ST-3
Sample Depth (ft)	6.0
Visual Classification (USCS)	Lean CLAY (CL)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	
Plastic Limit	
Plasticity Index	
Classification (USCS)	

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	116.8
Moisture Content (%)	33.1
Dry Unit Weight (pcf)	87.8

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.90
% Strain at q _∪	3.8





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas	Calculated by:	MN	
PROJECT NUMBER: 20242056.00	Checked by:	AB	


BORING NO.	B-3
Sample No.	ST-4
Sample Depth (ft)	8.0
Visual Classification (USCS)	Lean CLAY (CL)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	
Plastic Limit	
Plasticity Index	
Classification (USCS)	

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	122.8
Moisture Content (%)	26.9
Dry Unit Weight (pcf)	96.8

STRENGTH	
Undrained Shear Strength, S _i (tsf)	1.27
% Strain at q _∪	8.3





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas	Calculated by:	MN	
PROJECT NUMBER: 20242056.00	Checked by:	AB	


B-3
ST-5
13.0
Fat CLAY (CH)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	77
Plastic Limit	38
Plasticity Index	39
Classification (USCS)	СН

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	110.2
Moisture Content (%)	45.8
Dry Unit Weight (pcf)	75.6

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.19
% Strain at q _∪	0.8





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by:	ML
PROJECT LOCATION: Topeka, Kansas	Calculated by:	MN
PROJECT NUMBER: 20242056.00	Checked by:	AB


BORING NO.	B-3
Sample No.	ST-6
Sample Depth (ft)	18.0
Visual Classification (USCS)	Lean CLAY (CL)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	
Plastic Limit	
Plasticity Index	
Classification (USCS)	

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	125.3
Moisture Content (%)	24.6
Dry Unit Weight (pcf)	100.6

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.89
% Strain at q _∪	5.8





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas	Calculated by:	MN	
PROJECT NUMBER: 20242056.00	Checked by:	AB	


BORING NO.	B-4
Sample No.	ST-1
Sample Depth (ft)	0.5
Visual Classification (USCS)	SILT (ML), with sand

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	
Plastic Limit	
Plasticity Index	
Classification (USCS)	

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	119.5
Moisture Content (%)	22.2
Dry Unit Weight (pcf)	97.8

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.23
% Strain at q _∪	7.9





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport		Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas		Calculated by:	MN	
PROJECT NUMBER: 20242056.00	·	Checked by:	AB	


BORING NO.	B-4
Sample No.	ST-2
Sample Depth (ft)	3.0
Visual Classification (USCS)	SILT (ML)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	29
Plastic Limit	24
Plasticity Index	5
Classification (USCS)	ML

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	119.0
Moisture Content (%)	26.4
Dry Unit Weight (pcf)	94.1

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.17
% Strain at q _∪	8.5





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport		Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas	4	Calculated by:	MN	
PROJECT NUMBER: 20242056.00	K	Checked by:	AB	


BORING NO.	B-4
Sample No.	ST-3
Sample Depth (ft)	6.0
Visual Classification (USCS)	SILT (ML)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	
Plastic Limit	
Plasticity Index	
Classification (USCS)	

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	119.7
Moisture Content (%)	27.4
Dry Unit Weight (pcf)	94.0

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.25
% Strain at q _∪	9.2





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport		Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas	4	Calculated by:	MN	
PROJECT NUMBER: 20242056.00	K	Checked by:	AB	


BORING NO.	B-4
Sample No.	ST-4
Sample Depth (ft)	8.0
Visual Classification (USCS)	Lean CLAY (CL)

ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	
Plastic Limit	
Plasticity Index	
Classification (USCS)	

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	118.9
Moisture Content (%)	27.1
Dry Unit Weight (pcf)	93.5

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.24
% Strain at q _∪	9.2





PROJECT NAME: MTAA TOP Rehab Design - Philip Billard Airport	Tested by:	ML	
PROJECT LOCATION: Topeka, Kansas	Calculated by:	MN	
PROJECT NUMBER: 20242056.00	Checked by:	AB	


B-4
ST-5
13.0
Lean CLAY (CL)


ASTM DESIGNATION	
Unconfined Compression	ASTM D2166
Atterberg Limits	ASTM D4318
Visual Classification (USCS)	ASTM D2488

ATTERBERG LIMITS	
Liquid Limit	
Plastic Limit	
Plasticity Index	
Classification (USCS)	

DENSITY & MOISTURE	
Wet Unit Weight (pcf)	126.0
Moisture Content (%)	22.8
Dry Unit Weight (pcf)	102.6

STRENGTH	
Undrained Shear Strength, S _i (tsf)	0.99
% Strain at q _∪	5.2





Project Name:	MTAA TOP Rehab Design - Philip Billard Airport	Project Number:	20242056.00
Boring Number:	B-1	Tested by:	MN
Sample Number:	ST-5	Calculated by:	MN
Sample Depth:	13.0 ft	Checked by:	AB
			·

Visual Description: Tan, lean CLAY (CL), silty, trace sand

Coarse Analysis	
-----------------	--

Initial Air Dry Mass, Total: 577.2 grams	Sieve	Particle Size, mm	Cummulative Mass Retained, grams	Percent Retained	Percent Passing
	1"	25.40	0	0.00	100.0
	1/2"	12.70	0	0.00	100.0
	3/8"	9.53	0	0.00	100.0
	No.4	4.75	0.18	0.03	100.0
	No.10	2.00	0.64	0.08	99.9
	Pan				

Fine Analysis

Initial Air Dry Mass, Fine: 69.21 grams	Sieve	Particle Size, mm	Cummulative Mass Retained, grams	Percent Retained	Percent Passing
,	No.20	0.85	0	0.00	99.9
	No.40	0.43	0.05	0.07	99.8
	No.60	0.25	0.34	0.42	99.4
	No.100	0.15	5.7	7.74	91.7
	No.200	0.08	10.01	6.23	85.4
	Pan		10.36		84.9

Hydrometer analysis

Specific Gravity	2.65	Hydromete	Hydrometer Reading Combined Correction:						
Constant, a	1	Trydromete	Tryurometer Reading		Hygroscopic Corrected Mass, g. 69.17				
Elapsed Time	Temperature	Uncorrected, Ra Corrected, Rc		Effective	Constant	Particle Size	Percent Passing		
minutes	°C	oncorrected, rui	corrected, rec	Depth, L cm	K	mm	r creene r ussing		
2	21.6	26.0	20.3	13.0	0.01338	0.0341	29.3		
5	21.6	20.0	14.3	14.0	0.01338	0.0224	20.7		
15	21.5	14.5	8.8	15.0	0.01340	0.0134	12.7		
30	21.5	13.8	8.1	15.0	0.01340	0.0095	11.6		
60	21.4	13.0	7.3	15.2	0.01342	0.0068	10.5		
120	21.4	12.0	6.3	15.3	0.01342	0.0048	9.0		
240	21.3	11.5	5.7	15.5	0.01343	0.0034	8.2		
444	21.7	11.0	5.4	15.5	0.01337	0.0025	7.8		
1440	21.6	10.8	5.1	15.5	0.01338	0.0014	7.3		

Hygroscopic Moisture Correction					
Air Dry Mass + Tare:	28.74				
Oven Dry Mass + Tare:	28.73				
Tare:	13.15				
Correction Factor:	0.999358563				

Project Name: Project Number: MTAA TOP Rehab Design - Philip Billard Airport 20242056.00 **Boring Number:** Tested by: B-1 MN**Sample Number:** Calculated by: MN ST-5 Checked by: **Sample Depth:** 13.0 ft AB **Visual Description:** Tan, lean CLAY (CL), silty, trace sand

Sieve	Particle Size, mm	Percent Finer		
1"	25.40	100		
1/2"	12.70	100		
3/8"	9.53	100		
No.4	4.75	100		
No.10	2.00	100		
No.20	0.85	100		
No.40	0.425	100		
No.60	0.250	99		
No.100	0.150	92		
No.200	0.075	85		
	0.0341	29		
.s.is	0.0224	21		
ıaly	0.0134	13		
An	0.0095	12		
ter	0.0068	10		
me	0.0048	9		
Hydrometer Analysis	0.0034	8		
Hy	0.0025	8		
	0.0014	7		

Particle Size Description Soil Classification System

Particle	Size Range, mm	Percent of Specimen
Gravel	4.75 to 76.4	0
Coarse Sand	2.00 to 4.75	0
Medium Sand	0.43 to 2.00	0
Fine Sand	0.075 to 0.43	14
Silt	0.005 to 0.075	76
Clay	< 0.005	9


Project Name:MTAA TOP Rehab Design - Philip Billard AirportBoring Number:B-1Sample Number:ST-5Sample Depth:13.0 ftVisual Description:Tan, lean CLAY (CL), silty, trace sand

Project Number: 20242056.00

Tested by: MN


Calculated by: MN


Checked by: AB




CALIFORNIA BEARING RATIO TEST REPORT ASTM D 1883-07

% CBR Value @ 90% Compaction = 3.5 @ 0.1 in. penetration % CBR Value @ 90% Compaction = 4.5 @ 0.2 in. penetration







		Molded					
Specimen ID	Density, pcf	Percent of Max. Density	Moisture				
CBR-1	99.0	85.5	12.1				
CBR-2	109.7	94.7	11.9				
CBR-3	115.4	99.6	11.8				
Material Description							

Brown, lean CLAY (CL), silty, with sand

C	115.8	11.4	29	9
USCS	MAX DENSITY, pcf	OPTIMUM MOISTURE, %	ш	PI
19.5	25.6	18.0	10	0.9
6.5	8.8	20.5	10	1.2
2.0	2.2	23.8	10	1.3

Moisture of Top

1" Layer, %

Max

Swell,

%

Surcharge lbs

Remarks:

Compaction Method: ASTM D1557



8248 NW 101st Terrace #5 Kansas City, Missouri 64153 p| 816.599.7965 f| 816.599.7967 Project: MTAA Top Rehab Design - Philip Billard Airport

Location: Topeka, Kansas

CBR%

0.2 in

0.1 in.

Client: WSP

Sample No.: Bulk

Boring: CB-1 Project No.: 20242056.00

Depth: 2.0 to 5 ft. Date: 1.11.2024



PROCTOR TEST

PROJECT NAME: MTAA Top Rehab Design - Philip Billard Airport

115.8

PROJECT No.: 20242056

SAMPLE NUMBER: Bulk
SAMPLE LOCATION: CB-1

SAMPLE LOCATION: CB-1
DEPTH: 2.0 to 5.0 ft

VISUAL CLASS. (USCS): Brown, lean CLAY (CL), silty, with sand


TYPE OF COMPACTION	Mod.	D1557			
SIEVE ANALYSIS RESULTS	0.75	0.375	No. 4	PROCEDURE	
% Retained(cummulative)				Α	
SOIL WEIGHT DATA					
Determination Number	1	2	3	4	5
Weight- Soil + Mold (wet),g	3934.7	3929.6	3826.0	3930.0	
Weight of Mold,g	1971.6	1971.6	1971.6	1971.6	
Weight Wet Soil,g	1963.1	1958.0	1854.4	1958.4	
Volume of Mold (ft ³)	0.0333	0.0333	0.0333	0.0333	
MOISTURE DATA					
Weight- Soil + Tare (wet),g	2292.6	2253.6	2238.6	2274.4	
Weight- Soil + Tare (dry),g	2044.5	2028.6	2065.8	1990.0	
Weight- Tare,g	186.7	154.3	154.0	155.5	
COMPUTED DATA					
Wet unit weight (pcf)	130.0	129.6	122.8	129.7	
Moisture content (%)	13.4	12.0	9.0	15.5	
Dry unit weight (pcf)	114.7	115.7	112.6	112.3	

Optimum Moisture Content (%)	11.4
Natural Moisture Content (%)*	18.1
Liquid Limit	29
Plastic Limit	20
Plasticity Index	9
CLASSIFICATION. (USCS)*	CL

Maximum Dry Density (pcf)

Date
1/10/2025
1/11/2025
2/5/2025
1/11/2025

NOTE:			



Atterberg Limits




PROJECT MTAA TOP Rehab Design - Philip Billard Airport

DATE 1/22/2025

CB-1 SAMPLE # Bulk DEPTH BORING #

2.0 to 5.0 ft.

LIQUID LIMIT								
Run No.	1 (25-35)	2 (20-30)	3 (15-25)	4	5	6	7	
Tare No.	74	66	96			•		
Tare Plus Wet Soil, g	20.340	20.870	21.970					
Tare Plus Dry Soil, g	18.840	19.240	20.040					
Water, g	1.500	1.630	1.930					
Tare, g	13.560	13.620	13.570					
Dry Soil, g	5.280	5.620	6.470					
Water content, %	28.41	29.00	29.83					
Number of Blows	32	23	15					



LL 29 20 9 Symbol from plasticity chart CL

	Plastic LIMIT							
Run No.	1	2	3	4	5	6	7	
Tare No.	85	24			·			
Tare Plus Wet Soil, g	21.220	20.470			·			
Tare Plus Dry Soil, g	19.980	19.360			·			
Water, g	1.240	1.110			·			
Tare, g	13.680	13.740			·			
Dry Soil, g	6.300	5.620			·			
Water content, %	19.68	19.75			·			
Plastic Limit	19.7							
Remarks								

Computed By MN Checked By AB Technician ML

Project Name:	MTAA TOP Rehab Design - Philip Billard Airport	Project Number:	20242056.00	
Boring Number:	CB-1	Tested by:	MN	
Sample Number:	BULK	Calculated by:	MN	
Sample Depth:	2.0 to 5.0 ft.	Checked by:	AB	
Visual Description:	Brown, lean CLAY (CL), silty, with sand			

Coarse Analysis

Initial Air Dry Mass, Total: 359.7 grams	Sieve	Particle Size, mm	Cummulative Mass Retained, grams	Percent Retained	Percent Passing
	1"	25.40	0	0.00	100.0
	1/2"	12.70	4.98	1.38	98.6
	3/8"	9.53	16.08	3.09	95.5
	No.4	4.75	21.03	1.38	94.2
	No.10	2.00	26.04	1.39	92.8
	Pan				

Fine Analysis

Initial Air Dry Mass, Fine: 67.67 grams	Sieve	Particle Size, mm	Cummulative Mass Retained, grams	Percent Retained	Percent Passing
	No.20	0.85	0.6	0.89	91.9
	No.40	0.43	1.17	0.84	91.2
	No.60	0.25	1.84	0.99	90.2
	No.100	0.15	3.38	2.28	88.1
	No.200	0.08	7.87	6.64	82.0
	Pan		8.57		81.0

Hydrometer analysis

Specific Gravity	2.65	Hydromete	r Reading		C	ombined Correction:	
Constant, a	1	Hydrollicte	ricauling		Hygroscopic	Corrected Mass, g.	67.58
Elapsed Time	Temperature	Uncorrected, Ra	Corrected, Rc	Effective	Constant	Particle Size	Percent Passing
minutes	°C	oncorrected, ru	corrected, re	Depth, L cm	K	mm	r creene r assing
2	21.6	23.0	17.3	13.5	0.01338	0.0348	23.7
5	21.6	18.0	12.3	14.3	0.01338	0.0226	16.9
15	21.6	13.5	7.8	15.2	0.01338	0.0135	10.7
30	21.5	13.0	7.3	15.2	0.01340	0.0095	10.0
60	21.4	12.3	6.5	15.3	0.01342	0.0068	8.9
120	21.4	11.5	5.8	15.5	0.01342	0.0048	7.9
240	21.3	11.0	5.2	15.5	0.01343	0.0034	7.1
444	21.6	10.8	5.1	15.5	0.01338	0.0025	6.9
1440	21.5	10.0	4.3	15.6	0.01340	0.0014	5.9

Hygroscopic Moisture Correction				
Air Dry Mass + Tare:	29.02			
Oven Dry Mass + Tare:	29			
Tare:	13.11			
Correction Factor:	0.998742929			

Project Name: Project Number: MTAA TOP Rehab Design - Philip Billard Airport 20242056.00 **Boring Number:** Tested by: CB-1 MN**Sample Number:** Calculated by: BULK MNChecked by: **Sample Depth:** AB 2.0 to 5.0 ft. **Visual Description:** Brown, lean CLAY (CL), silty, with sand

Sieve	Particle Size, mm	Percent Finer
1"	25.40	100
1/2"	12.70	99
3/8"	9.53	96
No.4	4.75	94
No.10	2.00	93
No.20	0.85	92
No.40	0.425	91
No.60	0.250	90
No.100	0.150	88
No.200	0.075	82
	0.0348	24
'sis	0.0226	17
naly	0.0135	11
Ar	0.0095	10
ter	0.0068	9
ıme	0.0048	8
Hydrometer Analysis	0.0034	7
Hy	0.0025	7
	0.0014	6

Particle Size Description Soil Classification System

Particle	Size Range, mm	Percent of Specimen
Gravel	4.75 to 76.4	6
Coarse Sand	2.00 to 4.75	1
Medium Sand	0.43 to 2.00	2
Fine Sand	0.075 to 0.43	9
Silt	0.005 to 0.075	74
Clay	< 0.005	8


Project Name: MTAA TOP Rehab Design - Philip Billard Airport
Boring Number: CB-1
Sample Number: BULK
Sample Depth: 2.0 to 5.0 ft.
Visual Description: Brown, lean CLAY (CL), silty, with sand

Project Number: 20242056.00

Tested by: MN


Calculated by: MN

Checked by: AB



APPENDIX D


Pavement Core Photographs



<u>Material</u>	Approximate Thickness (in)	Notes
Asphalt	3.5	Approximately 4.0" of aggregate base.
Concrete	9.25	



<u>Material</u>	<u>Approximate</u>	<u>Notes</u>
	Thickness (in)	
Asphalt	1.5	Approximately 3.0" of aggregate base.
Concrete	9.0	



Material Approximate
Thickness (in)
Concrete 7.5

Approximately 4.0" of aggregate base.

Notes



Material Approximate
Thickness (in)
Concrete 6.0

Notes



MaterialApproximate
Thickness (in)NotesAsphalt4.0Undetermined length of pavement core left in ground upon client request.

APPENDIX B CONSTRUCTION SAFETY AND PHASING PLAN

CONSTRUCTION SAFETY AND PHASING PLAN

FOR

TERMINAL APRON REHABILITATION PHILIP BILLARD MUNICIPAL AIRPORT (TOP)

AIP POJECT NO. 3-20-0082-027 BIL-AIG GRANT NO. 3-20-0082-028

PHILIP BILLARD MUNICIPAL AIRPORT (TOP)
TOPEKA, KANSAS

Submitted to MTAA: February 14, 2025 100% Design Submission



300 Wyandotte Street, Suite 200 Kansas City, MO 64105 KS License No.: E-447 WSP Project No.: US0040451.4453

TABLE OF CONTENTS

INT	RODUCTION	1
1.	COORDINATION	2
	Contractor Progress Meetings	2
	Scope and Schedule Change Management	3
	FAA ATO Coordination	3
2.	PHASING	3
	Phase Elements	3
	Construction Safety Drawings	5
3.	AREAS AND OPERATIONS AFFECTED BY CONSTRUCTION ACTIVITY	5
	Identification of Affected Areas	5
	Mitigation of Effects	5
4.	PROTECTION OF NAVIGATION AIDS (NAVAIDs)	6
5.	CONTRACTOR ACCESS	7
	Location of Stockpiled Construction Materials	7
	Vehicle and Pedestrian Operations	7
6.	WILDLIFE MANAGEMENT	9
	Trash	9
	Standing Water	9
	Tall Grass and Seeds	9
	Poorly Maintained Fencing and Gates	9
	Disruption of Existing Wildlife Habitat	9
7.	FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT	9
8.	HAZARDOURS MATERIALS (HAZMAT) MANAGEMENT	10
9.	NOTIFICATIONS OF CONSTRUCTION ACTIVITIES	10
	Maintenance of a List of Responsible Representatives or Points of Contact	10
	Notice to Air Missions (NOTAM)	10
	Emergency Notification Procedures	10
	Coordination with ARFF Personnel	11
	Notification to the FAA	11
10.	INSPECTION REQUIREMENTS	12
	Daily (or more frequent) Inspections	12
	Final Inspections	12
11	LINDERGROUND LITHITIES	12

12. PENALTIES	12
13. SPECIAL CONDITIONS	13
14. RUNWAY AND TAXIWAY VISUAL AIDS	13
General	13
Markings	13
Lighting and Visual NAVAIDs	14
Signs	14
15. MARKING AND SIGNS FOR ACCESS ROUTES	14
16. HAZARD MARKING, LIGHTING AND SIGNS	14
General	14
Equipment	14
17. WORK ZONE LIGHTING FOR NIGHTTIME CONSTRUCTION	14
18. PROTECTION	14
Runway Safety Area (RSA)	14
Runway Object Free Area (ROFA)	14
Taxiway Safety Area (TSA)	15
Taxiway Object Free Area (TOFA)	15
Obstacle Free Zones (OFZ)	15
Runway Approach/Departure Surfaces	15
19 OTHER LIMITATIONS ON CONSTRUCTION	15

APPENDICES:

- 1 Safety and Phasing Plan Checklist 150/5370-2G, Appendix C
- 2 Construction Project Daily Safety Inspection Checklist 150/5370-2G, Appendix D
- 3 Construction Safety and Phasing Plans

INTRODUCTION

This program consists of pavement rehabilitation at Philip Billard Municipal Airport (TOP) located in Topeka, Kansas.

The work at TOP includes rehabilitation of existing pavement on the apron with ancillary grading. Pavement markings will be completed following this work.

In this document and for the duration of the project, Runway 13-31 and Runway 18-36 will remain open to all traffic, air or vehicular.

A Construction Notice to Proceed (NTP) shall be issued for this project. Completion is anticipated to be within the total contract time of Ninety (90) calendar days. All work may commence upon issuance of NTP, see Appendix 3 and Project Plans for more information.

This Narrative was prepared to meet the requirements of FAA Advisory Circular 150/5370-2G, "Operational Safety on Airports During Construction". The project area is shown in the attached Construction Safety and Phasing Plans in Appendix 3.

WSP USA Inc. is contracted to provide Project Representative and represent the owner during construction.

To ensure this highest level of safety is maintained, a Construction Safety Phasing Plan (CSPP) has been developed specifically for the Apron Pavement Rehabilitation Project – Philip Billard Municipal Airport (TOP). The purpose of the CSPP is to identify all construction activities that will occur within the Air Operations Area (AOA) of the airfield and define how each construction area will comply with the requirements of all applicable FAA rules and regulations.

The CSPP is a standalone document written to correspond with the safety and security set forth in Advisory Circular 150/5370-2G, in addition to all local codes, requirements and procedures. The CSPP is to be used by all personnel involved in the project. The CSPP covers the actions and responsibilities of design, construction, inspection, and airport personnel.

Prior to the start of the project, the Contractor must submit a "Safety Plan Compliance Document" (SPCD) to the Project Representative. The SPCD must demonstrate how the Contractor will meet the safety requirements of the contract and CSPP, including details on toolbox safety meetings, types, locations, and maintenance of barricades, work access routes, and proposed procedures used by the Contractor to monitor aircraft activity. Procedures utilized by the Contractor to eliminate conflicts between construction operations and aircraft traffic must be included in the SPCD. Within the content of the SPCD the Contractor shall include a statement that includes:

- 1. The Contractor has read and understands the CSPP.
- 2. The Contractor will comply with all the requirements and safety procedures detailed within the CSPP.

The SPCD must address all safety considerations specific to each project location in accordance with the advisory circular and any information not discussed in the original CSPP must be outlined in the SPCD. The SPCD must be submitted to the Project Representative for review and approval fourteen (14) calendar days prior to the pre-construction meeting so it can be discussed during the meeting as an agenda item.

Any changes to the constructability of the project must be outlined in the SPCD and re-submitted to the Project Representative for review and approval before continuation of that portion of work.

In the event that the Contractor's activities are found to be in non-compliance with the requirements of the CSPP or SPCD, the Project Representative will direct the Contractor in writing to immediately stop all operations of that particular work until such time all deficiencies are mitigated and/or corrected to the satisfaction of the Project Representative.

The CSPP and SPCD must be available at all times on the jobsite. It is the responsibility of the Contractor to ensure all construction personnel are familiar with the safety procedures and regulations of the Project Representative.

COORDINATION

Pre-bid coordination with project stakeholders will consist of a pre-bid meeting with the potential bidders to describe phasing restrictions, safety requirements and project details. The Contractor shall always provide FAA representative unencumbered access to FAA facilities and underground cables, if any, within or adjacent to the project location.

The Contractor must provide the Project Representative with the name of the safety officer and the field foreman who will be in charge during working hours. Additionally, the contractor shall identify the 24-hour emergency response telephone numbers for the supervisor(s) in charge.

The Contractor shall be fully aware and continuously monitor all requirements and activities for compliance with the contract documents and advisory circular 150/5370-2G "Operational Safety on Airports During Construction" as attached as an appendix to the specifications. The Contractor's SPCD shall address all safety considerations in accordance with the advisory circular.

The Contractor shall obey the instructions of the Project Representative at all times.

Contractor Progress Meetings

The Contractor shall provide a written safety plan compliance document (SPCD) to the Engineer for review and approval fourteen (14) calendar days prior to the pre-construction meeting so it can be discussed during the meeting as an agenda item. Construction cannot proceed until this plan has been accepted by the Project Representative. The SPCD shall demonstrate how the contractor will meet the safety requirements of the contract and CSPP, including details on tool box safety meetings, types, locations, and maintenance of barricades, work access routes, and proposed procedures used by the contractor to monitor aircraft activity. Procedures utilized by the contractor to eliminate conflicts between construction operations and aircraft traffic shall be included in the SPCD. The SPCD shall be updated and resubmitted for review and approval by the Airport and Engineer for each change in condition related to the project.

The Contractor shall provide the Project Representative a fourteen (14) day advance notice of intended work plans prior to the implementation of work.

There are no known FAA facilities or equipment within the project area. If any FAA facilities are located within project limits, the Contractor shall provide FAA ATO technicians unencumbered access to FAA facilities and underground cables within or adjacent to the project location at all times.

Progress meetings with stakeholders will be held on an as needed basis and as required by MTAA throughout the project duration. The Project Representative will conduct all construction progress status meetings as needed and as required by MTAA and manage the construction observation staff that will perform the required acceptance testing per the contract documents.

Scope and Schedule Change Management

During the execution of the construction, changes in conditions which impact the scope and/or schedule of the work may be necessary. If this occurs, the CSPP and SPCD must be updated and resubmitted for review and approval by the FAA and the Project Representative for each change in condition related to the project. Coordination with the project stakeholders will occur again as necessary when scope and schedule related changes warrant.

FAA ATO Coordination

The Contractor must have a heightened awareness of all aircraft in the vicinity of the project. The Contractor must always obey the aviation instructions of the FAA and the Project Representative. The Contractor must contact the Project Representative at the start of each week to inform them of their activities.

PHASING

The Project Representative must review and approve Contractor's proposed schedule prior to the issuance of NTP. Resubmittals may be required for review and final approval. Contractor to notify the Project Representative in writing if a change to schedule is proposed prior to the scheduled completion date. The construction schedule is subject to holiday moratoriums as determined by the FAA. The Contractor's schedule shall allow time to perform field inspections prior to the end of each working day.

Phase Elements

Construction will be split into 5 phases; this project generally includes the following scope of work for each phase:

PHASE 1A SCOPE OF WORK (15 CALENDER DAYS)

The major work items include:

- Sawcut paving limits
- Complete tie-down abandonment, removal to underlying PCC grade (5 locations)
- Asphalt milling (approximately 4,450 square yards)
- Concrete joint and crack repair
- Ancillary grading
- Placement of asphalt overlay
- Temporary pavement marking application

PHASE 1B SCOPE OF WORK (15 CALENDER DAYS)

The major work items include:

- Sawcut paving limits
- Complete tie-down abandonment, removal to underlying PCC grade (1 location)
- Asphalt milling (approximately 4,300 square yards)
- Concrete joint and crack repair
- Ancillary grading

- Placement of asphalt overlay
- Temporary pavement marking application
- Site grading/turf re-establishment to the infield.

PHASE 2 SCOPE OF WORK (15 CALENDER DAYS)

The major work items include:

- Complete PCC joint and crack repairs
- Application of thermoplastic coal-tar emulsion seal coat (approximately 10,050 square yards)
- Complete tie down abandonment, filling existing anchor recess (37 locations)
- Temporary pavement marking application
- Ditch line grading on northwest side of work area

PHASE 3A SCOPE OF WORK (7 CALENDER DAYS)

The major work items include:

- Sawcut paving limits
- Asphalt milling (approximately 2,430 square yards)
- Ancillary grading
- Catch basin frame grade adjustment
- Placement of asphalt overlay
- Temporary pavement marking application

PHASE 3B SCOPE OF WORK (7 CALENDER DAYS)

The major work items include:

- Sawcut paving limits
- Asphalt milling (approximately 490 square yards)
- Ancillary grading
- Placement of asphalt overlay
- Complete PCC joint and crack repairs
- Application of thermoplastic coal-tar emulsion seal coat (approximately 1,050 square yards)
- Temporary pavement marking application

1 calendar day shall be allowed for permanent marking, in addition to the above allowable time. Permanent markings shall be applied minimum 30-day following asphalt and seal coat application.

The Project Representative must approve contractor's proposed schedule prior to issuance of NTP. Contractor to notify the Project Representative in writing if a change to schedule is proposed prior to schedule element completion date.

Construction is set to begin upon issuance of a Notice-To-Proceed (NTP). The Contractor shall complete the work identified in this contract within Ninety (90) consecutive calendar days. Sections of the apron shall be closed until all work is completed in these areas. Work shall be allowed 7 days a week, from sunrise to sunset only.

Prior to starting work, the Contractor barricades shall be placed at the entrance to the airfield as specified in advisory circular 150/5370-2G, "Operational Safety on Airports During Construction". Barricades shall be places at locations as shown on the drawings.

Closures based on phasing as outline below:

Location	Phase 1A	Phase 1B	Phase 2	Phase 3A	Phase 3B
Runway 13-31	Open	Open	Open	Open	Open
Runway 18-36	Open	Open	Open	Open	Open
Taxiway A	Open	Open	Open	Closed T/W D TOFA to Conventional Hangar #3	Closed T/W C TOFA to Conventional Hangar #3
Taxiway B	Open	Open	Open	Open	Open
Taxiway C	Open	Open	Open	Open	Open
Taxiway C1	Open	Open	Open	Open	Open
Taxiway D	Open	Open	Open	Open	Open
Taxiway E	Open	Closed Apron to T/W A TOFA	Open	Open	Open
Terminal	West Partial Closure,	West Partial Closure,	East Partial Closure,	East Partial Closure,	Open
Apron	Access Maintained	Access Maintained	Access Maintained	Access Maintained	

Runway 13-31 and Runway 18-36 shall remain open for the duration of the project.

Contractor shall notify the Project Representative of intent to reopen and shall allow for, at minimum, one (1) day for the Project Representative to perform field inspections prior to opening airfield pavement to traffic. For reopening of all closed airfield pavements required by this project, all opening requirements must be fulfilled by the contractor and approved by the Project Representative prior to the planned and agreed upon reopening time.

Contractor to remove all barricades prior to reopening the apron. Removing Barricades shall be the last work item completed prior to reopening the apron.

Construction Safety Drawings

See Appendix 3 plans for work area limits, haul route details and contractor staging area.

AREAS AND OPERATIONS AFFECTED BY CONSTRUCTION ACTIVITY

Identification of Affected Areas

See Appendix 3 plans for the phasing of construction and safety areas for the project to avoid any safety problems with incursions of construction vehicles/pedestrians and aircraft operations and any other safety issue relating airport operations. Contractor personnel must control their equipment, vehicles and personnel to not impose an incursion with aircraft operations. Aircraft, airport vehicles, airline vehicles, fuel trucks and emergency vehicles must always have the right-of-way. The project has work within the movement area of the Air Operations Area (AOA). Coordination with the Project Representative is required. The Contractor must strictly adhere to speed restrictions on access roads and must not deviate from the designated routes.

Mitigation of Effects

Emergency operating conditions may require the Contractor's personnel and/or equipment be temporarily cleared from the safety areas. The contract documents will mandate that the Contractor immediately comply with directives from the Airport Operations and Air Traffic Control personnel during these emergency conditions.

<u>Access / Egress control to the AOA:</u> Access to the AOA will only be from the access gates identified on the Construction Safety and Phasing Plans, see Appendix 3.

It is the sole responsibility of the Contractor to control the access of personnel and vehicles through the non-manned construction access gates. No other vehicles or persons shall be given access by the Contractor.

<u>Precautions for control of vehicular traffic on AOA:</u> Contractor's vehicles must not be allowed access to portions of the airport other than the work and staging areas. The requirements for vehicle identification for when the Contractor's vehicles are operating in the AOA are outlined below in Section 5 - Contractor Access.

Means of separating construction area from AOA: The AOA will be separated from construction by use of low-profile barricades for airfield closure and delineation of the haul routes using barricades or other method as approved by the Project Representative. Low profile barricades will be supplied and maintained by the contractor. Barricades shall be relocated as necessary to maintain work area safety and to prevent accidental entry by others. Additional details can be found below in Sections 5, 15, and 16.

<u>Flaggers</u>: Flaggers shall be located at specified locations on the CSPP drawing.

<u>Barricades and their maintenance:</u> Contractor shall provide at their costs and use portable to establish limits of construction equipment when parked at the work areas.

<u>ARFF/Emergency Airport Operation Routes:</u> Open taxi routes will be available to Fire Fighter and Emergency personnel to access any portion of the open, operating AOA pavements. Contractor shall give right of way to all aircraft, Fire Fighter and Airport vehicles. Contractor vehicles must stay within the designated project/phase limits at all times.

<u>Safety flag on equipment:</u> All construction equipment that is not outfitted with a rotating yellow beacon light atop of the vehicle will display a 3-foot square orange and white checkered construction safety flag in a predominant location at the top of the vehicle.

Equipment height restrictions: Contractor equipment for this project shall not exceed 20 feet unless otherwise approved by the Project Representative. Construction equipment cannot exceed the 14 CFR PART 77 Surface or as indicated on the 7460-1 exhibits. If the Contractor chooses to use vehicles or equipment that exceed this height, the Contractor is responsible for submitting the information for an FAA airspace analysis (FAA Form 7460-1). The Contractor is advised that the FAA review may take up to ninety (90) calendar days from the time of submittal. The Contractor is responsible for all costs and time delays associated with the FAA 7460-1 applications related to special equipment.

PROTECTION OF NAVIGATION AIDS (NAVAIDS)

The Airport has a VOR station off site, construction shall have no effect on the OR. If NAVAIDSs are located, the contractor shall not damage in any way the physical condition of airport navigational aids, or NAVAIDs, or alter or affect in any way their function during this project other than as described in the scope of work.

CONTRACTOR ACCESS

Location of Stockpiled Construction Materials

Stockpiled materials shall only be allowed in the Contractor's staging area. Stockpiles, including barricades, shall not penetrate the 14 CFR Part 77 imaginary surfaces or create FOD. The Contractor is responsible for the security of their materials and must maintain stabilization of these stored equipment and materials to prevent FOD hazards and prevent wildlife attraction. The Project Representative will ensure that stockpiled materials and equipment adjacent to these areas are prominently marked and lighted during hours of restricted visibility or darkness. Any approved storage of equipment must not present a line of sight problem with vehicle traffic or aircraft. The contractor must maintain dust control for Staging Area. Contractor to water stockpiles in order to control windblown dust or particulates. Watering shall be incidental to project.

The maximum height of equipment, vehicles and materials stockpiled in the Contractor's staging area shall not be greater than 20 feet in height.

Vehicle and Pedestrian Operations

Contractor to access the airport and staging areas via NE Sardou Ave with equipment and supplies.

<u>Construction Site Parking:</u> The contractor's employee parking is located as shown on plans. No individual employee vehicle shall have access to any secure areas, including the airport runways/taxiways/aprons. All vehicles shall be parked at the designated Contractor parking areas.

<u>Construction Equipment Parking:</u> The contractor's storage/staging areas and parking for trailers and equipment are located as shown on plans. The Contractor shall park all construction equipment at these locations at the completion of each workday.

The Contractor shall not disturb any ground adjacent to the parking lot staging area. All equipment, vehicles, and materials stored/stockpiled within the staging area shall be kept to the paved area shown. Any damage caused to paved or unpaved areas adjacent to the staging area shall be restored to existing conditions. Contractor shall be responsible for any permitting necessary due to damage. No additional measurement or payment for work, materials, labor, tools, incidentals, or permits will be made due to contractor damage.

The Contractor shall not be permitted to operate or place equipment or materials outside specific work areas or haul routes. The Contractor's equipment, vehicles and materials are strictly restricted to the storage/staging area during non-working hours unless otherwise approved by the Project Representative.

The Contractor shall keep all personnel, equipment, and materials out of wetlands at all times.

<u>Access and Haul Routes:</u> The access location and haul routes are as shown on the Construction Safety & Phasing Plan, see Appendix 3. The Contractor shall strictly keep to the access roads and the work areas shown in the plans. The haul routes shown shall be utilized with no deviation unless instructed otherwise by the Project Representative.

The Contractor's use of haul routes shall not hinder the safe and unobstructed flow of airport traffic. Aircraft traffic shall have the right of way at all times. The Contractor must strictly adhere to speed restrictions on access roads and must not deviate from the designated route. Speed limit on haul routes and active aprons is 10 miles per hour unless otherwise posted.

The Contractor's vehicles for personnel, materials and/or equipment delivery shall use load covers and may be checked to confirm load and equipment are secure to the vehicle. Any material, parts of equipment, tools, trash or other debris that fall from the vehicle onto the access road are considered potential foreign object debris (FOD). Any FOD dropped from the contractor vehicles on the access road or other public roads must be retrieved and cleaned up immediately. Cleanliness of other public roads the contractor uses for hauling or access to the site must also be kept clean. Additional details can be found below in Section 7.

<u>Vehicle Identification and Operation:</u> While working within the AOA, the Contractor must do the following:

- Each motorized vehicle or equipment operating within the AOA must have a 3-foot square flag
 consisting of international orange and white squares in full view above the vehicle and/or a flashing
 yellow beacon. For fabric color specifications and lighting requirements, see current FAA Advisory
 Circular 150/5210-5D "Painting, Marking, and Lighting of Vehicles Used on an Airport".
- Each vehicle must have Contractor's name clearly identified on both sides of the vehicle.
- The Contractor must provide an updated list at the weekly progress meetings of the expected construction and material delivery vehicles to the Airport for the upcoming week.
- Open vehicle access routes shall be made available for emergency personnel. The contractor shall yield at all times to aircraft, airport vehicles, fuel trucks and emergency vehicles.
- Vehicles must remain within established haul routes and project limits. It is prohibited to use runways or taxiways or adjacent field areas unless specifically authorized.

Proper vehicle operations under normal conditions, lost communications and emergency conditions are to be discussed before the start of construction and updated as needed at weekly progress meetings.

<u>Training Requirements for Vehicle Drivers:</u> Vehicles and equipment may only enter the AOA through the identified access gates. Key personnel must complete ground vehicle training provided by MTAA at no cost to the contractor.

<u>Situational Awareness:</u> Vehicle drivers must confirm by personal observation that no aircraft is approaching their position (either in the air or on the ground) when given clearance to cross a runway, taxiway, or any other area open to airport operations. There is no requirement for an aircraft to have radio communications. Because aircraft do not always broadcast their positions or intentions, visual checking, radio monitoring, and situational awareness of the surroundings is critical to safety.

<u>Two-Way Radio Communication Procedures:</u> The Contractor shall obtain and is required to have at all times a sufficient number of operable radios, tuned to the CTAF Frequency (118.7 Hz). Superintendent to monitor radio at all times during working hours. All Contractor vehicles in the AOA must monitor the CTAF frequency at all times. The cost of providing radios shall be included in the cost of the project.

The Contractor must, before the start of construction, test their radio with the Project Representative to demonstrate the capabilities and to demonstrate the performance of the operator and the equipment.

Maintenance of the Secured Area of the Airport:

<u>Fencing and Gates:</u> The Contractor shall maintain airfield security and gate security at all times. The Contractor shall utilize the existing gates and maintain security at the airport. Contractor to

coordinate with MTAA to provide daisy chain lock or gain access to the project site via key pad at the existing gates.

Vehicle and equipment may only enter the Air Operations Area (AOA) through the identified access gate.

<u>Badging Requirements: Key personnel must obtain badges prior to the start of work by completing training through the MTAA.</u>

WILDLIFE MANAGEMENT

Trash

The Contractor must observe strict adherence to site cleanliness. The Contractor must maintain a clean worksite, clear of excess debris and trash, food garbage or other nuisance attractants. Trash is considered a hazard in that it may become windblown and become Foreign Object Debris (FOD); or it may attract unwanted wildlife which may present serious hazards to aircraft in the AOA.

Standing Water

During construction, the Contractor must ensure that there is no standing water within the work site and within the staging areas.

Tall Grass and Seeds

The airport is regularly maintained for vegetation (mowing, weed removal, etc.). These maintenance items are regularly scheduled and the Project Representative will continue them indefinitely. Any area that has become disturbed by the Contractor is the responsibility of the Contractor until vegetation has been established and accepted. Contractor shall maintain grass to no greater than 6 inches in height within 20 feet of edge of pavement. Only the seed indicated in the project documents will be allowed for use in and around the airport.

Poorly Maintained Fencing and Gates

The Contractor will be required to maintain in good working order any gate used for site access. Additionally, the contractor will be required to strictly follow airport security protocols for keeping the airfield secure at all times as well as for the entering/exiting the AOA.

Disruption of Existing Wildlife Habitat

No known habitat disruption should occur and no known issues are anticipated.

FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT

FOD is a serious danger to aircraft and can cause severe damage to aircraft, other vehicles, property or even people.

Any FOD on the active AOA surfaces or public roadways shall be immediately cleaned by the Contractor to the satisfaction of the Project Representative. The Contractor shall utilize whatever equipment is necessary to keep these routes free and clear of dust, debris, mud, etc. All equipment and labor necessary to maintain a clean route shall be considered incidental to the contract. Failure to keep the active AOA surfaces free of debris could result in the stoppage of the project. The Contractor is responsible for all damage to airport property or aircraft as a result of FOD in the construction areas.

The Contractor shall keep the project site and vehicles clean, using a "clean as you go" approach throughout the duration of the project. This shall include taking an inventory of tools before entering the AOA and after leaving the AOA to ensure no tools are unaccounted for or inadvertently left within the AOA.

HAZARDOURS MATERIALS (HAZMAT) MANAGEMENT

The Contractor shall be required to submit a safety and health plan, which details how their company manages and handles hazardous materials, for circumstances which may occur on this project. All lubricating liquids and solids (oils and greases) shall be secured and contained in dry areas until used by trained personnel or mechanics. All waste material shall be properly disposed of in accordance with all applicable environmental laws and according to manufacturer's directions. Construction fuel shall not be stored at the site. Excess material from the existing system shall be legally disposed of off airport property.

If hazardous materials are encountered on the site which are impacted by the work, the Contractor must notify the Project Representative immediately of their presence.

NOTIFICATIONS OF CONSTRUCTION ACTIVITIES

The Notice to Proceed will not be issued until the Contactor has submitted to the Project Representative for approval, and which has been approved in writing, the following items: A SPCD, a schedule with critical path identified and emergency contact information (Supervisor, Foreman, Project Manager), and schedule of values for lump sum work items. The list of emergency contact information shall be updated weekly, as necessary, at the weekly progress status meetings.

Maintenance of a List of Responsible Representatives or Points of Contact

The list of representatives and their contact information (24-hour contact information as required) from the Airport and the Contractor and all other associated parties must be maintained and kept current at all times. This list will initially be distributed at the pre-construction meeting prior to the Notice-to-Proceed for construction and must be updated weekly, as necessary, at the weekly progress status meetings (or more frequent if required).

Notice to Air Missions (NOTAM)

The Project Representative shall generate and maintain "Notice to Air Missions" (NOTAMS) to closures as required. The Contractor shall provide the Project Representative a minimum of fourteen (14) days advance notice on planned closures.

Emergency Notification Procedures

In the event of an emergency, the contractor shall call the appropriate airport representatives or emergency services immediately.

<u>Identification and qualifications of a dedicated security and safety point of contact</u>: The Contractor shall identify a qualified, dedicated safety and security point of contact that is approved by the Project Representative.

<u>24-hour emergency contacts for police, fire, medical response, and key project personnel</u>: Contact information for National Park Service and North Carolina Division of Aviation shall be provided at the preconstruction meeting. The Contractor shall produce an emergency contact list within seven (7) calendar days following the pre-construction meeting. At a minimum, the following emergency contacts for the airport shall be included on the contact list:

	CALL 911 FOR EMERGENCIES – FIRE/MEDICAL ASSISTANCE CALL (785)-862-1130 FOR SECURITY RELATED ISSUES						
Agency	Name	Title	Phone				
Metropolitan Topeka Airport Authority	Safety Department	Emergency Calles Only – Police & Fire	W (785) 862-1130				
Metropolitan Topeka Airport Authority	Eric Johnson	President & Director of Airport	W (785) 862-2362				
Metropolitan Topeka Airport Authority	Col. John Ross	Chief of Police & Fire Department	W (785) 862-2362				
Metropolitan Topeka Airport Authority	Rita Eggenberger	Operations Officer	W (785) 862-0399				
Metropolitan Topeka Airport Authority	Terry Poley	Director of Maintenance	W (785) 862-0711 C (785) 633-9957				
Metropolitan Topeka Airport Authority	Matt Anstaett	Deputy Director of Maintenance	W (785) 862-0711 C (785) 633-0759				
Midwest Air Traffic Control Services	Cote Werner	Air Traffic Control Tower Manager	W (785) 232-6015 C (402) 699-6693				
WSP USA INC.	Sam Stallbaumer, PE	Owner's Representative	W (816) 702-4244 C (210) 867-6532				

Coordination with ARFF Personnel

The Airport does not have an onsite Air Rescue and Fire Fighting (ARFF) emergency response team. The local fire protection district emergency phone numbers should be listed on the emergency contact list, provided by the Contractor, for any coordination that may be necessary between the Contractor and fire district. The Contractor shall have reference to this emergency contact list at all times.

Notification to the FAA

The Contractor will be required to coordinate directly with the Project Representative as needed.

An incursion with an aircraft is a serious safety infringement and is a federal violation that will be subject the contractor to the maximum fine allowed by Federal Aviation Administration.

FAA Form 7460-1, Notice of Proposed Construction or Alteration, is not required to be submitted to the FAA for vehicles or construction equipment 20 feet in height or less. If the Contractor chooses to use vehicles or equipment in excess of this height, the Contractor shall be responsible for submitting for an airspace analysis (FAA Form 7460-1). The Contractor is advised that the FAA review may take up to sixty (90) calendar days from the time of submittal. The Contractor will be responsible for all costs and time delays associated with the 7460-1 application.

INSPECTION REQUIREMENTS

The Contractor shall provide unencumbered access to FAA and the Project Representative of the work areas at all times.

Daily (or more frequent) Inspections

The Contractor is responsible for Quality Control inspection of their own work, as well as for all safety requirements for the project. The Contractor is required to adhere to the Contract Documents, which include all safety requirements of this Safety and Phasing Plan.

The Contractor shall identify, in writing to the Project Representative, the individuals responsible for conducting inspections prior to the inspection taking place.

The Contractor shall complete a daily inspection of the work site for safety by completing the FAA checklist in AC 150/5370-2G, "Operational Safety on Airports During Construction." The Contractor shall include sufficient time within the allowable closure requirements to accommodate inspections and acceptance of work by the Project Representative.

Reopening of taxiway and apron pavements after a construction or other closure shall only be approved by the Project Representative and will only be approved on the basis that the contractor has met the requirement for opening airfield pavements as outlined in the project documentation provided. The contractor shall include sufficient time within the allowable scheduled closure requirements to accommodate inspection of pavement to be opened by the Project Representative.

There must be no slopes greater than 5% and no drop-offs greater than 3 inches within the taxiway safety area, and no presence of FOD on the airfield pavement, in order to open the taxiway.

It is the Contractor's responsibility to address construction safety issues adjacent or incidental to the project, even if they are not directly related to this project.

Final Inspections

Any damage along the haul routes, due to the contractor's vehicles or equipment, must be repaired by the Contractor at their expense prior to the completion of the phase that the route is used.

UNDERGROUND UTILITIES

<u>Procedure for locating and protecting existing underground utilities, cables and wires:</u> The Contractor shall be responsible for the protection of existing pavements, turfed areas, underground pipes and utilities, and all other existing features unless otherwise noted on these plans. The Contractor will repair to original conditions all features including existing pavements and turfed areas disturbed by their activities to the satisfaction of the Project Representative. This repair will be considered incidental to the work and no additional compensation shall be approved.

PENALTIES

In the event an employee of the Contractor violates a safety provision, they shall be prohibited from returning to work on the AOA without remedial safety training and the approval of the Project

Representative. Violations may be deemed as just and sufficient cause to require the employee be permanently removed from the job site.

The Contractor shall be responsible for all costs and delays caused by safety or security violations. Construction personnel driving erratically on the airport, exceeding the 10 mph speed limit, or violating any other Airport driving rule or safety regulation, at a minimum, shall be removed from the project permanently. Airport Operations can remove any Contractor personnel, at any time, for any duration, due to a safety violation.

Non-compliance by the Contractor with airport rules and regulations or failure to comply with the approved CSPP and SPCD, airport security regulations, vehicle speed restrictions and any other applicable airport regulation may result in fines as allowed by law as well as the removal of the contractor personnel from the work site.

Liquidated Damages

Should the Contractor exceed the allowable number of calendar days to complete the work, a liquidated damage of \$1,500 per day may be applied to the contract in damages.

SPECIAL CONDITIONS

Emergency situations: Should a life-threatening injury occur on site, whether it be to the Contractor's workforce or Project Representative's inspection crew or others, the Project Representative shall be immediately notified. The Contractor shall follow all instructions by the Project Representative and FAA officials or their designees.

The Contractor shall yield to all safety personnel. In the event of a work stoppage due to aircraft emergency, the Contractor shall, if possible make safe the construction site and vacate the area.

The Contractor must take full responsibility of the safety of workers throughout the construction site and for the entire duration of the project. In particular, the Contractor shall be aware of aircraft activity on the airport and fully acquaint themselves with the dangers of jet blast and its effect on work in adjacent areas, especially in non-movement areas. Material capable of being displaced must not be stockpiled or stored without being secured in work areas adjacent to active aircraft operational areas.

RUNWAY AND TAXIWAY VISUAL AIDS

General

Closures will be noted with the use low profile barricades. Barricades should be secured to prevent movement from jet blast. The Contractor will be required to provide, place and maintain temporary barricades at clearly visible locations to keep pilots from errantly taxiing down a closed taxiway.

Markings

All taxiways and runway's will not be disturbed during this project, no temporary pavement markings shall be necessary.

Existing markings shall be removed during pavement mill. Markings shall be as shown on the Pavement Marking Plan.

Lighting and Visual NAVAIDs

No airfield lights shall be removed for this work. No temporary lights shall be used. Taxiway edge lights will be required covering within taxiway closures based on phase.

<u>Signs</u>

No airfield signs shall be removed for this work. Signs may require covering due to taxiway closures during work phases.

MARKING AND SIGNS FOR ACCESS ROUTES

Contractor to place "Construction Entrance, Construction Traffic Only" sign at haul/access road and public road per MUTCD standards. Sign to be incidental to project. Coordinate with engineer for location of sign. Remove sign at end of construction.

The Contractor must clearly mark all access and haul routes and install signage in accordance with current MUTCD.

HAZARD MARKING, LIGHTING AND SIGNS

General

The Contractor is responsible for replacing in-kind any markings destroyed, obliterated, or otherwise rendered unusable by construction activities, unless otherwise noted in the plans. Contractor must ensure continuity of service for lighting systems not associated with this project.

Equipment

All construction equipment vehicles and equipment shall have a flashing yellow beacon and/or 2 feet by 3 feet checkered orange and white flag attached to vehicles/equipment (such as cranes) as specified in AC 150/5210-5D "Painting, Marking, and Lighting of Vehicles Used on An Airport."

Barricades shall be low-profile with battery-operated flashing red lights.

WORK ZONE LIGHTING FOR NIGHTTIME CONSTRUCTION

Construction is prohibited from sundown to sunrise. No nighttime work is allowed.

PROTECTION

Runway Safety Area (RSA)

There shall be no work within any active RSA. The Contractor is not permitted to work within the RSA of an active runway. Runway 13-31 and Runway 18-36 shall remain open for duration of work for this project and operations will not be affected by construction.

Runway Object Free Area (ROFA)

There shall be no work within any active ROFA. The Contractor is not permitted to work within the ROFA of an active runway. Runway 13-31 and Runway 18-36 shall remain open for duration of work for this project and operations will not be affected by construction.

Taxiway Safety Area (TSA)

There will be no work within any active Taxiway Safety Area (TSA).

No open trenches or excavations are permitted within the TSA while the taxiway is open. Backfill trenches before the taxiway is opened. If backfilling excavations before the taxiway must be opened is impracticable, cover the excavations appropriately. Covering for open trenches must be designed to allow the safe operation of the heaviest aircraft operating on the taxiway across the trench without damage to the aircraft.

Taxiway Object Free Area (TOFA)

There will be no work within any active Taxiway Object Free Area (TOFA).

Obstacle Free Zones (OFZ)

There will be no work within any active Obstacle Free Zones (OFZ).

Runway Approach/Departure Surfaces

There will be no work within any active runway approach/departure areas or clearways.

OTHER LIMITATIONS ON CONSTRUCTION

The following restrictions will be in place during the construction of this project unless otherwise accepted by written authorization:

- No use of tall equipment (cranes, concrete pumps, and so on) unless a 7460-1 determination letter is used for such equipment.
- No use of open flames, welding or torches unless adequate fire safety precautions are provided and approved in writing by the Project Representative.
- No use of flare pots within the AOA at any time.
- No use of electrical blasting caps on or within 1,000 feet of airport property.
- No smoking on the AOA.
- No disruption of utilities serving the facilities occupied by the Project Representative or their tenants, unless permitted in writing (with provisions for temporary utilities in their place). Notify the Project Representative a minimum of 48 hours in advance of proposed utility disruptions and do not proceed with utility interruption without written permission.
- Night work is not permitted on this project.
- Contractor should be aware of jet blast at all times, especially while around active runways, taxiways and aprons. Barricades should be fixed to the group or pavement to prevent movement due to jet blast. Stockpiles and construction equipment should be kept away from places where jet blast is likely to occur (run-up aprons, taxiway corners, etc.)
- Contractor's working days or times may be limited at the Project Representative's discretion due to special operations or special events.

APPENDIX 1

SAFETY AND PHASING PLAN CHECKLIST 150/5370-2G, APPENDIX C

12/13/2017 AC 150/5370-2G Appendix C

APPENDIX C. SAFETY AND PHASING PLAN CHECKLIST

This appendix is keyed to <u>Chapter 2</u>. In the electronic version of this AC, clicking on the paragraph designation in the Reference column will access the applicable paragraph. There may be instances where the CSPP requires provisions that are not covered by the list in this appendix.

This checklist is intended as an aid, not a required submittal.

Table C-1. CSPP Checklist

Coordination	Reference	Addressed?			Remarks
		Yes	No	NA	
Ge	neral Considerat	tions			_
Requirements for predesign, prebid, and preconstruction conferences to introduce the subject of airport operational safety during construction are specified.	<u>2.5</u>				
Operational safety is a standing agenda item for construction progress meetings.	<u>2.5</u>				
Scheduling of the construction phases is properly addressed.	<u>2.6</u>				
Any formal agreements are established.	<u>2.5.3</u>				
Areas and Operation	ons Affected by C	Construction .	Activity	_	
Drawings showing affected areas are included.	<u>2.7.1</u>				
Closed or partially closed runways, taxiways, and aprons are depicted on drawings.	<u>2.7.1.1</u>				
Access routes used by ARFF vehicles affected by the project are addressed.	2.7.1.2				
Access routes used by airport and airline support vehicles affected by the project are addressed.	<u>2.7.1.3</u>				
Underground utilities, including water supplies for firefighting and drainage.	<u>2.7.1.4</u>				

Coordination	Reference	Addressed?		Remarks	
		Yes	No	NA	-
Approach/departure surfaces affected by heights of temporary objects are addressed.	<u>2.7.1.5</u>				
Construction areas, storage areas, and access routes near runways, taxiways, aprons, or helipads are properly depicted on drawings.	2.7.1				
Temporary changes to taxi operations are addressed.	<u>2.7.2.1</u>				
Detours for ARFF and other airport vehicles are identified.	2.7.2.2				
Maintenance of essential utilities and underground infrastructure is addressed.	2.7.2.3				
Temporary changes to air traffic control procedures are addressed.	2.7.2.4				
	NAVAIDs				
Critical areas for NAVAIDs are depicted on drawings.	<u>2.8</u>				
Effects of construction activity on the performance of NAVAIDS, including unanticipated power outages, are addressed.	2.8				
Protection of NAVAID facilities is addressed.	<u>2.8</u>				
The required distance and direction from each NAVAID to any construction activity is depicted on drawings.	2.8				
Procedures for coordination with FAA ATO/Technical Operations, including identification of points of contact, are included.	2.8, 2.13.1, 2.13.5.3.1, 2.18.1				
	Contractor Acces	SS		1	
The CSPP addresses areas to which contractor will have access and how	<u>2.9</u>				

Coordination	Reference	Addressed?		Remarks	
		Yes	No	NA	
the areas will be accessed.					
The application of 49 CFR Part 1542 Airport Security, where appropriate, is addressed.	2.9				
The location of stockpiled construction materials is depicted on drawings.	2.9.1				
The requirement for stockpiles in the ROFA to be approved by FAA is included.	2.9.1				
Requirements for proper stockpiling of materials are included.	2.9.1				
Construction site parking is addressed.	<u>2.9.2.1</u>				
Construction equipment parking is addressed.	2.9.2.2				
Access and haul roads are addressed.	2.9.2.3				
A requirement for marking and lighting of vehicles to comply with AC 150/5210-5, Painting, Marking and Lighting of Vehicles Used on an Airport, is included.	2.9.2.4				
Proper vehicle operations, including requirements for escorts, are described.	2.9.2.5, 2.9.2.6				
Training requirements for vehicle drivers are addressed.	<u>2.9.2.7</u>				
Two-way radio communications procedures are described.	2.9.2.9				
Maintenance of the secured area of the airport is addressed.	2.9.2.10				
W	Vildlife Managem	ent			
The airport operator's wildlife management procedures are addressed.	2.10				

Coordination	Reference	Addressed?			Remarks	
		Yes	No	NA		
Foreign (Object Debris Ma	anagement			•	
The airport operator's FOD management procedures are addressed.	2.11					
Hazardo	Hazardous Materials Management					
The airport operator's hazardous materials management procedures are addressed.	2.12					
Notification	on of Constructio	n Activities				
Procedures for the immediate notification of airport user and local FAA of any conditions adversely affecting the operational safety of the airport are detailed.	2.13					
Maintenance of a list by the airport operator of the responsible representatives/points of contact for all involved parties and procedures for contacting them 24 hours a day, seven days a week is specified.	2.13.1					
A list of local ATO/Technical Operations personnel is included.	2.13.1					
A list of ATCT managers on duty is included.	2.13.1					
A list of authorized representatives to the OCC is included.	2.13.2					
Procedures for coordinating, issuing, maintaining and cancelling by the airport operator of NOTAMS about airport conditions resulting from construction are included.	2.8, 2.13.2, 2.18.3.3.9					
Provision of information on closed or hazardous conditions on airport movement areas by the airport operator to the OCC is specified.	2.13.2					
Emergency notification procedures for medical, fire fighting, and police	2.13.3					

Coordination	Reference	Addressed?			Remarks	
		Yes	No	NA		
response are addressed.						
Coordination with ARFF personnel for non-emergency issues is addressed.	2.13.4					
Notification to the FAA under 14 CFR parts 77 and 157 is addressed.	2.13.5					
Reimbursable agreements for flight checks and/or design and construction for FAA owned NAVAIDs are addressed.	2.13.5.3.2					
Ins	pection Requirem	ients	•			
Daily and interim inspections by both the airport operator and contractor are specified.	2.14.1, 2.14.2					
Final inspections at certificated airports are specified when required.	2.14.3					
U	nderground Utilit	ties				
Procedures for protecting existing underground facilities in excavation areas are described.	<u>2.15</u>					
	Penalties		•			
Penalty provisions for noncompliance with airport rules and regulations and the safety plans are detailed.	<u>2.16</u>					
	Special Condition	ıs				
Any special conditions that affect the operation of the airport or require the activation of any special procedures are addressed.	<u>2.17</u>					
Runway and Taxiway Visual Aid	Runway and Taxiway Visual Aids - Marking, Lighting, Signs, and Visual NAVAIDs					
The proper securing of temporary airport markings, lighting, signs, and visual NAVAIDs is addressed.	<u>2.18.1</u>					
Frangibility of airport markings, lighting, signs, and visual NAVAIDs is specified.	2.18.1, 2.18.3, 2.18.4.2, 2.20.2.4					

Coordination	Reference	Addressed?		Remarks			
		Yes	No	NA			
The requirement for markings to be in compliance with <u>AC 150/5340-1</u> , <i>Standards for Airport Markings</i> , is specified.	2.18.2						
Detailed specifications for materials and methods for temporary markings are provided.	2.18.2						
The requirement for lighting to conform to AC 150/5340-30, Design and Installation Details for Airport Visual Aids; AC 150/5345-50, Specification for Portable Runway and Taxiway Lights; and AC 150/5345-53, Airport Lighting Certification Program, is specified.	<u>2.18.3</u>						
The use of a lighted X is specified where appropriate.	2.18.2.1.2, 2.18.3.2						
The requirement for signs to conform to AC 150/5345-44, Specification for Runway and Taxiway Signs; AC 50/5340-18, Standards for Airport Sign Systems; and AC 150/5345-53, Airport Lighting Certification Program, is specified.	2.18.4						
Marking a	and Signs For Ac	cess Routes					
The CSPP specifies that pavement markings and signs intended for construction personnel should conform to AC 150/5340-18 and, to the extent practicable, with the MUTCD and/or State highway specifications.	2.18.4.2						
Hazar	Hazard Marking and Lighting						
Prominent, comprehensible warning indicators for any area affected by construction that is normally accessible to aircraft, personnel, or vehicles are specified.	2.20.1						

Coordination	Reference	Addressed?		Remarks	
		Yes	No	NA	
Hazard marking and lighting are specified to identify open manholes, small areas under repair, stockpiled material, and waste areas.	2.20.1				
The CSPP considers less obvious construction-related hazards.	<u>2.20.1</u>				
Equipment that poses the least danger to aircraft but is sturdy enough to remain in place when subjected to typical winds, prop wash and jet blast is specified.	2.20.2.1				
The spacing of barricades is specified such that a breach is physically prevented barring a deliberate act.	<u>2.20.2.1</u>				
Red lights meeting the luminance requirements of the State Highway Department are specified.	2.20.2.2				
Barricades, temporary markers, and other objects placed and left in areas adjacent to any open runway, taxiway, taxi lane, or apron are specified to be as low as possible to the ground, and no more than 18 inch high.	2.20.2.3				
Barricades are specified to indicate construction locations in which no part of an aircraft may enter.	2.20.2.3				
Highly reflective barriers with lights are specified to barricade taxiways leading to closed runways.	<u>2.20.2.5</u>				
Markings for temporary closures are specified.	2.20.2.5				
The provision of a contractor's representative on call 24 hours a day for emergency maintenance of airport hazard lighting and barricades is specified.	<u>2.20.2.7</u>				

Coordination	Reference	Addressed?		Remarks	
		Yes	No	NA	
Work Zone Lig	hting for Nightti	me Construct	ion		1
If work is to be conducted at night, the CSPP identifies construction lighting units and their general locations and aiming in relationship to the ATCT and active runways and taxiways.	2.21				
Protection of R	unway and Taxiv	vay Safety Ar	eas		
The CSPP clearly states that no construction may occur within a safety area while the associated runway or taxiway is open for aircraft operations.	2.22.1.1, 2.22.3.1				
The CSPP specifies that the airport operator coordinates the adjustment of RSA or TSA dimensions with the ATCT and the appropriate FAA Airports Regional or District Office and issues a local NOTAM.	2.22.1.2, 2.22.3.2				
Procedures for ensuring adequate distance for protection from blasting operations, if required by operational considerations, are detailed.	2.22.3.3				
The CSPP specifies that open trenches or excavations are not permitted within a safety area while the associated runway or taxiway is open, subject to approved exceptions.	<u>2.22.1.4</u>				
Appropriate covering of excavations in the RSA or TSA that cannot be backfilled before the associated runway or taxiway is open is detailed.	2.22.1.4				
The CSPP includes provisions for prominent marking of open trenches and excavations at the construction site.	2.22.1.4				
Grading and soil erosion control to maintain RSA/TSA standards are	2.22.3.5				

Coordination	Reference	Addressed?		Remarks	
		Yes	No	NA	
addressed.					
The CSPP specifies that equipment is to be removed from the ROFA when not in use.	2.22.2				
The CSPP clearly states that no construction may occur within a taxiway safety area while the taxiway is open for aircraft operations.	2.22.3				
Appropriate details are specified for any construction work to be accomplished in a taxiway object free area.	2.22.4				
Measures to ensure that personnel, material, and/or equipment do not penetrate the OFZ or threshold siting surfaces while the runway is open for aircraft operations are included.	2.22.4.3.6				
Provisions for protection of runway approach/departure areas and clearways are included.	2.22.6				
Other Li	imitations on Cor	struction		_	
The CSPP prohibits the use of open flame welding or torches unless adequate fire safety precautions are provided and the airport operator has approved their use.	2.23.1.2				
The CSPP prohibits the use of electrical blasting caps on or within 1,000 ft (300 m) of the airport property.	2.23.1.3				

APPENDIX 2

CONSTRUCTION PROJECT DAILY SAFETY INSPECTION CHECKLIST 150/5370-2G, APPENDIX D

12/13/2017 AC 150/5370-2G Appendix D

APPENDIX D. CONSTRUCTION PROJECT DAILY SAFETY INSPECTION CHECKLIST

The situations identified below are potentially hazardous conditions that may occur during airport construction projects. Safety area encroachments, unauthorized and improper ground vehicle operations, and unmarked or uncovered holes and trenches near aircraft operating surfaces pose the most prevalent threats to airport operational safety during airport construction projects. The list below is one tool that the airport operator or contractor may use to aid in identifying and correcting potentially hazardous conditions. It should be customized as appropriate for each project including information such as the date, time and name of the person conducting the inspection.

Table D-1. Potentially Hazardous Conditions

Item	Action Required (Describe)	No Action Required (Check)
Excavation adjacent to runways, taxiways, and aprons improperly backfilled.		
Mounds of earth, construction materials, temporary structures, and other obstacles near any open runway, taxiway, or taxi lane; in the related Object Free area and aircraft approach or departure areas/zones; or obstructing any sign or marking.		
Runway resurfacing projects resulting in lips exceeding 3 inch (7.6 cm) from pavement edges and ends.		
Heavy equipment (stationary or mobile) operating or idle near AOA, in runway approaches and departures areas, or in OFZ.		
Equipment or material near NAVAIDs that may degrade or impair radiated signals and/or the monitoring of navigation and visual aids. Unauthorized or improper vehicle operations in localizer or glide slope critical areas, resulting in electronic interference and/or facility shutdown.		
Tall and especially relatively low visibility units (that is, equipment with slim profiles) — cranes, drills, and similar objects — located in critical areas, such as OFZ and		


Item	Action Required (Describe)	No Action Required (Check)
approach zones.		
Improperly positioned or malfunctioning lights or unlighted airport hazards, such as holes or excavations, on any apron, open taxiway, or open taxi lane or in a related safety, approach, or departure area.		
Obstacles, loose pavement, trash, and other debris on or near AOA. Construction debris (gravel, sand, mud, paving materials) on airport pavements may result in aircraft propeller, turbine engine, or tire damage. Also, loose materials may blow about, potentially causing personal injury or equipment damage.		
Inappropriate or poorly maintained fencing during construction intended to deter human and animal intrusions into the AOA. Fencing and other markings that are inadequate to separate construction areas from open AOA create aviation hazards.		
Improper or inadequate marking or lighting of runways (especially thresholds that have been displaced or runways that have been closed) and taxiways that could cause pilot confusion and provide a potential for a runway incursion. Inadequate or improper methods of marking, barricading, and lighting of temporarily closed portions of AOA create aviation hazards.		
Wildlife attractants — such as trash (food scraps not collected from construction personnel activity), grass seeds, tall grass, or standing water — on or near airports.		
Obliterated or faded temporary markings on active operational areas.		
Misleading or malfunctioning obstruction lights. Unlighted or unmarked obstructions in the approach to any open runway pose aviation hazards.		


Item	Action Required (Describe)	No Action Required (Check)
Failure to issue, update, or cancel NOTAMs about airport or runway closures or other construction related airport conditions.		
Failure to mark and identify utilities or power cables. Damage to utilities and power cables during construction activity can result in the loss of runway / taxiway lighting; loss of navigation, visual, or approach aids; disruption of weather reporting services; and/or loss of communications.		
Restrictions on ARFF access from fire stations to the runway / taxiway system or airport buildings.		
Lack of radio communications with construction vehicles in airport movement areas.		
Objects, regardless of whether they are marked or flagged, or activities anywhere on or near an airport that could be distracting, confusing, or alarming to pilots during aircraft operations.		
Water, snow, dirt, debris, or other contaminants that temporarily obscure or derogate the visibility of runway/taxiway marking, lighting, and pavement edges. Any condition or factor that obscures or diminishes the visibility of areas under construction.		
Spillage from vehicles (gasoline, diesel fuel, oil) on active pavement areas, such as runways, taxiways, aprons, and airport roadways.		
Failure to maintain drainage system integrity during construction (for example, no temporary drainage provided when working on a drainage system).		

Item	Action Required (Describe)	No Action Required (Check)
Failure to provide for proper electrical lockout and tagging procedures. At larger airports with multiple maintenance shifts/workers, construction contractors should make provisions for coordinating work on circuits.		
Failure to control dust. Consider limiting the amount of area from which the contractor is allowed to strip turf.		
Exposed wiring that creates an electrocution or fire ignition hazard. Identify and secure wiring, and place it in conduit or bury it.		
Site burning, which can cause possible obscuration.		
Construction work taking place outside of designated work areas and out of phase.		

APPENDIX 3

CONSTRUCTION SAFETY AND PHASING PLANS





GENERAL CONTRACT NOTES:

- 1. THE CONTRACTOR SHALL PROVIDE A PROJECT SUPERINTENDENT WHO SHALL BE ON THE PROJECT SITE AT ALL TIMES WHILE WORK IS BEING PERFORMED TO SUPERVISE AND DIRECT THE CONSTRUCTION. THE PROJECT SUPERINTENDENT SHALL SERVE AS THE ON-PROJECT SAFETY COORDINATOR FOR THE CONTRACTOR AND BE EQUIPPED WITH A RADIO CAPABLE OF COMMUNICATING WITH THE AIR TRAFFIC CONTROL TOWER (ATCT) FOR THE PURPOSES OF RECEIVING INSTRUCTIONS AND OBTAINING CLEARANCES AS NEEDED. THIS RADIO IS FOR THE PROJECT SUPERINTENDENT'S EXCLUSIVE USE ONLY AND SHALL BE ON HIS PERSON AT ALL TIMES. THE SUPERINTENDENT SHALL BE THE 24 HOUR ON-CALL REPRESENTATIVE FOR EMERGENCY SITUATIONS. THE PROJECT SUPERINTENDENT SHALL BE RESPONSIBLE FOR SECURING PERMISSION FROM THE ATCT FOR CONSTRUCTION VEHICLES TO ENTER INTO AIRCRAFT MOVEMENT AREAS, WHEN NECESSARY, AND TO COMMUNICATE WITH THE ATCT DURING THE CONSTRUCTION FOR THE PROJECT. CONTRACTOR SHALL NOT ACCESS AIRCRAFT MOVEMENT AREA WITHOUT TOWER PERMISSION. GROUND CONTROL RADIO FREQUENCY IS 121.9 MHZ. TOWER CONTROL RADIO FREQUENCY 1S 118.7 MHZ. GROUND FREQUENCY TO BE USED FOR A MAJORITY OF THE OPERATIONS. TOWER CONTROL FREQUENCY TO BE USED WHEN OCCUPYING A RUNWAY OPEN TO AIR TRAFFIC.
- CONTRACTOR SUPERINTENDENT SHALL BE RESPONSIBLE FOR COMMUNICATING WITH THE ATCT IN THE EVENT THAT ACCESS TO AIRCRAFT MOVEMENT AREAS BECOME NECESSARY AND TO RECEIVE SPECIAL INSTRUCTIONS FROM THE ATCT IN THE CASE OF AN EMERGENCY.
- 3. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING MOVEMENT OF WORKERS WITHIN THE AIRCRAFT OPERATIONS AREA, THE DELIVERY OF MATERIALS TO THE PROJECT SITE AND THE ESCORTS FOR THOSE VEHICLES ONTO AND FROM THE PROJECT SITE THROUGH THE AIRCRAFT OPERATIONS AREA. ESCORT VEHICLES SHALL BE REQUIRED TO HAVE RADIO COMMUNICATION WITH THE TOWER AT ALL TIMES (SUPERINTENDENT'S RADIO IS NOT TO BE USED BY ESCORT VEHICLES). ALL WORK ASSOCIATED WITH PROJECT WILL BE PERFORMED AS BID AND TO THE LIMITS INDICATED BELOW.
- 4. ACCESS ROUTES FROM AND THROUGH THE APRON AREA SHALL BE ADEQUATELY DELINEATED WITH CONES AND/OR BARRICADES TO MARK TRAVEL ROUTES FOR DELIVERY VEHICLES AND TO PREVENT VEHICLES FROM STRAYING FROM DESIGNATED TRAVEL ROUTES.
- 5. TRAFFIC CONTROL DEVICES SHALL BE ERECTED TO CONTROL CONSTRUCTION TRAFFIC TO ONE AREA OF THE RAMP TO BE UTILIZED AS ACCESS ROADWAYS. MAXIMUM PATHWAY WIDTH IS 30'.
- 6. SPEED LIMIT ON HAUL ROUTES, ACTIVE APRONS AND TAXIWAYS AND RUNWAYS IS 20 MPH UNLESS OTHERWISE
- 7. CONTRACTOR TO COORDINATE WITH MTAA GATE ACCESS TO STAGING AREA 2.
- 8. CONTRACTOR'S PERSONNEL WILL BE ALLOWED TO PARK PERSONAL VEHICLES IN STAGING AREA #1 & #2 DURING ALL PHASES
- 9. CONTRACTOR SHALL MAINTAIN CONTROL OF EQUIPMENT AND PERSONNEL AND PREVENT THE MOVEMENT OF THE SAME OUTSIDE OF THE PROJECT LIMITS AND/OR THROUGH ACTIVE AIRCRAFT OPERATION AREAS. ACTIVE AIRCRAFT OPERATION AREAS INCLUDE TAXIWAYS AND RUNWAYS NOT CLOSED DUE TO THE PROJECT REQUIREMENTS. FOR EXAMPLE, WHILE AIRCRAFT MAY BE MOVING ALONG OPEN TAXIWAYS, CONTRACTOR'S PERSONNEL WILL NOT BE PERMITTED TO ACCESS THESE OPEN TAXIWAYS WITHOUT SECURING PERMISSION FROM THE ATCT. CONTRACTOR EQUIPMENT, VEHICLES, AND PERSONNEL SHALL YIELD TO ALL AIRCRAFT MOVEMENT AND EMERGENCY EQUIPMENT. CONTRACTOR'S EQUIPMENT SHALL BE REMOVED FROM ROFA WHEN NOT IN USE.
- 10. THE NORMAL WORKDAY WILL OCCUR BETWEEN THE HOURS OF 7:00 AM AND 6:00 PM

PHASING NOTES:

THE PROJECT MUST BE COMPLETED WITHIN 90 CALENDAR DAYS AFTER THE NOTICE TO
PROCEED (MTP)

	TRAFFIC CONTROL QUANTITIES					
PHASE	DESCRIPTION	LOCATION	UNITS	QUANTITY		
1A	BARRICADES W/ LIGHTS	PCC APRON @ PHASE 1A SOUTH LIMIT PHASE 1A AND PHASE 2 LIMIT EDGE OF PHASE 1A & 1B LIMIT	EACH EACH EACH	9 8 33		
1B	BARRICADES W/ LIGHTS	PCC APRON @ PHASE 1B SOUTH LIMIT PHASE 1B AND PHASE 2 LIMIT EDGE OF PHASE 1A & 1B LIMIT TXY ECHO @ TXY ALPHA TOFA	EACH EACH EACH EACH	9 6 33 7		
2	BARRICADES W/ LIGHTS	PHASE 2 SOUTH LIMIT PHASE 3 WORK LIMIT @ TXY ALPHA TOFA	EACH EACH	14 15		
3A	BARRICADES W/ LIGHTS	PHASE 2 EAST WORK LIMIT TXY ALPHA @ TXY DELTA TOFA TXY ALPHA @ MIDPOINT OF CONVENTIONAL HANGAR	EACH EACH EACH	18 7 17		
3B	BARRICADES W/ LIGHTS	TXY ALPHA@ TXY CHARLIE TOFA TXY ALPHA @ MIDPOINT OF CONVENTIONAL HANGAR	EACH EACH	4 17		



WSP USA INC.
KANSAS
LICENSE NO. E-447
ANSAS CITY, MO 64105
161-702-4300 I www.wsp.com

MEROPOLITAN TOPEA AIRPORT AUTHORITY
TOPEA REGIONAL BILLARD AIRPORT

PHILIP BILLARD MUNICIPAL AIRPORT
TERMINAL APRON REHABILITATION

AIP CONSTRUCTION GRANT NO. 3-20-0082-027 BIL-AIG CONSTRUCTION GRANT NO. 3-20-0082-028

METROPOLITAN
PHILIP BILL
TERMINAL
AIP CONST

ISSUED FOR BID

SHEET TITLE

CONSTRUCTION SAFETY & PHASING PLAN - OVERALL SHEET 1 OF 2

 DATE
 FEBRUARY 14, 2025

 SCALE
 1" = 100"

 DRAWN BY
 BF

 CHECKED BY
 LDS

 APPROVED BY
 SFS

WSP PROJECT NUMBER US0040451.445

SHEET NUMBER GC0.01

0 50' 100' 200' HORIZONTAL SCALE 1"=100'

(S) AS NOTED


CALE (S) AS NOTED ON THIS SHEET ARE BASED ON A FULL SIZE 22 X 3

PHASE 3A NOTES:

- 1. PHASE 3A (2,430 SY) WILL CONSIST OF:
- 1.1. ISSUE NOTAMS FOR APRON AND TAXIWAY CLOSURES
- 1.2. SET UP OF LOW PROFILE BARRICADES
- 1.3. COVER TAXIWAY EDGE LIGHTING WITHIN CLOSED TAXIWAY SECTIONS
- 1.4. SAWCUT PAVING LIMITS
- 1.5. MILL EXISTING ASPHALT PAVEMENT
- 1.6. COMPLETE ASPHALT PAVING
- 1.7. TEMPORARY PAVEMENT MARKING APPLICATION
- 1.8. CLEAN PAVEMENT FOR AIRPORT/ENGINEER APPROVAL TOP OPEN PHASE 3A AREA
- 1.9. REMOVE LOW PROFILE BARRICADES AND TAXIWAY EDGE LIGHT COVERS
- TAXIWAY ALPHA WILL BE CLOSED BETWEEN TAXIWAY D AND MIDPOINT OF ADJACENT STONE HANGAR.
 ADDITIONALLY, ACCESS TO THE APRON OFF OF TAXIWAY A WILL BE CLOSED FOR THE DURATION OF WORK
 WITH PHASE 3A
- 3. PHASE 3A MUST BE COMPLETED WITHIN 7 CALENDAR DAYS.

PHASE 3B NOTES:

- 1. PHASE 3B (1,540 SY) WILL CONSIST OF:
- 1.1. ISSUE NOTAMS FOR APRON AND TAXIWAY CLOSURES
- 1.2. SET UP OF LOW PROFILE BARRICADES
- 1.3. COVER TAXIWAY EDGE LIGHTING WITHIN CLOSED TAXIWAY SECTIONS
- 1.4. SAWCUT PAVING LIMITS
- 1.5. MILL EXISTING ASPHALT PAVEMENT (490 SY)
- 1.6. COMPLETE ASPHALT PAVING
- 1.7. COMPLETE PCC JOINT AND CRACK REPAIR
- 1.8. APPLY THERMOPLASTIC COAL TA EMULSION (1,050 SY)
- 1.9. TEMPORARY PAVEMENT MARKING APPLICATION
- 1.10. CLEAN PAVEMENT FOR AIRPORT/ENGINEER APPROVAL TOP OPEN PHASE 3B AREA
- 1.11. REMOVE LOW PROFILE BARRICADES AND TAXIWAY EDGE LIGHT COVERS
- 2. TAXIWAY ALPHA WILL BE CLOSED BETWEEN TAXIWAY C AND MIDPOINT OF ADJACENT STONE HANGAR FOR THE DURATION OF WORK WITH PHASE 3B
- 3. PHASE 3A MUST BE COMPLETED WITHIN 7 CALENDAR DAYS.



PHASE 1A NOTES:


- 1. PHASE 1A (4,450 SY) WILL CONSIST OF:
- 1.1. ISSUE NOTAMS FOR APRON CLOSURES
- 1.2. SET UP OF LOW PROFILE BARRICADES1.3. SAWCUT PAVING LIMITS
- 1.4. COMPLETE TIE-DOWN ABANDONMENT TYPE 1
- 1.5. MILL EXISTING ASPHALT PAVEMENT
- 1.6. COMPLETE PCC JOINT AND CRACK REPAIRS
- 1.7. COMPLETE CONCRETE REPAIRS
- 1.8. COMPLETE ASPHALT PAVING
- 1.9. TEMPORARY PAVEMENT MARKING APPLICATION
- 1.10. COMPLETE SITE RESTORATION (TOPSOIL, SEEDING, ETC.)
- 1.11. CLEAN PAVEMENT FOR AIRPORT/ENGINEER APPROVAL TO OPEN PHASE 1A AREA.
- 1.12. REMOVE LOW PROFILE BARRICADES AND TAXIWAY EDGE LIGHT COVERS
- TERMINAL APRON WITHIN WORK AREA 1A WILL BE CLOSED FOR THE DURATION OF PHASE 1A.
- 3. A FLAGPERSON MUST BE PROVIDED TRAFFIC CONTROL AT ENTRANCE GATES FOR THE

PHASE 18 NOTES:

- 4. PHASE 1A MUST BE COMPLETED WITHIN 15 CALENDAR DAYS.
- 1. PHASE 1B (4,300 SY) WILL CONSIST OF:
- 1.1. ISSUE NOTAMS FOR APRON AND TAXIWAY CLOSURES1.2. SET UP OF LOW PROFILE BARRICADES
- 1.3. COVER TAXIWAY EDGE LIGHTING WITHIN CLOSED TAXIWAY SECTIONS
- 1.4. SAWCUT PAVING LIMITS
- 1.5. COMPLETE TIE-DOWN ABANDONMENT TYPE 1
- MILL EXISTING ASPHALT PAVEMENT
 COMPLETE PCC JOINT AND CRACK REPAIRS
- 1.8. COMPLETE ASPHALT PAVING
- 1.9. TEMPORARY PAVEMENT MARKING APPLICATION
- 1.10. COMPLETE SITE RESTORATION (TOPSOIL, SEEDING, ETC.)
- 1.11. CLEAN PAVEMENT FOR AIRPORT/ENGINEER APPROVAL TO OPEN PHASE 1B AREA.
- 1.12. REMOVE LOW PROFILE BARRICADES AND TAXIWAY EDGE LIGHT COVERS
- TAXIWAY ECHO WEST OF TAXIWAY ALPHA SHALL BE CLOSED FOR THE DURATION OF WORK WITHINT PHASE 1B
- 3. A FLAGPERSON MUST BE PROVIDED TRAFFIC CONTROL AT ENTRANCE GATES FOR THE DURATION OF WORK WITHING WORK AREA 1A
- 4. PHASE 1B MUST BE COMPLETED WITHIN 15 CALENDAR DAYS.

PHASE 2 NOTES:

- PHASE 2 (10,050 SY) WILL CONSIST OF:
- 1.1. ISSUE NOTAMS FOR APRON CLOSURES
- 1.2. SET UP OF LOW PROFILE BARRICADES
- 1.3. COMPLETE PCC JOINT AND CRACK REPAIRS
- 1.4. COMPLETE TIE-DOWN ABANDONMENT TYPE 2
- 1.5. APPLY THERMOPLASTIC COAL TAR EMULSION
- TEMPORARY PAVEMENT MARKING APPLICATION
 COMPLETE SITE RESTORATION (TOPSOIL, SEEDING, ETC.)
- B. CLEAN PAVEMENT FOR AIRPORT/ENGINEER APPROVAL TO OPEN PHASE 2 AREA
- 1.9. REMOVE LOW PROFILE BARRICADES
- 2. NO TAXIWAY CLOSURES ARE REQUIRED FOR THE DURATION OF WORK WITHIN THIS PHASE
- 3. PHASE 2 MUST BE COMPLETED WITHIN 15 CALENDAR DAYS.





METROPOUTAN TOPEKA AIRPORT AUTHORITY
TOPEKA REGIONAL | BILLARD AIRPORT
AIRPORT AUBINSE CENTRE

AUTHORITY

AIRPORT

TOPEKA

METROPOLITAN

JIAN TOPECA AIRPORT AUTHOR
GOONAL | BILLARD AIRPO

PHILIP BILLARD MUNICIPAL AIRPORT TERMINAL APRON REHABILITATION

E BY DESCRIPTION

ISSUED FOR BID

SHEET TI

SHEET TITLE

CONSTRUCTION SAFETY & PHASING PLAN - OVERALL

SHEET 2 OF 2

 DATE
 FEBRUARY 14, 2025

 SCALE
 1" = 100"

 DRAWN BY
 BF

 CHECKED BY
 LDS

 APPROVED BY
 SFS

WSP PROJECT NUMBER US0040451.445

SHEET NUMBER GC0.02

SHEET 5 OF 22

SCALE (S) AS NOTED ON THIS SHEET ARE BASED ON A FULL SIZE 22 X 3

1. COORDINATION

- A PRE-CONSTRUCTION CONFERENCE WILL BE HELD PRIOR TO THE START OF WORK ON THE PROJECT AT LEAST TWO WEEKS PRIOR TO THE START OF WORK. DURING THE PRE-CONSTRUCTION CONFERENCE, THE CONTRACTOR'S SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) AND HIS ADHERENCE TO HIS SAFETY PLAN WILL BE DISCUSSED. REVIEWS OF ADHERENCE TO THE SAFETY PLAN WILL TAKE PLACE DURING CONSTRUCTION PROGRESS MEETINGS.
- PROJECT PROGRESS MEETINGS WILL BE HELD DURING THE COURSE OF CONSTRUCTION. THOSE REQUIRED TO ATTEND THE MEETING WILL INCLUDE THE MTAA, THE OWNER'S REPRESENTATIVE, THE AIR TRAFFIC CONTROL TOWER CHIEF, THE CONTRACTOR (MINIMUM OF THE PROJECT SUPERINTENDENT) AND SUBCONTRACTORS WHO WILL BE PROVIDING WORK DURING THE PERIOD OF TIME BETWEEN THE CURRENT MEETING AND THE NEXT PROJECT PROGRESS MEETING. FAA FACILITIES PERSONNEL, SAFETY PERSONNEL, AND FIXED BASE OPERATORS (FBD) WILL HAVE A STANDING INVITATION TO THESE MEETINGS AND WILL ATTEND AS REQUIRED, OR IF THEY FELT THEY HAVE A NEED TO BE PRESENT. THE MEETING WILL GENERALLY BE HELD ON AS NEEDED BASIS, DEPENDING ON THE CRITICAL ITEMS OF WORK AND MUTUAL AGREEMENT BETWEEN THE MTAA, THE OWNER'S REPRESENTATIVE, AND THE CONTRACTOR. MEETING DATES AND TIMES WILL BE ESTABLISHED AT THE PRE-CONSTRUCTION CONFERENCE. MEETING LOCATIONS WILL BE AT THE MTAA MAINTENNANCE BUILDING OR OTHER DESIGNATED LOCATIONS AT PHILIP BULL ARD MUNICIPAL AIRPORT. TOPEKA KANSAS.
- SURVEY CREWS AND OTHER PROJECT ENTITIES MAY BE REQUIRED TO BE ON THE TERMINAL APRON, CONVENTIONAL HANGAR APRONS AND TAXIWAY A FOR PURPOSES OF CONSTRUCTING THE PROJECT. DURING
 THESE WORK ACTIVITIES, APRON AND TAXIWAY CLOSURES MAY BE OF RELATIVELY SHORT DURATION AND OF SUCH A NATURE THAT WORK CREWS WILL VACATE THE APRON OR TAXIWAY FOR THE TIME PERIOD
 NEEDED FOR AIRCRAFT OPERATIONS UPON NOTIFICATION FROM THE AIR TRAFFIC CONTROL TOWER (ATCT). CREWS SHALL HAVE AN AVIATION RADIO AND MONITOR ATCT FREQUENCIES FOR THE PURPOSE OF
 RECEIVING PERMISSIONS TO ENTER RESTRICTED AREAS AND TO VACATE THESE AREAS WHEN DIRECTED TO DO SO.

2. PHASING

- SEE SHEETS GC0.01-GC0.02 FOR PHASING OF THIS PROJECT.
- OWNER'S REPRESENTATIVE AND AIRPORT MANAGER WILL APPROVE A PROPOSED SCHEDULE FOR CONSTRUCTION OF EACH PHASE PRIOR TO ANY CONSTRUCTION
- CONTRACTOR MUST NOTIFY OWNER'S REPRESENTATIVE AND AIRPORT MANAGER IF A CHANGE IN SCHEDULE IS NEEDED.
- FOR CLOSED APRON OR TAXIWAYS, LOW PROFILE BARRICADES SHALL BE PLACED AT THE TOFA EDGE AT EACH TAXIWAY OPENING.

3. AREAS AND OPERATIONS AFFECTED BY THE CONSTRUCTION ACTIVITY

CONTRACTOR SHALL COMPLY WITH ALL REQUIREMENTS AND SAFETY PRECAUTIONS PRESENTED IN FEDERAL AVIATION ADMINISTRATION ADVISORY CIRCULAR 150/5370-2G, "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION." A COPY OF THE DOCUMENT CAN BE FOUND IN THE PROJECT MANUAL FOR REFERENCE AND USE, OR AT THE FEDERAL AVIATION ADMINISTRATION INTERNET WEBSITE.

(HTTPS://WWW.FAA.GOV/AIRPORTS/RESOURCES/ADVISORY_CIRCULARS/INDEX.CFM/GO/DOCUMENT.CURRENT/DOCUMENTNUMBER/150_5370-2).

OPERATIONAL REQUIREMENTS	NORMAL	PHASE 1A	PHASE 1B	PHASE 2	PHASE 2A	PHASE 2B
RUNWAY 13-31	5,099' X 100'	OPEN	OPEN	OPEN	OPEN	OPEN
RUNWAY 18-36	4,331' X 75'	OPEN	OPEN	OPEN	OPEN	OPEN
RUNWAY 13 NAVAIDS 1	ILS, GLIDE SLOPE, LOCALIZER, GPS (LPV)	ILS, GLIDE SLOPE, LOCALIZER, GPS (LPV)	ILS, GLIDE SLOPE, LOCALIZER, GPS (LPV)			
RUNWAY 31 NAVAIDS 1	GPS (LP),LOC BC, VASI, REIL	GPS (LP),LOC BC, VASI, REIL	GPS (LP),LOC BC, VASI, REIL	GPS (LP),LOC BC, VASI, REIL	GPS (LP),LOC BC, VASI, REIL	GPS (LP),LOC BC, VASI, REIL
RUNWAY 18 NAVAIDS 1	GPS(LNAV), VASI, REIL	GPS(LNAV), VASI, REIL	GPS(LNAV), VASI, REIL	GPS(LNAV), VASI, REIL	GPS(LNAV), VASI, REIL	GPS(LNAV), VASI, REIL
RUNWAY 36 NAVAIDS 1	GPS(LNAV), VASI	GPS(LNAV), VASI				
OTHER AIRFIELD NAVAIDS 1	ASOS, ATCT, ROTATING BEACON	ASOS, ATCT, ROTATING BEACON				
TAXIWAY ALPHA - MID POINT OF STONE HANGAR TWY BRAVO TOFA	OPEN	OPEN	OPEN	OPEN	CLOSED	OPEN
TAXIWAY ALPHA - MID POINT OF STONE HANGAR TO TWY CHARLIE TOFA	OPEN	OPEN	OPEN	OPEN	OPEN	CLOSED
TAXIWAY ALPHA - NORTH OF TWY CHARLIE ²	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN
TAXIWAY ALPHA - TWY DELTA TO TWY ECHO	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN
TAXIWAY BRAVO ²	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN
TAXIWAY CHARLIE - TWY ALPHA TO RWY 18-36 ²	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN
TAXIWAY CHARLIE - RWY 18-36 TO TWY CHARLIE ²	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN
TAXIWAY CHARLIE - TWY CHARLIE-1 TO RWY 13-3 ²	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN
TAXIWAY DELTA ²	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN
TAXIWAY ECHO - TERMINAL APRON TO TXY ALPHA	OPEN	OPEN	OPEN	CLOSED	OPEN	OPEN
TAXIWAY ECHO - TWY ALPHA TO RWY 18-36 ²	OPEN	OPEN	OPEN	OPEN	OPEN	OPEN

NOTE 1: ALL NAVIGATIONAL AIDS WILL REMAIN ACTIVE FOR THE DURATION OF THE PROJECT

NOTE 2: ALL TAXIWAYS ARE OPEN DURING THE DURATION OF THE PROJECT

*CONTRACTOR SHALL NOT DISTURB ANY NAVAID CRITICAL AREAS UNLESS SHOWN ON THE PLANS $\,$

4. PROTECTION OF NAVIGATIONAL AIDS (NAVAIDS)

PRIOR TO ANY CONSTRUCTION, THE CONTRACTOR SHALL WALK THE PROJECT LIMITS WITH THE OWNER, FAA AIRWAYS FACILITIES AND AIRPORT OPERATIONS TO IDENTIFY ANY AFFECTED NAVAIDS.

CONTRACTOR ACCESS

- ACCESS TO PHASE 1 AND CONTRACTOR STAGING AREA #1 WILL BE MADE BY MEANS OF NE SARDOU AVENUE (AIRPORT ACCESS ROAD). CONSTRUCTION TRAFFIC WILL

 TRAVEL EASTERLY ALONG THE GRAVEL SERVICE ROAD TO TAXIWAY ECHO AND PROCEED TO THE APRON. CONTRACTOR SHALL BE RESPONSIBLE FOR THE

 MAINTENANCE OF THE HALL ROAD DURING THE PROJECT.
- ACCESS TO THE PHASE 2A, PHASE 2B AND PHASE 3 WORK AREA AND CONTRACTOR STAGING AREA #2 & #3 WILL BE MADE BY MEANS OF NE SARDOU AVENUE (AIRPORT ACCESS ROAD). CONSTRUCTION TRAFFIC WILL TRAVEL NORTH ALONG THE (STONE) CONVENTIONAL HANGAR TO ACCESS THE CONTRACTOR STAGING AREA.

 CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF THE HAUL ROAD (AIRPORT ACCESS ROAD AND THE DRIVEWAY IN-BETWEEN THE TWO BOX HANGARS DURING THE PROJECT.
- IF CONTRACTOR PERSONNEL MUST MOVE ONIN AIRCRAFT MOVEMENT AREAS (APRON, RUNWAYS, AND TAXIWAYS), CONTRACTOR SHALL PROVIDE AN APPROVED GUARD AT ACCESS POINTS TO CONTROL THE ACCESS OF CONTRACTOR-ONLY PERSONNEL ONTO THE PROJECT SITE DURING THE PROJECT WORK. ACCESS GUARDS SHALL HAVE A RADIO OR CELLULAR TELEPHONE CAPABLE OF COMMUNICATING WITH THE PROJECT SUPERINTENDENT AND SHALL NOTIFY THE PROJECT SUPERINTENDENT IMMEDIATELY OF UNUSUAL CIRCUMSTANCES OR UNAUTHORIZED ENTRIES THROUGH THE GATE. CONSTRUCTION TRAFFIC SHALL BE LIMITED TO THE PATHWAYS INDICATED AS THEY HAVE BEEN DEEMED TO FORM THE MOST DIRECT ROUTE FROM THE ACCESS POINT TO THE PROJECT SITE. CONTRACTOR TO PROVIDE BACKGROUND INFORMATION AND EXPERIENCE LEVEL OF ACCESS GUARDS USED ON THE PROJECT FOR REVIEW AND APPROVAL BY THE AIRPORT OPERATIONS STAFF.
- CONTRACTOR SHALL COORDINATE SECURITY ARRANGEMENTS WITH THE MTAA DURING THE COURSE OF THE PROJECT. CONTRACTOR SHALL BE REQUIRED TO PROVIDE PERSONNEL AT ACCESS POINTS, AS NEEDED, TO CONTROL TRAFFIC ENTERING AND LEAVING THE PROJECT SITE. CONTRACTOR SHALL MEET THE SECURITY REQUIREMENTS ESTABLISHED BY THE APPROPRIATE CONTROLLING BODY AND SHALL BE RESPONSIBLE FOR ENSURING THAT CONTRACTOR'S PERSONNEL AND SUBCONTRACTOR'S PERSONNEL ADHERE TO SUCH REQUIREMENTS.
- CONTRACTOR SHALL MAINTAIN ALL ACCESS ROADS AND SHALL RESTORE TO EXISTING CONDITIONS OR BETTER
- ALL HIGH PROFILE EQUIPMENT SHALL BE LOWERED WHEN NOT IN USE.
- SEE SPECIAL PROVISIONS AND SAFETY PLAN REGARDING ACCESS AND SECURITY ISSUES.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE OF ELECTRICAL CABLING ALONG HAUL ROUTES, IN AND AROUND WORK AREAS, AND IN AND AROUND CONTRACTOR STAGING AREAS.

6. WILDLIFE MANAGEMENT

ALTHOUGH THE RESPONSIBILITY OF WILDLIFE MANAGEMENT AND ANY NECESSARY REMOVAL FOR THE AIRPORT RESIDES WITH METROPOLITAN TOPEKA AIRPORT
AUTHORITY, THE CONTRACTOR SHALL CONTACT AIRPORT OPERATIONS IMMEDIATELY IN THE EVENT THAT WILDLIFE IS OBSERVED.

TRASH

THE CONTRACTOR SHALL OBSERVE STRICT ADHERENCE TO SITE CLEANLINESS. DAILY END OF DAY AS WELL AS PERIODIC THROUGHOUT THE DAY VISUAL INSPECTIONS SHALL BE PERFORMED BY THE CONTRACTOR AND AIRPORT TO ENSURE SITE TRASH IS PICKED UP TO PREVENT FROM BEING BLOWN AROUND THE AIRFIELD. TRASH IS CONSIDERED A HAZARD IN THAT IT MAY BECOME WINDBLOWN AND BECOME FOREIGN OBJECT DEBRIS (FOD); OR IT MAY ATTRACT UNWANTED WILDLIFE WHICH MAY PRESENT SERIOUS HAZARDS TO AIRCRAFT IN THE AOA. CONTRACTOR SHALL BE RESPONSIBLE FOR PICKING UP ALL OBSERVED FOD REGARDLESS OF THE SOURCE OF THE FOD.

STANDING WATER

THE CONTRACTOR WILL BE REQUIRED TO USE TEMPORARY PUMPS, AS NEEDED, TO PROVIDE DRAINAGE TO ANY EXCAVATION AREAS IN ORDER TO PROTECT EXPOSED BASE OR SUBGRADE MATERIALS FROM OVER-SATURATION AND WEAKENING. THE CONTRACTOR WILL BE REQUIRED TO SPRAY WORK AREAS FREQUENTLY THROUGHOUT THE PROJECT TO KEEP DOWN DUST AND WINDBLOWN IRRITANTS FROM THE WORK SITE ONTO THE AIRFIELD, OUT OF THE AOA, OR OFF AIRPORT-PROPERTY. WATER SPRAYED FOR DUST CONTROL MAY ACCUMULATE AND MUST BE MANAGED. THE CONTRACTOR MAY EMPLOY THE USE OF TEMPORARY DITCHES IN EXCAVATION AREAS TO ALLOW POSITIVE DRAINAGE AND MINIMIZE STANDING WATER. STANDING WATER IS CONSIDERED A HAZARD IN THAT IT MAY ATTRACT UNWANTED WILDLIFE WHICH MAY PRESENT SERIOUS HAZARDS TO AIRCRAFT IN THE AOA.

TALL GRASS AND SEEDS

•• THE AIRPORT IS REGULARLY MAINTAINED FOR VEGETATION (MOWING, WEED REMOVAL, ETC.). THESE MAINTENANCE ITEMS ARE REGULARLY SCHEDULED AND THE AIRPORT WILL CONTINUE THEM INDEFINITELY. PROJECT WILL DISTURB SOME AREAS USUALLY MOWED BY THE AIRPORT. CONTRACTOR SHALL MOW ALL AREAS IMMEDIATELY ADJACENT TO THE WORK ZONES AT A WIDTH OF 30 FEET FROM DISTURBED AREA. NO DIRECT PAYMENT SHALL BE MADE FOR THIS MOWING AND THIS WORK SHALL BE CONSIDERED SUBSIDIARY TO THE BID ITEM "MOBILIZATION".

POORLY MAINTAINED FENCING AND GATES

- THE CONTRACTOR SHALL MAINTAIN, IN GOOD WORKING ORDER, ANY GATE HE USES FOR SITE ACCESS. ADDITIONALLY, THE CONTRACTOR WILL BE REQUIRED TO STRICTLY FOLLOW AIRPORT SECURITY PROTOCOLS FOR KEEPING THE AIRFIELD SECURE AT ALL TIMES AS WELL AS FOR ENTERING/EXITING THE AOA.
- DISRUPTION OF EXISTING WILDLIFE HABITAT.
- BECAUSE THE PROJECT AREA IS AN ACTIVE AREA OF THE AOA, NO KNOWN HABITAT DISRUPTION SHOULD OCCUR AND NO KNOWN ISSUES ARE ANTICIPATED.

7. FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT

- A MINIMUM OF ONE SWEEPER SHALL BE ON-SITE AND OPERATIONAL AT ALL TIMES. THE BROOM SHALL NOT BE COMPRISED OF STEEL BRISTLES. CONTRACTOR SHALL MAINTAIN EFFECTIVE CONTROL OF FOD AT ALL TIMES AND PRIOR TO OPENING APRONS AND TAXIWAYS TO AIRCRAFT. CONTRACTOR SHALL HAVE A MECHANIZED BROOM DEDICATED FOR THE EXCLUSIVE USE OF CLEANING AND REMOVING FOD FROM THE APRONS AND TAXIWAYS. THE ACCESS ROUTES (AND ANY USED TAXIWAYS AND APRON) SHALL BE SWEPT DAILY OR AS NEEDED TO PICK UP FOD, LOOSE DEBRIS, MUD, DIRT OR OTHER OBJECTS FROM THE ACCESS ROUTE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMMEDIATELY CLEANING UP ANY FOD GENERATED FROM CONSTRUCTION ACTIVITIES FROM ALL ACTIVE TAXIWAYS, AIRCRAFT MOVEMENT AREAS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING UP ANY FOD GENERATED FROM CONSTRUCTION ACTIVITIES FROM ALL CLOSED TAXIWAYS PRIOR TO THESE APRONS AND TAXIWAYS BEING REOPENED TO TRAFFIC.
- PILES OF RUBBLE AND/OR SUPPLIES ARE NOT PERMITTED ALONG ANY AREAS OPEN TO AIRCRAFT. ANY PILE GENERATED IN THESE AREAS SHALL BE CLEANED UP AND HAULED AWAY BEFORE THE END OF THE WORK DAY. ANY OPEN TRENCHES OR EXCAVATION ALONG AREAS OPEN TO AIRCRAFT SHALL BE BACKFILLED OR SECURELY COVERED AS SOON AS POSSIBLE AND NOT LEFT OPEN DURING NON-WORK HOURS. AIRCRAFT OPERATIONS WILL NOT BE ALLOWED ON A RUNWAY WHERE OPEN TRENCHES OR EXCAVATIONS OCCUR WITHIN THE ROFA.
- THE CONTRACTOR SHALL CONTROL DUST AND DEBRIS THAT RESULTS FROM HIS OPERATIONS. WASTE AND LOOSE MATERIALS SHALL NOT BE PLACED IN ACTIVE
 MOVEMENT AREAS, MATERIALS TRACKED ONTO THESE AREAS MUST BE REMOVED CONTINUALLY DURING THE COURSE OF THE PROJECT.
- CONTRACTOR SHALL CONTROL DUST CREATED BY THE DEMOLITION OF BUILDING AND ADJOINING GROUNDS. CONTRACTOR SHALL HAVE A WATER TRUCK ON SITE TO
 MOISTEN DEMOLITION DEBRIS DURING DEMOLITION AND DEBRIS REMOVAL PROCESSES TO ELIMINATE THE CREATION OF DUST.





LITAN TOPEKA AIRPORT AUTHOR EGIONAL | BILLARD AIRPO BINHISS CEMTER | BILLARD AIRPO

PHILIP BILLARD MUNICIPAL AIRPORT TERMINAL APRON REHABILITATION

AIRPORT

TOPEKA

ROPOLITAN

ET

S

AIP CONSTRUCTION GRANT NO. 3-20-0082-027 BIL-AIG CONSTRUCTION GRANT NO. 3-20-0082-0

NO. DATE BY DESCRIPTION

SSUED FOR BID

SHEET TITLE

CONSTRUCTION SAFETY & PHASING PLAN NOTES SHEET 1 OF 2

 DATE
 FEBRUARY 14, 2025

 SCALE
 NTS

 DRAWN BY
 BF

 CHECKED BY
 LDS

 APPROVED BY
 SFS

WSP PROJECT NUMBER US0040451.445

SHEET NUMBER

SHEET 6 OF 22

GC0.03

SCALE (S) AS NOTED ON THIS SHEET ARE BASED ON A FULL SIZE 22 X 34

. NOTIFICATION OF CONSTRUCTION ACTIVITIES

APPROPRIATE NOTICES TO AIR MISSIONS (NOTAMS) MUST BE ISSUED PRIOR TO COMMENCING WORK ACTIVITIES IN THE VICINITY OF AIRCRAFT OPERATION AREAS, CONTRACTOR SHALL COORDINATE WORK ACTIVITIES AND PROJECT SCHEDULE WITH THE METROPOLITAN TOPEKA AIRPORT AUTHORITY (MTAA) AT LEAST TWO WEEKS PRIOR TO EACH CHANGE IN CONSTRUCTION PHASING. MTAA SHALL COORDINATE ISSUANCE OF NOTAMS BASED UPON INFORMATION SUPPLIED BY THE CONTRACTOR. MTAA SHALL ISSUE NOTAMS AND CONFIRM THAT NOTAMS HAVE BEEN PUBLISHED. PRIOR TO MOVING INTO AIRCRAFT MOVEMENT AREAS TO FRECT TRAFFIC CONTROL. CONFIRMATION OF ISSUANCE OF NOTAMS WITH AIR TRAFFIC CONTROL TOWER SHALL BE MADE WHILE SECURING PERMISSION TO ENTER AIRCRAFT MOVEMENT AREAS.

EMERGENCY NOTIFICATION PROCEDURES

IDENTIFICATION AND QUALIFICATIONS OF A DEDICATED SECURITY AND SAFETY POINT OF CONTACT. THE CONTRACTOR PROJECT SUPERINTENDENT SHALL BE THE 24 HOUR ON-CALL REPRESENTATIVE

FOR EMERGENCY SITUATIONS

24 HOUR EMERGENCY CONTACTS FOR POLICE, FIRE, MEDICAL RESPONSE, AND KEY PROJECT PERSONNEL - THE CONTRACTOR SHALL PRODUCE AN EMERGENCY CONTACT LIST WITHIN 7 DAYS FOLLOWING THE PRE-CONSTRUCTION MEETING, AT A MINIMUM, THE FOLLOWING EMERGENCY CONTACTS SHALL BE INCLUDED ON THE CONTACT LIST

CALL 911 FOR EMERGENCIES - FIRE / MEDICAL ASSISTANCE CALL 785-862-1130 FOR SECURITY RELATED ISSUES							
AGENCY	NAME	TITLE	PHONE				
METROPOLITAN TOPEKA AIRPORT AUTHORITY	SAFETY DEPARTMENT	EMERGENCY CALLS ONLY - POLICE & FIRE	(785) 862-1130	w			
METROPOLITAN TOPEKA AIRPORT AUTHORITY	ERIC M. JOHNSON	PRESIDENT & DIRECTOR OF AIRPORTS	(785) 862-2362	w			
METROPOLITAN TOPEKA AIRPORT AUTHORITY	COL. JOHN ROSS	CHIEF OF POLICE AND FIRE DEPARTMENT	(785) 862-2362	w			
METROPOLITAN TOPEKA AIRPORT AUTHORITY	RITA EGGENBERGER	OPERATIONS OFFICER	(785) 862-0711	w			
METROPOLITAN TOPEKA	TERRY POLEY	DIRECTOR OF	(785) 862-0711	w			
AIRPORT AUTHORITY	-	MAINTENANCE	(785) 633-9957	С			
METROPOLITAN TOPEKA	MATT ANSTAETT	DEPUTY DIRECTOR OF	(785) 862-0711	w			
AIRPORT AUTHORITY		MAINTENANCE	(785) 633-0759	С			
MIDWEST AIR TRAFFIC CONTROL SERVICES	COTE WERNER	AIR TRAFFIC CONTROL TOWER MANAGER	(785) 232-6015	w			
MCDIICAINC	CANACTALI DALIMED DE	OVAVALEDIC DEDDECENTATIVE	(816) 702-4244	w			
WSP USA INC	SAM STALLBAUMER, PE	OWNER'S REPRESENTATIVE	(210) 867-6532	С			

9. INSPECTION REQUIREMENTS

- DAILY INSPECTIONS
- THE CONTRACTOR IS RESPONSIBLE FOR QUALITY CONTROL INSPECTION OF HIS/HER OWN WORK AS WELL AS FOR ALL SAFETY REQUIREMENTS FOR THE PROJECT. THE CONTRACTOR IS REQUIRED TO ADHERE TO THE CONTRACT DOCUMENTS, WHICH INCLUDE ALL SAFETY REQUIREMENTS OF THIS SAFETY AND PHASING PLAN. INSPECTIONS OF THE WORK ZONE CONES/BARRICADES, STOCKPILE AREAS, EQUIPMENT, EROSION/SEDIMENT CONTROL DEVICES AND ADJACENT SURFACES SHALL OCCUR ON A DAILY BASIS TO ENSURE ALL CONDITIONS MEET THE REQUIREMENTS SPECIFIED WITHIN THIS SAFETY & PHASING PLAN AND THE CONTRACT DOCUMENTS. THE CONTRACTOR WILL ALSO BE RESPONSIBLE FOR ANY INSPECTIONS OF MOVEMENT AREAS PRIOR TO THE AREA BEING OPENED FOR ANY AIRCRAFT, IT IS THE CONTRACTOR'S RESPONSIBILITY TO ADDRESS CONSTRUCTION SAFETY ISSUES ADJACENT OR INCIDENTAL TO THE PROJECT, EVEN IF THEY ARE NOT DIRECTLY RELATED TO THIS PROJECT.
- FINAL INSPECTIONS
- ANY DAMAGE ALONG THE HAUL ROUTES SHALL BE REPAIRED BY THE CONTRACTOR PRIOR TO THE COMPLETION OF THE PHASE FOR WHICH THE ROUTE IS USED. ALL HAUL ROLITES AND WORK AREAS SHALL BE INSPECTED BY CONTRACTOR/OWNER'S REPRESENTATIVE/MTAA PRIOR TO ANY PAVEMENT SECTION BEING RE-OPENED TO AIRCRAFT OR THE TRAVELING PUBLIC. THE CONTRACTOR SHALL PERFORM A FINAL INSPECTION OF ALL HAUL ROUTES NEAR THE COMPLETION OF PHASE 2 WITH ANY DEFECTS BEING REPAIRED AS BEING A CONDITION FOR SUBSTANTIAL COMPLETION FOR THE PROJECT

10. UNDERGROUND UTILITIES

- PROCEDURE FOR LOCATING AND PROTECTING EXISTING UNDERGROUND UTILITIES. CABLES, AND WIRES:
- PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL WALK THE JOB SITE WITH THE OWNER, AIRPORT OPERATIONS AND FAA TECHNICAL SERVICES TO IDENTIFY ANY EXISTING UNDERGROUND UTILITIES, CABLES, AND WIRES.
- THE CONTRACTOR SHALL VERIFY, IDENTIFY, LOCATE, MARK OUT, AND PROTECT THE ACTUAL LOCATIONS OF UTILITIES PRIOR TO ANY EXCAVATION, WHEN AT ALL FEASIBLE. THE CONTRACTOR WILL MARK EXISTING UTILITIES IN THE MOVEMENT AREA.
- THE CONTRACTOR SHALL COORDINATE WITH ALL APPROPRIATE AGENCIES.
- THE CONTRACTOR SHALL HAND-DIG WHEN WITHIN 3 FEET OF ANY KNOWN OR SUSPECTED UTILITY
- THE CONTRACTOR SHALL PROTECT ALL UNDERGROUND UTILITIES DURING THE DURATION OF THE PROJECT

11. PENALTIES

- . IN THE EVENT AN EMPLOYEE OF THE CONTRACTOR VIOLATES A SAFETY PROVISION, THEY SHALL BE PROHIBITED FROM RETURNING TO WORK ON THE AOA WITHOUT REMEDIAL SAFETY TRAINING AND THE APPROVAL OF THE AIRPORT. VIOLATIONS MAY BE DEEMED AS JUST AND SUFFICIENT CAUSE TO REQUIRE THE EMPLOYEE BE PERMANENTLY REMOVED FROM THE JOB SITE AT THE DISCRETION OF THE AIRPORT, SHOULD VIOLATIONS BY CONTRACTOR PERSONNEL BE SUBJECT TO FINES AS ASSESSED BY THE FEDERAL AVIATION ADMINISTRATION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PAYMENT OF SAID FINES AND THE REMOVAL OF THE EMPLOYEE RESPONSIBLE FOR THE VIOLATION TO BE REMOVED FROM THE PROJECT SITE PERMANENTLY.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS AND DELAYS CAUSED BY A SAFETY VIOLATION(S). CONSTRUCTION PERSONNEL DRIVING ERRATICALLY ON THE AIRPORT, EXCEEDING THE 20 MPH SPEED LIMIT, OR VIOLATING ANY OTHER AIRPORT DRIVING RULE OR SAFETY REGULATION, AT A MINIMUM, SHALL BE REMOVED FROM THE PROJECT PERMANENTLY. AIRPORT OPERATIONS CAN REMOVE ANY CONTRACTOR PERSONNEL, AT ANY TIME, FOR ANY DURATION, DUE TO A SAFETY VIOLATION. AIRPORT OPERATIONS SHALL REPORT ANY OCCURRENCES TO THE CONTRACTOR AND THE OWNER

12. SPECIAL CONDITIONS

- ALL CONTRACTOR'S SUPERVISORY PERSONNEL (PROJECT MANAGERS, SUPERINTENDENTS, FOREMEN, AND LEAD WORKERS) WHO WILL BE DIRECTING THE PROJECT. WORK, WHO WILL BE DRIVING EQUIPMENT ON THE AIRFIELD, OR ESCORTING OTHERS ON THE AIRFIELD SHALL BE REQUIRED TO TAKE AND PASS THE MTAA PEDESTRIAN/FLIGHT LINE DRIVING COURSE OF INSTRUCTION. TRUCK DRIVERS AND EQUIPMENT OPERATORS WHO WILL BE DRIVING STRICTLY WITHIN THE CONFINES OF THE HAUL ROUTES AND THE PROJECT AREA WILL NOT BE REQUIRED TO TAKE THIS TRAINING COURSE. THOSE DRIVERS OR OPERATORS WHO WILL BE DRIVING OUTSIDE OF THE HAUL ROUTES OR PROJECT LIMITS WILL BE REQUIRED TO TAKE AND PASS THE TRAINING COURSE. THIS COURSE OF INSTRUCTION LASTS APPROXIMATELY 1-2 HOURS AND WILL BE PROVIDED BY THE MTAA TO CONTRACTOR'S PERSONNEL AT NO COST TO THE CONTRACTOR, CONTRACTOR WILL ATTEMPT TO PROVIDE PERSONNEL FOR TRAINING IN GROUPS SO AS TO MINIMIZE THE NUMBER OF TRAINING SESSIONS. TRAINING SESSIONS SHALL BE COORDINATED WITH RITA EGGENBERGER. OPERATIONS OFFICER, 785-862-0399.
- CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ESCORT VEHICLES/PERSONNEL TO PROVIDE ESCORT FOR ASPHALT DELIVERY TRUCKS, CONCRETE READY-MIX TRUCKS OR OTHER VEHICLES THAT WILL DELIVER FRESH MATERIALS TO OR REMOVE MATERIALS FROM THE WORK SITE WITHIN THE AOA OR HAULING AWAY MATERIALS FROM THE AOA TO BE DISPOSED AT OFFSITE LOCATIONS. MTAA SAFETY PERSONNEL SHALL PROVIDE TRAINING FOR CONTRACTOR'S PERSONNEL AT THE ONSET OF THE PROJECT TO PROVIDE ESCORT AND AIRFIELD MOVEMENT TRAINING.

13. APRON, RUNWAY AND TAXIWAY VISUAL AIDS

• CLOSURES SHALL BE NOTED WITH THE USE OF LOW PROFILE BARRICADES AT APRON AND TAXIWAY CROSSINGS. BARRICADES SHALL BE SECURED TO PREVENT MOVEMENT FROM JET BLAST. THE AIRPORT WILL PROVIDE NOTAMS FOR CLOSURES AND THE CONTRACTOR WILL BE REQUIRED TO PROVIDE. PLACE AND MAINTAIN TEMPORARY BARRICADES AT CLEARLY VISIBLE LOCATIONS TO KEEP PILOTS FROM ERRANTLY TAXIING DOWN A CLOSED APRON OR CLOSED TAXIWAY, LOW PROFILE BARRICADES ARE TO BE PLACED AT THE RSA BOUNDARY.

LIGHTING AND VISUAL NAVAIDS

•• IF CLOSURES ARE REQUIRED, CLOSED TAXIWAY EDGE LIGHTS AND GUIDANCE SIGNAGE SHALL BE COVERED TO FURTHER ELIMINATE THE POSSIBILITY OF CONFUSING A PILOT. LIGHTING ACTIVITIES SHALL COMPLY WITH CURRENT FAA ADVISORY CIRCULAR 150/5340-30H "DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS". AC 150/5345-50B "SPECIFICATION FOR PORTABLE RUNWAY AND TAXIWAY LIGHTS" AND AC 150/5345-53D "AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM

SIGNS

- GUIDANCE SIGNAGE SHALL BE COVERED TO FURTHER ELIMINATE THE POSSIBILITY OF CONFUSING A PILOT. SIGNS MUST BE IN CONFORMANCE WITH CURRENT FAA ADVISORY CIRCULAR 150/5345-44K "SPECIFICATION FOR RUNWAY AND TAXIWAY SIGNS", AC 150-5340-18F "STANDARDS FOR AIRPORT SIGN SYSTEMS" AND AC 150/5345-53D "AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM"
- DO NOT COVER TAXIWAY DIRECTIONAL SIGNS THAT LEAD TO CLOSED TAXIWAYS.

14. MARKING AND SIGNS FOR ACCESS ROUTES

 THE ACCESS ROADS USED FOR HAULING AND DELIVERY OF MATERIALS TO THE SITE SHALL BE MARKED WITH TEMPORARY GUIDANCE SIGNS (STAKE MOUNTED OR SAW-HORSE, WEIGHTED DOWN WITH SAND BAGS) CONFORMING TO CURRENT FAA ADVISORY CIRCULAR 150/5345-44K, AC 150/5340-18F, MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) OR STATE HIGHWAY DEPARTMENT REQUIREMENTS. AT ALL ENTRANCES TO THE AOA, SPEED LIMIT SIGNS (20 MPH) SHALL BE PLACED. STOP SIGNS AND DIRECTION ARROW SIGNS SHALL BE PLACED AT KEY POINTS ALONG THE ACCESS ROAD TO ENSURE THE CONTRACTOR VEHICLES DRIVING THE ROUTE ADHERE TO YIELDING ALL AIRCRAFT THE RIGHT-OF-WAY AT ALL TIMES AND MINIMIZING POTENTIAL FOR ACCIDENTS OR ERRANTLY DRIVING OFF THE ROUTE.

15. HAZARD MARKING AND LIGHTING

- CONTRACTOR SHALL BE RESPONSIBLE FOR THE TRAFFIC CONTROL USED DURING THE COURSE OF THE PROJECT. CONTRACTOR SHALL FURNISH, INSTALL, MAINTAIN AND DISMANTLE ALL TRAFFIC CONTROL ITEMS USED DURING COURSE OF THE PROJECT. BARRICADES AROUND AIRCRAFT MOVEMENT AREAS MUST BE LOW PROFILE, LOW MASS BARRICADES SIMILAR TO THAT SHOWN ON SHEET C1.1.3.
- ALL VEHICLES AND EQUIPMENT THAT WILL BE CROSSING OR OPERATING IN THE AIR OPERATIONS AREAS OR ON ANY ACTIVE APRON OR TAXIWAY, AIRCRAFT MOVEMENT AREAS AND RUNWAY SAFETY AREAS SHALL BE MARKED WITH EITHER A FLAG OR A FLASHING BEACON. THE FLAGS (DAYTIME USE) SHALL BE ON A STAFF ATTACHED TO THE VEHICLE, 3-FOOT SQUARE WITH ORANGE AND WHITE CHECKERED PATTERN. BEACONS SHALL BE OF ADEQUATE SIZE AND STRENGTH AS TO BE VISIBLE FROM THE AIR AND MOUNTED ON THE UPPERMOST PART OF THE VEHICLE. ALL VEHICLES OPERATING DURING NIGHTTIME OPERATIONS SHALL BE EQUIPPED WITH A FLASHING AMBER BEACON.

- NO WORK SHALL OCCUR WITHIN A TOFA OF AN OPEN TAXIWAY
- ACTIVITIES SHOULD BE CONFINED TO AN AREA OR WORK ZONE SUCH THAT TRENCHES, OPEN EXCAVATIONS, AND CLEANING OPERATIONS CAN BE PERFORMED IN A RELATIVELY SHORT PERIOD OF TIME PRIOR TO THE END OF THE WORK DAY.
- ALL CONTRACTOR'S AND SUBCONTRACTORS' VEHICLES, PERSONNEL AND EQUIPMENT SHALL BE CONFINED TO THE LIMITS OF THE CONSTRUCTION PHASES, OCCUPYING ONLY THE PHASE WHERE WORK IS IN PROGRESS.

17. OTHER LIMITATIONS ON CONSTRUCTION

- FLARE POTS AND BLASTING ARE PROHIBITED FROM USE ON THIS PROJECT.
- OPEN FLAME WELDING, WITH ADEQUATE FIRE SAFETY PRECAUTIONS, WILL BE ALLOWED.
- BLASTING IN NOT ANTICIPATED FOR THE PROJECT AND WILL NOT BE ALLOWED.



SAS CITY, MO 64105 6-702-4300 | www.wsp. **MTAA**

AUTHORIT

AIRPORT

TOPEKA

ETROPOLITAN

S

PHILIP BILLARD MUNICIPAL AIRPORT TERMINAL APRON REHABILITATION AIP CONSTRUCTION GRANT NO. 3-20-0082-027 L-AIG CONSTRUCTION GRANT NO. 3-20-0082-0

ISSUED FOR BID

SHEET TITLE

CONSTRUCTION SAFETY & PHASING PLAN NOTES SHEET 2 OF 2

FEBRUARY 14, 202 DRAWN BY CHECKED BY

WSP PROJECT NUMBER US0040451.445

SHEET NUMBER


APPROVED BY

SHEET 7 OF 22

GC0.04


LDS

SFS







CONSTRUCTION SAFETY FLAG



NOTES:

COVER SHALL BE BLACK, SCHEDULE 40 PVC PIPE





SIDE VIEW TOP VIEW

LOW-PROFILE BARRICADE DETAIL

- 1. FLARES TO BE FLASHING AND BATTERY OPERATED. LENS TO BE RED AND ABLE TO ROTATE 90 DEGREES (AMBER LENS WILL NOT BE ACCEPTABLE).
- 2. ALTERNATING FLARE LENS ARE ROTATED 90 DEGREES TO ADJACENT LENS. 360 DEGREE LENSES WILL BE ACCEPTABLE.
- 3. SUPPORT BRACES TO BE SECURELY ATTACHED TO 2" X 8".
- 4. SAND BAGS OR OTHER ADEQUATE WEIGHT TO BE PLACED ON EACH SUPPORT BRACE OR FILLED WITH WATER.
- 5. FACING OF 2" X 8" TO BE COVERED WITH REFLECTIVE TAPE OR PAINT.
- 6. NO SEPARATE PAYMENT WILL BE MADE FOR THIS ITEM.
- 7. PLACE AT 12' CENTER TO CENTER INTERVALS (4' GAP).
- 8. BARRICADES SHALL BE LOCATED IN A LINE PARALLEL WITH THE RUNWAY OR THE TAXIWAY CENTERLINE OR AS SHOWN ON THE PLANS.
- 9. IN THE PRESENCE OF FOOT TRAFFIC, AND WHERE AGREED UPON BY MTAA, BARRICADES MUST BE INTERLOCKING AND HAVE NO SPACES BETWEEN THEM. GAPS BETWEEN BARRICADES MUST BE NO MORE THAN 4 FEET.
- 10. ALL BARRICADES MUST BE MOVED AT LEAST ONCE A WEEK AND THE CONTRACTOR MUST SWEEP ANY DEBRIS THAT HAS ACCUMULATED AND REMOVE THIS DEBRIS FROM SITE. THE BARRICADES MUST THEN BE REPLACED AT THE APPROPRIATE LOCATION.
- 11. BARRICADES MUST BE PLACED AT LOCATIONS SHOWN ON PLANS OR AS DIRECTED BY MTAA.
- 12. CONTRACTOR WILL BE RESPONSIBLE FOR MAINTAINING BARRICADES (INCLUDING LIGHTS) IN WORKING CONDITION AT ALL TIMES.
- 12. LOW PROFILE BARRICADES MUST BE PROVIDED BY THE CONTRACTOR. THE CONTRACTOR MUST SUPPLY A SUFFICIENT NUMBER OF BARRICADES FOR THE DURATION OF THE PROJECT. IT IS THE CONTRACTOR RESPONSIBILITY TO DETERMINE THE NUMBER OF BARRICADES FOR THE WORK AREAS AS IT RELATES TO THE CONTRACTOR'S WORK PLAN. THE COST FOR FURNISHING THE BARRICADES AS WELL AS MAINTENANCE, PLACEMENT AND SECURING (SEE NOTES 1-13), WILL BE CONSIDERED INCIDENTAL TO SAFETY AND SECURITY. CONTRACTOR TO ASSUME AT LEAST 1,700 LF OF BARRICADES FOR BIDDING PURPOSES.



MTAA

PHILIP BILLARD MUNICIPAL AIRPORT TERMINAL APRON REHABILITATION

AIP CONSTRUCTION GRANT NO. 3-20-0082-027 BIL-AIG CONSTRUCTION GRANT NO. 3-20-0082-028

METROPOLITAN TOPEKA AIRPORT AUTHORITY

ISSUED FOR BID

SHEET TITLE

CONSTRUCTION SAFETY & PHASING PLAN DETAILS

FEBRUARY 14, 2025 SCALE DRAWN BY LDS CHECKED BY

WSP PROJECT NUMBER US0040451.445

SFS

GC5.01 SHEET NUMBER

SHEET 8 OF 22

APPROVED BY



WSP USA Inc. 300 Wyandotte Suite 200 Kansas City, MO 64105